


# PIC16C62B/72A

#### 28-Pin 8-Bit CMOS Microcontrollers

#### **Microcontroller Core Features:**

- · High-performance RISC CPU
- Only 35 single word instructions to learn
- All single cycle instructions except for program branches, which are two cycle
- Operating speed: DC 20 MHz clock input DC - 200 ns instruction cycle
- 2K x 14 words of Program Memory,
   128 x 8 bytes of Data Memory (RAM)
- · Interrupt capability
- Eight level deep hardware stack
- · Direct, indirect, and relative addressing modes
- Power-on Reset (POR)
- Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Watchdog Timer (WDT) with its own on-chip RC oscillator for reliable operation
- Brown-out detection circuitry for Brown-out Reset (BOR)
- Programmable code-protection
- · Power saving SLEEP mode
- · Selectable oscillator options
- Low-power, high-speed CMOS EPROM technology
- Fully static design
- In-Circuit Serial Programming™ (ICSP)
- Wide operating voltage range: 2.5V to 5.5V
- High Sink/Source Current 25/25 mA
- Commercial, Industrial and Extended temperature ranges
- Low-power consumption:
  - < 2 mA @ 5V. 4 MHz</li>
  - 22.5 μA typical @ 3V, 32 kHz
  - < 1 μA typical standby current


#### Pin Diagram



#### **Peripheral Features:**

- Timer0: 8-bit timer/counter with 8-bit prescaler
- Timer1: 16-bit timer/counter with prescaler, can be incremented during sleep via external crystal/clock
- Timer2: 8-bit timer/counter with 8-bit period register, prescaler and postscaler
- · Capture, Compare, PWM module
- Capture is 16-bit, max. resolution is 12.5 ns, Compare is 16-bit, max. resolution is 200 ns, PWM maximum resolution is 10-bit
- 8-bit multi-channel Analog-to-Digital converter
- Synchronous Serial Port (SSP) with Enhanced SPI<sup>™</sup> and I<sup>2</sup>C<sup>™</sup>

#### **Pin Diagrams**



Key Features PICmicro™ Mid-Range Reference Manual (DS33023)	PIC16C62B	PIC16C72A
Operating Frequency	DC - 20 MHz	DC - 20 MHz
Resets (and Delays)	POR, BOR (PWRT, OST)	POR, BOR (PWRT, OST)
Program Memory (14-bit words)	2K	2K
Data Memory (bytes)	128	128
Interrupts	7	8
I/O Ports	Ports A,B,C	Ports A,B,C
Timers	3	3
Capture/Compare/PWM modules	1	1
Serial Communications	SSP	SSP
8-bit Analog-to-Digital Module	_	5 input channels

#### **Table of Contents**

1.0	Device Overview	
2.0	Memory Organization	
3.0	I/O Ports	
4.0	Timer0 Module	
5.0	Timer1 Module	
6.0	Timer2 Module	
7.0	Capture/Compare/PWM (CCP) Module	
8.0	Synchronous Serial Port (SSP) Module	
9.0	Analog-to-Digital Converter (A/D) Module	49
10.0	Special Features of the CPU	
	Instruction Set Summary	
12.0	Development Support	75
13.0	Electrical Characteristics	8 <sup>2</sup>
14.0	DC and AC Characteristics Graphs and Tables	103
15.0	Packaging Information	105
Appe	endix A: Revision History	11 <sup>2</sup>
	endix B: Conversion Considerations	
Appe	endix C: Migration from Base-line to Mid-Range Devices	112
Inde	X	113
On-L	ine Support	117
	der Response	
PIC1	16C62B/72A Product Identification System	119

#### To Our Valued Customers

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number. e.g., DS30000A is version A of document DS30000.

#### **New Customer Notification System**

Register on our web site (www.microchip.com/cn) to receive the most current information on our products.

#### Errata

An errata sheet may exist for current devices, describing minor operational differences (from the data sheet) and recommended workarounds. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)
- The Microchip Corporate Literature Center; U.S. FAX: (480) 786-7277

When contacting a sales office or the literature center, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Corrections to this Data Sheet**

We constantly strive to improve the quality of all our products and documentation. We have spent a great deal of time to ensure that this document is correct. However, we realize that we may have missed a few things. If you find any information that is missing or appears in error, please:

- Fill out and mail in the reader response form in the back of this data sheet.
- E-mail us at webmaster@microchip.com.

We appreciate your assistance in making this a better document.

# PIC16C62B/72A

**NOTES:** 

#### 1.0 DEVICE OVERVIEW


This document contains device-specific information. Additional information may be found in the PICmicro™ Mid-Range Reference Manual, (DS33023), which may be obtained from your local Microchip Sales Representative or downloaded from the Microchip website. The Reference Manual should be considered a complementary document to this data sheet, and is highly rec-

ommended reading for a better understanding of the device architecture and operation of the peripheral modules.

There are two devices (PIC16C62B, PIC16C72A) covered by this datasheet. The PIC16C62B does not have the A/D module implemented.

Figure 1-1 is the block diagram for both devices. The pinouts are listed in Table 1-1.

FIGURE 1-1: PIC16C62B/PIC16C72A BLOCK DIAGRAM



PIC16C62B/PIC16C72A PINOUT DESCRIPTION **TABLE 1-1** 

Pin Name	DIP Pin#	SOIC Pin#	I/O/P Type	Buffer Type	Description		
OSC1/CLKIN	9	9	I	ST/CMOS <sup>(3)</sup>	Oscillator crystal input/external clock source input.		
OSC2/CLKOUT	10	10	0	_	Oscillator crystal output. Connects to crystal or resonator in crystal oscillator mode. In RC mode, the OSC2 pin outputs CLKOUT which has 1/4 the frequency of OSC1, and denotes the instruction cycle rate.		
MCLR/VPP	1	1	I/P	ST	Master clear (reset) input or programming voltage input. This pin is an active low reset to the device.		
					PORTA is a bi-directional I/O port.		
RA0/AN0 <sup>(4)</sup>	2	2	I/O	TTL	RA0 can also be analog input 0		
RA1/AN1 <sup>(4)</sup>	3	3	I/O	TTL	RA1 can also be analog input 1		
RA2/AN2 <sup>(4)</sup>	4	4	I/O	TTL	RA2 can also be analog input 2		
RA3/AN3/VREF <sup>(4)</sup>	5	5	I/O	TTL	RA3 can also be analog input 3 or analog reference voltage		
RA4/T0CKI	6	6	I/O	ST	RA4 can also be the clock input to the Timer0 module.  Output is open drain type.		
RA5/ <del>SS/</del> AN4 <sup>(4)</sup>	7	7	I/O	TTL	RA5 can also be analog input 4 or the slave select for the synchronous serial port.		
					PORTB is a bi-directional I/O port. PORTB can be software programmed for internal weak pull-up on all inputs.		
RB0/INT	21	21	I/O	TTL/ST <sup>(1)</sup>	RB0 can also be the external interrupt pin.		
RB1	22	22	I/O	TTL			
RB2	23	23	I/O	TTL			
RB3	24	24	I/O	TTL			
RB4	25	25	I/O	TTL	Interrupt on change pin.		
RB5	26	26	I/O	TTL	Interrupt on change pin.		
RB6	27	27	I/O	TTL/ST <sup>(2)</sup>	Interrupt on change pin. Serial programming clock.		
RB7	28	28	I/O	TTL/ST <sup>(2)</sup>	Interrupt on change pin. Serial programming data.		
					PORTC is a bi-directional I/O port.		
RC0/T1OSO/T1CKI	11	11	I/O	ST	RC0 can also be the Timer1 oscillator output or Timer1 clock input.		
RC1/T1OSI	12	12	I/O	ST	RC1 can also be the Timer1 oscillator input.		
RC2/CCP1	13	13	I/O	ST	RC2 can also be the Capture1 input/Compare1 output/PWM1 output.		
RC3/SCK/SCL	14	14	I/O	ST	RC3 can also be the synchronous serial clock input/output for both SPI and I <sup>2</sup> C modes.		
RC4/SDI/SDA	15	15	I/O	ST	RC4 can also be the SPI Data In (SPI mode) or data I/O (I <sup>2</sup> C mode).		
RC5/SDO	16	16	I/O	ST	RC5 can also be the SPI Data Out (SPI mode).		
RC6	17	17	I/O	ST			
RC7	18	18	I/O	ST			
Vss	8, 19	8, 19	Р	_	Ground reference for logic and I/O pins.		
VDD	20	20	Р	_	Positive supply for logic and I/O pins.		
Legend: L = input	O = outr			innut/outnut	P – nower or program		

Legend: I = input

O = output — = Not used I/O = input/output TTL = TTL input

P = power or program ST = Schmitt Trigger input

Note 1: This buffer is a Schmitt Trigger input when configured as the external interrupt.

2: This buffer is a Schmitt Trigger input when used in serial programming mode.3: This buffer is a Schmitt Trigger input when configured in RC oscillator mode and a CMOS input otherwise.

4: The A/D module is not available on the PIC16C62B.

#### 2.0 MEMORY ORGANIZATION

There are two memory blocks in each of these microcontrollers. Each block (Program Memory and Data Memory) has its own bus, so that concurrent access can occur.


Additional information on device memory may be found in the PICmicro™ Mid-Range Reference Manual, (DS33023).

#### 2.1 Program Memory Organization

The PIC16C62B/72A devices have a 13-bit program counter capable of addressing an 8K x 14 program memory space. Each device has 2K x 14 words of program memory. Accessing a location above 07FFh will cause a wraparound.

The reset vector is at 0000h and the interrupt vector is at 0004h.

FIGURE 2-1: PROGRAM MEMORY MAP AND STACK



#### 2.2 <u>Data Memory Organization</u>

The data memory is partitioned into multiple banks which contain the General Purpose Registers and the Special Function Registers. Bits RP1 and RP0 are the bank select bits.

RP1<sup>(1)</sup> RP0

(STATUS<6:5>)

- =  $00 \rightarrow Bank0$
- =  $01 \rightarrow Bank1$
- = 10 → Bank2 (not implemented)
- = 11 → Bank3 (not implemented)

Note 1: Maintain this bit clear to ensure upward compatibility with future products.

Each bank extends up to 7Fh (128 bytes). The lower locations of each bank are reserved for the Special Function Registers. Above the Special Function Registers are General Purpose Registers, implemented as static RAM. All implemented banks contain Special Function Registers. Some "high use" Special Function Registers from one bank may be mirrored in another bank for code reduction and quicker access.

#### 2.2.1 GENERAL PURPOSE REGISTER FILE

The register file can be accessed either directly, or indirectly through the File Select Register FSR (Section 2.5).

FIGURE 2-2: REGISTER FILE MAP

			· <del>-</del>
File			File
Address			Address
00h	INDF <sup>(1)</sup>	INDF <sup>(1)</sup>	80h
01h	TMR0	OPTION_REG	81h
02h	PCL	PCL	82h
03h	STATUS	STATUS	83h
04h	FSR	FSR	84h
05h	PORTA	TRISA	85h
06h	PORTB	TRISB	86h
07h	PORTC	TRISC	87h
08h	_	_	88h
09h	_	_	89h
0Ah	PCLATH	PCLATH	8Ah
0Bh	INTCON	INTCON	8Bh
0Ch	PIR1	PIE1	8Ch
0Dh	_	_	8Dh
0Eh	TMR1L	PCON	8Eh
0Fh	TMR1H	_	8Fh
10h	T1CON	_	90h
11h	TMR2	_	91h
12h	T2CON	PR2	92h
13h	SSPBUF	SSPADD	93h
14h	SSPCON	SSPSTAT	94h
15h	CCPR1L	_	95h
16h	CCPR1H	_	96h
17h	CCP1CON	_	97h
18h	_	_	98h
19h		_	99h
1Ah	_	_	9Ah
1Bh		_	9Bh
1Ch	_	_	9Ch
1Dh		_	9Dh
1Eh	ADRES <sup>(2)</sup>		9Eh
1Fh	ADCON0 <sup>(2)</sup>	ADCON1 <sup>(2)</sup>	9Fh
20h			A0h
		General Purpose	
	General	Registers	BFh
	Purpose	_	C0h
	Registers	_	- ***
7Fh		_	FFh
[	Bank 0	Bank 1	]
Uni		ata memory local	tions,
	l as '0'.		,
Note 1: No	ot a physical red	aister.	

Note 1: Not a physical register.

2: These registers are not implemented on the PIC16C62B, read as '0'.

#### 2.2.2 SPECIAL FUNCTION REGISTERS

The Special Function Registers are registers used by the CPU and Peripheral Modules for controlling the desired operation of the device. These registers are implemented as static RAM. A list of these registers is given in Table 2-1. The Special Function Registers can be classified into two sets; core (CPU) and peripheral. Those registers associated with the core functions are described in detail in this section. Those related to the operation of the peripheral features are described in detail in the peripheral feature section.

TABLE 2-1 SPECIAL FUNCTION REGISTER SUMMARY

Addr	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other resets (4)
Bank 0											
00h	INDF <sup>(1)</sup>	Addressing	this locatio	n uses conte	ents of FSR	to address d	ata memory	(not a physi	cal register)	0000 0000	0000 0000
01h	TMR0	Timer0 mo	dule's regist	er						xxxx xxxx	uuuu uuuu
02h	PCL <sup>(1)</sup>	Program C	ounter's (PC	C) Least Sigr	nificant Byte	1				0000 0000	0000 0000
03h	STATUS <sup>(1)</sup>	IRP <sup>(5)</sup>	RP1 <sup>(5)</sup>	RP0	TO	PD	Z	DC	С	0001 1xxx	000q quuu
04h	FSR <sup>(1)</sup>	Indirect dat	a memory a	address poin	iter					xxxx xxxx	uuuu uuuu
05h	PORTA <sup>(6,7)</sup>	_	-	PORTA Dat	ta Latch who	en written: Po	ORTA pins w	hen read		0x 0000	0u 0000
06h	PORTB <sup>(6,7)</sup>	PORTB Da	ta Latch wh	en written: F	PORTB pins	when read				xxxx xxxx	uuuu uuuu
07h	PORTC <sup>(6,7)</sup>	PORTC Da	PRTC Data Latch when written: PORTC pins when read							xxxx xxxx	uuuu uuuu
08h-09h	_	Unimpleme	nimplemented								_
0Ah	PCLATH <sup>(1,2)</sup>	_	— — Write Buffer for the upper 5 bits of the Program Counter						0 0000	0 0000	
0Bh	INTCON <sup>(1)</sup>	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF <sup>(3)</sup>	ı	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
0Dh	_	Unimpleme	ented							_	_
0Eh	TMR1L	Holding reg	ister for the	Least Signi	ficant Byte o	of the 16-bit 7	TMR1 registe	er		xxxx xxxx	uuuu uuuu
0Fh	TMR1H	Holding reg	ister for the	Most Signif	icant Byte o	f the 16-bit T	MR1 registe	r		xxxx xxxx	uuuu uuuu
10h	T1CON	_	1	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	00 0000	uu uuuu
11h	TMR2	Timer2 mo	dule's regist	er						0000 0000	0000 0000
12h	T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	-000 0000
13h	SSPBUF	Synchrono	us Serial Po	rt Receive E	Buffer/Transr	nit Register				xxxx xxxx	uuuu uuuu
14h	SSPCON	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	0000 0000
15h	CCPR1L	Capture/Co	mpare/PWI	M Register1	(LSB)					xxxx xxxx	uuuu uuuu
16h	CCPR1H	Capture/Co	Capture/Compare/PWM Register1 (MSB)								uuuu uuuu
17h	CCP1CON	_	_	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	00 0000
18h-1Dh	_	Unimpleme	Unimplemented —								_
1Eh	ADRES <sup>(3)</sup>	A/D Result	Register							xxxx xxxx	uuuu uuuu
1Fh	ADCON0 <sup>(3)</sup>	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000 00-0	0000 00-0

Legend: x = unknown, u = unchanged, q = value depends on condition, -= unimplemented, read as '0', Shaded locations are unimplemented, read as '0'.

- Note 1: These registers can be addressed from either bank.
  - 2: The upper byte of the program counter is not directly accessible. PCLATH is a holding register for PC<12:8> whose contents are transferred to the upper byte of the program counter.
  - 3: A/D not implemented on the PIC16C62B, maintain as '0'.
  - 4: Other (non power-up) resets include: external reset through MCLR and the Watchdog Timer Reset.
  - 5: The IRP and RP1 bits are reserved. Always maintain these bits clear.
  - **6:** On any device reset, these pins are configured as inputs.
  - **7:** This is the value that will be in the port output latch.

TABLE 2-1 SPECIAL FUNCTION REGISTER SUMMARY (Cont.'d)

Addr	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other resets (4)
Bank 1											
80h	INDF <sup>(1)</sup>	Addressing	this location	n uses conte	ents of FSR	to address d	ata memory	(not a physi	cal register)	0000 0000	0000 0000
81h	OPTION_REG	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111
82h	PCL <sup>(1)</sup>	Program Co	ounter's (PC	C) Least Sigr	nificant Byte	1				0000 0000	0000 0000
83h	STATUS <sup>(1)</sup>	IRP <sup>(5)</sup>	RP1 <sup>(5)</sup>	RP0	TO	PD	Z	DC	С	0001 1xxx	000q quuu
84h	FSR <sup>(1)</sup>	Indirect dat	ndirect data memory address pointer								uuuu uuuu
85h	TRISA	_	PORTA Data Direction Register							11 1111	11 1111
86h	TRISB	PORTB Da	ORTB Data Direction Register								1111 1111
87h	TRISC	PORTC Da	ORTC Data Direction Register								1111 1111
88h-89h	_	Unimpleme	nted							_	_
8Ah	PCLATH <sup>(1,2)</sup>	_	1	_	Write Buffe	r for the upp	er 5 bits of th	e Program (	Counter	0 0000	0 0000
8Bh	INTCON <sup>(1)</sup>	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
8Ch	PIE1	_	ADIE <sup>(3)</sup>	_	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
8Dh	_	Unimpleme	nted							_	_
8Eh	PCON	_	_	_	_	_	_	POR	BOR	qq	uu
8Fh-91h	_	Unimpleme	nted							_	_
92h	PR2	Timer2 Per	imer2 Period Register								1111 1111
93h	SSPADD	Synchronous Serial Port (I <sup>2</sup> C mode) Address Register								0000 0000	0000 0000
94h	SSPSTAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000 0000	0000 0000
95h-9Eh	_	Unimpleme	ented							_	_
9Fh	ADCON1 <sup>(3)</sup>	_	_	_	_	_	PCFG2	PCFG1	PCFG0	000	000

Legend: x = unknown, u = unchanged, q = value depends on condition, -= unimplemented, read as '0', Shaded locations are unimplemented, read as '0'.

**Note 1:** These registers can be addressed from either bank.

- 2: The upper byte of the program counter is not directly accessible. PCLATH is a holding register for PC<12:8> whose contents are transferred to the upper byte of the program counter.
- 3: A/D not implemented on the PIC16C62B, maintain as '0'.
- 4: Other (non power-up) resets include: external reset through MCLR and the Watchdog Timer Reset.
- 5: The IRP and RP1 bits are reserved. Always maintain these bits clear.
- 6: On any device reset, these pins are configured as inputs.
- 7: This is the value that will be in the port output latch.

#### 2.2.2.1 STATUS REGISTER

The STATUS register, shown in Register 2-1, contains the arithmetic status of the ALU, the RESET status and the bank select bits for data memory.

The STATUS register can be the destination for any instruction, as with any other register. If the STATUS register is the destination for an instruction that affects the Z, DC or C bits, the write to these three bits is disabled. These bits are set or cleared according to the device logic. The  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are not writable. The result of an instruction with the STATUS register as destination may be different than intended.

For example, CLRF STATUS will clear the upper-three bits and set the Z bit. This leaves the STATUS register as 000u uluu (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect the Z, C or DC bits from the STATUS register. For other instructions, not affecting any status bits, see the "Instruction Set Summary."

- **Note 1:** The IRP and RP1 bits are reserved. Maintain these bits clear to ensure upward compatibility with future products.
- Note 2: The C and DC bits operate as a borrow and digit borrow bit, respectively, in subtraction. See the SUBLW and SUBWF instructions.

#### REGISTER 2-1: STATUS REGISTER (ADDRESS 03h, 83h)

R/W-0	R/W-0	R/W-0	R-1	R-1	R/W-x	R/W-x	R/W-x				
IRP bit7	RP1	RP0	TO	PD	Z	DC	C bit0	R = Readable bit W = Writable bit			
								U = Unimplemented bit, read as '0'			
								- n = Value at POR reset			
bit 7:	IRP: Register Bank Select bit (used for indirect addressing) (reserved, maintain clear)										
bit 6-5:		•		ct bits (us	ed for direc	t addressin	g)				
		k 1 (80h - F k 0 (00h - 7									
	Each bank	k is 128 byt	tes								
		lote: RP1 is reserved, maintain clear									
bit 4:	-	TO: Time-out bit  1 = After power-up, CLRWDT instruction, or SLEEP instruction									
		oower-up, c T time-out		struction,	Or SLEEP II	nstruction					
bit 3:	PD: Powe										
		oower-up o ecution of t									
bit 2:	Z: Zero bit										
				•	peration is a peration is a						
bit 1:								r borrow, the polarity is reversed			
					t of the resubit of the res						
bit 0:	•	•					, ,	ow, the polarity is reversed)			
	<ul> <li>1 = A carry-out from the most significant bit of the result occurred</li> <li>0 = No carry-out from the most significant bit of the result occurred</li> </ul>										
				J							
								ding the two's complement of the either the high or low order bit a			
	the source		. 3.0.0 (10	, ,				and the state of t			

#### 2.2.2.2 OPTION\_REG REGISTER

The OPTION\_REG register is a readable and writable register, which contains various control bits to configure the TMR0 prescaler/WDT postscaler (single assignable register known as the prescaler), the External INT Interrupt, TMR0 and the weak pull-ups on PORTB.

**Note:** To achieve a 1:1 prescaler assignment for the TMR0 register, assign the prescaler to the Watchdog Timer.

#### REGISTER 2-2: OPTION\_REG REGISTER (ADDRESS 81h)

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1					
RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	R = Readable bit				
bit7							bit0	W = Writable bit - n = Value at POR rese				
bit 7:	RBPU: PO							II = Valde at 1 Ott 1656				
		<ul><li>= PORTB pull-ups are disabled</li><li>= PORTB pull-ups are enabled for all PORTB inputs</li></ul>										
	0 = PORTI	B pull-ups	s are enal	oled for all	PORTB inp	outs						
bit 6:	INTEDG: I											
	1 = Interru											
	0 = Interru	pt on falli	ng edge o	of RB0/INT	「 pin							
bit 5:	TOCS: TMI											
	1 = Transit			•								
	0 = Interna	al instruct	ion cycle	clock (CLł	(OUT)							
bit 4:	TOSE: TMI	R0 Sourc	e Edge S	elect bit								
					on RA4/T0							
	0 = Increm	ent on lo	w-to-high	transition	on RA4/T0	CKI pin						
bit 3:	PSA: Pres	caler Ass	signment b	oit								
	1 = Presca											
	0 = Presca	aler is ass	signed to t	he Timer(	) module							
bit 2-0:	PS2:PS0:	Prescale	r Rate Se	lect bits								
	Bit Value	TMR0 R	ate WD	Γ Rate								
	000	1:2	1	: 1								
	001	1:4		2								
	010	1.0										
		011 1:16 1:8										
	100											
	110	1:04	•	: 64								
	111 1:256 1:128											

#### 2.2.2.3 INTCON REGISTER

The INTCON Register is a readable and writable register, which contains various interrupt enable and flag bits for the TMR0 register overflow, RB Port change and External RB0/INT pin interrupts.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>). User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

#### REGISTER 2-3: INTCON REGISTER (ADDRESS 0Bh, 8Bh)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x				
GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	R = Readable bit			
bit7							bit0	W = Writable bit - n = Value at POR reset			
bit 7:	1 = Enab	oal Interrup les all un-roles all inte	masked in								
bit 6:											
bit 5:	<b>T0IE</b> : TMR0 Overflow Interrupt Enable bit  1 = Enables the TMR0 interrupt  0 = Disables the TMR0 interrupt										
bit 4:	IINTE: RB0/INT External Interrupt Enable bit  1 = Enables the RB0/INT external interrupt  0 = Disables the RB0/INT external interrupt										
bit 3:	1 = Enab	Port Cha les the RE bles the RE	port char	nge interru	ıpt						
bit 2:	TolF: TMR0 Overflow Interrupt Flag bit  1 = TMR0 register has overflowed (software must clear bit)  0 = TMR0 register did not overflow										
bit 1:	INTF: RB0/INT External Interrupt Flag bit  1 = The RB0/INT external interrupt occurred (software must clear bit)  0 = The RB0/INT external interrupt did not occur										
bit 0:	RBIF: RB Port Change Interrupt Flag bit  1 = At least one of the RB7:RB4 input pins have changed state (clear by reading PORTB)  0 = None of the RB7:RB4 input pins have changed state										

Note:

# PIC16C62B/72A

#### 2.2.2.4 PIE1 REGISTER

This register contains the individual enable bits for the peripheral interrupts.

**Note:** Bit PEIE (INTCON<6>) must be set to enable any peripheral interrupt.

#### REGISTER 2-4: PIE1 REGISTER (ADDRESS 8Ch)

U-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0					
_	ADIE <sup>(1)</sup>	_	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	R = Readable bit				
bit7	bit0  W = Writable bit  U = Unimplemented bit, read as '0'  - n = Value at POR reset  Unimplemented: Read as '0'											
bit 7:	Unimpler	Jnimplemented: Read as '0'										
bit 6:	1 = Enabl	ADIE <sup>(1)</sup> : A/D Converter Interrupt Enable bit  1 = Enables the A/D interrupt  0 = Disables the A/D interrupt										
bit 5-4:	Unimpler	Jnimplemented: Read as '0'										
bit 3:	1 = Enabl	SSPIE: Synchronous Serial Port Interrupt Enable bit  1 = Enables the SSP interrupt  0 = Disables the SSP interrupt										
bit 2:	1 = Enabl	CCP1 Inter les the CCF les the CC	°1 interru	pt								
bit 1:	TMR2IE: TMR2 to PR2 Match Interrupt Enable bit  1 = Enables the TMR2 to PR2 match interrupt  0 = Disables the TMR2 to PR2 match interrupt											
bit 0:	TMR1IE: TMR1 Overflow Interrupt Enable bit  1 = Enables the TMR1 overflow interrupt  0 = Disables the TMR1 overflow interrupt											
Note 1:												

#### 2.2.2.5 PIR1 REGISTER

This register contains the individual flag bits for the Peripheral interrupts.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>). User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

#### REGISTER 2-5: PIR1 REGISTER (ADDRESS 0Ch)

U-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0			
_	ADIF <sup>(1)</sup>		_	SSPIF	CCP1IF	TMR2IF	TMR1IF	R = Readable bit		
oit7	bit0 W = Writable bit U = Unimplemen read as '0' - n = Value at POF									
oit 7:	Unimplem	nented: R	ead as '0	,						
bit 6:	<b>ADIF</b> (1): AA 1 = An A/E 0 = The AA	onvers convers	ion compl	eted (mus	t be cleared	d in softwa	re)			
bit 5-4:	Unimplem	nented: R	ead as '0	,						
bit 3:	1 = The tra	SPIF: Synchronous Serial Port Interrupt Flag bit  = The transmission/reception is complete (must be cleared in software)  = Waiting to transmit/receive								
bit 2:	Capture M 1 = A TMF 0 = No TM Compare I 1 = A TMF 0 = No TM PWM Mod	CCP1IF: CCP1 Interrupt Flag bit  Capture Mode  L = A TMR1 register capture occurred (must be cleared in software)  D = No TMR1 register capture occurred  Compare Mode  L = A TMR1 register compare match occurred (must be cleared in software)  D = No TMR1 register compare match occurred (must be cleared in software)  D = No TMR1 register compare match occurred  COMPAND MODE  Unused in this mode								
bit 1:	1 = TMR2	TMR2IF: TMR2 to PR2 Match Interrupt Flag bit  L = TMR2 to PR2 match occurred (must be cleared in software)  D = No TMR2 to PR2 match occurred								
bit 0:	<b>TMR1IF</b> : 7 1 = TMR1 0 = TMR1	register of	overflowed	d (must be	bit cleared in	software)				
Note 1:	The PIC160 bit clear.	C62B does	not have a	an A/D mod	ule. This bit I	ocation is re	eserved on th	ese devices. Always maintain th		

Note:

### PIC16C62B/72A

#### 2.2.2.6 PCON REGISTER

The Power Control register (PCON) contains flag bits to allow differentiation between a Power-on Reset (POR), Brown-Out Reset (BOR) and resets from other sources. .


Note: On Power-on Reset, the state of the BOR bit is unknown and is not predictable.

If the BODEN bit in the configuration word is set, the user must first set the BOR bit on a POR, and check it on subsequent resets.

If BOR is cleared while POR remains set, a Brown-out reset has occurred.

If the BODEN bit is clear, the BOR bit may be ignored.

#### REGISTER 2-6: PCON REGISTER (ADDRESS 8Eh)



#### 2.3 PCL and PCLATH

The program counter (PC) specifies the address of the instruction to fetch for execution. The PC is 13 bits wide. The low byte is called the PCL register and is readable and writable. The high byte is called the PCH register. This register contains the PC<12:8> bits and is not directly accessible. All updates to the PCH register go through the PCLATH register.

#### 2.3.1 STACK

The stack allows any combination of up to 8 program calls and interrupts to occur. The stack contains the return address from this branch in program execution.

Mid-range devices have an 8 level deep hardware stack. The stack space is not part of either program or data space and the stack pointer is not accessible. The PC is PUSHed onto the stack when a CALL instruction is executed or an interrupt causes a branch. The stack is POPed in the event of a RETURN, RETLW or a RETFIE instruction execution. PCLATH is not modified when the stack is PUSHed or POPed.

After the stack has been PUSHed eight times, the ninth push overwrites the value that was stored from the first push. The tenth push overwrites the second push (and so on).

#### 2.4 Program Memory Paging

The CALL and GOTO instructions provide 11 bits of address to allow branching within any 2K program memory page. When doing a CALL or GOTO instruction, the upper bit of the address is provided by PCLATH<3>. The user must ensure that the page select bit is programmed to address the proper program memory page. If a return from a CALL instruction (or interrupt) is executed, the entire 13-bit PC is popped from the stack. Therefore, manipulation of the PCLATH<3> bit is not required for the return instructions.

#### 2.5 <u>Indirect Addressing, INDF and FSR</u> Registers

The INDF register is not a physical register. Addressing INDF actually addresses the register whose address is contained in the FSR register (FSR is a pointer).

Reading INDF itself indirectly (FSR = 0) will produce 00h. Writing to the INDF register indirectly results in a no-operation (although STATUS bits may be affected).

A simple program to clear RAM locations 20h-2Fh using indirect addressing is shown in Example 2-1.

# EXAMPLE 2-1: HOW TO CLEAR RAM USING INDIRECT ADDRESSING


movlw 0x20 ;initialize pointer
movwf FSR ; to RAM

NEXT clrf INDF ;clear INDF register
incf FSR ;inc pointer
btfss FSR,4 ;all done?
goto NEXT ;NO, clear next

CONTINUE
: ;YES, continue

An effective 9-bit address is obtained by concatenating the 8-bit FSR register and the IRP bit (STATUS<7>), as shown in Figure 2-3. However, IRP is not used in the PIC16C62B/72A.

FIGURE 2-3: DIRECT/INDIRECT ADDRESSING



#### 3.0 I/O PORTS

Some I/O port pins are multiplexed with an alternate function for the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.

Additional information on I/O ports may be found in the PICmicro $^{\text{TM}}$  Mid-Range Reference Manual, (DS33023).

#### 3.1 PORTA and the TRISA Register

PORTA is a 6-bit wide bi-directional port. The corresponding data direction register is TRISA. Setting a TRISA bit (=1) will make the corresponding PORTA pin an input, i.e., put the corresponding output driver in a hi-impedance mode. Clearing a TRISA bit (=0) will make the corresponding PORTA pin an output, (i.e., put the contents of the output latch on the selected pin).

The PORTA register reads the state of the pins, whereas writing to it will write to the port latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified, and then written to the port data latch.

Pin RA4 is multiplexed with the Timer0 module clock input to become the RA4/T0CKI pin. The RA4/T0CKI pin is a Schmitt Trigger input and an open drain output. All other RA port pins have TTL input levels and full CMOS output drivers.

Pin RA5 is multiplexed with the SSP to become the RA5/ $\overline{\text{SS}}$  pin.

On the PIC16C72A device, other PORTA pins are multiplexed with analog inputs and analog VREF input. The operation of each pin is selected by clearing/setting the control bits in the ADCON1 register (A/D Control Register1).

**Note:** On a Power-on Reset, pins with analog functions are configured as analog inputs with digital input buffers disabled. A digital read of these pins will return '0'.

The TRISA register controls the direction of the RA pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set when using them as analog inputs.

# FIGURE 3-1: BLOCK DIAGRAM OF RA3:RA0 AND RA5 PINS




FIGURE 3-2: BLOCK DIAGRAM OF RA4/T0CKI PIN




TABLE 3-1 PORTA FUNCTIONS

Name	Bit#	Buffer	Function
RA0/AN0	bit0	TTL	Input/output or analog input <sup>(1)</sup>
RA1/AN1	bit1	TTL	Input/output or analog input(1)
RA2/AN2	bit2	TTL	Input/output or analog input <sup>(1)</sup>
RA3/AN3/VREF	bit3	TTL	Input/output or analog input <sup>(1)</sup> or VREF <sup>(1)</sup>
RA4/T0CKI	bit4	ST	Input/output or external clock input for Timer0 Output is open drain type
RA5/SS/AN4	bit5	TTL	Input/output or slave select input for synchronous serial port or analog input <sup>(1)</sup>

Legend: TTL = TTL input, ST = Schmitt Trigger input

Note 1: The PIC16C62B does not implement the A/D module.

#### TABLE 3-2 SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
05h	PORTA (for PIC16C72A only)	_	_	RA5	RA4	RA3	RA2	RA1	RA0	0x 0000	0u 0000
05h	PORTA (for PIC16C62B only)	-	_	RA5	RA4	RA3	RA2	RA1	RA0	xx xxxx	uu uuuu
85h	TRISA	_	_	PORTA	Data D	irection	Register			11 1111	11 11111
9Fh	ADCON1 <sup>(1)</sup>	_	_	_	_	_	PCFG2	PCFG1	PCFG0	000	000


Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTA.**Note 1:**The PIC16C62B does not implement the A/D module. Maintain this register clear.

#### 3.2 PORTB and the TRISB Register

PORTB is an 8-bit wide bi-directional port. The corresponding data direction register is TRISB. Setting a TRISB bit (=1) will make the corresponding PORTB pin an input, (i.e., put the corresponding output driver in a hi-impedance mode). Clearing a TRISB bit (=0) will make the corresponding PORTB pin an output, (i.e., put the contents of the output latch on the selected pin).

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by clearing bit RBPU (OPTION\_REG<7>). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset.

FIGURE 3-3: BLOCK DIAGRAM OF RB3:RB0 PINS



Four of PORTB's pins, RB7:RB4, have an interrupt on change feature. Only pins configured as inputs can cause this interrupt to occur (i.e. any RB7:RB4 pin configured as an output is excluded from the interrupt on change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are OR'ed together to generate the RB Port Change Interrupt with flag bit RBIF (INTCON<0>).

This interrupt can wake the device from SLEEP. The user, in the interrupt service routine, can clear the interrupt in the following manner:


- Any read or write of PORTB. This will end the mismatch condition.
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared.

The interrupt on change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt on change feature. Polling of PORTB is not recommended while using the interrupt on change feature.

RB0/INT is an external interupt pin and is configured using the INTEDG bit (OPTION\_REG<6>). RB0/INT is discussed in detail in Section 10.10.1.

FIGURE 3-4: BLOCK DIAGRAM OF RB7:RB4 PINS



2: To enable weak pull-ups, set the appropriate TRIS bit(s) and clear the RBPU bit (OPTION\_REG<7>).

**TABLE 3-3** PORTB FUNCTIONS

Name	Bit#	Buffer	Function
RB0/INT	bit0	TTL/ST <sup>(1)</sup>	Input/output pin or external interrupt input. Internal software programmable weak pull-up.
RB1	bit1	TTL	Input/output pin. Internal software programmable weak pull-up.
RB2	bit2	TTL	Input/output pin. Internal software programmable weak pull-up.
RB3	bit3	TTL	Input/output pin. Internal software programmable weak pull-up.
RB4	bit4	TTL	Input/output pin (with interrupt on change). Internal software programmable weak pull-up.
RB5	bit5	TTL	Input/output pin (with interrupt on change). Internal software programmable weak pull-up.
RB6	bit6	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt on change). Internal software programmable weak pull-up. Serial programming clock.
RB7	bit7	TTL/ST <sup>(2)</sup>	Input/output pin (with interrupt on change). Internal software programmable weak pull-up. Serial programming data.

Legend: TTL = TTL input, ST = Schmitt Trigger input

Note 1: This buffer is a Schmitt Trigger input when configured as the external interrupt.

2: This buffer is a Schmitt Trigger input when used in serial programming mode.

#### **TABLE 3-4** SUMMARY OF REGISTERS ASSOCIATED WITH PORTB

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other resets
06h	PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	xxxx xxxx	uuuu uuuu
86h	TRISB	PORTB I	DRTB Data Direction Register					1111 1111	1111 1111		
81h	OPTION_REG	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111

Legend: x = unknown, u = unchanged. Shaded cells are not used by PORTB.


#### 3.3 PORTC and the TRISC Register

PORTC is an 8-bit wide bi-directional port. The corresponding data direction register is TRISC. Setting a TRISC bit (=1) will make the corresponding PORTC pin an input, (i.e., put the corresponding output driver in a hi-impedance mode). Clearing a TRISC bit (=0) will make the corresponding PORTC pin an output, (i.e., put the contents of the output latch on the selected pin).

PORTC is multiplexed with several peripheral functions (Table 3-5). PORTC pins have Schmitt Trigger input buffers.

When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output, while other peripherals override the TRIS bit to make a pin an input. Since the TRIS bit override maybe in effect while the peripheral is enabled, read-modify-write instructions (BSF, BCF, XORWF) with TRISC as destination should be avoided. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

FIGURE 3-5: PORTC BLOCK DIAGRAM (PERIPHERAL OUTPUT OVERRIDE)



- Note 1: I/O pins have diode protection to VDD and Vss.
  - 2: Port/Peripheral select signal selects between port data and peripheral output.
  - **3:** Peripheral OE (output enable) is only activated if peripheral select is active.

© 1999 Microchip Technology Inc. Preliminary DS35008B-page 23

# PIC16C62B/72A

TABLE 3-5 PORTC FUNCTIONS

Name	Bit#	Buffer Type	Function	TRISC Override
RC0/T1OSO/T1CKI	bit0	ST	Input/output port pin or Timer1 oscillator output/Timer1 clock input	Yes
RC1/T1OSI	bit1	ST	Input/output port pin or Timer1 oscillator input	Yes
RC2/CCP1	bit2	ST	Input/output port pin or Capture1 input/Compare1 output/PWM1 output	No
RC3/SCK/SCL	bit3	ST	RC3 can also be the synchronous serial clock for both SPI and I <sup>2</sup> C modes.	No
RC4/SDI/SDA	bit4	ST	RC4 can also be the SPI Data In (SPI mode) or data I/O (I <sup>2</sup> C mode).	No
RC5/SDO	bit5	ST	Input/output port pin or Synchronous Serial Port data output	No
RC6	bit6	ST	Input/output port pin	No
RC7	bit7	ST	Input/output port pin	No

Legend: ST = Schmitt Trigger input

#### TABLE 3-6 SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other resets
07h	PORTC	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	xxxx xxxx	uuuu uuuu
87h	TRISC	PORTC I	PORTC Data Direction Register							1111 1111	1111 1111

Legend: x = unknown, u = unchanged.

#### 4.0 TIMERO MODULE

The Timer0 module timer/counter has the following features:

- 8-bit timer/counter
  - Read and write
  - INT on overflow
- · 8-bit software programmable prescaler
- · INT or EXT clock select
  - EXT clock edge select

Figure 4-1 is a simplified block diagram of the Timer0 module.

Additional information on timer modules is available in the  $PICmicro^{TM}$  Mid-Range Reference Manual, (DS33023).

#### 4.1 <u>Timer0 Operation</u>

Timer0 can operate as a timer or as a counter.

Timer mode is selected by clearing bit TOCS (OPTION\_REG<5>). In timer mode, the Timer0 module will increment every instruction cycle (without prescaler). If the TMR0 register is written, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0 register.

Counter mode is selected by setting bit T0CS (OPTION\_REG<5>). In counter mode, Timer0 will increment either on every rising or falling edge of pin RA4/T0CKI. The incrementing edge is determined by the Timer0 Source Edge Select bit T0SE (OPTION\_REG<4>). Clearing bit T0SE selects the rising edge. Restrictions on the external clock input are discussed below.

When an external clock input is used for Timer0, it must meet certain requirements. The requirements ensure the external clock can be synchronized with the internal phase clock (Tosc). Also, there is a delay in the actual incrementing of Timer0 after synchronization. Additional information on external clock requirements is available in the Electrical Specifications section of this manual, and in the PICmicro™ Mid-Range Reference Manual, (DS33023).

#### 4.2 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module, or as a postscaler for the Watchdog Timer, respectively (Figure 4-2). For simplicity, this counter is being referred to as "prescaler" throughout this data sheet. There is only one prescaler available which is shared between the Timer0 module and the Watchdog Timer. A prescaler assignment for the Timer0 module means that there is no prescaler for the Watchdog Timer, and vice-versa.

The prescaler is not readable or writable.

The PSA and PS2:PS0 bits (OPTION\_REG<3:0>) determine the prescaler assignment and prescale ratio.


Clearing bit PSA will assign the prescaler to the Timer0 module. When the prescaler is assigned to the Timer0 module, prescale values of 1:2, 1:4, ..., 1:256 are selectable.

Setting bit PSA will assign the prescaler to the Watchdog Timer (WDT). When the prescaler is assigned to the WDT, prescale values of 1:1, 1:2, ..., 1:128 are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g. CLRF 1, MOVWF 1, BSF 1,x....etc.) will clear the prescaler. When assigned to WDT, a CLRWDT instruction will clear the prescaler along with the WDT.

**Note:** Writing to TMR0 when the prescaler is assigned to Timer0 will clear the prescaler count, but will not change the prescaler assignment or ratio.

FIGURE 4-1: TIMERO BLOCK DIAGRAM



#### 4.2.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control, (i.e., it can be changed "on-the-fly" during program execution).

Note:

To avoid an unintended device RESET, a specific instruction sequence (shown in the PICmicro™ Mid-Range Reference Manual, DS33023) must be executed when changing the prescaler assignment from Timer0 to the WDT. This sequence must be followed even if the WDT is disabled.

#### 4.3 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h. This overflow sets bit T0IF (INTCON<2>). The interrupt can be masked by clearing bit T0IE (INTCON<5>). Bit T0IF must be cleared in software by the Timer0 module interrupt service routine before re-enabling this interrupt. The TMR0 interrupt cannot awaken the processor from SLEEP since the timer is shut off during SLEEP.

#### FIGURE 4-2: BLOCK DIAGRAM OF THE TIMERO/WDT PRESCALER




TABLE 4-1 REGISTERS ASSOCIATED WITH TIMER0

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other resets	
01h	TMR0	Timer0	module's r	egister						xxxx xxxx	uuuu uuuu	
0Bh,8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u	
81h	OPTION_REG	RBPU	RBPU INTEDG TOCS TOSE PSA PS2 PS1 PS0						1111 1111	1111 1111		
85h	TRISA	_	_	PORTA	PORTA Data Direction Register						11 1111	

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by Timer0.

#### 5.0 TIMER1 MODULE

The Timer1 module timer/counter has the following features:

- 16-bit timer/counter
- · Readable and writable
- · Internal or external clock select
- Interrupt on overflow from FFFFh to 0000h
- · Reset from CCP module trigger

Timer1 has a control register, shown in Register 5-1. Timer1 can be enabled/disabled by setting/clearing control bit TMR1ON (T1CON<0>).

Figure 5-1 is a simplified block diagram of the Timer1 module.

Additional information on timer modules is available in the  $PICmicro^{TM}$  Mid-Range Reference Manual, (DS33023).

#### 5.1 <u>Timer1 Operation</u>

Timer1 can operate in one of these modes:

- · As a timer
- · As a synchronous counter
- · As an asynchronous counter

The operating mode is determined by the clock select bit, TMR1CS (T1CON<1>).

In timer mode, Timer1 increments every instruction cycle. In counter mode, it increments on every rising edge of the external clock input.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored.

Timer1 also has an internal "reset input". This reset can be generated by the CCP module as a special event trigger (Section 7.0).

#### **REGISTER 5-1:T1CON: TIMER1 CONTROL REGISTER (ADDRESS 10h)**

U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
_	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	R = Readable bit
t7							bit0	W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR reset
oit 7-6:	Unimple	mented: R	lead as '0'					
oit 5-4:	11 = 1:8 10 = 1:4 01 = 1:2	1:T1CKPS Prescale v Prescale v Prescale v Prescale v	alue alue alue	Input Cloc	k Prescale	Select bits	S	
bit 3:	1 = Oscil 0 = Oscil	<b>N</b> : Timer1 lator is ena lator is shu illator is tur	abled (TRI at off	SC<1:0> iç	nored)			
bit 2:	TMR1CS 1 = Do no 0 = Sync TMR1CS	ot synchror hronize ext	nize exterr ternal cloc	nal clock in k input	put			
bit 1:	1 = Exter	: Timer1 C nal clock fi nal clock (F	rom pin R			n the rising	edge)	
bit 0:		I: Timer1 C les Timer1 s Timer1						

#### FIGURE 5-1: TIMER1 BLOCK DIAGRAM



#### 5.2 <u>Timer1 Oscillator</u>

A crystal oscillator circuit is built-in between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON<3>). When the Timer1 oscillator is enabled, RC0 and RC1 pins become T1OSO and T1OSI inputs, overriding TRISC<1:0>.

The oscillator is a low power oscillator rated up to 200 kHz. It will continue to run during SLEEP. It is primarily intended for a 32 kHz crystal. Table 5-1 shows the capacitor selection for the Timer1 oscillator.

The Timer1 oscillator is identical to the LP oscillator. The user must provide a software time delay to ensure proper oscillator start-up.

TABLE 5-1 CAPACITOR SELECTION FOR THE TIMER1 OSCILLATOR

Osc Type											
LP	32 kHz	33 pF	23 bF								
	100 kHz	√15 pF>									
	200 kHz	15 pF	√(15°pF								
These v	alues are for o	design guidan	ce only.								
Crystals Tested:											
32.768 kHz	32.768 kHz   Epson C-00(1R32.768K-A   ± 20 PPM										
100 kHz	Epson C2	00.00 KC-P	± 20 PPM								
200 kHz	STD XTL 20	0.000 kHz	± 20 PPM								
Note 1: Higher capacitance increases the stability of oscillator but also increases the start-up time.  2: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.											

#### 5.3 <u>Timer1 Interrupt</u>

The TMR1 Register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR1 Interrupt, if enabled, is generated on overflow and is latched in interrupt flag bit TMR1IF (PIR1<0>). This interrupt can be enabled by setting TMR1 interrupt enable bit TMR1IE (PIE1<0>).

## 5.4 Resetting Timer1 using a CCP Trigger Output

If the CCP module is configured in compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer1 and start an A/D conversion (if the A/D module is enabled).

Note:	The special event trigger from the CCP1
	module will not set interrupt flag bit
	TMR1IF (PIR1<0>).

Timer1 must be configured for either timer or synchronized counter mode to take advantage of this feature. If Timer1 is running in asynchronous counter mode, this reset operation may not work.

In the event that a write to Timer1 coincides with a special event trigger from CCP1, the write will take precedence

In this mode of operation, the CCPR1H:CCPR1L registers pair effectively becomes the period register for Timer1.

#### TABLE 5-2 REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
0Bh,8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	_	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
8Ch	PIE1	_	ADIE	_	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
0Eh	TMR1L	Holding	registe	r for the Lea	st Significar	t Byte of the	16-bit TMF	R1 register		xxxx xxxx	uuuu uuuu
0Fh	TMR1H	Holding	registe	ister for the Most Significant Byte of the 16-bit TMR1 register							uuuu uuuu
10h	T1CON	_	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	00 0000	uu uuuu

 $\textbf{Legend:} \quad \textbf{x} = \textbf{unknown}, \ \textbf{u} = \textbf{unchanged}, \ \textbf{-} = \textbf{unimplemented read as '0'}. \ \textbf{Shaded cells are not used by the Timer1 module}.$ 

# PIC16C62B/72A

**NOTES:** 

#### 6.0 TIMER2 MODULE

The Timer2 module timer has the following features:


- 8-bit timer (TMR2 register)
  - Readable and writable
- 8-bit period register (PR2)
  - Readable and writable
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- Interrupt on match (TMR2 = PR2)
- · Timer2 can be used by SSP and CCP

Timer2 has a control register, shown in Register 6-1. Timer2 can be shut off by clearing control bit TMR2ON (T2CON<2>) to minimize power consumption.

Figure 6-1 is a simplified block diagram of the Timer2 module.

Additional information on timer modules is available in the PICmicro<sup>™</sup> Mid-Range Reference Manual, (DS33023).

#### FIGURE 6-1: TIMER2 BLOCK DIAGRAM



by the SSP Module as a baud clock.

#### REGISTER 6-1:T2CON: TIMER2 CONTROL REGISTER (ADDRESS 12h)

U-0 — bit7	R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 TOUTPS3 TOUTPS2 TOUTPS1 TOUTPS0 TMR2ON T2CKPS1 T2CKPS0 bit0	R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR reset
bit 7:	Unimplemented: Read as '0'	
bit 6-3:	TOUTPS3:TOUTPS0: Timer2 Output Postscale Select bits  0000 = 1:1 Postscale  0001 = 1:2 Postscale  0010 = 1:3 Postscale  •  •  1111 = 1:16 Postscale	
bit 2:	TMR2ON: Timer2 On bit 1 = Timer2 is on 0 = Timer2 is off	
bit 1-0:	T2CKPS1:T2CKPS0: Timer2 Clock Prescale Select bits  00 = Prescaler is 1  01 = Prescaler is 4  1x = Prescaler is 16	

#### 6.1 <u>Timer2 Operation</u>

The Timer2 output is also used by the CCP module to generate the PWM "On-Time", and the PWM period with a match with PR2.

The TMR2 register is readable and writable, and is cleared on any device reset.

The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T2CKPS1:T2CKPS0 (T2CON<1:0>).

The match output of TMR2 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling) to generate a TMR2 interrupt (latched in flag bit TMR2IF, (PIR1<1>)).

The prescaler and postscaler counters are cleared when any of the following occurs:

- · a write to the TMR2 register
- a write to the T2CON register
- any device reset (Power-on Reset, MCLR reset, Watchdog Timer reset or Brown-out Reset)

TMR2 is not cleared when T2CON is written.

#### 6.2 Timer2 Interrupt

The Timer2 module has an 8-bit period register PR2. Timer2 increments from 00h until it matches PR2 and then resets to 00h on the next increment cycle. PR2 is a readable and writable register. The PR2 register is initialized to FFh upon reset.

#### 6.3 Output of TMR2

The output of TMR2 (before the postscaler) is fed to the Synchronous Serial Port module, which optionally uses it to generate shift clock.

#### TABLE 6-1 REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
0Bh,8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	1	-	SSPIF	CCP1IF	TMR2IF	TMR1IF	-00- 0000	0000 0000
8Ch	PIE1	_	ADIE	-	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	0000 0000
11h	TMR2	Timer2 mod	dule's registe	r						0000 0000	0000 0000
12h	T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	-000 0000
92h	PR2	Timer2 Peri	imer2 Period Register								1111 1111

 $\mbox{Legend:} \hspace{0.5cm} \mbox{$x = $ unknown, u = $ unchanged, $- = $ unimplemented read as '0'. Shaded cells are not used by the Timer2 module. }$ 

#### 7.0 CAPTURE/COMPARE/PWM (CCP) MODULE

The CCP (Capture/Compare/PWM) module contains a 16-bit register, which can operate as a 16-bit capture register, as a 16-bit compare register or as a PWM master/slave duty cycle register. Table 7-1 shows the timer resources of the CCP module modes.

Capture/Compare/PWM Register 1 (CCPR1) is comprised of two 8-bit registers: CCPR1L (low byte) and CCPR1H (high byte). The CCP1CON register controls the operation of CCP1. All are readable and writable.

Additional information on the CCP module is available in the PICmicro™ Mid-Range Reference Manual, (DS33023).

**TABLE 7-1 CCP MODE - TIMER** RESOURCE

CCP Mode	Timer Resource				
Capture	Timer1				
Compare	Timer1				
PWM	Timer2				

#### **TABLE 7-2** INTERACTION OF TWO CCP MODULES

CCPx Mode	<b>CCPy Mode</b>	Interaction				
Capture	Capture	Same TMR1 time-base.				
Capture	Compare	The compare should be configured for the special event trigger, which clears TMR1.				
Compare	Compare	The compare(s) should be configured for the special event trigger, which clears TMR1.				
PWM	PWM	The PWMs will have the same frequency and update rate (TMR2 interrupt).				
PWM	Capture	None.				
PWM	Compare	None.				

#### **REGISTER 7-1:CCP1CON REGISTER (ADDRESS 17h)**

U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
	1	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0	R = Readable bit
bit7							bit0	W = Writable bit U = Unimplemented bit, read as '0' - n = Value at POR reset

bit 7-6: Unimplemented: Read as '0'

bit 5-4: CCP1X:CCP1Y: PWM Least Significant bits

Capture Mode: Unused Compare Mode: Unused

PWM Mode: These bits are the two LSbs of the PWM duty cycle. The eight MSbs are found in CCPR1L.

bit 3-0: CCP1M3:CCP1M0: CCP1 Mode Select bits

0000 = Capture/Compare/PWM off (resets CCP1 module)

0100 = Capture mode, every falling edge 0101 = Capture mode, every rising edge 0110 = Capture mode, every 4th rising edge 0111 = Capture mode, every 16th rising edge

1000 = Compare mode, set output on match (CCP1IF bit is set)

1001 = Compare mode, clear output on match (CCP1IF bit is set)

1010 = Compare mode, generate software interrupt on match (CCP1IF bit is set, CCP1 pin is unaffected)

1011 = Compare mode, trigger special event (CCP1IF bit is set; CCP1 resets TMR1 and starts an A/D conversion (if A/D module is enabled))

11xx = PWM mode


#### 7.1 Capture Mode

In Capture mode, CCPR1H:CCPR1L captures the 16-bit value of the TMR1 register, when an event occurs on pin RC2/CCP1. An event is defined as:

- every falling edge
- · every rising edge
- · every 4th rising edge
- · every 16th rising edge

An event is selected by control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). When a capture is made, the interrupt request flag bit ,CCP1IF (PIR1<2>), is set. It must be cleared in software. If another capture occurs before the value in register CCPR1 is read, the old captured value will be lost.

# FIGURE 7-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



#### 7.1.1 CCP PIN CONFIGURATION

In Capture mode, the RC2/CCP1 pin should be configured as an input by setting the TRISC<2> bit.

**Note:** If the RC2/CCP1 is configured as an output, a write to the port can cause a capture condition.

#### 7.1.2 TIMER1 MODE SELECTION

Timer1 must be running in timer mode or synchronized counter mode for the CCP module to use the capture feature. In asynchronous counter mode, the capture operation may not work consistently.

#### 7.1.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should clear CCP1IE (PIE1<2>) before changing the capture mode to avoid false interrupts. Clear the interrupt flag bit, CCP1IE before setting CCP1IE.

#### 7.1.4 CCP PRESCALER

There are four prescaler settings, specified by bits CCP1M3:CCP1M0. Whenever the CCP module is turned off, or the CCP module is not in capture mode, the prescaler counter is cleared. This means that any reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared, therefore the first capture may be from a non-zero prescaler. Example 7-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

### EXAMPLE 7-1: CHANGING BETWEEN CAPTURE PRESCALERS

CLRF CCP1CON ;Turn CCP module off

MOVLW NEW\_CAPT\_PS ;Load the W reg with
; the new prescaler
; mode value and CCP ON

MOVWF CCP1CON ;Load CCP1CON with this
; value


#### 7.2 Compare Mode

In Compare mode, the 16-bit CCPR1 register value is constantly compared against the TMR1 register pair value. When a match occurs, the RC2/CCP1 pin is:

- · driven High
- · driven Low
- · remains Unchanged

The action on the pin is based on the value of control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). The interrupt flag bit, CCP1IF, is set on all compare matches.

# FIGURE 7-2: COMPARE MODE OPERATION BLOCK DIAGRAM



#### 7.2.1 CCP PIN CONFIGURATION

The user must configure the RC2/CCP1 pin as an output by clearing the TRISC<2> bit.

**Note:** Clearing the CCP1CON register will force the RC2/CCP1 compare output latch to the default low level. This is not the data latch.

#### 7.2.2 TIMER1 MODE SELECTION

Timer1 must be running in Timer mode or Synchronized Counter mode if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

#### 7.2.3 SOFTWARE INTERRUPT MODE

When a generated software interrupt is chosen, the CCP1 pin is not affected. Only a CCP interrupt is generated (if enabled).

#### 7.2.4 SPECIAL EVENT TRIGGER

In this mode, an internal hardware trigger is generated, which may be used to initiate an action.

The special event trigger output of CCP1 resets the TMR1 register pair. This allows the CCPR1 register to effectively be a 16-bit programmable period register for Timer1.

The special trigger output of CCP1 resets the TMR1 register pair and starts an A/D conversion (if the A/D module is enabled).

#### TABLE 7-3 REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, AND TIMER1

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
0Bh,8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	_	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
8Ch	PIE1	_	ADIE	_	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
87h	TRISC	PORTC Data Direction Register								1111 1111	1111 1111
0Eh	TMR1L	Holding register for the Least Significant Byte of the 16-bit TMR1 register									uuuu uuuu
0Fh	TMR1H	Holding register for the Most Significant Byte of the 16-bit TMR1register									uuuu uuuu
10h	T1CON	_	_	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	00 0000	uu uuuu
15h	CCPR1L	Capture/Compare/PWM register1 (LSB)								xxxx xxxx	uuuu uuuu
16h	CCPR1H	Capture/Compare/PWM register1 (MSB)								xxxx xxxx	uuuu uuuu
17h	CCP1CON	_	_	CCP1X	CCP1Y	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by Capture and Timer1.

#### 7.3 PWM Mode


In Pulse Width Modulation (PWM) mode, the CCP1 pin produces up to a 10-bit resolution PWM output. Since the CCP1 pin is multiplexed with the PORTC data latch, the TRISC<2> bit must be cleared to make the CCP1 pin an output.

Note: Clearing the CCP1CON register will force the CCP1 PWM output latch to the default low level. This is not the PORTC I/O data latch

Figure 7-3 shows a simplified block diagram of the CCP module in PWM mode.

For a step by step procedure on how to set up the CCP module for PWM operation, see Section 7.3.3.


### FIGURE 7-3: SIMPLIFIED PWM BLOCK DIAGRAM



Note 1: 8-bit timer is concatenated with 2-bit internal Q clock or 2 bits of the prescaler to create 10-bit time-base.

A PWM output (Figure 7-4) has a time base (period) and a time that the output stays high (on-time). The frequency of the PWM is the inverse of the period (1/period).

#### FIGURE 7-4: PWM OUTPUT



#### 7.3.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula:

PWM frequency is defined as 1 / [PWM period].

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

· TMR2 is cleared

Note:

- The CCP1 pin is set (exception: if PWM duty cycle = 0%, the CCP1 pin will not be set)
- The PWM duty cycle is latched from CCPR1L into CCPR1H

The Timer2 postscaler (see Section 6.0) is not used in the determination of the PWM frequency. The postscaler could be used to have a servo update rate at a different frequency than the PWM output.

#### 7.3.2 PWM ON-TIME

The PWM on-time is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available. CCPR1L contains eight MSbs and CCP1CON<5:4> contains two LSbs. This 10-bit value is represented by CCPR1L:CCP1CON<5:4>. The following equation is used to calculate the PWM duty cycle in time:

CCPR1L and CCP1CON<5:4> can be written to at any time, but the on-time value is not latched into CCPR1H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read-only register.

The CCPR1H register and a 2-bit internal latch are used to double buffer the PWM on-time. This double buffering is essential for glitchless PWM operation.

When the CCPR1H and 2-bit latch match TMR2 concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCP1 pin is cleared.

Maximum PWM resolution (bits) for a given PWM frequency:

Resolution = 
$$\frac{\log \left( \frac{Fosc}{Fpwm} \right)}{\log(2)}$$
 bits

**Note:** If the PWM on-time value is larger than the PWM period, the CCP1 pin will not be cleared.

For an example PWM period and on-time calculation, see the PICmicro $^{\text{TM}}$  Mid-Range Reference Manual, (DS33023).

#### 7.3.3 SET-UP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- Set the PWM period by writing to the PR2 register.
- Set the PWM on-time by writing to the CCPR1L register and CCP1CON<5:4> bits.
- Make the CCP1 pin an output by clearing the TRISC<2> bit.
- 4. Set the TMR2 prescale value and enable Timer2 by writing to T2CON.
- 5. Configure the CCP1 module for PWM operation.

#### TABLE 7-4 EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 20 MHz

PWM Frequency	1.22 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescaler (1, 4, 16)	16	4	1	1	1	1
PR2 Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	5.5

#### TABLE 7-5 REGISTERS ASSOCIATED WITH PWM AND TIMER2

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
0Bh,8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	_	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
8Ch	PIE1	_	ADIE	_	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
87h	TRISC	PORTC D	ata Direction	on Register						1111 1111	1111 1111
11h	TMR2	Timer2 mo	dule's regis	ter						0000 0000	0000 0000
92h	PR2	Timer2 mo	dule's perio	d register						1111 1111	1111 1111
12h	T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	-000 0000
15h	CCPR1L	Capture/C	Capture/Compare/PWM register1 (LSB)						xxxx xxxx	uuuu uuuu	
16h	CCPR1H	Capture/Compare/PWM register1 (MSB)						xxxx xxxx	uuuu uuuu		
17h	CCP1CON	_	—         ССР1X         ССР1Y         ССР1M3         ССР1M2         ССР1M1         ССР1M0							00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by PWM and Timer2.

© 1999 Microchip Technology Inc. Preliminary DS35008B-page 37

**NOTES:** 

# 8.0 SYNCHRONOUS SERIAL PORT (SSP) MODULE

#### 8.1 SSP Module Overview

The Synchronous Serial Port (SSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be Serial EEPROMs, shift registers, display drivers, A/D converters, etc. The SSP module can operate in one of two modes:

- Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I2C)

For more information on SSP operation (including an  $I^2C$  Overview), refer to the PICmicro<sup>TM</sup> Mid-Range Reference Manual, (DS33023). Also, refer to Application Note AN578, "Use of the SSP Module in the  $I^2C$  Multi-Master Environment."

#### 8.2 SPI Mode

This section contains register definitions and operational characteristics of the SPI module.

Additional information on SPI operation may be found in the PICmicro $^{TM}$  Mid-Range Reference Manual, (DS33023).

### 8.2.1 OPERATION OF SSP MODULE IN SPI MODE

A block diagram of the SSP Module in SPI Mode is shown in Figure 8-1.

The SPI mode allows 8-bits of data to be synchronously transmitted and received simultaneously. To accomplish communication, three pins are used:

- Serial Data Out (SDO)RC5/SDO
- Serial Data In (SDI)RC4/SDI/SDA
- Serial Clock (SCK)RC3/SCK/SCL

Additionally, a fourth pin may be used when in a slave mode of operation:

Slave Select (SS)RA5/SS/AN4

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits in the SSPCON register (SSPCON<5:0>) and SSPSTAT<7:6>. These control bits allow the following to be specified:

- · Master Operation (SCK is the clock output)
- Slave Mode (SCK is the clock input)
- Clock Polarity (Idle state of SCK)
- Clock Edge (Output data on rising/falling edge of SCK)
- Clock Rate (master operation only)
- · Slave Select Mode (Slave mode only)

To enable the serial port, SSP Enable bit, SSPEN (SSPCON<5>) must be set. To reset or reconfigure SPI mode, clear bit SSPEN, re-initialize the SSPCON reg-

ister, and then set bit SSPEN. This configures the SDI, SDO, SCK and  $\overline{SS}$  pins as serial port pins. For the pins to behave as the serial port function, they must have their data direction bits (in the TRISC register) appropriately programmed. That is:

SDI must have TRISC<4> set


Note:

- SDO must have TRISC<5> cleared
- SCK (master operation) must have TRISC<3> cleared
- SCK (Slave mode) must have TRISC<3> set
- SS must have TRISA<5> set (if used)

Note: When the SPI is in Slave Mode with SS pin control enabled, (SSPCON<3:0> = 0100) the SPI module will reset if the SS pin is set to VDD

If the SPI is used in Slave Mode with CKE = '1', then the  $\overline{SS}$  pin control must be

FIGURE 8-1: SSP BLOCK DIAGRAM (SPI MODE)



DS35008B-page 39

TABLE 8-1 REGISTERS ASSOCIATED WITH SPI OPERATION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
0Bh,8Bh	INTCON	GIE	PEIE	T0IE	INTE	RBIE	TOIF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	_	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
8Ch	PIE1	_	ADIE	_	_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
13h	SSPBUF	Synchronou	s Serial P	ort Receiv	e Buffer/	Transmit F	Register			xxxx xxxx	uuuu uuuu
14h	SSPCON	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	0000 0000
94h	SSPSTAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	0000 0000	0000 0000
85h	TRISA	_	_	PORTA Data Direction Register					11 1111	11 1111	
87h	TRISC	PORTC Data	TC Data Direction Register						1111 1111	1111 1111	

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used by the SSP in SPI mode.


#### 8.3 SSP I<sup>2</sup>C Operation

The SSP module in I<sup>2</sup>C mode fully implements all slave functions, except general call support, and provides interrupts on start and stop bits in hardware to support firmware implementations of the master functions. The SSP module implements the standard mode specifications, as well as 7-bit and 10-bit addressing.

Two pins are used for data transfer. These are the RC3/SCK/SCL pin, which is the clock (SCL), and the RC4/SDI/SDA pin, which is the data (SDA). The user must configure these pins as inputs or outputs through the TRISC<4:3> bits.

The SSP module functions are enabled by setting SSP Enable bit SSPEN (SSPCON<5>).

FIGURE 8-2: SSP BLOCK DIAGRAM (I<sup>2</sup>C MODE)



The SSP module has five registers for I<sup>2</sup>C operation. These are the:

- SSP Control Register (SSPCON)
- SSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- SSP Shift Register (SSPSR) Not accessible
- SSP Address Register (SSPADD)

The SSPCON register allows control of the I<sup>2</sup>C operation. Four mode selection bits (SSPCON<3:0>) allow one of the following I<sup>2</sup>C modes to be selected:

- I<sup>2</sup>C Slave mode (7-bit address)
- I<sup>2</sup>C Slave mode (10-bit address)
- I<sup>2</sup>C Slave mode (7-bit address), with start and stop bit interrupts enabled for firmware master mode support
- I<sup>2</sup>C Slave mode (10-bit address), with start and stop bit interrupts enabled for firmware master mode support
- I<sup>2</sup>C start and stop bit interrupts enabled for firmware master mode support, slave mode idle

Selection of any I<sup>2</sup>C mode, with the SSPEN bit set, forces the SCL and SDA pins to be operated as open drain outputs, provided these pins are programmed to inputs by setting the appropriate TRISC bits.

Additional information on SSP I<sup>2</sup>C operation may be found in the PICmicro<sup>™</sup> Mid-Range Reference Manual, (DS33023).

#### 8.3.1 SLAVE MODE

In slave mode, the SCL and SDA pins must be configured as inputs (TRISC<4:3> set). The SSP module will override the input state with the output data when required (slave-transmitter).

When an address is matched or the data transfer after an address match is received, the hardware automatically will generate the acknowledge (ACK) pulse, and load the SSPBUF register with the received value in the SSPSR register.

There are certain conditions that will cause the SSP module not to give this  $\overline{ACK}$  pulse. This happens if either of the following conditions occur:

- a) The buffer full bit BF (SSPSTAT<0>) was set before the transfer was completed.
- b) The overflow bit SSPOV (SSPCON<6>) was set before the transfer was completed.

In this case, the SSPSR register value is not loaded into the SSPBUF, but bit SSPIF (PIR1<3>) is set. Table 8-2 shows what happens when a data transfer byte is received, given the status of bits BF and SSPOV. The shaded cells show the condition where user software did not properly clear the overflow condition. Flag bit BF is cleared by reading the SSPBUF register, while bit SSPOV is cleared through software.

The SCL clock input must have a minimum high and low for proper operation. The high and low times of the I<sup>2</sup>C specification, as well as the requirement of the SSP module, is shown in timing parameter #100, THIGH, and parameter #101, TLOW.

#### 8.3.1.1 ADDRESSING

Once the SSP module has been enabled, it waits for a START condition to occur. Following the START condition, 8 bits are shifted into the SSPSR register. All incoming bits are sampled with the rising edge of the clock (SCL) line. The value of register SSPSR<7:1> is compared to the value of the SSPADD register. The address is compared on the falling edge of the eighth clock (SCL) pulse. If the addresses match and the BF and SSPOV bits are clear, the following events occur:

- The SSPSR register value is loaded into the SSPBUF register.
- b) The buffer full bit, BF is set.
- c) An ACK pulse is generated.
- d) SSP interrupt flag bit, SSPIF (PIR1<3>), is set (interrupt is generated if enabled) on the falling edge of the ninth SCL pulse.

In 10-bit address mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit  $R/\overline{W}$  (SSPSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal

 $^{\prime}1111~0~A9~A8~0^{\prime},$  where A9 and A8 are the two MSbs of the address. The sequence of events for 10-bit address is as follows, with steps 7- 9 for slave-transmitter:

- Receive first (high) byte of Address (bits SSPIF, BF, and bit UA (SSPSTAT<1>) are set).
- Update the SSPADD register with second (low) byte of Address (clears bit UA and releases the SCL line).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- Receive second (low) byte of Address (bits SSPIF, BF, and UA are set).
- Update the SSPADD register with the first (high) byte of Address, if match releases SCL line, this will clear bit UA.
- 6. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 7. Receive repeated START condition.
- Receive first (high) byte of Address (bits SSPIF and BF are set).
- Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.

TABLE 8-2 DATA TRANSFER RECEIVED BYTE ACTIONS

	ts as Data s Received			Set bit SSPIF
BF	SSPOV	$SSPSR \to SSPBUF$	Generate ACK Pulse	(SSP Interrupt occurs if enabled)
0	0	Yes	Yes	Yes
1	0	No	No	Yes
1	1	No	No	Yes
0	1	Yes	No	Yes

Note: Shaded cells show the conditions where the user software did not properly clear the overflow condition.


#### 8.3.1.2 RECEPTION

When the  $R/\overline{W}$  bit of the address byte is clear and an address match occurs, the  $R/\overline{W}$  bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register.

When the address byte overflow condition exists, then no acknowledge (ACK) pulse is given. An overflow condition is defined as either bit BF (SSPSTAT<0>) is set or bit SSPOV (SSPCON<6>) is set.

An SSP interrupt is generated for each data transfer byte. Flag bit SSPIF (PIR1<3>) must be cleared in software. The SSPSTAT register is used to determine the status of the byte.

FIGURE 8-3: I<sup>2</sup>C WAVEFORMS FOR RECEPTION (7-BIT ADDRESS)



© 1999 Microchip Technology Inc. Preliminary DS35008B-page 43

#### 8.3.1.3 TRANSMISSION


When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register. The ACK pulse will be sent on the ninth bit and the CKP will be cleared by hardware, holding SCL low. Slave devices cause the master to wait by holding the SCL line low. The transmit data is loaded into the SSPBUF register, which in turn loads the SSPSR register. When bit CKP (SSP-CON<4>) is set, pin RC3/SCK/SCL releases SCL. When the SCL line goes high, the master may resume operating the SCL line and receiving data. The master must monitor the SCL pin prior to asserting another clock pulse. The slave devices may be holding off the master by stretching the clock. The eight data bits are

shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time (Figure 8-4).

An SSP interrupt is generated for each data transfer byte. Flag bit SSPIF must be cleared in software, and the SSPSTAT register used to determine the status of the byte. Flag bit SSPIF is set on the falling edge of the ninth clock pulse.

As a slave-transmitter, the  $\overline{ACK}$  pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. If the SDA line was high (not  $\overline{ACK}$ ), then the data transfer is complete. When the  $\overline{ACK}$  is latched by the slave, the slave logic is reset (resets SSPSTAT register) and the slave then monitors for another occurrence of the START bit. If the SDA line was low ( $\overline{ACK}$ ), the transmit data must be loaded into the SSPBUF register, which also loads the SSPSR register. Then pin RC3/SCK/SCL should be enabled by setting bit CKP.

FIGURE 8-4: I<sup>2</sup>C WAVEFORMS FOR TRANSMISSION (7-BIT ADDRESS)



#### 8.3.2 MASTER OPERATION

Master operation is supported in firmware using interrupt generation on the detection of the START and STOP conditions. The STOP (P) and START (S) bits are cleared by a reset or when the SSP module is disabled. The STOP (P) and START (S) bits will toggle based on the START and STOP conditions. Control of the  $\rm I^2C$  bus may be taken when the P bit is set, or the bus is idle and both the S and P bits are clear.

In master operation, the SCL and SDA lines are manipulated in software by clearing the corresponding TRISC<4:3> bit(s). The output level is always low, irrespective of the value(s) in PORTC<4:3>. So when transmitting data, a '1' data bit must have the TRISC<4> bit set (input) and a '0' data bit must have the TRISC<4> bit cleared (output). The same scenario is true for the SCL line with the TRISC<3> bit.

The following events will cause SSP Interrupt Flag bit, SSPIF, to be set (SSP Interrupt if enabled):

- · START condition
- · STOP condition
- · Byte transfer completed

Master operation can be done with either the slave mode idle (SSPM3:SSPM0 = 1011) or with the slave active. When both master operation and slave modes are used, the software needs to differentiate the source(s) of the interrupt.

For more information on master operation, see *AN554* - *Software Implementation of I*<sup>2</sup>*C Bus Master.* 

#### 8.3.3 MULTI-MASTER OPERATION

In multi-master operation, the interrupt generation on the detection of the START and STOP conditions allows the determination of when the bus is free. The STOP (P) and START (S) bits are cleared from a reset or when the SSP module is disabled. The STOP (P) and START (S) bits will toggle based on the START and STOP conditions. Control of the I<sup>2</sup>C bus may be taken when bit P (SSPSTAT<4>) is set, or the bus is idle and both the S and P bits clear. When the bus is busy, enabling the SSP Interrupt will generate the interrupt when the STOP condition occurs.

In multi-master operation, the SDA line must be monitored to see if the signal level is the expected output level. This check only needs to be done when a high level is output. If a high level is expected and a low level is present, the device needs to release the SDA and SCL lines (set TRISC<4:3>). There are two stages where this arbitration can be lost, these are:

- Address Transfer
- Data Transfer

When the slave logic is enabled, the slave continues to receive. If arbitration was lost during the address transfer stage, communication to the device may be in progress. If addressed, an  $\overline{ACK}$  pulse will be generated. If arbitration was lost during the data transfer stage, the device will need to re-transfer the data at a later time.

For more information on master operation, see AN578 - Use of the SSP Module in the of  $I^2C$  Multi-Master Environment.

TABLE 8-3 REGISTERS ASSOCIATED WITH I<sup>2</sup>C OPERATION

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other resets
0Bh, 8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	T0IF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	_	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
8Ch	PIE1	_	ADIE		_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
13h	SSPBUF	Synchronou	ıs Serial F	ort Recei	ve Buffer	/Transmit	Register			xxxx xxxx	uuuu uuuu
93h	SSPADD	Synchronou	ıs Serial F	Port (I <sup>2</sup> C n	node) Add	dress Reg	gister			0000 0000	0000 0000
14h	SSPCON	WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	0000 0000
94h	SSPSTAT	SMP <sup>(1)</sup>	CKE <sup>(1)</sup>	D/Ā	Р	S	R/W	UA	BF	0000 0000	0000 0000
87h	TRISC	PORTC Data Direction register								1111 1111	1111 1111

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by SSP module in SPI mode.

**Note 1:** Maintain these bits clear in I<sup>2</sup>C mode.

#### REGISTER 8-1: SSPSTAT: SYNC SERIAL PORT STATUS REGISTER (ADDRESS 94h)

R/W-0	R/W-0	R-0	R-0	R-0	R-0	R-0	R-0
SMP	CKE	D/Ā	Р	S	R/W	UA	BF

bit0

R = Readable bit

W = Writable bit

U = Unimplemented bit, read as '0'

- n =Value at POR reset

bit 7: SMP: SPI data input sample phase

#### **SPI Master Operation**

- 1 = Input data sampled at end of data output time
- 0 = Input data sampled at middle of data output time

SPI Slave Mode

SMP must be cleared when SPI is used in slave mode

I<sup>2</sup>C Mode

bit7

This bit must be maintained clear

bit 6: CKE: SPI Clock Edge Select

SPI Mode

CKP = 0

- 1 = Data transmitted on rising edge of SCK
- 0 = Data transmitted on falling edge of SCK

#### CKP = 1

- 1 = Data transmitted on falling edge of SCK
- 0 = Data transmitted on rising edge of SCK

#### <u>I<sup>2</sup>C Mode</u>

This bit must be maintained clear

- bit 5: **D/A**: Data/Address bit (I<sup>2</sup>C mode only)
  - 1 = Indicates that the last byte received or transmitted was data
  - 0 = Indicates that the last byte received or transmitted was address
- bit 4: **P**: Stop bit (I<sup>2</sup>C mode only. This bit is cleared when the SSP module is disabled, or when the Start bit is detected last, SSPEN is cleared)
  - 1 = Indicates that a stop bit has been detected last (this bit is '0' on RESET)
  - 0 = Stop bit was not detected last
- bit 3: **S**: Start bit (I<sup>2</sup>C mode only. This bit is cleared when the SSP module is disabled, or when the Stop bit is detected last, SSPEN is cleared)
  - 1 = Indicates that a start bit has been detected last (this bit is '0' on RESET)
  - 0 = Start bit was not detected last
- bit 2:  $R/\overline{W}$ : Read/Write bit information (I<sup>2</sup>C mode only)

This bit holds the R/W bit information following the last address match. This bit is only valid from the address match to the next start bit, stop bit, or  $\overline{ACK}$  bit.

- 1 = Read
- 0 = Write
- bit 1: **UA**: Update Address (10-bit I<sup>2</sup>C mode only)
  - 1 = Indicates that the user needs to update the address in the SSPADD register
  - 0 = Address does not need to be updated
- bit 0: BF: Buffer Full Status bit

Receive (SPI and I<sup>2</sup>C modes)

- 1 = Receive complete, SSPBUF is full
- 0 = Receive not complete, SSPBUF is empty

Transmit (I<sup>2</sup>C mode only)

- 1 = Transmit in progress, SSPBUF is full
- 0 = Transmit complete, SSPBUF is empty

#### REGISTER 8-2: SSPCON: SYNC SERIAL PORT CONTROL REGISTER (ADDRESS 14h)

R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 WCOL SSPOV **SSPEN CKP** SSPM3 SSPM2 SSPM1 SSPM0 R = Readable bit W = Writable bit bit7 bit0 U = Unimplemented bit, read as '0' - n =Value at POR reset

bit 7: WCOL: Write Collision Detect bit

1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)

0 = No collision

bit 6: SSPOV: Receive Overflow Indicator bit

#### In SPI mode

1 = A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in slave mode. The user must read the SSPBUF, even if only transmitting data, to avoid setting overflow. In master operation, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

0 = No overflow

#### In I<sup>2</sup>C mode

1 = A byte is received while the SSPBUF register is still holding the previous byte. SSPOV is a "don't care" in transmit mode. SSPOV must be cleared in software in either mode.

0 = No overflow

bit 5: SSPEN: Synchronous Serial Port Enable bit

#### In SPI mode

- 1 = Enables serial port and configures SCK, SDO, and SDI as serial port pins
- 0 = Disables serial port and configures these pins as I/O port pins

#### In I<sup>2</sup>C mode

- 1 = Enables the serial port and configures the SDA and SCL pins as serial port pins
- 0 = Disables serial port and configures these pins as I/O port pins

In both modes, when enabled, these pins must be properly configured as input or output.

bit 4: CKP: Clock Polarity Select bit

#### In SPI mode

- 1 = Idle state for clock is a high level
- 0 = Idle state for clock is a low level

#### In I<sup>2</sup>C mode

SCK release control

- 1 = Enable clock
- 0 = Holds clock low (clock stretch)
- bit 3-0: SSPM3:SSPM0: Synchronous Serial Port Mode Select bits
  - 0000 = SPI master operation, clock = Fosc/4
  - 0001 = SPI master operation, clock = Fosc/16
  - 0010 = SPI master operation, clock = Fosc/64
  - 0011 = SPI master operation, clock = TMR2 output/2
  - 0100 = SPI slave mode, clock = SCK pin.  $\overline{SS}$  pin control enabled.
  - 0101 = SPI slave mode, clock = SCK pin. SS pin control disabled. SS can be used as I/O pin
  - $0110 = I^2C$  slave mode, 7-bit address
  - $0111 = I^2C$  slave mode, 10-bit address
  - $1011 = I^2C$  firmware controlled master operation (slave idle)
  - $1110 = I^2C$  slave mode, 7-bit address with start and stop bit interrupts enabled
  - $1111 = I^2C$  slave mode, 10-bit address with start and stop bit interrupts enabled

**NOTES:** 

# 9.0 ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

**Note:** This section applies to the PIC16C72A only.

The analog-to-digital (A/D) converter module has five input channels.

The A/D allows conversion of an analog input signal to a corresponding 8-bit digital number (refer to Application Note AN546 for use of A/D Converter). The output of the sample and hold is the input into the converter, which generates the result via successive approximation. The analog reference voltage is software selectable to either the device's positive supply voltage (VDD) or the voltage level on the RA3/AN3/VREF pin.

The A/D converter has the feature of being able to operate while the device is in SLEEP mode. To operate in sleep, the A/D conversion clock must be derived from the A/D's internal RC oscillator.

Additional information on the A/D module is available in the  $PICmicro^{TM}$  Mid-Range Reference Manual, (DS33023).

The A/D module has three registers. These registers are:

- A/D Result Register (ADRES)
- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)

A device reset forces all registers to their reset state. This forces the A/D module to be turned off, and any conversion is aborted.

The ADCON0 register, shown in Figure 9-1, controls the operation of the A/D module. The ADCON1 register, shown in Figure 9-2, configures the functions of the port pins. The port pins can be configured as analog inputs (RA3 can also be a voltage reference) or as digital I/O.

#### **REGISTER 9-1:ADCONO REGISTER (ADDRESS 1Fh)**

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0
ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON
hit7							bit0

R = Readable bit

W = Writable bit

U = Unimplemented bit, read as '0'

- n = Value at POR reset

bit 7-6: ADCS1:ADCS0: A/D Conversion Clock Select bits

00 = Fosc/2

01 = Fosc/8

10 = Fosc/32

11 = FRC (clock derived from an internal RC oscillator)

bit 5-3: CHS2:CHS0: Analog Channel Select bits

000 = channel 0, (RA0/AN0)

001 = channel 1, (RA1/AN1)

010 = channel 2, (RA2/AN2)

011 = channel 3, (RA3/AN3)

100 = channel 4, (RA5/AN4)

bit 2: GO/DONE: A/D Conversion Status bit

#### If ADON = 1

- 1 = A/D conversion in progress (setting this bit starts the A/D conversion)
- 0 = A/D conversion not in progress (This bit is automatically cleared by hardware when the A/D conversion is complete)

bit 1: Unimplemented: Read as '0'

bit 0: ADON: A/D On bit

1 = A/D converter module is operating

0 = A/D converter module is shutoff and consumes no operating current

#### **REGISTER 9-2:ADCON1 REGISTER (ADDRESS 9Fh)**

U-0 U-0 U-0 U-0 U-0 R/W-0 R/W-0 R/W-0

— — — — — PCFG2 PCFG1 PCFG0

bit0

R = Readable bit

W = Writable bit

U = Unimplemented bit, read as '0'

- n = Value at POR reset

bit 7-3: Unimplemented: Read as '0'

bit7

bit 2-0: PCFG2:PCFG0: A/D Port Configuration Control bits

PCFG2:PCFG0	RA0	RA1	RA2	RA5	RA3	VREF
000	Α	Α	Α	Α	Α	VDD
001	Α	Α	Α	Α	VREF	RA3
010	Α	Α	Α	Α	Α	Vdd
011	Α	Α	Α	Α	VREF	RA3
100	Α	Α	D	D	Α	VDD
101	Α	Α	D	D	VREF	RA3
11x	D	D	D	D	D	Vdd

A = Analog input

D = Digital I/O


When the A/D conversion is complete, the result is loaded into the ADRES register, the GO/DONE bit, ADCON0<2>, is cleared, and the A/D interrupt flag bit, ADIF, is set. The block diagram of the A/D module is shown in Figure 9-1.

The value that is in the ADRES register is not modified for a Power-on Reset. The ADRES register will contain unknown data after a Power-on Reset.

After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see Section 9.1. After this acquisition time has elapsed, the A/D conversion can be started. The following steps should be followed for doing an A/D conversion:

- 1. Configure the A/D module:
  - Configure analog pins / voltage reference / and digital I/O (ADCON1)
  - Select A/D input channel (ADCON0)
  - Select A/D conversion clock (ADCON0)
  - Turn on A/D module (ADCON0)
- 2. Configure A/D interrupt (if desired):
  - · Clear ADIF bit
  - · Set ADIE bit
  - · Set GIE bit
- 3. Wait the required acquisition time.
- 4. Start conversion:
  - Set GO/DONE bit (ADCON0)
- 5. Wait for A/D conversion to complete, by either:
  - Polling for the GO/DONE bit to be cleared OR
  - · Waiting for the A/D interrupt
- Read A/D Result register (ADRES), clear bit ADIF if required.
- For next conversion, go to step 1 or step 2 as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2TAD is required before next acquisition starts.

FIGURE 9-1: A/D BLOCK DIAGRAM



© 1999 Microchip Technology Inc. Preliminary DS35008B-page 51

#### 9.1 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (Chold) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 9-2. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor Chold. The sampling switch (Rss) impedance varies over the device voltage (Vdd). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is 10  $\mathbf{k}\Omega$ . After the analog input channel is selected (changed), this acquisition must pass before the conversion can be started.

To calculate the minimum acquisition time, TACQ, see Equation 9-1. This equation calculates the acquisition time to within 1/2 LSb error (512 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified accuracy.

**Note:** When the conversion is started, the holding capacitor is disconnected from the input pin.

In general;

Assuming Rs =  $10k\Omega$ 


 $Vdd = 3.0V (Rss = 10k\Omega)$ 

Temp. =  $50^{\circ}$ C (122°F)

TACQ  $\approx$  13.0  $\mu$ Sec

By increasing VDD and reducing Rs and Temp., TACQ can be substantially reduced.

#### FIGURE 9-2: ANALOG INPUT MODEL



#### **EQUATION 9-1: ACQUISITION TIME**

TACQ = Amplifier Settling Time +

Hold Capacitor Charging Time +

Temperature Coefficient

= TAMP + TC + TCOFF

TAMP =  $5\mu$ S

 $Tc = -(51.2pF)(1k\Omega + Rss + Rs) In(1/511)$ 

TCOFF =  $(Temp - 25^{\circ}C)(0.05\mu S/^{\circ}C)$ 

#### 9.2 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 9.5TAD per 8-bit conversion. The source of the A/D conversion clock is software selectable. The four possible options for TAD are:

- 2Tosc
- 8Tosc
- 32Tosc
- Internal RC oscillator

For correct A/D conversions, the A/D conversion clock (TAD) must be selected to ensure a minimum TAD time of 1.6  $\mu$ s.

The A/D module can operate during sleep mode, but the RC oscillator must be selected as the A/D clock source prior to the SLEEP instruction.

Table 9-1 shows the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

#### 9.3 Configuring Analog Port Pins

The ADCON1 and TRISA registers control the operation of the A/D port pins. The port pins that are desired as analog inputs must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS2:CHS0 bits and the TRIS bits.

- Note 1: When reading the port register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as digital inputs, will convert an analog input. Analog levels on a digitally configured input will not affect the conversion accuracy.
- Note 2: Analog levels on any pin that is defined as a digital input (including the AN4:AN0 pins) may cause the input buffer to consume current that is out of the devices specification.

TABLE 9-1 TAD vs. DEVICE OPERATING FREQUENCIES

AD Cloc	k Source (TAD)	Device Frequency						
Operation	ADCS1:ADCS0	20 MHz	5 MHz	1.25 MHz	333.33 kHz			
2Tosc	00	100 ns <sup>(2)</sup>	400 ns <sup>(2)</sup>	1.6 µs	6 μs			
8Tosc	01	400 ns <sup>(2)</sup>	1.6 μs	6.4 μs	24 μs <sup>(3)</sup>			
32Tosc	10	1.6 μs	6.4 μs	25.6 μs <sup>(3)</sup>	96 μs <sup>(3)</sup>			
RC <sup>(5)</sup>	11	2 - 6 μs <sup>(1,4)</sup>	2 - 6 μs <sup>(1,4)</sup>	2 - 6 μs <sup>(1,4)</sup>	2 - 6 μs <sup>(1)</sup>			

Legend: Shaded cells are outside of recommended range.

- **Note 1:** The RC source has a typical TAD time of 4  $\mu$ s.
  - 2: These values violate the minimum required TAD time.
  - 3: For faster conversion times, the selection of another clock source is recommended.
  - **4:** When device frequency is greater than 1 MHz, the RC A/D conversion clock source is recommended for sleep operation only.
  - 5: For extended voltage devices (LC), please refer to Electrical Specifications section.

© 1999 Microchip Technology Inc. Preliminary DS35008B-page 53

#### 9.4 A/D Conversions

**Note:** The GO/DONE bit should **NOT** be set in the same instruction that turns on the A/D.

#### 9.5 Use of the CCP Trigger

An A/D conversion can be started by the "special event trigger" of the CCP1 module. This requires that the CCP1M3:CCP1M0 bits (CCP1CON<3:0>) be programmed as 1011 and that the A/D module be enabled (ADON bit is set). When the trigger occurs, the

GO/DONE bit will be set, starting the A/D conversion, and the Timer1 counter will be reset to zero. Timer1 is reset to automatically repeat the A/D acquisition period with minimal software overhead. The appropriate analog input channel must be selected and the minimum acquisition time must pass before the "special event trigger" sets the GO/DONE bit (starts a conversion).

If the A/D module is not enabled (ADON is cleared), then the "special event trigger" will be ignored by the A/D module, but will still reset the Timer1 counter.

TABLE 9-2 SUMMARY OF A/D REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
0Bh,8Bh	INTCON	GIE	PEIE	TOIE	INTE	RBIE	T0IF	INTF	RBIF	0000 000x	0000 000u
0Ch	PIR1	_	ADIF	-	_	SSPIF	CCP1IF	TMR2IF	TMR1IF	-0 0000	-0 0000
8Ch	PIE1	_	ADIE		_	SSPIE	CCP1IE	TMR2IE	TMR1IE	-0 0000	-0 0000
1Eh	ADRES	A/D Res	ult Regist	er						xxxx xxxx	uuuu uuuu
1Fh	ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000 00-0	0000 00-0
9Fh	ADCON1	_	_		_	_	PCFG2	PCFG1	PCFG0	000	000
05h	PORTA	_		RA5	RA4	RA3	RA2	RA1	RA0	0x 0000	0u 0000
85h	TRISA	_	_	PORTA I	Data Direct	tion Regis	ter	•	•	11 1111	11 1111

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used for A/D conversion.

# 10.0 SPECIAL FEATURES OF THE CPU

The PIC16C62B/72A devices have a host of features intended to maximize system reliability, minimize cost through elimination of external components, provide power saving operating modes and offer code protection. These are:

- Oscillator Mode Selection
- Reset
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Brown-out Reset (BOR)
- · Interrupts
- · Watchdog Timer (WDT)
- SLEEP
- Code protection
- · ID locations
- In-circuit serial programming<sup>™</sup> (ICSP)

These devices have a Watchdog Timer, which can be shut off only through configuration bits. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in reset until the crystal oscillator is stable. The

other is the Power-up Timer (PWRT), which provides a fixed delay on power-up only and is designed to keep the part in reset while the power supply stabilizes. With these two timers on-chip, most applications need no external reset circuitry.

SLEEP mode is designed to offer a very low current power-down mode. The user can wake-up from SLEEP through external reset, Watchdog Timer Wake-up, or through an interrupt. Several oscillator options are also made available to allow the part to fit the application. The RC oscillator option saves system cost while the LP crystal option saves power. A set of configuration bits are used to select various options.

Additional information on special features is available in the PICmicro<sup>™</sup> Mid-Range Reference Manual, (DS33023).

#### 10.1 Configuration Bits

The configuration bits can be programmed (read as '0') or left unprogrammed (read as '1') to select various device configurations. These bits are mapped in program memory location 2007h.

The user will note that address 2007h is beyond the user program memory space. In fact, it belongs to the special test/configuration memory space (2000h - 3FFFh), which can be accessed only during programming.

#### FIGURE 10-1: CONFIGURATION WORD

CP1 **PWRTE** CP1 CP0 CP1 CP0 CP1 CP0 BODEN CP0 WDTE FOSC1 FOSC0 Register: **CONFIG** Address: 2007h bit13 bit0 bit 13-8 CP1:CP0: Code Protection bits (2) 5-4: 11 = Code protection off 10 = Upper half of program memory code protected 01 = Upper 3/4th of program memory code protected 00 = All memory is code protected Unimplemented: Read as '1' bit 7: BODEN: Brown-out Reset Enable bit (1) bit 6: 1 = BOR enabled 0 = BOR disabled PWRTE: Power-up Timer Enable bit (1) bit 3: 1 = PWRT disabled 0 = PWRT enabled bit 2: WDTE: Watchdog Timer Enable bit 1 = WDT enabled 0 = WDT disabled bit 1-0: FOSC1:FOSC0: Oscillator Selection bits 11 = RC oscillator 10 = HS oscillator 01 = XT oscillator 00 = LP oscillator Note 1: Enabling Brown-out Reset automatically enables Power-up Timer (PWRT), regardless of the value of bit PWRTE. All of the CP1:CP0 pairs must be given the same value to enable the code protection scheme listed.

#### 10.2 Oscillator Configurations

#### 10.2.1 OSCILLATOR TYPES

The PIC16CXXX can be operated in four different oscillator modes. The user can program two configuration bits (FOSC1 and FOSC0) to select one of these four modes:

LP Low Power CrystalXT Crystal/Resonator


HS High Speed Crystal/Resonator

RC Resistor/Capacitor

## 10.2.2 CRYSTAL OSCILLATOR/CERAMIC RESONATORS

In XT, LP or HS modes, a crystal or ceramic resonator is connected to the OSC1/CLKIN and OSC2/CLKOUT pins to establish oscillation (Figure 10-2). The PIC16CXXX oscillator design requires the use of a parallel cut crystal. Use of a series cut crystal may give a frequency out of the crystal manufacturers specifications. When in XT, LP or HS modes, the device can use an external clock source to drive the OSC1/CLKIN pin (Figure 10-3).

FIGURE 10-2: CRYSTAL/CERAMIC
RESONATOR OPERATION
(HS, XT OR LP
OSC CONFIGURATION)



**Note1:** See Table 10-1 and Table 10-2 for recommended values of C1 and C2.

- A series resistor (RS) may be required for AT strip cut crystals.
- 3: RF varies with the crystal chosen.

FIGURE 10-3: EXTERNAL CLOCK INPUT OPERATION (HS, XT OR LP OSC CONFIGURATION)




TABLE 10-1 CERAMIC RESONATORS

Ranges Te	Ranges Tested:								
Mode	Freq	OSC1	O\$C2						
XT	455 kHz	68 - 100 pF	68 - 100 pF						
	2.0 MHz	15 - 68 pF 🤇	15 - 68 pF						
	4.0 MHz	15 - 68 pF	15 - 68 pF						
HS	8.0 MHz	10 - 68/pF\>	े10 - 68 pF						
16.0 MHz 10 - 22 pF 10 - 22 pF									
The	se values are f	ior design guidar	nce only. See						
note	es at bottom of	page.							
Resonator	rs Used: 🚫								
455 kHz	Panasonie E	FO-A455K04B	± 0.3%						
2.0 MHz	Murata Erie (	CSA2.00MG	± 0.5%						
4.0 MHz Mucata Erie CSA4.00MG ± 0.5%									
8.0 MHz Murata Erie CSA8.00MT ± 0.5%									
16.8 MHz Murata Erie CSA16.00MX ± 0.5%									
Resona	ators did not hav	ve built-in capacito	ors.						

TABLE 10-2 CAPACITOR SELECTION FOR CRYSTAL OSCILLATOR


Osc Type	Crystal Freq	Cap. Range C1	Cap. Range C2
LP	32 kHz	33 pF	33 pF
	200 kHz	15 pF	15/AF
XT	200 kHz	47-68 pF	47-68 bF
	1 MHz	15 pF <	√ 15 pF
	4 MHz	15 pF	15 pF
HS	4 MHz	15 pt	15 pF
	8 MHz	15-33 p€>	15-33 pF
	20 MHz	(15-33 pF	15-33 pF
	values are	for design guidar page.	nce only. See
	Crys	tals Used	
32 kHz	Epson C-00	01R32.768K-A	± 20 PPM
200 kHz	STO XTL 2	00.000KHz	± 20 PPM
1 MHz	ECS ECS-	± 50 PPM	
4 MHz	ECS ECS-4	± 50 PPM	
8 MHz	EPSON CA	± 30 PPM	
20 MHz	EPSON CA	A-301 20.000M-C	± 30 PPM

- **Note 1:** Higher capacitance increases the stability of the oscillator, but also increases the start-up time.
  - Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
  - **3:** Rs may be required in HS mode, as well as XT mode, to avoid overdriving crystals with low drive level specification.
  - 4: Oscillator performance should be verified when migrating between devices (including PIC16C62A to PIC16C62B and PIC16C72 to PIC16C72A)

#### 10.2.3 RC OSCILLATOR

For timing insensitive applications, the "RC" device option offers additional cost savings. The RC oscillator frequency is a function of the supply voltage, the resistor (REXT) and capacitor (CEXT) values, and the operating temperature. In addition to this, the oscillator frequency will vary from unit to unit due to normal process parameter variation. Furthermore, the difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to take into account variation due to tolerance of external R and C components used. Figure 10-4 shows how the R/C combination is connected to the PIC16CXXX.

#### FIGURE 10-4: RC OSCILLATOR MODE



#### 10.3 Reset

The PIC16CXXX differentiates between various kinds of reset:

- Power-on Reset (POR)
- MCLR reset during normal operation
- MCLR reset during SLEEP
- WDT Reset (during normal operation)
- WDT Wake-up (during SLEEP)
- Brown-out Reset (BOR)

Some registers are not affected in any reset condition; their status is unknown on POR and unchanged by any other reset. Most other registers are reset to a "reset state" on Power-on Reset (POR), on the  $\overline{\text{MCLR}}$  and WDT Reset, on  $\overline{\text{MCLR}}$  reset during SLEEP, and on Brown-out Reset (BOR). They are not affected by a WDT Wake-up from SLEEP, which is viewed as the resumption of normal operation. The  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are set or cleared depending on the reset situation, as indicated in Table 10-4. These bits are used in software to determine the nature of the reset. See Table 10-6 for a full description of reset states of all registers.


A simplified block diagram of the on-chip reset circuit is shown in Figure 10-5.

The PICmicro devices have a MCLR noise filter in the MCLR reset path. The filter will ignore small pulses. However, a valid MCLR pulse must meet the minimum pulse width (TmcL, Specification #30).

No internal reset source (WDT, BOR, POR) willdrive the  $\overline{\text{MCLR}}$  pin low.

© 1999 Microchip Technology Inc. Preliminary DS35008B-page 57

#### FIGURE 10-5: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT




#### 10.4 Power-On Reset (POR)

A Power-on Reset pulse is generated on-chip when VDD rise is detected (in the range of 1.5V - 2.1V). To take advantage of the POR, just tie the MCLR pin directly (or through a resistor) to VDD. This will eliminate external RC components usually needed to create a Power-on Reset. A maximum rise time for VDD is specified (SVDD, parameter D004). For a slow rise time, see Figure 10-6.

When the device starts normal operation (exits the reset condition), device operating parameters (voltage, frequency, temperature,...) must be met to ensure operation. If these conditions are not met, the device must be held in reset until the operating conditions are met. Brown-out Reset may be used to meet the start-up conditions.

FIGURE 10-6: EXTERNAL POWER-ON
RESET CIRCUIT (FOR SLOW
VDD POWER-UP)



- Note 1: External Power-on Reset circuit is required only if VDD power-up slope is too slow. The diode D helps discharge the capacitor quickly when VDD powers down.
  - 2:  $R < 40 \text{ k}\Omega$  is recommended to make sure that voltage drop across R does not violate the device's electrical specification.
  - 3: R1 =  $100\Omega$  to 1 k $\Omega$  will limit any current flowing into  $\overline{\text{MCLR}}$  from external capacitor C in the event of  $\overline{\text{MCLR}}/\text{VPP}$  pin breakdown due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS).

#### 10.5 Power-up Timer (PWRT)

The Power-up Timer provides a fixed nominal time-out (TPWRT, parameter #33) from the POR. The Power-up Timer operates on an internal RC oscillator. The chip is kept in reset as long as the PWRT is active. The PWRT's time delay allows VDD to rise to an acceptable level. A configuration bit is provided to enable/disable the PWRT.

The power-up time delay will vary from chip-to-chip due to VDD, temperature and process variation. See DC parameters for details.

#### 10.6 Oscillator Start-up Timer (OST)

The Oscillator Start-up Timer (OST) provides a delay of 1024 oscillator cycles (from OSC1 input) after the PWRT delay is over (Tost, parameter #32). This ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP and HS modes and only on Power-on Reset or wake-up from SLEEP.

**Note:** The OST delay may not occur when the device wakes from SLEEP.

#### 10.7 Brown-Out Reset (BOR)

The configuration bit, BODEN, can enable or disable the Brown-Out Reset circuit. If VPP falls below Vbor (parameter #35, about  $100\mu S$ ), the brown-out situation will reset the device. If VDD falls below VBOR for less than TBOR, a reset may not occur.

Once the brown-out occurs, the device will remain in brown-out reset until VDD rises above VBOR. The power-up timer then keeps the device in reset for TPWRT (parameter #33, about 72mS). If VDD should fall below VBOR during TPWRT, the brown-out reset process will restart when VDD rises above VBOR with the power-up timer reset. The power-up timer is always enabled when the brown-out reset circuit is enabled, regardless of the state of the  $\overline{PWRT}$  configuration bit.

#### 10.8 <u>Time-out Sequence</u>

When a POR reset occurs, the PWRT delay starts (if enabled). When PWRT ends, the OST counts 1024 oscillator cycles (LP, XT, HS modes only). When OST completes, the device comes out of reset. The total time-out will vary based on oscillator configuration and the status of the PWRT. For example, in RC mode with the PWRT disabled, there will be no time-out at all.

If MCLR is kept low long enough, the time-outs will expire. Bringing MCLR high will begin execution immediately. This is useful for testing purposes or to synchronize more than one PIC16CXXX device operating in parallel.

Table 10-5 shows the reset conditions for the STATUS, PCON and PC registers, while Table 10-6 shows the reset conditions for all the registers.

#### 10.9 <u>Power Control/Status Register</u> (PCON)

The BOR bit is unknown on Power-on Reset. If the Brown-out Reset circuit is used, the BOR bit must be set by the user and checked on subsequent resets to see if it was cleared, indicating a Brown-out has occurred.

POR (Power-on Reset Status bit) is cleared on a Power-on Reset and unaffected otherwise. The user

#### **Status Register**

IDD	DD1	RP0	=	DD	7	500	0
IRP	RP1	RP0	10	PD		DC	C

#### **PCON Register**

			POR	BOR

#### TABLE 10-3 TIME-OUT IN VARIOUS SITUATIONS

0	Power-	-up	D	Wake-up from		
Oscillator Configuration	PWRTE = 0 PWRTE = 1		Brown-out	SLEEP		
XT, HS, LP	72 ms + 1024Tosc	1024Tosc	72 ms + 1024Tosc	1024Tosc		
RC	72 ms	_	72 ms	_		

#### TABLE 10-4 STATUS BITS AND THEIR SIGNIFICANCE

POR	BOR	TO	PD	
0	х	1	1	Power-on Reset
0	х	0	х	Illegal, TO is set on POR
0	х	х	0	Illegal, PD is set on POR
1	0	1	1	Brown-out Reset
1	1	0	1	WDT Reset
1	1	0	0	WDT Wake-up
1	1	u	u	MCLR Reset during normal operation
1	1	1	0	MCLR Reset during SLEEP or interrupt wake-up from SLEEP

#### TABLE 10-5 RESET CONDITION FOR SPECIAL REGISTERS

Condition	Program Counter	STATUS Register	PCON Register
Power-on Reset	000h	0001 1xxx	0x
MCLR Reset during normal operation	000h	000u uuuu	uu
MCLR Reset during SLEEP	000h	0001 0uuu	uu
WDT Reset	000h	0000 1uuu	uu
WDT Wake-up	PC + 1	uuu0 0uuu	uu
Brown-out Reset	000h	0001 1uuu	u0
Interrupt wake-up from SLEEP	PC + 1 <sup>(1)</sup>	uuu1 0uuu	uu

Legend: u = unchanged, x = unknown, - = unimplemented bit read as '0'.

Note 1: When the wake-up is due to an interrupt and the GIE bit is set, the PC is loaded with the interrupt vector (0004h).

TABLE 10-6 INITIALIZATION CONDITIONS FOR ALL REGISTERS

D		cable ices	Power-on Reset, Brown-out Reset	MCLR Resets WDT Reset	Wake-up via WDT or Interrupt		
W	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
INDF	62B	72A	N/A	N/A	N/A		
TMR0	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PCL	62B	72A	0000h	0000h	PC + 1 <sup>(2)</sup>		
STATUS	62B	72A	0001 1xxx	000q quuu <b>(3)</b>	uuuq quuu(3)		
FSR	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PORTA <sup>(4)</sup>	62B	72A	0x 0000	0u 0000	uu uuuu		
PORTB <sup>(5)</sup>	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PORTC <sup>(5)</sup>	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PCLATH	62B	72A	0 0000	0 0000	u uuuu		
INTCON	62B	72A	0000 000x	0000 000u	uuuu uuuu(1)		
DID 4	62B	72A	0000	0000	uuuu <b>(1)</b>		
PIR1	62B	72A	-0 0000	-0 0000	-u uuuu <b>(1)</b>		
TMR1L	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
TMR1H	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
T1CON	62B	72A	00 0000	uu uuuu	uu uuuu		
TMR2	62B	72A	0000 0000	0000 0000	uuuu uuuu		
T2CON	62B	72A	-000 0000	-000 0000	-uuu uuuu		
SSPBUF	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
SSPCON	62B	72A	0000 0000	0000 0000	uuuu uuuu		
CCPR1L	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
CCPR1H	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
CCP1CON	62B	72A	00 0000	00 0000	uu uuuu		
ADRES	62B	72A	xxxx xxxx	uuuu uuuu	uuuu uuuu		
ADCON0	62B	72A	0000 00-0	0000 00-0	uuuu uu-u		
OPTION_REG	62B	72A	1111 1111	1111 1111	uuuu uuuu		
TRISA	62B	72A	11 1111	11 1111	uu uuuu		
TRISB	62B	72A	1111 1111	1111 1111	uuuu uuuu		
TRISC	62B	72A	1111 1111	1111 1111	uuuu uuuu		
DIE 4	62B	72A	0000	0000	uuuu		
PIE1	62B	72A	-0 0000	-0 0000	-u uuuu		
PCON	62B	72A	0q	uq	uq		
PR2	62B	72A	1111 1111	1111 1111	1111 1111		
SSPADD	62B	72A	0000 0000	0000 0000	uuuu uuuu		
SSPSTAT	62B	72A	0000 0000	0000 0000	uuuu uuuu		
ADCON1	62B	72A	000	000	uuu		

Legend: u = unchanged, x = unknown, -= unimplemented bit, read as '0', <math>q = value depends on condition

Note 1: One or more bits in INTCON and/or PIR1 will be affected (to cause wake-up).

<sup>2:</sup> When the wake-up is due to an interrupt and the GIE bit is set, the PC is loaded with the interrupt vector (0004h).

**<sup>3:</sup>** See Table 10-5 for reset value for specific condition.

<sup>4:</sup> On any device reset, these pins are configured as inputs.

<sup>5:</sup> This is the value that will be in the port output latch.

#### 10.10 Interrupts

The interrupt control register (INTCON) records individual interrupt requests in flag bits. It also has individual and global interrupt enable bits.

Note: Individual interrupt flag bits are set regardless of the status of their corresponding mask bit or the GIE bit.

A global interrupt enable bit, GIE (INTCON<7>) enables or disables all interrupts. When bit GIE is enabled, and an interrupt's flag bit and mask bit are set, the interrupt will vector immediately. Individual interrupts can be disabled through their corresponding enable bits in various registers. Individual interrupt flag bits are set regardless of the status of the GIE bit. The GIE bit is cleared on reset.

The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit, which reenables interrupts.


The RB0/INT pin interrupt, the RB port change interrupt and the TMR0 overflow interrupt flags are contained in the INTCON register.

The peripheral interrupt flags are contained in the special function registers PIR1 and PIR2. The corresponding interrupt enable bits are contained in special function registers PIE1 and PIE2, and the peripheral interrupt enable bit is contained in special function register INTCON.

When an interrupt is responded to, the GIE bit is cleared to disable any further interrupts, the return address is pushed onto the stack and the PC is loaded with 0004h. Once in the interrupt service routine, the source of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bit must be cleared in software before re-enabling interrupts to avoid recursive interrupts.

For external interrupt events, such as the INT pin or PORTB change interrupt, the interrupt latency will be three or four instruction cycles, depending on when the interrupt event occurs. The latency is the same for one or two cycle instructions. Individual interrupt flag bits are set regardless of the status of their corresponding mask bit or the GIE bit

#### FIGURE 10-7: INTERRUPT LOGIC



#### 10.10.1 INT INTERRUPT

The external interrupt on RB0/INT pin is edge triggered: either rising, if bit INTEDG (OPTION\_REG<6>) is set, or falling, if the INTEDG bit is clear. When a valid edge appears on the RB0/INT pin, flag bit INTF (INTCON<1>) is set. This interrupt can be disabled by clearing enable bit INTE (INTCON<4>). Flag bit INTF must be cleared in software in the interrupt service routine before re-enabling this interrupt. The INT interrupt can wake-up the processor from SLEEP, if bit INTE was set prior to going into SLEEP. The status of global interrupt enable bit GIE decides whether or not the processor branches to the interrupt vector following wake-up. See Section 10.13 for details on SLEEP mode.

#### 10.10.2 TMR0 INTERRUPT

An overflow (FFh  $\rightarrow$  00h) in the TMR0 register will set flag bit T0IF (INTCON<2>). The interrupt can be enabled/disabled by setting/clearing enable bit T0IE (INTCON<5>). (Section 4.0)

#### 10.10.3 PORTB INTCON CHANGE

An input change on PORTB<7:4> sets flag bit RBIF (INTCON<0>). The interrupt can be enabled/disabled by setting/clearing enable bit RBIE (INTCON<4>). (Section 3.2)

#### 

During an interrupt, only the return PC value is saved on the stack. Typically, users may wish to save key registers during an interrupt, (i.e., W register and STATUS register). This will have to be implemented in software.

Example 10-1 stores and restores the W and STATUS registers. The register, W\_TEMP, must be defined in each bank and must be defined at the same offset from the bank base address (i.e., if W\_TEMP is defined at 0x20 in bank 0, it must also be defined at 0xA0 in bank 1).

The example:

- a) Stores the W register.
- b) Stores the STATUS register in bank 0.
- c) Stores the PCLATH register.
- Executes the interrupt service routine code (User-generated).
- e) Restores the STATUS register (and bank select bit).
- f) Restores the W and PCLATH registers.

#### **EXAMPLE 10-1: SAVING STATUS, W, AND PCLATH REGISTERS IN RAM**

```
W_TEMP
                           ;Copy W to TEMP register, could be bank one or zero
SWAPF
         STATUS, W
                           ;Swap status to be saved into W
CLRF
         STATUS
                           ; bank 0, regardless of current bank, Clears IRP, RP1, RP0
MOVWF
         STATUS_TEMP
                          ; Save status to bank zero STATUS_TEMP register
:(ISR)
SWAPF
         STATUS_TEMP,W
                           ;Swap STATUS_TEMP register into W
                           ; (sets bank to original state)
MOVWF
         STATUS
                           ; Move W into STATUS register
SWAPF
         W_TEMP,F
                          ;Swap W_TEMP
SWAPF
         W_TEMP,W
                           ;Swap W_TEMP into W
```

#### 10.12 Watchdog Timer (WDT)

The Watchdog Timer is a free running on-chip RC oscillator which does not require any external components. This RC oscillator is separate from the RC oscillator of the OSC1/CLKIN pin. The WDT will run, even if the clock on the OSC1/CLKIN and OSC2/CLKOUT pins of the device has been stopped, for example, by execution of a SLEEP instruction.

During normal operation, a WDT time-out generates a device RESET (Watchdog Timer Reset). If the device is in SLEEP mode, a WDT time-out causes the device to wake-up and continue with normal operation (Watchdog Timer Wake-up). The  $\overline{\text{TO}}$  bit in the STATUS register will be cleared upon a Watchdog Timer time-out.


The WDT can be permanently disabled by clearing configuration bit WDTE (Section 10.1).

The WDT time-out period (TWDT, parameter #31) is multiplied by the prescaler ratio, when the prescaler is assigned to the WDT. The prescaler assignment (assigned to either the WDT or Timer0) and prescaler ratio are set in the OPTION\_REG register.

Note: The CLRWDT and SLEEP instructions clear the WDT and the postscaler, if assigned to the WDT, and prevent it from timing out and generating a device RESET condition.

When a CLRWDT instruction is executed and the prescaler is assigned to the WDT, the prescaler count will be cleared, but the prescaler assignment is not changed.

#### FIGURE 10-8: WATCHDOG TIMER BLOCK DIAGRAM



Note:

#### FIGURE 10-9: SUMMARY OF WATCHDOG TIMER REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
2007h	Config. bits		BODEN	CP1	CP0	PWRTE	WDTE	FOSC1	FOSC0
81h	OPTION_REG	RBPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0

Legend: Shaded cells are not used by the Watchdog Timer.

#### 10.13 Power-down Mode (SLEEP)

Power-down mode is entered by executing a SLEEP instruction.

If enabled, the Watchdog Timer will be cleared but keeps running, the  $\overline{PD}$  bit (STATUS<3>) is cleared, the  $\overline{TO}$  (STATUS<4>) bit is set, and the oscillator driver is turned off. The I/O ports maintain the status they had, before the <code>SLEEP</code> instruction was executed (driving high, low or hi-impedance).

For lowest current consumption in this mode, place all I/O pins at either VDD or Vss, ensure no external circuitry is drawing current from the I/O pin, power-down the A/D and disable external clocks. Pull all I/O pins that are hi-impedance inputs, high or low externally, to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or Vss for lowest current consumption. The contribution from on-chip pull-ups on PORTB should be considered.

The  $\overline{\text{MCLR}}$  pin must be at a logic high level (VIHMC, parameter D042).

#### 10.13.1 WAKE-UP FROM SLEEP

The device can wake up from SLEEP through one of the following events:

- External reset input on MCLR pin.
- Watchdog Timer Wake-up (if WDT was enabled).
- Interrupt from INT pin, RB port change, or some Peripheral Interrupts.

External  $\overline{\text{MCLR}}$  Reset will cause a device reset. All other events are considered a continuation of program execution and cause a "wake-up". The  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits in the STATUS register can be used to determine the cause of device reset. The  $\overline{\text{PD}}$  bit, which is set on power-up, is cleared when SLEEP is invoked. The  $\overline{\text{TO}}$  bit is cleared if a WDT time-out occurred (and caused wake-up).

The following peripheral interrupts can wake the device from SLEEP:

- 1. TMR1 interrupt. Timer1 must be operating as an asynchronous counter.
- 2. CCP capture mode interrupt.
- Special event trigger (Timer1 in asynchronous mode using an external clock. CCP1 is in compare mode).
- 4. SSP (Start/Stop) bit detect interrupt.
- 5. SSP transmit or receive in slave mode (SPI/I<sup>2</sup>C).
- 6. USART RX or TX (synchronous slave mode).

Other peripherals cannot generate interrupts since during SLEEP, no on-chip clocks are present.

When the SLEEP instruction is being executed, the next instruction (PC + 1) is pre-fetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is

regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device resumes execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction and then branches to the interrupt address (0004h). In cases where the execution of the instruction following SLEEP is not desirable, a NOP should follow the SLEEP instruction.

#### 10.13.2 WAKE-UP USING INTERRUPTS


When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If the interrupt occurs before the execution of a SLEEP instruction, the SLEEP instruction will complete as a NOP. Therefore, the WDT and WDT postscaler will not be cleared, the TO bit will not be set and PD bits will not be cleared.
- If the interrupt occurs during or after the execution of a SLEEP instruction, the device will immediately wake up from sleep. The SLEEP instruction will be completely executed before the wake-up. Therefore, the WDT and WDT postscaler will be cleared, the TO bit will be set and the PD bit will be cleared.

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.

To ensure that the WDT is cleared, a CLRWDT instruction should be executed before a SLEEP instruction.

#### FIGURE 10-10: WAKE-UP FROM SLEEP THROUGH INTERRUPT



- 2: Tost = 1024Tosc (drawing not to scale) This delay will not be there for RC osc mode.
- 3: GIE = '1' assumed. In this case after wake- up, the processor jumps to the interrupt routine. If GIE = '0', execution will continue in-line.
- 4: CLKOUT is not available in these osc modes, but shown here for timing reference.

#### 10.14 Program Verification/Code Protection

If the code protection bits have not been programmed, the on-chip program memory can be read out for verification purposes.

**Note:** Microchip does not recommend code protecting windowed devices.

#### 10.15 ID Locations

Four memory locations (2000h - 2003h) are designated as ID locations where the user can store checksum or other code-identification numbers. These locations are not accessible during normal execution, but are readable and writable during program/verify. It is recommended that only the 4 least significant bits of the ID location are used.

For ROM devices, these values are submitted along with the ROM code.

#### 10.16 <u>In-Circuit Serial Programming</u>™

PIC16CXXX microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data, and three more lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices, and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

For complete details of serial programming, please refer to the In-Circuit Serial Programming (ICSP™) Guide, DS30277.

#### 11.0 INSTRUCTION SET SUMMARY

Each PIC16CXXX instruction is a 14-bit word divided into an OPCODE which specifies the instruction type and one or more operands which further specify the operation of the instruction. The PIC16CXX instruction set summary in Table 11-2 lists **byte-oriented**, **bit-oriented**, and **literal and control** operations. Table 11-1 shows the opcode field descriptions.

For **byte-oriented** instructions, 'f' represents a file register designator and 'd' represents a destination designator. The file register designator specifies which file register is to be used by the instruction.

The destination designator specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the W register. If 'd' is one, the result is placed in the file register specified in the instruction.

For **bit-oriented** instructions, 'b' represents a bit field designator which selects the number of the bit affected by the operation, while 'f' represents the number of the file in which the bit is located.

For **literal and control** operations, 'k' represents an eight or eleven bit constant or literal value.

TABLE 11-1 OPCODE FIELD DESCRIPTIONS

Field	Description
f	Register file address (0x00 to 0x7F)
W	Working register (accumulator)
b	Bit address within an 8-bit file register
k	Literal field, constant data or label
x	Don't care location (= 0 or 1) The assembler will generate code with x = 0. It is the recommended form of use for compatibility with all Microchip software tools.
d	Destination select; d = 0: store result in W, d = 1: store result in file register f. Default is d = 1
PC	Program Counter
TO	Time-out bit
$\overline{ t PD}$	Power-down bit
Z	Zero bit
DC	Digit Carry bit
С	Carry bit

The instruction set is highly orthogonal and is grouped into three basic categories:

- Byte-oriented operations
- Bit-oriented operations
- · Literal and control operations

All instructions are executed within one single instruction cycle, unless a conditional test is true or the program counter is changed as a result of an instruction. In this case, the execution takes two instruction cycles with the second cycle executed as a NOP. One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction

execution time is 1  $\mu$ s. If a conditional test is true or the program counter is changed as a result of an instruction, the instruction execution time is 2  $\mu$ s.

Table 11-2 lists the instructions recognized by the MPASM assembler.

Figure 11-1 shows the general formats that the instructions can have.


**Note:** To maintain upward compatibility with future PIC16CXXX products, <u>do not use</u> the OPTION and TRIS instructions.

All examples use the following format to represent a hexadecimal number:

0xhh

where h signifies a hexadecimal digit.

## FIGURE 11-1: GENERAL FORMAT FOR INSTRUCTIONS



A description of each instruction is available in the  $PICmicro^{TM}$  Mid-Range Reference Manual, (DS33023).

TABLE 11-2 PIC16CXXX INSTRUCTION SET

Mnemonic,		Description	Cycles		14-Bit	Opcode	9	Status	Notes
Operands				MSb			LSb	Affected	
BYTE-ORIENTED FILE REGISTER OPERATIONS									
ADDWF	f, d	Add W and f	1	00	0111	dfff	ffff	C,DC,Z	1,2
ANDWF	f, d	AND W with f	1	00	0101	dfff	ffff	Z	1,2
CLRF	f	Clear f	1	00	0001	lfff	ffff	Z	2
CLRW	-	Clear W	1	00	0001	0000	0011	Z	
COMF	f, d	Complement f	1	00	1001	dfff	ffff	Z	1,2
DECF	f, d	Decrement f	1	00	0011	dfff	ffff	Z	1,2
DECFSZ	f, d	Decrement f, Skip if 0	1(2)	00	1011	dfff	ffff		1,2,3
INCF	f, d	Increment f	1	00	1010	dfff	ffff	Z	1,2
INCFSZ	f, d	Increment f, Skip if 0	1(2)	00	1111	dfff	ffff		1,2,3
IORWF	f, d	Inclusive OR W with f	ì	00	0100	dfff	ffff	Z	1,2
MOVF	f, d	Move f	1	00	1000	dfff	ffff	Z	1,2
MOVWF	f	Move W to f	1	00	0000	lfff	ffff		
NOP	-	No Operation	1	00	0000	0xx0	0000		
RLF	f, d	Rotate Left f through Carry	1	00	1101	dfff	ffff	С	1,2
RRF	f, d	Rotate Right f through Carry	1	0.0	1100	dfff	ffff	С	1,2
SUBWF	f, d	Subtract W from f	1	00	0010	dfff	ffff	C,DC,Z	1,2
SWAPF	f, d	Swap nibbles in f	1	00	1110	dfff	ffff		1,2
XORWF	f, d	Exclusive OR W with f	1	00	0110	dfff	ffff	Z	1,2
BIT-ORIENT	ED FIL	E REGISTER OPERATIONS							•
BCF	f, b	Bit Clear f	1	01	00bb	bfff	ffff		1,2
BSF	f, b	Bit Set f	1	01	01bb	bfff	ffff		1,2
BTFSC	f, b	Bit Test f, Skip if Clear	1 (2)	01	10bb	bfff	ffff		3
BTFSS	f, b	Bit Test f, Skip if Set	1 (2)	01	11bb	bfff	ffff		3
LITERAL AN	ND CO	NTROL OPERATIONS							•
ADDLW	k	Add literal and W	1	11	111x	kkkk	kkkk	C,DC,Z	
ANDLW	k	AND literal with W	1	11	1001	kkkk	kkkk	Z	
CALL	k	Call subroutine	2	10	0kkk	kkkk	kkkk		
CLRWDT	-	Clear Watchdog Timer	1	0.0	0000	0110	0100	TO,PD	
GOTO	k	Go to address	2	10	1kkk	kkkk	kkkk		
IORLW	k	Inclusive OR literal with W	1	11	1000	kkkk	kkkk	Z	
MOVLW	k	Move literal to W	1	11	00xx	kkkk	kkkk		
RETFIE	-	Return from interrupt	2	0.0	0000	0000	1001		
RETLW	k	Return with literal in W	2	11	01xx	kkkk	kkkk		
RETURN	-	Return from Subroutine	2	0.0	0000	0000	1000		
SLEEP	-	Go into standby mode	1	0.0	0000	0110	0011	TO,PD	
SUBLW	k	Subtract W from literal	1	11	110x	kkkk	kkkk	C,DC,Z	
XORLW	k	Exclusive OR literal with W	1	11	1010	kkkk		Z Z	
			l						

Note 1: When an I/O register is modified as a function of itself (e.g., MOVF PORTB, 1), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

<sup>2:</sup> If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned to the Timer0 Module.

**<sup>3:</sup>** If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

### 11.1 <u>Instruction Descriptions</u>

ADDLW	Add Literal and W				
Syntax:	[label] ADDLW k				
Operands:	$0 \leq k \leq 255$				
Operation:	$(W) + k \to (W)$				
Status Affected:	C, DC, Z				
Description:	The contents of the W register are added to the eight bit literal 'k' and the result is placed in the W register.				

ANDWF	AND W with f				
Syntax:	[label] ANDWF f,d				
Operands:	$0 \le f \le 127$ $d \in [0,1]$				
Operation:	(W) .AND. (f) $\rightarrow$ (destination)				
Status Affected:	Z				
Description:	AND the W register with register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.				

ADDWF	Add W and f
Syntax:	[label] ADDWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) + (f) $\rightarrow$ (destination)
Status Affected:	C, DC, Z
Description:	Add the contents of the W register with register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

BCF	Bit Clear f
Syntax:	[label] BCF f,b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	$0 \rightarrow (f \mathord{<} b \mathord{>})$
Status Affected:	None
Description:	Bit 'b' in register 'f' is cleared.

ANDLW	AND Literal with W
Syntax:	[ <i>label</i> ] ANDLW k
Operands:	$0 \le k \le 255$
Operation:	(W) .AND. (k) $\rightarrow$ (W)
Status Affected:	Z
Description:	The contents of W register are AND'ed with the eight bit literal 'k'. The result is placed in the W register.

BSF	Bit Set f
Syntax:	[label] BSF f,b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	$1 \rightarrow (f < b >)$
Status Affected:	None
Description:	Bit 'b' in register 'f' is set.

© 1999 Microchip Technology Inc. Preliminary DS35008B-page 69

BTFSS	Bit Test f, Skip if Set	CLRF	Clear f
Syntax:	[ <i>label</i> ] BTFSS f,b	Syntax:	[label] CLRF f
Operands:	$0 \le f \le 127$	Operands:	$0 \le f \le 127$
	$0 \le b < 7$	Operation:	$00h \rightarrow (f)$
Operation:	skip if $(f < b >) = 1$	·	$1 \rightarrow Z$
Status Affected:	None	Status Affected:	Z
Description:	If bit 'b' in register 'f' is '0', then the next instruction is executed.  If bit 'b' is '1', then the next instruction is discarded and a NOP is executed instead, making this a 2TCY instruction.	Description:	The contents of register 'f' are cleared and the Z bit is set.

BTFSC	Bit Test, Skip if Clear	CLRW	Clear W
Syntax:	[ <i>label</i> ] BTFSC f,b	Syntax:	[label] CLRW
Operands:	$0 \le f \le 127$	Operands:	None
	$0 \le b \le 7$	Operation:	$00h \rightarrow (W)$
Operation:	skip if $(f < b >) = 0$		$1 \rightarrow Z$
Status Affected:	None	Status Affected:	Z
Description:	If bit 'b' in register 'f' is '1', then the next instruction is executed.  If bit 'b' in register 'f' is '0', then the next instruction is discarded, and a NOP is executed instead, making this a 2Tcy instruction.	Description:	W register is cleared. Zero bit (Z) is set.

CALL	Call Subroutine	CLRWDT	Clear Watchdog Timer
Syntax:	[label] CALL k	Syntax:	[label] CLRWDT
Operands:	$0 \le k \le 2047$	Operands:	None
Operation:	(PC)+ 1 $\rightarrow$ TOS, k $\rightarrow$ PC<10:0>, (PCLATH<4:3>) $\rightarrow$ PC<12:11>	Operation:	$\begin{array}{l} \text{00h} \rightarrow \text{WDT} \\ \text{0} \rightarrow \text{WDT prescaler,} \\ \text{1} \rightarrow \overline{\text{TO}} \end{array}$
Status Affected:	None		$1 \rightarrow \overline{PD}$
Description:  Call Subroutine. First, return address (PC+1) is pushed onto the stack. The eleven bit immediate address is loaded into PC bits <10:0>. The upper bits of the PC are loaded from PCLATH.  CALL is a two cycle instruction.		Status Affected:	TO, PD
	Description:	CLRWDT instruction resets the Watchdog Timer. It also resets the prescaler of the WDT. Status bits TO and PD are set.	

COMF	Complement f	GOTO	Unconditional Branch
Syntax:	[ label ] COMF f,d	Syntax:	[label] GOTO k
Operands:	$0 \le f \le 127$	Operands:	$0 \leq k \leq 2047$
	d ∈ [0,1]	Operation:	$k \rightarrow PC < 10:0 >$
Operation:	$(\bar{f}) \to (destination)$		$PCLATH \mathord{<} 4:3 \mathord{>} \to PC \mathord{<} 12:11 \mathord{>}$
Status Affected:	Z	Status Affected:	None
Description:	The contents of register 'f' are complemented. If 'd' is 0, the result is stored in W. If 'd' is 1, the result is stored back in register 'f'.	Description:	GOTO is an unconditional branch. The eleven bit immediate value is loaded into PC bits <10:0>. The upper bits of PC are loaded from PCLATH<4:3>. GOTO is a two cycle instruction.

DECF	Decrement f	INCF	Increment f
Syntax:	[label] DECF f,d	Syntax:	[ label ] INCF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$	Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 $\rightarrow$ (destination)	Operation:	(f) + 1 $\rightarrow$ (destination)
Status Affected:	Z	Status Affected:	Z
Description:	Decrement register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.	Description:	The contents of register 'f' are incremented. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'.

DECFSZ	Decrement f, Skip if 0	INCFSZ	Increment f, Skip if 0
Syntax:	[ label ] DECFSZ f,d	Syntax:	[ label ] INCFSZ f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$	Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 $\rightarrow$ (destination); skip if result = 0	Operation:	(f) + 1 $\rightarrow$ (destination), skip if result = 0
Status Affected:	None	Status Affected:	None
Description:	The contents of register 'f' are decremented. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'. If the result is 1, the next instruction, is executed. If the result is 0, then a NOP is executed instead making it a 2TCY instruction.	Description:	The contents of register 'f' are incremented. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'. If the result is 1, the next instruction is executed. If the result is 0, a NOP is executed instead making it a 2TCY instruction.

IORLW	Inclusive OR Literal with W	MOVLW	Move Literal to W
Syntax:	[ label ] IORLW k	Syntax:	[ label ] MOVLW k
Operands:	$0 \leq k \leq 255$	Operands:	$0 \leq k \leq 255$
Operation:	(W) .OR. $k \rightarrow$ (W)	Operation:	$k \rightarrow (W)$
Status Affected:	Z	Status Affected:	None
Description:	The contents of the W register is OR'ed with the eight bit literal 'k'. The result is placed in the W register.	Description:	The eight bit literal 'k' is loaded into W register. The don't cares will assemble as 0's.

IORWF	Inclusive OR W with f	MOVWF	Move W to f
Syntax:	[ label ] IORWF f,d	Syntax:	[ label ] MOVWF f
Operands:	$0 \le f \le 127$	Operands:	$0 \le f \le 127$
	d ∈ [0,1]	Operation:	(W)  o (f)
Operation:	(W) .OR. (f) $\rightarrow$ (destination)	Status Affected:	None
Status Affected:	Z	Description:	Move data from W register to register
Description:	Inclusive OR the W register with register 'f'. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'.	·	۴.

MOVF	Move f	
Syntax:	[ label ] MOVF f,d	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	(f) $\rightarrow$ (destination)	
Status Affected:	Z	
Description:	The contents of register f is moved to a destination dependant upon the status of d. If $d=0$ , destination is W register. If $d=1$ , the destination is file register f itself. $d=1$ is useful to test a file register since status flag Z is affected.	

No Operation
[ label ] NOP
None
No operation
None
No operation.

stored back in register 'f'.

placed back in register 'f'.

Register f

Register f

RETFIE	Return from Interrupt	RLF	Rotate Left f through Carry
Syntax:	[ label ] RETFIE	Syntax:	[ label ] RLF f,d
Operands: Operation:	None $TOS \rightarrow PC$ .	Operands:	$0 \le f \le 127$ $d \in [0,1]$
operane	1 → GIE	Operation:	See description below
Status Affected:	None	Status Affected:	С
		Description:	The contents of register 'f' are rotated one bit to the left through the Carry Flag. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is

RETLW	Return with Literal in W	RRF	Rotate Right f through Carry
Syntax:	[ label ] RETLW k	Syntax:	[label] RRF f,d
Operands:	$0 \le k \le 255$	Operands:	$0 \le f \le 127$
Operation:	$k \rightarrow (W);$		d ∈ [0,1]
	$TOS \to PC$	Operation:	See description below
Status Affected:	None	Status Affected:	С
Description:	The W register is loaded with the eight bit literal 'k'. The program counter is loaded from the top of the stack (the return address). This is a two cycle	Description:	The contents of register 'f' are rotated one bit to the right through the Carry Flag. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is

instruction.

RETURN	Return from Subroutine	SLEEP	
Syntax: Operands: Operation: Status Affected: Description:	[ label ] RETURN  None  TOS → PC  None  Return from subroutine. The stack is POPed and the top of the stack (TOS) is loaded into the program counter. This is a two cycle instruction.	Syntax: Operands: Operation: Status Affected: Description:	[ label ] SLEEP  None $00h \rightarrow WDT$ , $0 \rightarrow WDT$ prescaler, $1 \rightarrow \overline{TO}$ , $0 \rightarrow \overline{PD}$ $\overline{TO}$ , $\overline{PD}$ The power-down status bit, $\overline{PD}$ is cleared. Time-out status bit, $\overline{TO}$ is set. Watchdog Timer and its prescaler are cleared. The processor is put into SLEEP mode with the oscillator stopped.

## PIC16C62B/72A

SUBLW	Subtract W from Literal	XORLW	Exclusive OR Literal with W
Syntax:	[label] SUBLW k	Syntax:	[label] XORLW k
Operands:	$0 \le k \le 255$	Operands:	$0 \le k \le 255$
Operation:	$k - (W) \rightarrow (W)$	Operation:	(W) .XOR. $k \rightarrow (W)$
Status Affected:	C, DC, Z	Status Affected:	Z
Description:	The W register is subtracted (2's complement method) from the eight bit literal 'k'. The result is placed in the W register.	Description:	The contents of the W register are XOR'ed with the eight bit literal 'k'. The result is placed in the W register.

**XORWF** 

SUBWF	Subtract W from f
Syntax:	[ label ] SUBWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - (W) $\rightarrow$ (destination)
Status Affected:	C, DC, Z
Description:	Subtract (2's complement method) W register from register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

Syntax:	[label] XORWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .XOR. (f) $\rightarrow$ (destination)
Status Affected:	Z
Description:	Exclusive OR the contents of the W register with register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

Exclusive OR W with f

SWAPF	Swap Nibbles in f
Syntax:	[label] SWAPF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f<3:0>) \rightarrow (destination<7:4>),  (f<7:4>) \rightarrow (destination<3:0>)$
Status Affected:	None
Description:	The upper and lower nibbles of register 'f' are exchanged. If 'd' is 0, the result is placed in W register. If 'd' is 1, the result is placed in register 'f'.

## 12.0 DEVELOPMENT SUPPORT

The PICmicro<sup>®</sup> microcontrollers are supported with a full range of hardware and software development tools:

- · Integrated Development Environment
  - MPLAB™ IDE Software
- · Assemblers/Compilers/Linkers
  - MPASM Assembler
  - MPLAB-C17 and MPLAB-C18 C Compilers
  - MPLINK/MPLIB Linker/Librarian
- Simulators
  - MPLAB-SIM Software Simulator
- Emulators
  - MPLAB-ICE Real-Time In-Circuit Emulator
  - PICMASTER®/PICMASTER-CE In-Circuit Emulator
  - ICEPIC™
- · In-Circuit Debugger
  - MPLAB-ICD for PIC16F877
- · Device Programmers
  - PRO MATE® II Universal Programmer
  - PICSTART<sup>®</sup> Plus Entry-Level Prototype Programmer
- · Low-Cost Demonstration Boards
  - SIMICE
  - PICDEM-1
  - PICDEM-2
  - PICDEM-3
  - PICDEM-17
  - SEEVAL<sup>®</sup>
  - KEELOQ®

## 12.1 <u>MPLAB Integrated Development</u> <u>Environment Software</u>

- The MPLAB IDE software brings an ease of software development previously unseen in the 8-bit microcontroller market. MPLAB is a Windows®-based application which contains:
- · Multiple functionality
  - editor
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
- A full featured editor
- · A project manager
- · Customizable tool bar and key mapping
- · A status bar
- On-line help

MPLAB allows you to:

- Edit your source files (either assembly or 'C')
- One touch assemble (or compile) and download to PICmicro tools (automatically updates all project information)
- · Debug using:
  - source files
  - absolute listing file
  - object code

The ability to use MPLAB with Microchip's simulator, MPLAB-SIM, allows a consistent platform and the ability to easily switch from the cost-effective simulator to the full featured emulator with minimal retraining.

### 12.2 MPASM Assembler

MPASM is a full featured universal macro assembler for all PICmicro MCU's. It can produce absolute code directly in the form of HEX files for device programmers, or it can generate relocatable objects for MPLINK.

MPASM has a command line interface and a Windows shell and can be used as a standalone application on a Windows 3.x or greater system. MPASM generates relocatable object files, Intel standard HEX files, MAP files to detail memory usage and symbol reference, an absolute LST file which contains source lines and generated machine code, and a COD file for MPLAB debugging.

MPASM features include:

- MPASM and MPLINK are integrated into MPLAB projects.
- MPASM allows user defined macros to be created for streamlined assembly.
- MPASM allows conditional assembly for multi purpose source files.
- MPASM directives allow complete control over the assembly process.

## 12.3 MPLAB-C17 and MPLAB-C18 C Compilers

The MPLAB-C17 and MPLAB-C18 Code Development Systems are complete ANSI 'C' compilers and integrated development environments for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers, respectively. These compilers provide powerful integration capabilities and ease of use not found with other compilers.

For easier source level debugging, the compilers provide symbol information that is compatible with the MPLAB IDE memory display.

### 12.4 MPLINK/MPLIB Linker/Librarian

MPLINK is a relocatable linker for MPASM and MPLAB-C17 and MPLAB-C18. It can link relocatable objects from assembly or C source files along with precompiled libraries using directives from a linker script.

MPLIB is a librarian for pre-compiled code to be used with MPLINK. When a routine from a library is called from another source file, only the modules that contains that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications. MPLIB manages the creation and modification of library files.

#### MPLINK features include:

- MPLINK works with MPASM and MPLAB-C17 and MPLAB-C18.
- MPLINK allows all memory areas to be defined as sections to provide link-time flexibility.

#### MPLIB features include:

- MPLIB makes linking easier because single libraries can be included instead of many smaller files.
- MPLIB helps keep code maintainable by grouping related modules together.
- MPLIB commands allow libraries to be created and modules to be added, listed, replaced, deleted, or extracted.

### 12.5 MPLAB-SIM Software Simulator

The MPLAB-SIM Software Simulator allows code development in a PC host environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file or user-defined key press to any of the pins. The execution can be performed in single step, execute until break, or trace mode.

MPLAB-SIM fully supports symbolic debugging using MPLAB-C17 and MPLAB-C18 and MPASM. The Software Simulator offers the flexibility to develop and debug code outside of the laboratory environment making it an excellent multi-project software development tool.

# 12.6 MPLAB-ICE High Performance Universal In-Circuit Emulator with MPLAB IDE

The MPLAB-ICE Universal In-Circuit Emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers (MCUs). Software control of MPLAB-ICE is provided by the MPLAB Integrated Development Environment (IDE), which allows editing, "make" and download, and source debugging from a single environment.

Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB-ICE allows expansion to support new PICmicro microcontrollers.

The MPLAB-ICE Emulator System has been designed as a real-time emulation system with advanced features that are generally found on more expensive development tools. The PC platform and Microsoft<sup>®</sup> Windows 3.x/95/98 environment were chosen to best make these features available to you, the end user.

MPLAB-ICE 2000 is a full-featured emulator system with enhanced trace, trigger, and data monitoring features. Both systems use the same processor modules and will operate across the full operating speed range of the PICmicro MCU.

### 12.7 PICMASTER/PICMASTER CE

The PICMASTER system from Microchip Technology is a full-featured, professional quality emulator system. This flexible in-circuit emulator provides a high-quality, universal platform for emulating Microchip 8-bit PICmicro microcontrollers (MCUs). PICMASTER systems are sold worldwide, with a CE compliant model available for European Union (EU) countries.

### 12.8 **ICEPIC**

ICEPIC is a low-cost in-circuit emulation solution for the Microchip Technology PIC16C5X, PIC16C6X, PIC16C7X, and PIC16CXXX families of 8-bit one-time-programmable (OTP) microcontrollers. The modular system can support different subsets of PIC16C5X or PIC16CXXX products through the use of interchangeable personality modules or daughter boards. The emulator is capable of emulating without target application circuitry being present.

## 12.9 MPLAB-ICD In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB-ICD, is a powerful, low-cost run-time development tool. This tool is based on the flash PIC16F877 and can be used to develop for this and other PICmicro microcontrollers from the PIC16CXXX family. MPLAB-ICD utilizes the In-Circuit Debugging capability built into the PIC16F87X. This feature, along with Microchip's In-Circuit Serial Programming protocol, offers cost-effective in-circuit flash programming and debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by watching variables. single-stepping and setting break points. Running at full speed enables testing hardware in real-time. The MPLAB-ICD is also a programmer for the flash PIC16F87X family.

## 12.10 PRO MATE II Universal Programmer

The PRO MATE II Universal Programmer is a full-featured programmer capable of operating in stand-alone mode as well as PC-hosted mode. PRO MATE II is CE compliant.

The PRO MATE II has programmable VDD and VPP supplies which allows it to verify programmed memory at VDD min and VDD max for maximum reliability. It has an LCD display for instructions and error messages, keys to enter commands and a modular detachable socket assembly to support various package types. In stand-alone mode the PRO MATE II can read, verify or program PICmicro devices. It can also set code-protect bits in this mode.

## 12.11 PICSTART Plus Entry Level Development System

The PICSTART programmer is an easy-to-use, low-cost prototype programmer. It connects to the PC via one of the COM (RS-232) ports. MPLAB Integrated Development Environment software makes using the programmer simple and efficient.

PICSTART Plus supports all PICmicro devices with up to 40 pins. Larger pin count devices such as the PIC16C92X, and PIC17C76X may be supported with an adapter socket. PICSTART Plus is CE compliant.

## 12.12 <u>SIMICE Entry-Level</u> <u>Hardware Simulator</u>

SIMICE is an entry-level hardware development system designed to operate in a PC-based environment with Microchip's simulator MPLAB-SIM. Both SIMICE and MPLAB-SIM run under Microchip Technology's MPLAB Integrated Development Environment (IDE) software. Specifically, SIMICE provides hardware simulation for Microchip's PIC12C5XX, PIC12CE5XX, and PIC16C5X families of PICmicro 8-bit microcontrollers. SIMICE works in conjunction with MPLAB-SIM to provide non-real-time I/O port emulation. SIMICE enables a developer to run simulator code for driving the target system. In addition, the target system can provide input to the simulator code. This capability allows for simple and interactive debugging without having to manually generate MPLAB-SIM stimulus files. SIMICE is a valuable debugging tool for entry-level system development.

## 12.13 <u>PICDEM-1 Low-Cost PICmicro</u> <u>Demonstration Board</u>

The PICDEM-1 is a simple board which demonstrates the capabilities of several of Microchip's microcontrollers. The microcontrollers supported are: PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The users can program the sample microcontrollers provided with

the PICDEM-1 board, on a PRO MATE II or PICSTART-Plus programmer, and easily test firmware. The user can also connect the PICDEM-1 board to the MPLAB-ICE emulator and download the firmware to the emulator for testing. Additional prototype area is available for the user to build some additional hardware and connect it to the microcontroller socket(s). Some of the features include an RS-232 interface, a potentiometer for simulated analog input, push-button switches and eight LEDs connected to PORTB.

## 12.14 PICDEM-2 Low-Cost PIC16CXX Demonstration Board

The PICDEM-2 is a simple demonstration board that supports the PIC16C62, PIC16C64, PIC16C65, PIC16C73 and PIC16C74 microcontrollers. All the necessary hardware and software is included to run the basic demonstration programs. The user can program the sample microcontrollers provided with the PICDEM-2 board, on a PRO MATE II programmer or PICSTART-Plus, and easily test firmware. The MPLAB-ICE emulator may also be used with the PICDEM-2 board to test firmware. Additional prototype area has been provided to the user for adding additional hardware and connecting it to the microcontroller socket(s). Some of the features include a RS-232 interface, push-button switches, a potentiometer for simulated analog input, a Serial EEPROM to demonstrate usage of the I<sup>2</sup>C bus and separate headers for connection to an LCD module and a keypad.

## 12.15 PICDEM-3 Low-Cost PIC16CXXX Demonstration Board

The PICDEM-3 is a simple demonstration board that supports the PIC16C923 and PIC16C924 in the PLCC package. It will also support future 44-pin PLCC microcontrollers with a LCD Module. All the necessary hardware and software is included to run the basic demonstration programs. The user can program the sample microcontrollers provided with the PICDEM-3 board, on a PRO MATE II programmer or PICSTART Plus with an adapter socket, and easily test firmware. The MPLAB-ICE emulator may also be used with the PICDEM-3 board to test firmware. Additional prototype area has been provided to the user for adding hardware and connecting it to the microcontroller socket(s). Some of the features include an RS-232 interface, push-button switches, a potentiometer for simulated analog input, a thermistor and separate headers for connection to an external LCD module and a keypad. Also provided on the PICDEM-3 board is an LCD panel, with 4 commons and 12 seqments, that is capable of displaying time, temperature and day of the week. The PICDEM-3 provides an additional RS-232 interface and Windows 3.1 software for showing the demultiplexed LCD signals on a PC. A simple serial interface allows the user to construct a hardware demultiplexer for the LCD signals.

## PIC16C62B/72A

## 12.16 PICDEM-17

The PICDEM-17 is an evaluation board that demonstrates the capabilities of several Microchip microcon-PIC17C752, trollers. including PIC17C756, PIC17C762, and PIC17C766. All necessary hardware is included to run basic demo programs, which are supplied on a 3.5-inch disk. A programmed sample is included, and the user may erase it and program it with the other sample programs using the PRO MATE II or PICSTART Plus device programmers and easily debug and test the sample code. In addition, PICDEM-17 supports down-loading of programs to and executing out of external FLASH memory on board. The PICDEM-17 is also usable with the MPLAB-ICE or PICMASTER emulator, and all of the sample programs can be run and modified using either emulator. Additionally, a generous prototype area is available for user hardware.

## 12.17 <u>SEEVAL Evaluation and Programming</u> <u>System</u>

The SEEVAL SEEPROM Designer's Kit supports all Microchip 2-wire and 3-wire Serial EEPROMs. The kit includes everything necessary to read, write, erase or program special features of any Microchip SEEPROM product including Smart Serials™ and secure serials. The Total Endurance™ Disk is included to aid in trade-off analysis and reliability calculations. The total kit can significantly reduce time-to-market and result in an optimized system.

## 12.18 <u>KeeLoo Evaluation and Programming Tools</u>

KEELOQ evaluation and programming tools support Microchips HCS Secure Data Products. The HCS evaluation kit includes an LCD display to show changing codes, a decoder to decode transmissions, and a programming interface to program test transmitters.

TABLE 12-1: DEVELOPMENT TOOLS FROM MICROCHIP

		(	<b>X</b>	×	١	X	>	K	<b>&gt;</b>	X	K	>	X	<b>Z</b> )		,	X	0
	PIC12CXX	PIC14000	PIC16C5)	PIC16C6)	PIC16CXX	PIC16F62	(7381319	XT3813I9	PIC16C8)	PIC16F8X	PIC16C9X	PIC17C4	XTJT1JIA	PIC18CXX	93CXX S2CXX\	нсеххх	MCRFXX	WCP2510
MPLAB™ Integrated O Development Environment	>	>	>	>	>	>	>	>	>	>	>	>	>	>				
@ MPLAB™ C17 Compiler												>	>					
MPLAB™ C18 Compiler														>				
Ø MPASM/MPLINK	>	^	>	>	>	>	>	>	>	>	>	>	>	>	>	>		
<u>α</u> MPLAB™-ICE	>	^	>	>	>	**>	>	>	>	>	>	>	>	>				
PICMASTER/PICMASTER-CE	>	>	>	>	^		>	>	>		^	>	>					
E ICEPIC™ Low-Cost II In-Circuit Emulator	<i>&gt;</i>		~	^	^		>	>	>		^							
e ggg ggg MPLAB-ICD In-Circuit Debugger G				*			*			>								
PICSTART®Plus Low-Cost Universal Dev. Kit	>	~	^	,	>	**^	>	>	>	>	>	^	^	<b>,</b>				
B PRO MATE <sup>®</sup> II O Universal Programmer	>	<b>&gt;</b>	>	>	>	**	>	>	>	>	>	>	>	>	>	>		
SIMICE	>		>															
PICDEM-1			>		>		<b>₹</b>		>			>						
PICDEM-2				7			<b>†</b>							>				
g PICDEM-3											^							
PICDEM-14A		~																
FICDEM-17													^					
KEELoo® Evaluation Kit																>		
KEELoo Transponder Kit																<i>&gt;</i>		
ö microlD™ Programmer's Kit																	^	
125 kHz microID Developer's Kit																	^	
a 125 kHz Anticollision microlD Developer's Kit																	>	
13.56 MHz Anticollision microlD Developer's Kit																	>	
MCP2510 CAN Developer's Kit																		>

\*\* Contact Microchip Technology Inc. for availability date.
† Development tool is available on select devices.

## PIC16C62B/72A

**NOTES:** 

## 13.0 ELECTRICAL CHARACTERISTICS

## Absolute Maximum Ratings (†)

Ambient temperature under bias	55°C to +125°C
Storage temperature	65°C to +150°C
Voltage on any pin with respect to Vss (except VDD, MCLR, and RA4)	0.3V to (VDD + 0.3V)
Voltage on VDD with respect to Vss	0.3V to +7.5V
Voltage on MCLR with respect to Vss (Note 2)	0V to +13.25V
Voltage on RA4 with respect to Vss	0V to +8.5V
Total power dissipation (Note 1)	
Maximum current out of Vss pin	300 mA
Maximum current into VDD pin	250 mA
Input clamp current, IIK (VI < 0 or VI > VDD)	±20 mA
Output clamp current, loκ (Vo < 0 or Vo > VDD)	±20 mA
Maximum output current sunk by any I/O pin	25 mA
Maximum output current sourced by any I/O pin	25 mA
Maximum current sunk by PORTA and PORTB (combined)	200 mA
Maximum current sourced by PORTA and PORTB (combined)	200 mA
Maximum current sunk by PORTC	200 mA
Maximum current sourced by PORTC	200 mA

- **Note 1:** Power dissipation is calculated as follows: Pdis = VDD x {IDD  $\Sigma$  IOH} +  $\Sigma$  {(VDD-VOH) x IOH} +  $\Sigma$ (Vol x IOL)
  - 2: Voltage spikes below Vss at the  $\overline{\text{MCLR/VPP}}$  pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100 $\Omega$  should be used when applying a "low" level to the  $\overline{\text{MCLR/VPP}}$  pin, rather than pulling this pin directly to Vss.

† NOTICE: Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

FIGURE 13-1: PIC16C62B/72A-20 VOLTAGE-FREQUENCY GRAPH





FIGURE 13-2: PIC16LC62B/72A AND PIC16C62B/72A/JW VOLTAGE-FREQUENCY GRAPH






FIGURE 13-3: PIC16C62B/72A-04 VOLTAGE-FREQUENCY GRAPH

**Preliminary** © 1998 Microchip Technology Inc. DS35008B-page 83

## 13.1 DC Characteristics: PIC16C62B/72A-04 (Commercial, Industrial, Extended) PIC16C62B/72A-20 (Commercial, Industrial, Extended)

DC CHA	RACTE	RISTICS	Standar Operatir			0°C -40°C	
Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
D001 D001A	VDD	Supply Voltage	4.0 4.5 VBOR*	- - -	5.5 5.5 5.5	V V V	XT, RC and LP osc mode HS osc mode BOR enabled (Note 7)
D002*	VDR	RAM Data Retention Voltage (Note 1)	-	1.5	-	V	
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal	-	Vss	-	V	See section on Power-on Reset for details
D004* D004A*	SVDD	VDD Rise Rate to ensure internal Power-on Reset signal	0.05 TBD	-	-	V/ms	PWRT enabled (PWRTE bit clear) PWRT disabled (PWRTE bit set) See section on Power-on Reset for details
D005	VBOR	Brown-out Reset voltage trip point	3.65	-	4.35	V	BODEN bit set
D010	IDD	Supply Current (Note 2, 5)	-	2.7	5	mA	XT, RC osc modes FOSC = 4 MHz, VDD = 5.5V (Note 4)
D013			-	10	20	mA	HS osc mode Fosc = 20 MHz, VDD = 5.5V
D020 D021 D021B	IPD	Power-down Current (Note 3, 5)	- - - -	10.5 1.5 1.5 2.5	42 16 19 19	μΑ μΑ μΑ μΑ	VDD = 4.0V, WDT enabled, -40°C to +85°C VDD = 4.0V, WDT disabled, 0°C to +70°C VDD = 4.0V, WDT disabled, -40°C to +85°C VDD = 4.0V, WDT disabled, -40°C to +125°C
D022* D022A*	Δlwdt Δlbor	Module Differential Current (Note 6) Watchdog Timer Brown-out Reset		6.0 TBD	20 200	μΑ μΑ	WDTE BIT SET, VDD = 4.0V BODEN bit set, VDD = 5.0V

- \* These parameters are characterized but not tested.
- † Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.
- Note 1: This is the limit to which VDD can be lowered without losing RAM data.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors such as I/O pin loading and switching rate, oscillator type, internal code execution pattern, and temperature also have an impact on the current consumption.
    - The test conditions for all IDD measurements in active operation mode are:
    - OSC1 = external square wave, from rail to rail; all I/O pins tristated, pulled to VDD,
    - MCLR = VDD; WDT enabled/disabled as specified.
  - 3: The power-down current in SLEEP mode does not depend on the oscillator type. Power-down current is measured with the part in SLEEP mode, with all I/O pins in hi-impedance state and tied to VDD and Vss.
  - **4:** For RC osc mode, current through Rext is not included. The current through the resistor can be estimated by the formula Ir = VDD/2Rext (mA) with Rext in kOhm.
  - 5: Timer1 oscillator (when enabled) adds approximately 20 μA to the specification. This value is from characterization and is for design guidance only. This is not tested.
  - **6:** The  $\Delta$  current is the additional current consumed when this peripheral is enabled. This current should be added to the base IDD or IPD measurement.
  - 7: This is the voltage where the device enters the Brown-out Reset. When BOR is enabled, the device will perform a brown-out reset when VDD falls below VBOR.

## 13.2 DC Characteristics: PIC16LC62B/72A-04 (Commercial, Industrial)

DC CHA	RACTEI	RISTICS	Standard Operating Conditions (unless otherwise stated)  Operating temperature $0^{\circ}C \le TA \le +70^{\circ}C$ for commercial $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial				
Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
D001	VDD	Supply Voltage	2.5 VBOR*	-	5.5 5.5	V	LP, XT, RC osc modes (DC - 4 MHz) BOR enabled (Note 7)
D002*	VDR	RAM Data Retention Voltage (Note 1)	-	1.5	-	V	
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal	-	Vss	-	٧	See section on Power-on Reset for details
D004* D004A*	SVDD	VDD Rise Rate to ensure internal Power-on Reset signal	0.05 TBD	-	-	V/ms	PWRT enabled (PWRTE bit clear) PWRT disabled (PWRTE bit set) See section on Power-on Reset for details
D005	VBOR	Brown-out Reset voltage trip point	3.65	-	4.35	V	BODEN bit set
D010	IDD	Supply Current (Note 2, 5)	-	2.0	3.8	mA	XT, RC osc modes FOSC = 4 MHz, VDD = 3.0V (Note 4)
D010A			-	22.5	48	μА	LP OSC MODE FOSC = 32 kHz, VDD = 3.0V, WDT disabled
D020 D021 D021A	IPD	Power-down Current (Note 3, 5)	- - -	7.5 0.9 0.9	30 5 5	μΑ μΑ μΑ	VDD = 3.0V, WDT enabled, $-40^{\circ}$ C to $+85^{\circ}$ C VDD = 3.0V, WDT disabled, $0^{\circ}$ C to $+70^{\circ}$ C VDD = 3.0V, WDT disabled, $-40^{\circ}$ C to $+85^{\circ}$ C
D022* D022A*	Δlwdt Δlbor	Module Differential Current (Note 6) Watchdog Timer Brown-out Reset	- -	6.0 TBD	20 200	μΑ μΑ	WDTE BIT SET, VDD = 4.0V BODEN bit set, VDD = 5.0V

<sup>\*</sup> These parameters are characterized but not tested.

- Note 1: This is the limit to which VDD can be lowered without losing RAM data.
  - 2: The supply current is mainly a function of the operating voltage and frequency. Other factors such as I/O pin loading and switching rate, oscillator type, internal code execution pattern, and temperature also have an impact on the current consumption.
    - The test conditions for all IDD measurements in active operation mode are:
    - OSC1 = external square wave, from rail to rail; all I/O pins tristated, pulled to VDD,
    - MCLR = VDD; WDT enabled/disabled as specified.
  - 3: The power-down current in SLEEP mode does not depend on the oscillator type. Power-down current is measured with the part in SLEEP mode, with all I/O pins in hi-impedance state and tied to VDD and Vss.
  - **4:** For RC osc mode, current through Rext is not included. The current through the resistor can be estimated by the formula Ir = VDD/2Rext (mA) with Rext in kOhm.
  - 5: Timer1 oscillator (when enabled) adds approximately 20  $\mu$ A to the specification. This value is from characterization and is for design guidance only. This is not tested.
  - **6:** The  $\Delta$  current is the additional current consumed when this peripheral is enabled. This current should be added to the base IDD or IPD measurement.
  - 7: This is the voltage where the device enters the Brown-out Reset. When BOR is enabled, the device will perform a brown-out reset when VDD falls below VBOR.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

**DC CHARACTERISTICS** 

13.3 DC Characteristics: PIC16C62B/72A-04 (Commercial, Industrial, Extended)

PIC16C62B/72A-20 (Commercial, Industrial, Extended)

PIC16LC62B/72A-04 (Commercial, Industrial)

Standard Operating Conditions (unless otherwise stated)

Operating temperature  $0^{\circ}C \leq TA \leq +70^{\circ}C$  for commercial

-40°C  $\leq$  TA  $\leq$  +85°C for industrial -40°C  $\leq$  TA  $\leq$ +125°C for extended

Operating voltage VDD range as described in DC spec Section 13.1

and Section 13.2

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
		Input Low Voltage					
	VIL	I/O ports					
D030		with TTL buffer	Vss	-	0.15VDD	V	For entire VDD range
D030A			Vss	-	V8.0	V	4.5V ≤ VDD ≤ 5.5V
D031		with Schmitt Trigger buffer	Vss	-	0.2Vdd	V	
D032		MCLR, OSC1 (in RC mode)	Vss	-	0.2Vdd	V	
D033		OSC1 (in XT, HS and LP modes)	Vss	-	0.3VDD	V	Note1
		Input High Voltage					
	VIH	I/O ports		-			
D040		with TTL buffer	2.0	-	Vdd	V	4.5V ≤ VDD ≤ 5.5V
D040A			0.25VD D + 0.8V	-	Vdd	V	For entire VDD range
D041		with Schmitt Trigger buffer	0.8VDD	-	VDD	V	For entire VDD range
D042		MCLR	0.8VDD	-	VDD	V	
D042A		OSC1 (XT, HS and LP modes)	0.7Vdd	-	VDD	V	Note1
D043		OSC1 (in RC mode)	0.9Vpd	-	Vdd	V	
		Input Leakage Current (Notes 2, 3)					
D060	IIL	I/O ports	-	-	±1	μΑ	Vss ≤ VPIN ≤ VDD, Pin at hi-impedance
D061		MCLR, RA4/T0CKI	-	-	±5	μΑ	Vss ≤ VPIN ≤ VDD
D063		OSC1	-	-	±5	μΑ	Vss ≤ VPIN ≤ VDD, XT, HS and LP osc modes
D070	IPURB	PORTB weak pull-up current	50	250	400	μΑ	VDD = 5V, VPIN = VSS
D080	Vol	Output Low Voltage I/O ports	-	-	0.6	٧	IOL = 8.5 mA, VDD = 4.5V, -40°C to +85°C

These parameters are characterized but not tested.

- 2: The leakage current on the MCLR/VPP pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
- 3: Negative current is defined as current sourced by the pin.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

**Note 1:** In RC oscillator mode, the OSC1/CLKIN pin is a Schmitt Trigger input. It is not recommended that the device be driven with external clock in RC mode.

Standard Operating Conditions (unless otherwise stated)

Operating temperature  $0^{\circ}C \leq TA \leq +70^{\circ}C$  for commercial

-40°C  $\leq$  TA  $\leq$  +85°C for industrial -40°C  $\leq$  TA  $\leq$ +125°C for extended

Operating voltage VDD range as described in DC spec Section 13.1

and Section 13.2

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
			-	-	0.6	V	IOL = 7.0 mA, VDD = 4.5V, -40°C to +125°C
D083		OSC2/CLKOUT (RC osc mode)	-	-	0.6	V	IOL = 1.6 mA, $VDD = 4.5V$ , $-40^{\circ}C$ to $+85^{\circ}C$
			-	-	0.6	V	IOL = 1.2 mA, $VDD = 4.5V$ , $-40^{\circ}C$ to $+125^{\circ}C$
		Output High Voltage					
D090	Vон	I/O ports (Note 3)	VDD-0.7	-	-	V	IOH = $-3.0$ mA, VDD = $4.5$ V, $-40$ °C to $+85$ °C
			VDD-0.7	-	-	V	IOH = -2.5 mA, VDD = 4.5V, -40°C to +125°C
D092		OSC2/CLKOUT (RC osc mode)	VDD-0.7	-	-	V	IOH = -1.3 mA, VDD = $4.5$ V, $-40$ °C to $+85$ °C
			VDD-0.7	-	-	V	IOH = -1.0 mA, VDD = 4.5V, -40°C to +125°C
D150*	Vod	Open-Drain High Voltage	-	-	8.5	V	RA4 pin
		Capacitive Loading Specs on Output Pins					
D100	Cosc <sub>2</sub>	OSC2 pin	-	-	15	pF	In XT, HS and LP modes when external clock is used to drive OSC1.
D101	Сю	All I/O pins and OSC2 (in RC mode)	-	-	50	pF	
D102	Cb	SCL, SDA in I <sup>2</sup> C mode	-	-	400	pF	

<sup>\*</sup> These parameters are characterized but not tested.

**DC CHARACTERISTICS** 

- **Note 1:** In RC oscillator mode, the OSC1/CLKIN pin is a Schmitt Trigger input. It is not recommended that the device be driven with external clock in RC mode.
  - 2: The leakage current on the MCLR/VPP pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
  - 3: Negative current is defined as current sourced by the pin.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

## 13.4 AC (Timing) Characteristics

## 13.4.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created following one of the following formats:

1. TppS2p	pS	3. Tcc:st	(I <sup>2</sup> C specifications only)
2. TppS		4. Ts	(I <sup>2</sup> C specifications only)
Т			
F	Frequency	Т	Time
Lowercase	e letters (pp) and their meanings:		
рр			
СС	CCP1	osc	OSC1
ck	CLKOUT	rd	RD
CS	CS	rw	RD or WR
di	SDI	sc	SCK
do	SDO	SS	SS
dt	Data in	tO	T0CKI
io	I/O port	t1	T1CKI
mc	MCLR	wr	WR
Uppercase	e letters and their meanings:		
S			
F	Fall	Р	Period
Н	High	R	Rise
I	Invalid (Hi-impedance)	V	Valid
L	Low	Z	Hi-impedance
I <sup>2</sup> C only			
AA	output access	High	High
BUF	Bus free	Low	Low
Tcc:st (I <sup>2</sup>	C specifications only)		
CC			
HD	Hold	SU	Setup
ST			
DAT	DATA input hold	STO	STOP condition
STA	START condition		


## 13.4.2 TIMING CONDITIONS

The temperature and voltages specified in Table 13-1 apply to all timing specifications unless otherwise noted. Figure 13-4 specifies the load conditions for the timing specifications.

## TABLE 13-1: TEMPERATURE AND VOLTAGE SPECIFICATIONS - AC

AC CHARACTERISTICS	Standard Operating Conditions (unless otherwise stated)							
	Operating temperature $0^{\circ}C \le TA \le +70^{\circ}C$ for commercial							
	-40°C ≤ TA ≤ +85°C for industrial							
	-40°C ≤ TA ≤+125°C for extended							
	Operating voltage VDD range as described in DC spec Section 13.1 and Section 13.2.							
	LC parts operate for commercial/industrial temp's only.							

## FIGURE 13-4: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



### 13.4.3 TIMING DIAGRAMS AND SPECIFICATIONS

FIGURE 13-5: EXTERNAL CLOCK TIMING




TABLE 13-2: EXTERNAL CLOCK TIMING REQUIREMENTS

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
1A	Fosc	External CLKIN Frequency	DC	_	4	MHz	RC and XT osc modes
		(Note 1)	DC	_	4	MHz	HS osc mode (-04)
			DC	_	20	MHz	HS osc mode (-20)
			DC	_	200	kHz	LP osc mode
		Oscillator Frequency	DC	_	4	MHz	RC osc mode
		(Note 1)	0.1	_	4	MHz	XT osc mode
			4	_	20	MHz	HS osc mode
			5		200	kHz	LP osc mode
1	Tosc	External CLKIN Period	250		_	ns	RC and XT osc modes
		(Note 1)	250	_	_	ns	HS osc mode (-04)
			50	_	_	ns	HS osc mode (-20)
			5	_	_	μs	LP osc mode
		Oscillator Period	250	_	_	ns	RC osc mode
		(Note 1)	250	_	10,000	ns	XT osc mode
			250	_	250	ns	HS osc mode (-04)
			50	_	250	ns	HS osc mode (-20)
			5	_		μs	LP osc mode
2	TCY	Instruction Cycle Time (Note 1)	200		DC	ns	Tcy = 4/Fosc
3*	TosL,	External Clock in (OSC1) High	100		_	ns	XT oscillator
	TosH	or Low Time	2.5	_	_	μs	LP oscillator
			15	_	_	ns	HS oscillator
4*	TosR,	External Clock in (OSC1) Rise	_	_	25	ns	XT oscillator
	TosF	or Fall Time	_	_	50	ns	LP oscillator
			_	_	15	ns	HS oscillator

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time-base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKIN pin.

When an external clock input is used, the "Max." cycle time limit is "DC" (no clock) for all devices.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 13-6: CLKOUT AND I/O TIMING




TABLE 13-3: CLKOUT AND I/O TIMING REQUIREMENTS

Param No.	Sym	Characteristic		Min	Тур†	Max	Units	Conditions
10*	TosH2ckL	OSC1↑ to CLKOUT↓	_	75	200	ns	Note 1	
11*	TosH2ckH	OSC1↑ to CLKOUT↑		_	75	200	ns	Note 1
12*	TckR	CLKOUT rise time		_	35	100	ns	Note 1
13*	TckF	CLKOUT fall time		_	35	100	ns	Note 1
14*	TckL2ioV	CLKOUT ↓ to Port out valid		_	_	0.5Tcy + 20	ns	Note 1
15*	TioV2ckH	Port in valid before CLKOU	т ↑	Tosc + 200	_	_	ns	Note 1
16*	TckH2ioI	Port in hold after CLKOUT	$\uparrow$	0	_	_	ns	Note 1
17*	TosH2ioV	OSC1↑ (Q1 cycle) to Port of	out valid	_	50	150	ns	
18*	TosH2iol	OSC1↑ (Q2 cycle) to Port	PIC16CXX	100	_	_	ns	
18A*		input invalid (I/O in hold time)	PIC16LCXX	200	_	_	ns	
19*	TioV2osH	Port input valid to OSC11 (	/O in setup time)	0	_	_	ns	
20*	TioR	Port output rise time	PIC16CXX	_	10	40	ns	
20A*			PIC16LCXX	_	_	80	ns	
21*	TioF	Port output fall time	PIC16CXX	_	10	40	ns	
21A*			PIC16LCXX	_	_	80	ns	
22††*	Tinp	INT pin high or low time		Tcy	_	_	ns	
23††*	Trbp	RB7:RB4 change INT high	or low time	Tcy	_	_	ns	

<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** Measurements are taken in RC Mode where CLKOUT output is 4 x Tosc.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

<sup>††</sup>These parameters are asynchronous events not related to any internal clock edge.

FIGURE 13-7: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING




FIGURE 13-8: BROWN-OUT RESET TIMING




TABLE 13-4: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER AND BROWN-OUT RESET REQUIREMENTS

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
30	TmcL	MCLR Pulse Width (low)	2	_	_	μs	VDD = 5V, -40°C to +125°C
31*	Twdt	Watchdog Timer Time-out Period (No Prescaler)	7	18	33	ms	VDD = 5V, -40°C to +125°C
32	Tost	Oscillator Start-up Timer Period	_	1024 Tosc	_	_	Tosc = OSC1 period
33*	Tpwrt	Power-up Timer Period	28	72	132	ms	$VDD = 5V, -40^{\circ}C \text{ to } +125^{\circ}C$
34	Tıoz	I/O Hi-impedance from MCLR Low or WDT reset	_	_	2.1	μs	
35	TBOR	Brown-out Reset Pulse Width	100	_	_	μs	VDD ≤ BVDD (D005)

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

T0CKI T10SO/T1CKI TMR0 or TMR1 Note: Refer to Figure 13-4 for load conditions.

FIGURE 13-9: TIMERO AND TIMER1 EXTERNAL CLOCK TIMINGS

**TABLE 13-5**: **TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS** 

Param No.	Sym		Characteristic		Min	Тур†	Max	Units	Conditions
40*	Tt0H	T0CKI High Pulse W	/idth	No Prescaler	0.5Tcy + 20	_	_	ns	Must also meet
				With Prescaler	10	_	_	ns	parameter 42
41*	TtOL	T0CKI Low Pulse W	idth	No Prescaler	0.5Tcy + 20	_	_	ns	Must also meet
		,		With Prescaler	10	_	_	ns	parameter 42
42*	Tt0P	T0CKI Period		No Prescaler	Tcy + 40	_	_	ns	
				With Prescaler	Greater of: 20 or TCY + 40 N	_	_	ns	N = prescale value (2, 4,, 256)
45*	Tt1H	T1CKI High Time	Synchronous, P	rescaler = 1	0.5Tcy + 20	_	_	ns	Must also meet
			Synchronous,	PIC16CXX	15	_	_	ns	parameter 47
			Prescaler = 2,4,8	PIC16LCXX	25	_	_	ns	
			Asynchronous	PIC16CXX	30	_	_	ns	
				PIC16LCXX	50	_	_	ns	
46*	Tt1L	T1CKI Low Time	Synchronous, P	rescaler = 1	0.5Tcy + 20	_	_	ns	Must also meet
			Synchronous, Prescaler = 2,4,8	PIC16CXX	15	_	_	ns	parameter 47
				PIC16LCXX	25	_	_	ns	
			Asynchronous	PIC16CXX	30	_	_	ns	
				PIC16LCXX	50	_	_	ns	
47*	Tt1P	T1CKI input period	Synchronous	PIC16CXX	GREATER OF: 30 OR <u>TCY + 40</u> N	-	_	ns	N = prescale value (1, 2, 4, 8)
				PIC16LCXX	GREATER OF: 50 OR <u>TCY + 40</u> N				N = prescale value (1, 2, 4, 8)
			Asynchronous	PIC16CXX	60	_	_	ns	
				PIC16LCXX	100	_	_	ns	
	Ft1		cillator input frequency range enabled by setting bit T1OSCEN)		DC	_	200	kHz	
48	TCKEZtmr1	Delay from external	clock edge to time	er increment	2Tosc	_	7Tosc	_	

**Preliminary** © 1998 Microchip Technology Inc. DS35008B-page 93

These parameters are characterized but not tested.
 Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 13-10: CAPTURE/COMPARE/PWM TIMINGS




TABLE 13-6: CAPTURE/COMPARE/PWM REQUIREMENTS

Param	Sym		Characteristic			Typ†	Max	Units	Conditions
No.									
50*	TccL	CCP1 input low	No Prescaler		0.5Tcy + 20	_	_	ns	
		time	With Prescaler	PIC16CXX	10	_	_	ns	
				PIC16LCXX	20	_	_	ns	
51*	TccH	CCP1 input high	No Prescaler		0.5Tcy + 20	_	_	ns	
		time	With Prescaler	PIC16CXX	10	_	_	ns	
				PIC16LCXX	20	_	_	ns	
52*	TccP	CCP1 input period	d		3Tcy + 40 N	_	_	ns	N = prescale value (1,4, or 16)
53*	TccR	CCP1 output rise	time	PIC16CXX	_	10	25	ns	
				PIC16LCXX	_	25	45	ns	
54*	TccF	CCP1 output fall t	ime	PIC16CXX	_	10	25	ns	
				PIC16LCXX	_	25	45	ns	

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.




FIGURE 13-11: EXAMPLE SPI MASTER MODE TIMING (CKE = 0)

TABLE 13-7: EXAMPLE SPI MODE REQUIREMENTS (MASTER MODE, CKE = 0)

Param. No.	Symbol	Characterist	ic	Min	Тур†	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input		Tcy	_	_	ns	
71	TscH	SCK input high time	Continuous	1.25Tcy + 30	_	_	ns	
71A		(slave mode)	Single Byte	40	_	_	ns	Note 1
72	TscL	SCK input low time	Continuous	1.25Tcy + 30	_	_	ns	
72A		(slave mode)	Single Byte	40	_	_	ns	Note 1
73	TdiV2scH, TdiV2scL	Setup time of SDI data input to SCK edge		100	_	_	ns	
73A	Тв2в	Last clock edge of Byte1 to the 1st clock edge of Byte2		1.5Tcy + 40	_	_	ns	Note 1
74	TscH2diL, TscL2diL	Hold time of SDI data input	t to SCK edge	100	_	_	ns	
75	TdoR	SDO data output rise time	PIC16CXX	_	10	25	ns	
			PIC16LCXX	_	20	45	ns	
76	TdoF	SDO data output fall time		_	10	25	ns	
78	TscR	SCK output rise time	PIC16CXX	_	10	25	ns	
		(master mode)	naster mode) PIC16LCXX		20	45	ns	
79	TscF	SCK output fall time (master mode)		_	10	25	ns	
80	TscH2doV,	SDO data output valid	PIC16CXX	_	_	50	ns	
	TscL2doV	after SCK edge	PIC16LCXX		_	100	ns	

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Specification 73A is only required if specifications 71A and 72A are used.

SS SCK (CKP = 0)SCK (CKP = 1)MSb LSb SDO 75, 76 SDI MSb IN LSb IN

FIGURE 13-12: EXAMPLE SPI MASTER MODE TIMING (CKE = 1)

**TABLE 13-8: EXAMPLE SPI MODE REQUIREMENTS (MASTER MODE, CKE = 1)** 

Refer to Figure 13-4 for load conditions.

Param.	Symbol	Characteris	tic	Min	Тур†	Max	Units	Conditions
71	TscH	SCK input high time	Continuous	1.25Tcy + 30	_	_	ns	
71A		(slave mode)	Single Byte	40	_	_	ns	Note 1
72	TscL	SCK input low time	Continuous	1.25Tcy + 30	_	_	ns	
72A		(slave mode)	Single Byte	40	_	_	ns	Note 1
73	TdiV2scH, TdiV2scL	Setup time of SDI data inpedge	out to SCK	100	_	_	ns	
73A	Тв2в	Last clock edge of Byte1 to the 1st clock edge of Byte2		1.5Tcy + 40	_	_	ns	Note 1
74	TscH2diL, TscL2diL	Hold time of SDI data input to SCK edge		100	_	_	ns	
75	TdoR	SDO data output rise	PIC16CXX	_	10	25	ns	
		time	PIC16LCXX		20	45	ns	
76	TdoF	SDO data output fall time		_	10	25	ns	
78	TscR	SCK output rise time	PIC16CXX	_	10	25	ns	
		(master mode)	PIC16LCXX		20	45	ns	
79	TscF	SCK output fall time (mas	ter mode)	_	10	25	ns	
80	TscH2doV,	SDO data output valid	PIC16CXX		—	50	ns	
	TscL2doV	after SCK edge	PIC16LCXX		_	100	ns	
81	TdoV2scH, TdoV2scL	SDO data output setup to	SCK edge	Tcy		_	ns	

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Specification 73A is only required if specifications 71A and 72A are used.




FIGURE 13-13: EXAMPLE SPI SLAVE MODE TIMING (CKE = 0)

TABLE 13-9: EXAMPLE SPI MODE REQUIREMENTS (SLAVE MODE TIMING (CKE = 0)

Param. No.	Symbol	Characterist	ic	Min	Тур†	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input		Tcy	_	_	ns	
71	TscH	SCK input high time Continuous		1.25Tcy + 30	_	_	ns	
71A		(slave mode)	Single Byte	40	_	_	ns	Note 1
72	TscL	SCK input low time	Continuous	1.25Tcy + 30	_	_	ns	
72A		(slave mode)	Single Byte	40	_	_	ns	Note 1
73	TdiV2scH, TdiV2scL	Setup time of SDI data inp	ut to SCK edge	100	_	_	ns	
73A	Тв2в	Last clock edge of Byte1 to the 1st clock edge of Byte2		1.5Tcy + 40	_	_	ns	Note 1
74	TscH2diL, TscL2diL	Hold time of SDI data inpu	t to SCK edge	100	_	_	ns	
75	TdoR	SDO data output rise time	PIC16CXX	_	10	25	ns	
			PIC16LCXX		20	45	ns	
76	TdoF	SDO data output fall time		_	10	25	ns	
77	TssH2doZ	SS↑ to SDO output hi-impe	edance	10	_	50	ns	
78	TscR	SCK output rise time	PIC16CXX		10	25	ns	
		(master mode)	PIC16LCXX		20	45	ns	
79	TscF	SCK output fall time (maste	er mode)	_	10	25	ns	
80	TscH2doV,	SDO data output valid	PIC16CXX	_	_	50	ns	
	TscL2doV	after SCK edge	PIC16LCXX		_	100	ns	
83	TscH2ssH, TscL2ssH	SS ↑ after SCK edge		1.5Tcy + 40	_	_	ns	

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Specification 73A is only required if specifications 71A and 72A are used.

FIGURE 13-14: EXAMPLE SPI SLAVE MODE TIMING (CKE = 1)




TABLE 13-10: EXAMPLE SPI SLAVE MODE REQUIREMENTS (CKE = 1)

Param. No.	Symbol	Characteris	stic	Min	Тур†	Max	Units	Conditions
70	TssL2scH, TssL2scL	SS↓ to SCK↓ or SCK↑ input		Tcy	_	_	ns	
71	TscH	SCK input high time	Continuous	1.25Tcy + 30	_	_	ns	
71A		(slave mode)	Single Byte	40	_	_	ns	Note 1
72	TscL	SCK input low time	Continuous	1.25Tcy + 30	_	_	ns	
72A		(slave mode)	Single Byte	40	_	_	ns	Note 1
73A	Тв2в	Last clock edge of Byte1 edge of Byte2	to the 1st clock	1.5Tcy + 40	_	_	ns	Note 1
74	TscH2diL, TscL2diL	Hold time of SDI data inp	Hold time of SDI data input to SCK edge		_	_	ns	
75	TdoR	SDO data output rise	PIC16CXX	_	10	25	ns	
		time	PIC16LCXX		20	45	ns	
76	TdoF	SDO data output fall time	Э	_	10	25	ns	
77	TssH2doZ	SS↑ to SDO output hi-im	pedance	10	_	50	ns	
78	TscR	SCK output rise time	PIC16CXX	_	10	25	ns	
		(master mode)	PIC16LCXX	_	20	45	ns	
79	TscF	SCK output fall time (ma	ster mode)	_	10	25	ns	
80	TscH2doV,	SDO data output valid	PIC16CXX	_	_	50	ns	
	TscL2doV	after SCK edge	PIC16LCXX	_	_	100	ns	
82	TssL2doV	SDO data output valid	PIC16CXX	_	_	50	ns	
		after SS↓ edge	PIC16LCXX	_	_	100	ns	
83	TscH2ssH, TscL2ssH	SS ↑ after SCK edge		1.5Tcy + 40	_	_	ns	

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: Specification 73A is only required if specifications 71A and 72A are used.

FIGURE 13-15: I<sup>2</sup>C BUS START/STOP BITS TIMING




TABLE 13-11: I<sup>2</sup>C BUS START/STOP BITS REQUIREMENTS

Parameter	Sym	Characteristic		Min	Ту	Max	Unit	Conditions
No.					р		s	
90*	TSU:STA	START condition	100 kHz mode	4700	_	_	ns	Only relevant for repeated
		Setup time	400 kHz mode	600	_	_		START condition
91*	THD:STA	START condition	100 kHz mode	4000	_	_	ns	After this period the first clock
		Hold time	400 kHz mode	600	_	_		pulse is generated
92*	Tsu:sto	STOP condition	100 kHz mode	4700	_	_	ns	
		Setup time	400 kHz mode	600	_	_		
93	THD:STO	STOP condition	100 kHz mode	4000	_	_	ns	
		Hold time	400 kHz mode	600	_	_		

<sup>\*</sup> These parameters are characterized but not tested.

## PIC16C62B/72A

## FIGURE 13-16: I<sup>2</sup>C BUS DATA TIMING




TABLE 13-12: I<sup>2</sup>C BUS DATA REQUIREMENTS

Param. No.	Sym Characteristic		Min	Max	Units	Conditions	
100*	THIGH	Clock high time	100 kHz mode	4.0	_	μs	Device must operate at a minimum of 1.5 MHz
			400 kHz mode	0.6	_	μs	Device must operate at a minimum of 10 MHz
			SSP Module	1.5TcY	_		
101*	TLOW	Clock low time	100 kHz mode	4.7	_	μs	Device must operate at a minimum of 1.5 MHz
			400 kHz mode	1.3	_	μs	Device must operate at a minimum of 10 MHz
			SSP Module	1.5TcY	_		
102* TR		SDA and SCL rise	100 kHz mode	_	1000	ns	
	time		400 kHz mode	20 + 0.1Cb	300	ns	Cb is specified to be from 10-400 pF
103* TF	TF	SDA and SCL fall	100 kHz mode	_	300	ns	
		time	400 kHz mode	20 + 0.1Cb	300	ns	Cb is specified to be from 10-400 pF
90*	90* TSU:STA	START condition setup time	100 kHz mode	4.7	_	μs	Only relevant for repeated
			400 kHz mode	0.6	_	μs	START condition
91*	THD:STA	START condition hold	100 kHz mode	4.0	_	μs	After this period the first clock
		time	400 kHz mode	0.6	_	μs	pulse is generated
106*	THD:DAT	Data input hold time	100 kHz mode	0	_	ns	
			400 kHz mode	0	0.9	μS	
107*	TSU:DAT	DAT Data input setup time	100 kHz mode	250	_	ns	Note 2
			400 kHz mode	100	_	ns	
92*	Tsu:sto	STOP condition setup	100 kHz mode	4.7	_	μs	
		time	400 kHz mode	0.6	_	μs	
109*	TAA	Output valid from	100 kHz mode	_	3500	ns	Note 1
		clock	400 kHz mode	_		ns	
110*	TBUF	Bus free time	100 kHz mode	4.7	_	μs	Time the bus must be free
			400 kHz mode	1.3	_	μs	before a new transmission can start
	Cb	Bus capacitive loading			400	pF	

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of START or STOP conditions.

<sup>2:</sup> A fast-mode (400 kHz) I<sup>2</sup>C-bus device can be used in a standard-mode (100 kHz) I<sup>2</sup>C-bus system, but the requirement Tsu:DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the LOW period of the SCL signal. If such a device does stretch the LOW period of the SCL signal, it must output the next data bit to the SDA line TR max.+tsu;DAT = 1000 + 250 = 1250 ns (according to the standard-mode I<sup>2</sup>C bus specification) before the SCL line is released.

TABLE 13-13: A/D CONVERTER CHARACTERISTICS:
PIC16C72A-04 (COMMERCIAL, INDUSTRIAL, EXTENDED)
PIC16C72A-20 (COMMERCIAL, INDUSTRIAL, EXTENDED)

PIC16LC72A-04 (COMMERCIAL, INDUSTRIAL)

Param No.	Sym	n Characteristic		Min	Typ†	Max	Units	Conditions
A01	NR	Resolution	_	_	8-bits	bit	$VREF = VDD = 5.12V$ , $VSS \le VAIN \le VREF$	
A02	EABS	Total Absolute error	_	_	< ± 1	LSB	VREF = VDD = 5.12V, VSS ≤ VAIN ≤ VREF	
A03	EIL	Integral linearity error	_	_	< ± 1	LSB	$VREF = VDD = 5.12V$ , $VSS \le VAIN \le VREF$	
A04	EDL	Differential linearity e	_	_	< ± 1	LSB	$VREF = VDD = 5.12V$ , $VSS \le VAIN \le VREF$	
A05	EFS	Full scale error		_	< ± 1	LSB	VREF = VDD = 5.12V, VSS ≤ VAIN ≤ VREF	
A06	Eoff	Offset error		_	< ± 1	LSB	VREF = VDD = 5.12V, VSS ≤ VAIN ≤ VREF	
A10	_	Monotonicity	_	guaranteed (Note 3)		_	Vss ≤ Vain ≤ Vref	
A20	VREF	Reference voltage	2.5V	_	VDD + 0.3	V		
A25	Vain	Analog input voltage		Vss - 0.3	_	VREF + 0.3	V	
A30	ZAIN	Recommended impe analog voltage sourc	_	_	10.0	kΩ		
A40	IAD	A/D conversion	PIC16CXX	_	180	1	μΑ	Average current con-
		current (VDD)	PIC16LCXX	_	90	ı	μΑ	sumption when A/D is on. (Note 1)
A50	O IREF VREF input current (Note 2)		10	_	1000	μΑ	During VAIN acquisition. Based on differential of VHOLD to VAIN to charge CHOLD, see Section 9.1.	
								During A/D conver- sion cycle


<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** When A/D is off, it will not consume any current other than minor leakage current. The power-down current spec includes any such leakage from the A/D module.

- 2: VREF current is from RA3 pin or VDD pin, whichever is selected as reference input.
- 3: The A/D conversion result never decreases with an increase in the Input Voltage and has no missing codes.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

## FIGURE 13-17: A/D CONVERSION TIMING



**Note 1:** If the A/D clock source is selected as RC, a time of TcY is added before the A/D clock starts. This allows the SLEEP instruction to be executed.

**TABLE 13-14: A/D CONVERSION REQUIREMENTS** 

Param No.	Sym	Characteristic		Min	Тур†	Max	Unit s	Conditions
130	TAD	A/D clock period	PIC16CXX	1.6	_	_	μs	Tosc based, VREF ≥ 3.0V
			PIC16LCXX	2.0	_		μs	Tosc based, VREF full range
			PIC16CXX	2.0	4.0	6.0	μs	A/D RC Mode
			PIC16LCXX	3.0	6.0	9.0	μs	A/D RC Mode
131	TCNV	Conversion time (not time) (Note 1)	including S/H	11	_	11	TAD	
132	TACQ	Acquisition time		Note 2	20	_	μs	
				5*		_	μs	The minimum time is the amplifier settling time. This may be used if the "new" input voltage has not changed by more than 1 LSb (i.e., 20.0 mV @ 5.12V) from the last sampled voltage (as stated on CHOLD).
134	TGO	Q4 to A/D clock start		_	Tosc/2	_	_	If the A/D clock source is selected as RC, a time of Tcy is added before the A/D clock starts. This allows the SLEEP instruction to be executed.
135	Tswc	Switching from convetime	ert → sample	1.5		ı	TAD	

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: ADRES register may be read on the following TcY cycle.

2: See Section 9.1 for min conditions.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

## 14.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES

The graphs and tables provided in this section are for design guidance and are not tested.

In some graphs or tables, the data presented are **outside specified operating range** (i.e., outside specified VDD range). This is for **information only** and devices are guaranteed to operate properly only within the specified range.

The data presented in this section is a **statistical summary** of data collected on units from different lots over a period of time and matrix samples. 'Typical' represents the mean of the distribution at  $25^{\circ}$ C. 'Max' or 'min' represents (mean +  $3\sigma$ ) or (mean -  $3\sigma$ ) respectively, where  $\sigma$  is standard deviation, over the whole temperature range.

## Graphs and Tables not available at this time.

Data is not available at this time but you may reference the *PIC16C72 Series Data Sheet* (DS39016,) DC and AC characteristic section, which contains data similar to what is expected.

## PIC16C62B/72A

**NOTES:** 

## 15.0 PACKAGING INFORMATION

## 15.1 Package Marking Information


28-Lead PDIP (Skinny DIP)



## Example



#### 28-Lead CERDIP Windowed



### Example




### 28-Lead SOIC



## Example



### 28-Lead SSOP




### Example



Legend: MM...M Microchip part number information XX...XCustomer specific information\* AΑ Year code (last 2 digits of calendar year) BB Week code (week of January 1 is week '01') Facility code of the plant at which wafer is manufactured С O = Outside Vendor C = 5" Line S = 6" Line H = 8" Line D Mask revision number Ε Assembly code of the plant or country of origin in which part was assembled Note: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line thus limiting the number of available characters for customer specific information.

\* Standard OTP marking consists of Microchip part number, year code, week code, facility code, mask rev#, and assembly code. For OTP marking beyond this, certain price adders apply. Please check with your Microchip Sales Office. For QTP devices, any special marking adders are included in QTP price.

#### 28-Lead Skinny Plastic Dual In-line (SP) - 300 mil (PDIP) 15.2



		INCHES*		MILLIMETERS			
Dimension	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		28			28	
Pitch	р		.100			2.54	
Top to Seating Plane	Α	.140	.150	.160	3.56	3.81	4.06
Molded Package Thickness	A2	.125	.130	.135	3.18	3.30	3.43
Base to Seating Plane	A1	.015			0.38		
Shoulder to Shoulder Width	E	.300	.313	.325	7.62	7.94	8.26
Molded Package Width	E1	.279	.307	.335	7.09	7.80	8.51
Overall Length	D	1.345	1.365	1.385	34.16	34.67	35.18
Tip to Seating Plane	L	.125	.130	.135	3.18	3.30	3.43
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38
Upper Lead Width	B1	.040	.053	.065	1.02	1.33	1.65
Lower Lead Width	В	.016	.019	.022	0.41	0.48	0.56
Overall Row Spacing	eB	.320	.350	.430	8.13	8.89	10.92
Mold Draft Angle Top	α	5	10	15	5	10	15
Mold Draft Angle Bottom	β	5	10	15	5	10	15


\*Controlling Parameter

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MO-095

Drawing No. C04-070


## 15.3 <u>28-Lead Ceramic Dual In-line with Window (JW) – 300 mil (CERDIP)</u>



		INCHES*		MILLIMETERS			
Dimension	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		28			28	
Pitch	р		.100			2.54	
Top to Seating Plane	Α	.170	.183	.195	4.32	4.64	4.95
Ceramic Package Height	A2	.155	.160	.165	3.94	4.06	4.19
Standoff	A1	.015	.023	.030	0.38	0.57	0.76
Shoulder to Shoulder Width	Е	.300	.313	.325	7.62	7.94	8.26
Ceramic Pkg. Width	E1	.285	.290	.295	7.24	7.37	7.49
Overall Length	D	1.430	1.458	1.485	36.32	37.02	37.72
Tip to Seating Plane	L	.135	.140	.145	3.43	3.56	3.68
Lead Thickness	С	.008	.010	.012	0.20	0.25	0.30
Upper Lead Width	B1	.050	.058	.065	1.27	1.46	1.65
Lower Lead Width	В	.016	.019	.021	0.41	0.47	0.53
Overall Row Spacing	eВ	.345	.385	.425	8.76	9.78	10.80
Window Width	W1	.130	.140	.150	3.30	3.56	3.81
Window Length	W2	.290	.300	.310	7.37	7.62	7.87

\*Controlling Parameter
JEDEC Equivalent: MO-058
Drawing No. C04-080

#### 28-Lead Plastic Small Outline (SO) - Wide, 300 mil (SOIC) 15.4




		INCHES*		MILLIMETERS			
Dimension	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		28			28	
Pitch	р		.050			1.27	
Overall Height	Α	.093	.099	.104	2.36	2.50	2.64
Molded Package Thickness	A2	.088	.091	.094	2.24	2.31	2.39
Standoff	A1	.004	.008	.012	0.10	0.20	0.30
Overall Width	Е	.394	.407	.420	10.01	10.34	10.67
Molded Package Width	E1	.288	.295	.299	7.32	7.49	7.59
Overall Length	D	.695	.704	.712	17.65	17.87	18.08
Chamfer Distance	h	.010	.020	.029	0.25	0.50	0.74
Foot Length	L	.016	.033	.050	0.41	0.84	1.27
Foot Angle Top	ф	0	4	8	0	4	8
Lead Thickness	С	.009	.011	.013	0.23	0.28	0.33
Lead Width	В	.014	.017	.020	0.36	0.42	0.51
Mold Draft Angle Top	α	0	12	15	0	12	15
Mold Draft Angle Bottom	β	0	12	15	0	12	15

<sup>\*</sup>Controlling Parameter

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MS-013

Drawing No. C04-052

#### 28-Lead Plastic Shrink Small Outline (SS) - 209 mil, 5.30 mm (SSOP) 15.5



		INCHES			MILLIMETERS*		
Dimensio	n Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	р		.026			0.66	
Overall Height	Α	.068	.073	.078	1.73	1.85	1.98
Molded Package Thickness	A2	.064	.068	.072	1.63	1.73	1.83
Standoff	A1	.002	.006	.010	0.05	0.15	0.25
Overall Width	Е	.299	.309	.319	7.59	7.85	8.10
Molded Package Width	E1	.201	.207	.212	5.11	5.25	5.38
Overall Length	D	.396	.402	.407	10.06	10.20	10.34
Foot Length	L	.022	.030	.037	0.56	0.75	0.94
Lead Thickness	С	.004	.007	.010	0.10	0.18	0.25
Foot Angle	φ	0	4	8	0.00	101.60	203.20
Lead Width	В	.010	.013	.015	0.25	0.32	0.38
Mold Draft Angle Top	α	0	5	10	0	5	10
Mold Draft Angle Bottom	β	0	5	10	0	5	10

<sup>\*</sup>Controlling Parameter

Notes:
Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side.

JEDEC Equivalent: MS-150

Descript No. 204-273

Drawing No. C04-073

**Preliminary** © 1999 Microchip Technology Inc. DS35008B-page 109

**NOTES:** 

## **APPENDIX A: REVISION HISTORY**

Version	Date	Revision Description
A	7/98	This is a new data sheet. However, the devices described in this data sheet are the upgrades to the devices found in the <i>PIC16C6X Data Sheet</i> , DS30234, and the <i>PIC16C7X Data Sheet</i> , DS30390.

APPENDIX B: CONVERSION CONSIDERATIONS

Considerations for converting from previous versions of devices to the ones listed in this data sheet are listed in Table B-1.

## TABLE B-1: CONVERSION CONSIDERATIONS

Difference	PIC16C62A/72	PIC16C62B/72A	
Voltage Range	2.5V - 6.0V	2.5V - 5.5V	
SSP module	Basic SSP (2 mode SPI)	SSP (4 mode SPI)	
CCP module	CCP does not reset TMR1 when in special event trigger mode.	N/A	
Timer1 module	Writing to TMR1L register can cause over-flow in TMR1H register.	N/A	

© 1999 Microchip Technology Inc. Preliminary DS35008B-page 111

## APPENDIX C: MIGRATION FROM BASE-LINE TO MID-RANGE DEVICES

This section discusses how to migrate from a baseline device (i.e., PIC16C5X) to a mid-range device (i.e., PIC16CXXX).

The following are the list of modifications over the PIC16C5X microcontroller family:

- Instruction word length is increased to 14-bits.
   This allows larger page sizes both in program memory (2K now as opposed to 512 before) and register file (128 bytes now versus 32 bytes before).
- A PC high latch register (PCLATH) is added to handle program memory paging. Bits PA2, PA1, PA0 are removed from STATUS register.
- 3. Data memory paging is redefined slightly. STATUS register is modified.
- Four new instructions have been added: RETURN, RETFIE, ADDLW, and SUBLW. Two instructions TRIS and OPTION are being phased out although they are kept for compati-bility with PIC16C5X.
- OPTION\_REG and TRIS registers are made addressable.
- Interrupt capability is added. Interrupt vector is at 0004h.
- 7. Stack size is increased to 8 deep.
- 8. Reset vector is changed to 0000h.
- Reset of all registers is revisited. Five different reset (and wake-up) types are recognized. Registers are reset differently.
- Wake up from SLEEP through interrupt is added.

- 11. Two separate timers, Oscillator Start-up Timer (OST) and Power-up Timer (PWRT) are included for more reliable power-up. These timers are invoked selectively to avoid unnecessary delays on power-up and wake-up.
- 12. PORTB has weak pull-ups and interrupt on change feature.
- 13. T0CKI pin is also a port pin (RA4) now.
- 14. FSR is made a full eight bit register.
- 15. "In-circuit serial programming" is made possible. The user can program PIC16CXX devices using only five pins: VDD, Vss, MCLR/VPP, RB6 (clock) and RB7 (data in/out).
- 16. PCON status register is added with a Power-on Reset status bit (POR).
- Code protection scheme is enhanced such that portions of the program memory can be protected, while the remainder is unprotected.
- 18. Brown-out protection circuitry has been added. Controlled by configuration word bit BODEN. Brown-out reset ensures the device is placed in a reset condition if VDD dips below a fixed setpoint.

To convert code written for PIC16C5X to PIC16CXXX, the user should take the following steps:

- Remove any program memory page select operations (PA2, PA1, PA0 bits) for CALL, GOTO.
- Revisit any computed jump operations (write to PC or add to PC, etc.) to make sure page bits are set properly under the new scheme.
- 3. Eliminate any data memory page switching. Redefine data variables to reallocate them.
- Verify all writes to STATUS, OPTION, and FSR registers since these have changed.
- 5. Change reset vector to 0000h.

#### **INDEX** Α Code Protection .......55, 66 A/D ......49 A/D Converter Enable (ADIE Bit) ......14 A/D Converter Flag (ADIF Bit) ......15, 51 Compare (CCP Module) ......35 Block Diagram .......35 A/D Converter Interrupt, Configuring ......51 CCP Pin Configuration ......35 CCPR1H:CCPR1L Registers .......35 Special Event Trigger ......29, 35, 54 Analog Port Pins ......6 Analog Port Pins, Configuring ......53 Configuration Bits ......55 Block Diagram .....51 Block Diagram, Analog Input Model ......52 Channel Select (CHS2:CHS0 Bits) ......49 Clock Select (ADCS1:ADCS0 Bits) ......49 Data Memory ...... 8 Configuring the Module ......51 Bank Select (RP1:RP0 Bits) ......8, 11 Conversion Clock (TAD) ......53 General Purpose Registers ...... 8 Register File Map ...... 8 Conversions ......54 Special Function Registers .......9 Converter Characteristics ......101 DC Characteristics ......84, 86 Module On/Off (ADON Bit) ......49 Port Configuration Control (PCFG2:PCFG0 Bits) ...... 50 Sampling Requirements ......52 Special Event Trigger (CCP) ......35, 54 Timing Diagram ......102 Electrical Characteristics ...... 81 Absolute Maximum Ratings ......81 ADON Bit ......49 CHS2:CHS0 Bits ......49 Firmware Instructions ...... 67 ADCON1 Register ......10, 49, 50 PCFG2:PCFG0 Bits ......50 Architecture ACK Pulse ......41, 42, 43, 44, 45 PIC16C62B/PIC16C72A Block Diagram .....5 Addressing ...... 42 Assembler Block Diagram ......41 MPASM Assembler ......75 Buffer Full Status (BF Bit) .......46 В Clock Polarity Select (CKP Bit) ......47 Data/Address (D/A Bit) .......46 Banking, Data Memory ......8, 11 Master Mode ...... 45 Brown-out Reset (BOR) ......55, 57, 59, 60, 61 Mode Select (SSPM3:SSPM0 Bits) ......47 BOR Enable (BODEN Bit) ......55 Multi-Master Mode ......45 BOR Status (BOR Bit) ......16 Read/Write Bit Information (R/W Bit) .... 42, 43, 44, 46 Timing Diagram ......92 Receive Overflow Indicator (SSPOV Bit) ...... 47 C Reception .......43 Reception Timing Diagram ......43 Capture (CCP Module) ......34 Slave Mode ...... 41 Block Diagram ......34 Start (S Bit) ......45, 46 CCP Pin Configuration ......34 Stop (P Bit) ......45, 46 CCPR1H:CCPR1L Registers ......34 Synchronous Serial Port Enable (SSPEN Bit) ......... 47 Changing Between Capture Prescalers ......34 Timing Diagram, Data ......100 Software Interrupt ......34 Timer1 Mode Selection ......34 Transmission ...... 44 Capture/Compare/PWM Update Address (UA Bit) ......46 ID Locations .......55, 66 Capture/Compare/PWM (CCP) ......33 In-Circuit Serial Programming (ICSP) ......55, 66 CCP1CON Register ...... 9, 33 Indirect Addressing ...... 18 FSR Register ......8, 9, 18 INDF Register ......9 Enable (CCP1IE Bit) ......14 Flag (CCP1IF Bit) ......15 RC2/CCP1 Pin ......6 Timing Diagram ......94

Instruction Set	67	RB0/INT Enable (INTE Bit)	13
ADDLW	69	SSP Enable (SSPIE Bit)	14
ADDWF	69	TMR0 Overflow Enable (T0IE Bit)	
ANDLW	69	TMR1 Overflow Enable (TMR1IE Bit)	
ANDWF		TMR2 to PR2 Match Enable (TMR2IE Bit)	
BCF		Interrupts, Flag Bits	1-
BSF		A/D Converter Flag (ADIF Bit)	15 5
BTFSC		CCP1 Flag (CCP1IF Bit)15,	34, 35
BTFSS		Interrupt on Change (RB7:RB4)	
CALL	70	Flag (RBIF Bit)13,	
CLRF	70	RB0/INT Flag (INTF Bit)	13
CLRW	70	SSP Flag (SSPIF Bit)	
CLRWDT	70	TMR0 Overflow Flag (T0IF Bit)	
COMF		TMR1 Overflow Flag (TMR1IF Bit)	
DECF		,	
		TMR2 to PR2 Match Flag (TMR2IF Bit)	13
DECFSZ		K	
GOTO			
INCF	71	KeeLoq® Evaluation and Programming Tools	78
INCFSZ	71	M	
IORLW	72		
IORWF	72	Master Clear (MCLR)	6
MOVF		MCLR Reset, Normal Operation57,	60, 61
MOVLW		MCLR Reset, SLEEP57,	
		Memory Organization	00, 0
MOVWF		Data Memory	,
NOP			
RETFIE	73	Program Memory	
RETLW	73	MPLAB Integrated Development Environment Softwar	e 75
RETURN	73	0	
RLF	73	_	
RRF	73	OPCODE Field Descriptions	
SLEEP		OPTION_REG Register	.10, 12
SUBLW		INTEDG Bit	
		PS2:PS0 Bits	
SUBWF		PSA Bit	
SWAPF		RBPU Bit	
XORLW	74		
XORWF	74	TOCS Bit	,
Summary Table	68	TOSE Bit	,
INTCON Register	9, 13	OSC1/CLKIN Pin	6
GIE Bit	,	OSC2/CLKOUT Pin	6
INTE Bit		Oscillator Configuration	.55, 56
INTF Bit		HS	.56, 60
		LP	.56. 60
PEIE Bit		RC6,	,
RBIE Bit		Selection (FOSC1:FOSC0 Bits)	,
RBIF Bit	,	XT	
T0IE Bit	13		
T0IF Bit	13	Oscillator, Timer1	
Interrupt Sources	55, 62	Oscillator, WDT	64
A/D Conversion Complete	51	Р	
Block Diagram		<del>-</del>	
Capture Complete (CCP)		Packaging	105
		Paging, Program Memory	7, 17
Compare Complete (CCP)		PCON Register	
Interrupt on Change (RB7:RB4)		BOR Bit	
RB0/INT Pin, External	,	POR Bit	
SSP Receive/Transmit Complete	39	PICDEM-1 Low-Cost PICmicro Demo Board	
TMR0 Overflow	26, 63		
TMR1 Overflow	27, 29	PICDEM-2 Low-Cost PIC16CXX Demo Board	
TMR2 to PR2 Match	32	PICDEM-3 Low-Cost PIC16CXXX Demo Board	
TMR2 to PR2 Match (PWM)		PICSTART® Plus Entry Level Development System	
Interrupts, Context Saving During		PIE1 Register	.10, 14
		ADIE Bit	
Interrupts, Enable Bits	4.4	CCP1IE Bit	
A/D Converter Enable (ADIE Bit)		SSPIE Bit	
CCP1 Enable (CCP1IE Bit)		TMR1IE Bit	
Global Interrupt Enable (GIE Bit)	13, 62		
Interrupt on Change (RB7:RB4)		TMR2IE Bit	14
Enable (RBIE Bit)	13, 63	Pinout Descriptions	
Peripheral Interrupt Enable (PEIE Bit)		PIC16C62B/PIC16C72A	6
- F			

		_	
PIR.	1 Register	,	
	ADIF Bit		
	CCP1IF Bit		. 15
	SSPIF Bit		.15
	TMR1IF Bit		15
	TMR2IF Bit		
Dain			
	nter, FSR		
POF	RTA		
	Analog Port Pins		6
	PORTA Register	9,	19
	RA3:RA0 and RA5 Port Pins		19
	RA4/T0CKI Pin		
	RA5/SS/AN4 Pin		
	TRISA Register		
POF	RTB		
	PORTB Register	9,	21
	Pull-up Enable (RBPU Bit)		
	RB0/INT Edge Select (INTEDG Bit)		12
	RB0/INT Pin, External		
	RB3:RB0 Port Pins		
	RB7:RB4 Interrupt on Change		63
	RB7:RB4 Interrupt on Change		
	Enable (RBIE Bit)	. 13.	63
	RB7:RB4 Interrupt on Change	,	•
	Flag (RBIF Bit)13,	24	60
	RB7:RB4 Port Pins		
	TRISB Register	. 10,	21
POF	RTC		6
	Block Diagram		. 23
	PORTC Register		
	RC0/T1OSO/T1CKI Pin		
	RC1/T1OSI Pin		
	RC2/CCP1 Pin		6
	RC3/SCK/SCL Pin	6,	39
	RC4/SDI/SDA Pin	6.	39
	RC5/SDO Pin		
	RC6 Pin	,	
	RC7 Pin		
	TRISC Register	. 10,	23
Post	tscaler, Timer2		
	Select (TOUTPS3:TOUTPS0 Bits)		. 31
Post	tscaler, WDT		
	Assignment (PSA Bit)	12	25
	Block Diagram		. 26
	Rate Select (PS2:PS0 Bits)	. 12,	25
	Switching Between Timer0 and WDT		
Pow	ver-on Reset (POR)55, 57, 59,	60,	61
	Oscillator Start-up Timer (OST)	. 55.	59
	POR Status (POR Bit)	,	16
	Power Control (PCON) Register		
	Power-down (PD Bit)		
	Power-on Reset Circuit, External		
	Power-up Timer (PWRT)	. 55,	59
	PWRT Enable (PWRTE Bit)		
	Time-out (TO Bit)		
	Time-out Sequence		
	Timing Diagram		
	scaler, Capture		
Pres	scaler, Timer0		25
	Assignment (PSA Bit)		
	Block Diagram		
	Rate Select (PS2:PS0 Bits)		
_	Switching Between Timer0 and WDT		
Pres	scaler, Timer1		
	Select (T1CKPS1:T1CKPS0 Bits)		. 27

Prescaler, Timer2	
Select (T2CKPS1:T2CKPS0 Bits)	
PRO MATE® II Universal Programmer	77
Program Counter	
PCL Register9	
PCLATH Register9, 17	
Reset Conditions	
Program Memory	
Interrupt Vector	
Paging7	, 17
Program Memory Map	
Reset Vector	
Program Verification	
Programming Pin (Vpp)	6
Programming, Device Instructions	67
PWM (CCP Module)	36
Block Diagram	36
CCPR1H:CCPR1L Registers	36
Duty Cycle	
Example Frequencies/Resolutions	37
Output Diagram	36
Period	36
Set-Up for PWM Operation	37
TMR2 to PR2 Match31	
TMR2 to PR2 Match Enable (TMR2IE Bit)	14
TMR2 to PR2 Match Flag (TMR2IF Bit)	
Q	
Q-Clock	36
D	
R	
D 1 4 E1	
Register File Map	8
Register File Map	8
Register File Map	8 , 57
Register File Map	8 , 57 58
Register File Map	8 , 57 58 61
Register File Map  Reset	8 , 57 58 61 60
Register File Map	8 , 57 58 61 60
Register File Map  Reset	8 , 57 58 61 60 60
Register File Map  Reset	8 57 58 61 60 60
Reset Conditions for All Registers Reset Conditions for PCON Register Reset Conditions for Program Counter Reset Conditions for STATUS Register Timing Diagram Revision History	8 57 58 61 60 60
Register File Map  Reset	8 58 61 60 60 92
Register File Map  Reset	8 ., 57 58 60 60 60 92 111
Register File Map  Reset	8 58 61 60 60 60 92 1111
Register File Map  Reset	8 58 61 60 60 60 92 1111
Register File Map  Reset	8 , 57 58 60 60 60 92 111
Register File Map  Reset	8 , 57 58 61 60 60 92 1111
Register File Map  Reset	8 , 57 58 60 60 60 92 1111
Register File Map  Reset	8 60 60 60 78 78 78 55
Register File Map  Reset	8 60 60 60 78 78 78 55
Register File Map  Reset	8 61 60 60 78 78 78 78
Register File Map  Reset	8 , 57 58 61 60 60 92 111 78 78 76 95 1
Register File Map  Reset	8 , 57 58 61 60 60 92 1111 78 76 55 9 46 46 46 46
Register File Map  Reset	8 , 57 58 61 60 60 92 1111 78 76 55 9 46 46 46 47
Register File Map  Reset	8 , 57 58 60 60 92 111 78 76 95 1
Register File Map  Reset	8 , 57 58 60 60 92 111 78 76 95 1
Register File Map  Reset	8 , 57 58 60 92 111 78 76 55 76 46 47 47 47
Register File Map  Reset	8, 57, 58, 92, 1111 78, 65, 65, 146, 47, 46, 47, .
Register File Map  Reset	8, 57, 58, 92, 92, 92, 92, 92, 94,
Register File Map  Reset	8, 57, 58, 61, 78, 78, 78, 78, 78, 78, 46, 47, 47, 47, 47, 47, 48, 47, 47, 48, 47, 48, 48, 49

SSP	39	Timer1	27
Enable (SSPIE Bit)	14	Block Diagram	
Flag (SSPIF Bit)		Capacitor Selection	
RA5/SS/AN4 Pin		Clock Source Select (TMR1CS Bit)	
RC3/SCK/SCL Pin	6	External Clock Input Sync (T1SYNC Bit)	
RC4/SDI/SDA Pin	6	Module On/Off (TMR1ON Bit)	
RC5/SDO Pin	6	Oscillator	
SSPADD Register	10	Oscillator Enable (T1OSCEN Bit)	
SSPBUF Register		Overflow Enable (TMR1IE Bit)	
SSPCON Register		Overflow Flag (TMR1IF Bit)	
SSPSTAT Register	•	Overflow Interrupt	
TMR2 Output for Clock Shift		RC0/T1OSO/T1CKI Pin	
Write Collision Detect (WCOL Bit)		RC1/T10SI	
SSPCON Register		Special Event Trigger (CCP)	
CKP Bit		T1CON Register	
SSPEN Bit		Timing Diagram	
SSPM3:SSPM0 Bits		TMR1H Register	
SSPOV Bit		TMR1L Register	
WCOL Bit		Timer2	
SSPSTAT Register		Block Diagram	31
BF Bit		PR2 Register	
CKE Bit		SSP Clock Shift	, ,
D/A Bit	_	T2CON Register	
P bit		TMR2 Register	,
. <u></u> .	,	S .	,
R/W Bit S Bit		TMR2 to PR2 Match Enable (TMR2IE Bit)	
	- , -	TMR2 to PR2 Match Flag (TMR2IF Bit)	
SMP Bit		TMR2 to PR2 Match Interrupt	31, 32, 36
UA Bit		Timing Diagrams	
Stack		I <sup>2</sup> C Reception (7-bit Address)	
STATUS Register		Wake-up from SLEEP via Interrupt	
C Bit		Timing Diagrams and Specifications	
DC Bit		A/D Conversion	
IRP Bit		Brown-out Reset (BOR)	
PD Bit	,	Capture/Compare/PWM (CCP)	94
<u>RP</u> 1:RP0 Bits		CLKOUT and I/O	
TO Bit		External Clock	
Z Bit	11	I <sup>2</sup> C Bus Data	
Т		I <sup>2</sup> C Bus Start/Stop Bits	
		Oscillator Start-up Timer (OST)	
T1CON Register	,	Power-up Timer (PWRT)	
T1CKPS1:T1CKPS0 Bits		Reset	
T10SCEN Bit		Timer0 and Timer1	
T1SYNC Bit		Watchdog Timer (WDT)	92
TMR1CS Bit		W	
TMR1ON Bit	27	<del></del>	
T2CON Register	,	W Register	
T2CKPS1:T2CKPS0 Bits	31	Wake-up from SLEEP	
TMR2ON Bit		Interrupts	
TOUTPS3:TOUTPS0 Bits		MCLR Reset	
Timer0		Timing Diagram	
Block Diagram	25	WDT Reset	
Clock Source Edge Select (T0SE Bit)	•	Watchdog Timer (WDT)	
Clock Source Select (T0CS Bit)	12, 25	Block Diagram	
Overflow Enable (T0IE Bit)	13	Enable (WDTE Bit)	55, 64
Overflow Flag (T0IF Bit)	13, 63	Programming Considerations	
Overflow Interrupt	26, 63	RC Oscillator	
RA4/T0CKI Pin, External Clock		Timing Diagram	92
Timing Diagram	93	WDT Reset, Normal Operation	57, 60, 61
TMR0 Register	9	WDT Reset, SLEEP	
		WWW, On-Line Support	3

## **ON-LINE SUPPORT**

Microchip provides on-line support on the Microchip World Wide Web (WWW) site.

The web site is used by Microchip as a means to make files and information easily available to customers. To view the site, the user must have access to the Internet and a web browser, such as Netscape or Microsoft Explorer. Files are also available for FTP download from our FTP site.

## Connecting to the Microchip Internet Web Site

The Microchip web site is available by using your favorite Internet browser to attach to:

#### www.microchip.com

The file transfer site is available by using an FTP service to connect to:

### ftp://ftp.microchip.com

The web site and file transfer site provide a variety of services. Users may download files for the latest Development Tools, Data Sheets, Application Notes, User's Guides, Articles and Sample Programs. A variety of Microchip specific business information is also available, including listings of Microchip sales offices, distributors and factory representatives. Other data available for consideration is:

- · Latest Microchip Press Releases
- Technical Support Section with Frequently Asked Questions
- Design Tips
- · Device Errata
- Job Postings
- · Microchip Consultant Program Member Listing
- Links to other useful web sites related to Microchip Products
- Conferences for products, Development Systems, technical information and more
- · Listing of seminars and events

## Systems Information and Upgrade Hot Line

The Systems Information and Upgrade Line provides system users a listing of the latest versions of all of Microchip's development systems software products. Plus, this line provides information on how customers can receive any currently available upgrade kits. The Hot Line Numbers are:

1-800-755-2345 for U.S. and most of Canada, and 1-480-786-7302 for the rest of the world.

981103

**Trademarks:** The Microchip name, logo, PIC, PICmicro, PICSTART, PICMASTER and PRO MATE are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries. *Flex*ROM, MPLAB and *fuzzy*-LAB are trademarks and SQTP is a service mark of Microchip in the U.S.A.

All other trademarks mentioned herein are the property of their respective companies.

## **READER RESPONSE**


It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 786-7578.

Please list the following information, and use this outline to provide us with your comments about this Data Sheet.

IO:	Technical Publications Manager	Total Pages Sent
RE:		
Fron		<u> </u>
		FAX: ()
Арр	lication (optional):	
Wou	uld you like a reply?YN	
	· · · · · · · · · · · · · · · · · · ·	Number: DS35008B
	ioo. Tiotoocanter	
Que	estions:	
1.	What are the best features of this document?	,
2.	How does this document meet your hardware	e and software development needs?
3.	Do you find the organization of this data shee	et easy to follow? If not, why?
4.	What additions to the data sheet do you think	would enhance the structure and subject?
5.	What deletions from the data sheet could be	made without affecting the overall usefulness?
6.	Is there any incorrect or misleading information	on (what and where)?
7.	How would you improve this document?	
•		
8.	How would you improve our software, system	is, and silicon products?

## PIC16C62B/72A PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery refer to the factory or the listed sales office.



<sup>\*</sup> JW Devices are UV erasable and can be programmed to any device configuration. JW Devices meet the electrical requirement of each oscillator type (including LC devices).

## **Sales and Support**

#### **Data Sheets**

Products supported by a preliminary Data Sheet may have an errata sheet describing minor operational differences and recommended workarounds. To determine if an errata sheet exists for a particular device, please contact one of the following:

- 1. Your local Microchip sales office
- 2. The Microchip Corporate Literature Center U.S. FAX: (480) 786-7277
- 3. The Microchip Worldwide Site (www.microchip.com)

Please specify which device, revision of silicon and Data Sheet (include Literature #) you are using.

## **New Customer Notification System**

Register on our web site (www.microchip.com/cn) to receive the most current information on our products.

© 1998 Microchip Technology Inc.

Preliminary

DS35008B-page 119

## Note the following details of the code protection feature on PICmicro® MCUs.

- The PICmicro family meets the specifications contained in the Microchip Data Sheet.
- Microchip believes that its family of PICmicro microcontrollers is one of the most secure products of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the PICmicro microcontroller in a manner outside the operating specifications contained in the data sheet. The person doing so may be engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable".
- Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our product.

If you have any further questions about this matter, please contact the local sales office nearest to you.

Information contained in this publication regarding device applications and the like is intended through suggestion only and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. No representation or warranty is given and no liability is assumed by Microchip Technology Incorporated with respect to the accuracy or use of such information, or infringement of patents or other intellectual property rights arising from such use or otherwise. Use of Microchip's products as critical components in life support systems is not authorized except with express written approval by Microchip. No licenses are conveyed, implicitly or otherwise, under any intellectual property rights.

#### **Trademarks**

The Microchip name and logo, the Microchip logo, FilterLab, KEELOQ, microID, MPLAB, PIC, PICmicro, PICMASTER, PICSTART, PRO MATE, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

dsPIC, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, microPort, Migratable Memory, MPASM, MPLIB, MPLINK, MPSIM, MXDEV, PICC, PICDEM, PICDEM.net, rfPIC, Select Mode and Total Endurance are trademarks of Microchip Technology Incorporated in the U.S.A.

Serialized Quick Turn Programming (SQTP) is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2002, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.





Microchip received QS-9000 quality system certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona in July 1999. The Company's quality system processes and procedures are QS-9000 compliant for its PICmicro® 8-bit MCUs, KEELO© code hopping devices, Serial EEPROMs and microperipheral products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001 certified.



## WORLDWIDE SALES AND SERVICE

#### **AMERICAS**

#### **Corporate Office**

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support: 480-792-7627 Web Address: http://www.microchip.com

#### **Rocky Mountain**

2355 West Chandler Blvd. Chandler, AZ 85224-6199
Tel: 480-792-7966 Fax: 480-792-7456

#### Atlanta

500 Sugar Mill Road, Suite 200B Atlanta, GA 30350
Tel: 770-640-0034 Fax: 770-640-0307

#### **Boston**

2 Lan Drive, Suite 120 Westford, MA 01886 Tel: 978-692-3848 Fax: 978-692-3821

## Chicago

333 Pierce Road, Suite 180 Itasca, IL 60143

Tel: 630-285-0071 Fax: 630-285-0075

#### **Dallas**

4570 Westgrove Drive, Suite 160 Addison, TX 75001 Tel: 972-818-7423 Fax: 972-818-2924

#### Detroit

Tri-Atria Office Building 32255 Northwestern Highway, Suite 190 Farmington Hills, MI 48334 Tel: 248-538-2250 Fax: 248-538-2260

## Kokomo

2767 S. Albright Road Kokomo, Indiana 46902 Tel: 765-864-8360 Fax: 765-864-8387

### Los Angeles

18201 Von Karman, Suite 1090 Irvine, CA 92612

Tel: 949-263-1888 Fax: 949-263-1338

## **New York**

150 Motor Parkway, Suite 202 Hauppauge, NY 11788 Tel: 631-273-5305 Fax: 631-273-5335

### San Jose

Microchip Technology Inc. 2107 North First Street, Suite 590 San Jose, CA 95131 Tel: 408-436-7950 Fax: 408-436-7955

#### Toronto

6285 Northam Drive, Suite 108 Mississauga, Ontario L4V 1X5, Canada Tel: 905-673-0699 Fax: 905-673-6509

## ASIA/PACIFIC

#### Australia

Microchip Technology Australia Pty Ltd Suite 22, 41 Rawson Street Epping 2121, NSW Australia

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

### China - Beijing

Microchip Technology Consulting (Shanghai) Co., Ltd., Beijing Liaison Office Unit 915

Bei Hai Wan Tai Bldg. No. 6 Chaoyangmen Beidajie Beijing, 100027, No. China Tel: 86-10-85282100 Fax: 86-10-85282104

#### China - Chengdu

Microchip Technology Consulting (Shanghai)
Co., Ltd., Chengdu Liaison Office
Rm. 2401, 24th Floor, Ming Xing Financial Tower No. 88 TIDU Street Chengdu 610016, China Tel: 86-28-6766200 Fax: 86-28-6766599

#### China - Fuzhou

Microchip Technology Consulting (Shanghai) Co., Ltd., Fuzhou Liaison Office Unit 28F, World Trade Plaza No. 71 Wusi Road Fuzhou 350001, China Tel: 86-591-7503506 Fax: 86-591-7503521

### China - Shanghai

Microchip Technology Consulting (Shanghai) Co., Ltd. Room 701, Bldg. B

Far East International Plaza No. 317 Xian Xia Road Shanghai, 200051

Tel: 86-21-6275-5700 Fax: 86-21-6275-5060

## China - Shenzhen

Microchip Technology Consulting (Shanghai) Co., Ltd., Shenzhen Liaison Office Rm. 1315, 13/F, Shenzhen Kerry Centre, Renminnan Lu Shenzhen 518001, China Tel: 86-755-2350361 Fax: 86-755-2366086

## **Hong Kong**

Microchip Technology Hongkong Ltd. Unit 901-6, Tower 2, Metroplaza 223 Hing Fong Road Kwai Fong, N.T., Hong Kong Tel: 852-2401-1200 Fax: 852-2401-3431

#### India

Microchip Technology Inc. India Liaison Office Divvasree Chambers 1 Floor, Wing A (A3/A4) No. 11, O'Shaugnessey Road Bangalore, 560 025, India Tel: 91-80-2290061 Fax: 91-80-2290062

#### Japan

Microchip Technology Japan K.K. Benex S-1 6F 3-18-20, Shinyokohama Kohoku-Ku, Yokohama-shi Kanagawa, 222-0033, Japan Tel: 81-45-471- 6166 Fax: 81-45-471-6122

#### Korea

Microchip Technology Korea 168-1, Youngbo Bldg. 3 Floor Samsung-Dong, Kangnam-Ku Seoul, Korea 135-882

Tel: 82-2-554-7200 Fax: 82-2-558-5934

#### Singapore

Microchip Technology Singapore Pte Ltd. 200 Middle Road #07-02 Prime Centre Singapore, 188980 Tel: 65-334-8870 Fax: 65-334-8850

## Taiwan

Microchip Technology Taiwan 11F-3, No. 207 Tung Hua North Road Taipei, 105, Taiwan

Tel: 886-2-2717-7175 Fax: 886-2-2545-0139

#### **EUROPE**

#### Denmark

Microchip Technology Nordic ApS Regus Business Centre Lautrup hoj 1-3 Ballerup DK-2750 Denmark Tel: 45 4420 9895 Fax: 45 4420 9910

#### France

Microchip Technology SARL Parc d'Activite du Moulin de Massy 43 Rue du Saule Trapu Batiment A - Ier Etage 91300 Massy, France Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany** Microchip Technology GmbH Gustav-Heinemann Ring 125 D-81739 Munich, Germany Tel: 49-89-627-144 0 Fax: 49-89-627-144-44

### Italy

Microchip Technology SRL Centro Direzionale Colleoni Palazzo Taurus 1 V. Le Colleoni 1 20041 Agrate Brianza Milan, Italy Tel: 39-039-65791-1 Fax: 39-039-6899883

#### **United Kingdom**

Arizona Microchip Technology Ltd. 505 Eskdale Road Winnersh Triangle Wokingham Berkshire, England RG41 5TU Tel: 44 118 921 5869 Fax: 44-118 921-5820

01/18/02