

# dsPIC30F3014/4013 Data Sheet

High-Performance, 16-bit Digital Signal Controllers

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the
  intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not
  mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION. QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### Trademarks

The Microchip name and logo, the Microchip logo, dsPIC, KEELOQ, KEELOQ logo, MPLAB, PIC, PICmicro, PICSTART, PIC<sup>32</sup> logo, rfPIC and UNI/O are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

FilterLab, Hampshire, HI-TECH C, Linear Active Thermistor, MXDEV, MXLAB, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, dsSPEAK, ECAN, ECONOMONITOR, FanSense, HI-TIDE, In-Circuit Serial Programming, ICSP, Mindi, MiWi, MPASM, MPLAB Certified logo, MPLIB, MPLINK, mTouch, Omniscient Code Generation, PICC, PICC-18, PICDEM, PICDEM.net, PICkit, PICtail, REAL ICE, rfLAB, Select Mode, Total Endurance, TSHARC, UniWinDriver, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2010, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

ISBN: 978-1-60932-666-1

Microchip received ISO/TS-16949:2002 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEŁLOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

# QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV ISO/TS 16949:2002



### High-Performance, 16-Bit Digital Signal Controllers

Note: This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

#### **High-Performance Modified RISC CPU:**

- · Modified Harvard Architecture
- C Compiler Optimized Instruction Set Architecture
- · Flexible Addressing modes
- · 83 Base Instructions
- 24-Bit Wide Instructions, 16-Bit Wide Data Path
- Up to 48 Kbytes On-Chip Flash Program Space
- · 2 Kbytes of On-Chip Data RAM
- 1 Kbyte of Nonvolatile Data EEPROM
- 16 x 16-Bit Working Register Array
- Up to 30 MIPS Operation:
  - DC to 40 MHz External Clock Input
  - 4 MHz-10 MHz Oscillator Input with PLL Active (4x, 8x, 16x)
- Up to 33 Interrupt Sources:
  - 8 user-selectable priority levels
  - 3 external interrupt sources
  - 4 processor traps

#### **DSP Features:**

- Dual Data Fetch
- · Modulo and Bit-Reversed modes
- Two 40-Bit Wide Accumulators with Optional saturation Logic
- 17-Bit x 17-Bit Single-Cycle Hardware Fractional/Integer Multiplier
- All DSP Instructions are Single Cycle
  - Multiply-Accumulate (MAC) Operation
- Single-Cycle ±16 Shift

#### **Peripheral Features:**

- High-Current Sink/Source I/O Pins: 25 mA/25 mA
- Up to Five 16-Bit Timers/Counters; Optionally Pair Up
  - 16-Bit Timers into 32-Bit Timer modules
- Up to Four 16-Bit Capture Input Functions
- Up to Four 16-Bit Compare/PWM Output Functions
- Data Converter Interface (DCI) Supports Common Audio Codec Protocols, Including I<sup>2</sup>S and AC'97
- 3-Wire SPI module (supports 4 Frame modes)
- I<sup>2</sup>C<sup>™</sup> module Supports Multi-Master/Slave mode and 7-Bit/10-Bit Addressing
- Up to Two Addressable UART modules with FIFO Buffers
- CAN bus module Compliant with CAN 2.0B Standard

#### **Analog Features:**

- 12-Bit Analog-to-Digital Converter (ADC) with:
  - 200 ksps conversion rate
  - Up to 13 input channels
  - Conversion available during Sleep and Idle
- Programmable Low-Voltage Detection (PLVD)
- Programmable Brown-out Reset

#### **Special Microcontroller Features:**

- · Enhanced Flash Program Memory:
  - 10,000 erase/write cycle (min.) for industrial temperature range, 100K (typical)
- Data EEPROM Memory:
  - 100,000 erase/write cycle (min.) for industrial temperature range, 1M (typical)
- Self-Reprogrammable under Software Control
- Power-on Reset (POR), Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Flexible Watchdog Timer (WDT) with On-Chip Low-Power RC Oscillator for Reliable Operation
- Fail-Safe Clock Monitor Operation:
  - Detects clock failure and switches to on-chip low-power RC oscillator
- Programmable Code Protection
- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>)
- Selectable Power Management modes:
  - Sleep, Idle and Alternate Clock modes


#### **CMOS Technology:**


- · Low-Power, High-Speed Flash Technology
- Wide Operating Voltage Range (2.5V to 5.5V)
- Industrial and Extended Temperature Ranges
- Low-Power Consumption


#### dsPIC30F3014/4013 Controller Family


| Device       | i     | Program Memory |              | SRAM  | EEPROM | Timer  | r Input Output |                  | Codec                   | A/D 12-Bit | RT | Ы  | ТМ               | Z |
|--------------|-------|----------------|--------------|-------|--------|--------|----------------|------------------|-------------------------|------------|----|----|------------------|---|
|              | Pins  | Bytes          | Instructions | Bytes | Bytes  | 16-Bit | Cap            | Comp/<br>Std PWM | Interface               | 200 Ksps   | NA | IS | l <sup>2</sup> C | ၓ |
| dsPIC30F3014 | 40/44 | 24K            | 8K           | 2048  | 1024   | 3      | 2              | 2                | _                       | 13 ch      | 2  | 1  | 1                | 0 |
| dsPIC30F4013 | 40/44 | 48K            | 16K          | 2048  | 1024   | 5      | 4              | 4                | AC'97, I <sup>2</sup> S | 13 ch      | 2  | 1  | 1                | 1 |


#### Pin Diagrams











#### **Table of Contents**

| 1.0   | Device Overview   | 1 <sup>•</sup> |
|-------|---|----------------|
| 2.0   | CPU Architecture Overview                                 | 15             |
| 3.0   | Memory Organization                                       | 2              |
| 4.0   | Address Generator Units                                   | 37             |
| 5.0   | Flash Program Memory                                      | 43             |
| 6.0   | Data EEPROM Memory  | 49             |
| 7.0   | I/O Ports   | 53             |
| 8.0   | Interrupts  | 59             |
| 9.0   | Timer1 Module   | 6              |
| 10.0  | Timer2/3 Module   | 7°             |
| 11.0  | Timer4/5 Module   | 7              |
| 12.0  | Input Capture Module                                      | 8 <sup>,</sup> |
| 13.0  | Output Compare Module                                     | 8              |
| 14.0  | I2C <sup>TM</sup> Module                                  | 9 <sup>.</sup> |
|       | SPI Module  | _              |
| 16.0  | Universal Asynchronous Receiver Transmitter (UART) Module | 103            |
| 17.0  | CAN Module  |                |
| 18.0  | Data Converter Interface (DCI) Module                     | 12             |
|       | 12-bit Analog-to-Digital Converter (ADC) Module           |                |
| 20.0  | System Integration  | 14′            |
| 21.0  | Instruction Set Summary                                   | 159            |
| 22.0  | Development Support                                       | 16             |
|       | Electrical Characteristics                                |                |
| 24.0  | Packaging Information                                     | 21′            |
| Index |   | . 219          |
| The I | Microchip Web Site  | 22             |
| Custo | omer Change Notification Service                          | 22             |
| Custo | omer Support  | 22             |
| Read  | er Response   | 226            |
| Prod  | uct Identification System                                 | 22             |

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

#### http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

NOTES:


#### 1.0 DEVICE OVERVIEW

Note: This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the

peripherals, register descriptions and general device functionality, refer to the "dsPlC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

This document contains specific information for the dsPIC30F3014/4013 Digital Signal Controller (DSC) devices. The dsPIC30F3014/4013 devices contain extensive Digital Signal Processor (DSP) functionality within a high-performance, 16-bit microcontroller (MCU) architecture. Figure 1-1 and Figure 1-2 show device block diagrams for dsPIC30F3014 and dsPIC30F4013, respectively.

#### FIGURE 1-1: dsPIC30F3014 BLOCK DIAGRAM






FIGURE 1-2: dsPIC30F4013 BLOCK DIAGRAM

Table 1-1 provides a brief description of device I/O pinouts and the functions that may be multiplexed to a port pin. Multiple functions may exist on one port pin. When multiplexing occurs, the peripheral module's functional requirements may force an override of the data direction of the port pin.

**TABLE 1-1: PINOUT I/O DESCRIPTIONS** 

| Pin Name   | Pin<br>Type                                   | Buffer<br>Type                         | Description   |
|--|---|--|---|
| AN0-AN12   | _   | Analog                                 | Analog input channels. AN6 and AN7 are also used for device programming data and clock inputs, respectively.  |
| AVDD   | Р   | Р                                      | Positive supply for analog module. This pin must be connected at all times.   |
| AVss   | Р   | Р                                      | Ground reference for analog module. This pin must be connected at all times.  |
| CLKI   | 0   | ST/CMOS                                | External clock source input. Always associated with OSC1 pin function.  Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode. Optionally functions as CLKO in RC and EC modes.  |
| CLKO<br>CN0-CN7,<br>CN17-CN18                                      | I   | ST                                     | Always associated with OSC2 pin function.  Input change notification inputs. Can be software programmed for internal weak pull-ups on all inputs.   |
| COFS<br>CSCK<br>CSDI<br>CSDO                                       | I/O<br>I/O<br>I                               | ST<br>ST<br>ST<br>—                    | Data Converter Interface Frame Synchronization pin. Data Converter Interface Serial Clock input/output pin. Data Converter Interface Serial data input pin. Data Converter Interface Serial data output pin.  |
| C1RX<br>C1TX   | -<br>0  | ST<br>—                                | CAN1 bus receive pin. CAN1 bus transmit pin.  |
| EMUD<br>EMUC<br>EMUD1<br>EMUC1<br>EMUD2<br>EMUC2<br>EMUD3<br>EMUC3 | 1/O<br>1/O<br>1/O<br>1/O<br>1/O<br>1/O<br>1/O | ST<br>ST<br>ST<br>ST<br>ST<br>ST<br>ST | ICD Primary Communication Channel data input/output pin. ICD Primary Communication Channel clock input/output pin. ICD Secondary Communication Channel data input/output pin. ICD Secondary Communication Channel clock input/output pin. ICD Tertiary Communication Channel data input/output pin. ICD Tertiary Communication Channel clock input/output pin. ICD Quaternary Communication Channel data input/output pin. ICD Quaternary Communication Channel clock input/output pin. |
| IC1, IC2, IC7,<br>IC8  | I   | ST                                     | Capture inputs 1,2, 7 and 8.  |
| INT0<br>INT1<br>INT2   | <br>  | ST<br>ST<br>ST                         | External interrupt 0. External interrupt 1. External interrupt 2.   |
| LVDIN  |   | Analog                                 | Low-Voltage Detect Reference Voltage Input pin.   |
| MCLR   | I/P   | ST                                     | Master Clear (Reset) input or programming voltage input. This pin is an active-low Reset to the device.   |
| OCFA<br>OC1-OC4  | I<br>0  | ST<br>—                                | Compare Fault A input (for Compare channels 1, 2, 3 and 4). Compare outputs 1 through 4.  |
| OSC1<br>OSC2   | I<br>I/O                                      | ST/CMOS                                | Oscillator crystal input. ST buffer when configured in RC mode; CMOS otherwise. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode. Optionally functions as CLKO in RC and EC modes.  |
| PGD<br>PGC   | I/O<br>I                                      | ST<br>ST                               | In-Circuit Serial Programming data input/output pin. In-Circuit Serial Programming clock input pin.   |

**Legend:** CMOS = CMOS compatible input or output Analog = Analog input

= Schmitt Trigger input with CMOS levels ST 0 = Output ı

Ρ = Input = Power

TABLE 1-1: PINOUT I/O DESCRIPTIONS (CONTINUED)

| TABLE 1-1. THOUT TO DESCRIPTIONS (CONTINUED) |                    |                     |  |  |  |  |  |  |  |
|--|--------------------|---------------------|--|--|--|--|--|--|--|
| Pin Name                                     | Pin<br>Type        | Buffer<br>Type      | Description  |  |  |  |  |  |  |
| RA11   | I/O                | ST                  | PORTA is a bidirectional I/O port.   |  |  |  |  |  |  |
| RB0-RB12                                     | I/O                | ST                  | PORTB is a bidirectional I/O port.   |  |  |  |  |  |  |
| RC13-RC15                                    | I/O                | ST                  | PORTC is a bidirectional I/O port.   |  |  |  |  |  |  |
| RD0-RD3,<br>RD8, RD9                         | I/O                | ST                  | PORTD is a bidirectional I/O port.   |  |  |  |  |  |  |
| RF0-RF5                                      | I/O                | ST                  | PORTF is a bidirectional I/O port.   |  |  |  |  |  |  |
| SCK1<br>SDI1<br>SDO1<br>SS1                  | I/O<br>I<br>O<br>I | ST<br>ST<br>—<br>ST | Synchronous serial clock input/output for SPI1. SPI1 data in. SPI1 data out. SPI1 slave synchronization.                                     |  |  |  |  |  |  |
| SCL<br>SDA                                   | I/O<br>I/O         | ST<br>ST            | Synchronous serial clock input/output for I <sup>2</sup> C <sup>™</sup> . Synchronous serial data input/output for I <sup>2</sup> C.         |  |  |  |  |  |  |
| SOSCO<br>SOSCI                               | 0                  | ST/CMOS             | 32 kHz low-power oscillator crystal output. 32 kHz low-power oscillator crystal input. ST buffer when configured in RC mode; CMOS otherwise. |  |  |  |  |  |  |
| T1CK<br>T2CK                                 | l<br>I             | ST<br>ST            | Timer1 external clock input. Timer2 external clock input.  |  |  |  |  |  |  |
| U1RX<br>U1TX<br>U1ARX<br>U1ATX               |                    | ST<br>—<br>ST<br>—  | UART1 receive. UART1 transmit. UART1 alternate receive. UART1 alternate transmit.  |  |  |  |  |  |  |
| VDD  | Р                  | _                   | Positive supply for logic and I/O pins.  |  |  |  |  |  |  |
| Vss  | Р                  | _                   | Ground reference for logic and I/O pins.   |  |  |  |  |  |  |
| VREF+  | I                  | Analog              | Analog voltage reference (high) input.   |  |  |  |  |  |  |
| VREF-  | I                  | Analog              | Analog voltage reference (low) input.  |  |  |  |  |  |  |

Legend:CMOS = CMOS compatible input or outputAnalog = Analog inputST = Schmitt Trigger input with CMOS levelsO = OutputI = InputP = Power

### 2.0 CPU ARCHITECTURE OVERVIEW

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

#### 2.1 Core Overview

This section contains a brief overview of the CPU architecture of the dsPIC30F.

The core has a 24-bit instruction word. The Program Counter (PC) is 23 bits wide with the Least Significant bit (LSb) always clear (refer to **Section 3.1 "Program Address Space"**), and the Most Significant bit (MSb) is ignored during normal program execution, except for certain specialized instructions. Thus, the PC can address up to 4M instruction words of user program space. An instruction prefetch mechanism is used to help maintain throughput. Program loop constructs, free from loop count management overhead, are supported using the DO and REPEAT instructions, both of which are interruptible at any point.

The working register array consists of 16-bit x 16-bit registers, each of which can act as data, address or offset registers. One working register (W15) operates as a Software Stack Pointer for interrupts and calls.

The data space is 64 Kbytes (32K words) and is split into two blocks, referred to as X and Y data memory. Each block has its own independent Address Generation Unit (AGU). Most instructions operate solely through the X memory, AGU, which provides the appearance of a single, unified data space. The Multiply-Accumulate (MAC) class of dual source DSP instructions operate through both the X and Y AGUs, splitting the data address space into two parts (see Section 3.2 "Data Address Space"). The X and Y data space boundary is device-specific and cannot be altered by the user. Each data word consists of 2 bytes, and most instructions can address data either as words or bytes.

There are two methods of accessing data stored in program memory:

- The upper 32 Kbytes of data space memory can be mapped into the lower half (user space) of program space at any 16K program word boundary, defined by the 8-bit Program Space Visibility Page (PSVPAG) register. This lets any instruction access program space as if it were data space, with a limitation that the access requires an additional cycle. Moreover, only the lower 16 bits of each instruction word can be accessed using this method.
- Linear indirect access of 32K word pages within program space is also possible using any working register, via table read and write instructions.
   Table read and write instructions can be used to access all 24 bits of an instruction word.

Overhead-free circular buffers (Modulo Addressing) are supported in both X and Y address spaces. This is primarily intended to remove the loop overhead for DSP algorithms.

The X AGU also supports Bit-Reversed Addressing on destination effective addresses to greatly simplify input or output data reordering for radix-2 FFT algorithms. Refer to **Section 4.0 "Address Generator Units"** for details on Modulo and Bit-Reversed Addressing.

The core supports Inherent (no operand), Relative, Literal, Memory Direct, Register Direct, Register Indirect, Register Offset and Literal Offset Addressing modes. Instructions are associated with predefined addressing modes, depending upon their functional requirements.

For most instructions, the core is capable of executing a data (or program data) memory read, a working register (data) read, a data memory write and a program (instruction) memory read per instruction cycle. As a result, 3-operand instructions are supported, allowing C = A+B operations to be executed in a single cycle.

A DSP engine has been included to significantly enhance the core arithmetic capability and throughput. It features a high-speed, 17-bit x 17-bit multiplier, a 40-bit ALU, two 40-bit saturating accumulators and a 40-bit bidirectional barrel shifter. Data in the accumulator, or any working register, can be shifted up to 15 bits right, or 16 bits left in a single cycle. The DSP instructions operate seamlessly with all other instructions and have been designed for optimal real-time performance. The MAC class of instructions can concurrently fetch two data operands from memory while multiplying two W registers. To enable this concurrent fetching of data operands, the data space has been split for these instructions and linear is for all others. This has been achieved in a transparent and flexible manner by dedicating certain working registers to each address space for the MAC class of instructions.

The core does not support a multi-stage instruction pipeline. However, a single-stage instruction prefetch mechanism is used, which accesses and partially decodes instructions a cycle ahead of execution, in order to maximize available execution time. Most instructions execute in a single cycle with certain exceptions.

The core features a vectored exception processing structure for traps and interrupts, with 62 independent vectors. The exceptions consist of up to 8 traps (of which 4 are reserved) and 54 interrupts. Each interrupt is prioritized based on a user-assigned priority between 1 and 7 (1 being the lowest priority and 7 being the highest), in conjunction with a predetermined 'natural order'. Traps have fixed priorities ranging from 8 to 15.

#### 2.2 Programmer's Model

The programmer's model is shown in Figure 2-1 and consists of 16 x 16-bit working registers (W0 through W15), 2 x 40-bit accumulators (AccA and AccB), STATUS register (SR), Data Table Page register (TBLPAG), Program Space Visibility Page register (PSVPAG), DO and REPEAT registers (DOSTART, DOEND, DCOUNT and RCOUNT) and Program Counter (PC). The working registers can act as data, address or offset registers. All registers are memory mapped. W0 acts as the W register for file register addressing.

Some of these registers have a shadow register associated with each of them, as shown in Figure 2-1. The shadow register is used as a temporary holding register and can transfer its contents to or from its host register upon the occurrence of an event. None of the shadow registers are accessible directly. The following rules apply for transfer of registers into and out of shadows.

- PUSH.S and POP.S W0, W1, W2, W3, SR (DC, N, OV, Z and C bits only) are transferred.
- DO instruction DOSTART, DOEND, DCOUNT shadows are pushed on loop start and popped on loop end.

When a byte operation is performed on a working register, only the Least Significant Byte of the target register is affected. However, a benefit of memory mapped working registers is that both the Least and Most Significant Bytes can be manipulated through byte-wide data memory space accesses.

#### 2.2.1 SOFTWARE STACK POINTER/ FRAME POINTER

The dsPIC<sup>®</sup> DSC devices contain a software stack. W15 is the dedicated Software Stack Pointer (SP) and is automatically modified by exception processing and subroutine calls and returns. However, W15 can be referenced by any instruction in the same manner as all other W registers. This simplifies the reading, writing and manipulation of the Stack Pointer (e.g., creating Stack Frames).

**Note:** In order to protect against misaligned stack accesses, W15<0> is always clear.

W15 is initialized to 0x0800 during a Reset. The user may reprogram the SP during initialization to any location within data space.

W14 has been dedicated as a Stack Frame Pointer, as defined by the LNK and ULNK instructions. However, W14 can be referenced by any instruction in the same manner as all other W registers.

#### 2.2.2 STATUS REGISTER


The dsPIC DSC core has a 16-bit STATUS register (SR), the Least Significant Byte (LSB) of which is referred to as the SR Low byte (SRL) and the Most Significant Byte (MSB) as the SR High byte (SRH). See Figure 2-1 for SR layout.

SRL contains all the MCU ALU operation status flags (including the Z bit), as well as the CPU Interrupt Priority Level Status bits, IPL<2:0> and the Repeat Active Status bit, RA. During exception processing, SRL is concatenated with the MSB of the PC to form a complete word value which is then stacked.

The upper byte of the STATUS register contains the DSP adder/subtracter Status bits, the DO Loop Active bit (DA) and the Digit Carry (DC) Status bit.

#### 2.2.3 PROGRAM COUNTER

The program counter is 23 bits wide; bit 0 is always clear. Therefore, the PC can address up to 4M instruction words.



#### 2.3 Divide Support

The dsPIC DSC devices feature a 16/16-bit signed fractional divide operation, as well as 32/16-bit and 16/16-bit signed and unsigned integer divide operations, in the form of single instruction iterative divides. The following instructions and data sizes are supported:

- 1. DIVF 16/16 signed fractional divide
- 2. DIV.sd 32/16 signed divide
- 3. DIV.ud 32/16 unsigned divide
- 4. DIV.s 16/16 signed divide
- 5. DIV.u 16/16 unsigned divide

The 16/16 divides are similar to the 32/16 (same number of iterations), but the dividend is either zero-extended or sign-extended during the first iteration.

The divide instructions must be executed within a REPEAT loop. Any other form of execution (e.g., a series of discrete divide instructions) will not function correctly because the instruction flow depends on RCOUNT. The divide instruction does not automatically set up the RCOUNT value and it must, therefore, be explicitly and correctly specified in the REPEAT instruction, as shown in Table 2-1 (REPEAT will execute the target instruction {operand value+1} times). The REPEAT loop count must be setup for 18 iterations of the DIV/DIVF instruction. Thus, a complete divide operation requires 19 cycles.

Note: 7

The divide flow is interruptible. However, the user needs to save the context as appropriate.

TABLE 2-1: DIVIDE INSTRUCTIONS

| Instruction | Function  |
|-------------|---|
| DIVF        | Signed fractional divide: Wm/Wn → W0; Rem → W1              |
| DIV.sd      | Signed divide: (Wm+1:Wm)/Wn → W0; Rem → W1                  |
| DIV.s       | Signed divide: Wm/Wn $\rightarrow$ W0; Rem $\rightarrow$ W1 |
| DIV.ud      | Unsigned divide: (Wm+1:Wm)/Wn → W0; Rem → W1                |
| DIV.u       | Unsigned divide: Wm/Wn → W0; Rem → W1                       |

#### 2.4 DSP Engine

The DSP engine consists of a high-speed, 17-bit x 17-bit multiplier, a barrel shifter and a 40-bit adder/subtracter (with two target accumulators, round and saturation logic).

The DSP engine also has the capability to perform inherent accumulator-to-accumulator operations, which require no additional data. These instructions are ADD, SUB and NEG.

The dsPIC30F is a single-cycle instruction flow architecture, therefore, concurrent operation of the DSP engine with MCU instruction flow is not possible. However, some MCU ALU and DSP engine resources may be used concurrently by the same instruction (e.g., ED, EDAC). (See Table 2-2 for DSP instructions.)

The DSP engine has various options selected through various bits in the CPU Core Configuration register (CORCON), as listed below:

- 1. Fractional or integer DSP multiply (IF).
- 2. Signed or unsigned DSP multiply (US).
- 3. Conventional or convergent rounding (RND).
- 4. Automatic saturation on/off for AccA (SATA).
- 5. Automatic saturation on/off for AccB (SATB).
- 6. Automatic saturation on/off for writes to data memory (SATDW).
- Accumulator Saturation mode selection (ACCSAT).

**Note:** For CORCON layout, see Table 3-3.

A block diagram of the DSP engine is shown in Figure 2-2.

TABLE 2-2: DSP INSTRUCTION SUMMARY

| Instruction | Algebraic<br>Operation | ACC WB? |  |  |  |  |
|-------------|------------------------|---------|--|--|--|--|
| CLR         | A = 0                  | Yes     |  |  |  |  |
| ED          | $A = (x - y)^2$        | No      |  |  |  |  |
| EDAC        | $A = A + (x - y)^2$    | No      |  |  |  |  |
| MAC         | A = A + (x * y)        | Yes     |  |  |  |  |
| MAC         | A = A + x2             | No      |  |  |  |  |
| MOVSAC      | No change in A         | Yes     |  |  |  |  |
| MPY         | A = x * y              | No      |  |  |  |  |
| MPY.N       | A = -x * y             | No      |  |  |  |  |
| MSC         | A = A - x * y          | Yes     |  |  |  |  |

FIGURE 2-2: **DSP ENGINE BLOCK DIAGRAM** 40 40-Bit Accumulator A 40 Round 40-Bit Accumulator B Logic Saturate Carry/Borrow Out Adder Carry/Borrow In Negate 40 40 40 Barrel 16 Shifter 40 Sign-Extend Y Data Bus 32 16 Zero Backfill 32 33 17-Bit Multiplier/Scaler -16 <sub>-</sub>16 To/From W Array

#### 2.4.1 MULTIPLIER

The 17-bit x 17-bit multiplier is capable of signed or unsigned operation and can multiplex its output using a scaler to support either 1.31 fractional (Q31) or 32-bit integer results. Unsigned operands are zero-extended into the 17th bit of the multiplier input value. Signed operands are sign-extended into the 17th bit of the multiplier input value. The output of the 17-bit x 17-bit multiplier/scaler is a 33-bit value, which is signextended to 40 bits. Integer data is inherently represented as a signed two's complement value, where the MSB is defined as a sign bit. Generally speaking, the range of an N-bit two's complement integer is  $-2^{N-1}$  to  $2^{N-1} - 1$ . For a 16-bit integer, the data range is -32768 (0x8000) to 32767 (0x7FFF) including '0'. For a 32-bit integer, the data range is -2,147,483,648 (0x8000 0000) to 2,147,483,645 (0x7FFF FFFF).

When the multiplier is configured for fractional multiplication, the data is represented as a two's complement fraction, where the MSB is defined as a sign bit and the radix point is implied to lie just after the sign bit (QX format). The range of an N-bit two's complement fraction with this implied radix point is -1.0 to  $(1-2^{1-N})$ . For a 16-bit fraction, the Q15 data range is -1.0 (0x8000) to 0.999969482 (0x7FFF) including '0' and has a precision of 3.01518x10<sup>-5</sup>. In Fractional mode, the 16x16 multiply operation generates a 1.31 product, which has a precision of 4.65661 x  $10^{-10}$ .

The same multiplier is used to support the MCU multiply instructions, which includes integer 16-bit signed, unsigned and mixed sign multiplies.

The MUL instruction can be directed to use byte or word-sized operands. Byte operands direct a 16-bit result, and word operands direct a 32-bit result to the specified register(s) in the W array.

### 2.4.2 DATA ACCUMULATORS AND ADDER/SUBTRACTER

The data accumulator consists of a 40-bit adder/subtracter with automatic sign extension logic. It can select one of two accumulators (A or B) as its preaccumulation source and post-accumulation destination. For the ADD and LAC instructions, the data to be accumulated or loaded can be optionally scaled via the barrel shifter prior to accumulation.

### 2.4.2.1 Adder/Subtracter, Overflow and Saturation

The adder/subtracter is a 40-bit adder with an optional zero input into one side and either true or complement data into the other input. In the case of addition, the carry/borrow input is active-high and the other input is true data (not complemented), whereas in the case of subtraction, the carry/borrow input is active-low and the other input is complemented. The adder/subtracter generates overflow Status bits, SA/SB and OA/OB, which are latched and reflected in the STATUS register:

- Overflow from bit 39: this is a catastrophic overflow in which the sign of the accumulator is destroyed.
- Overflow into guard bits 32 through 39: this is a recoverable overflow. This bit is set whenever all the guard bits are not identical to each other.

The adder has an additional saturation block which controls accumulator data saturation if selected. It uses the result of the adder, the overflow Status bits described above, and the SATA/B (CORCON<7:6>) and ACCSAT (CORCON<4>) mode control bits to determine when and to what value to saturate.

Six STATUS register bits have been provided to support saturation and overflow. They are:

- OA: AccA overflowed into guard bits
- OB: AccB overflowed into guard bits
- Acce overnowed into guard
  - AccA saturated (bit 31 overflow and saturation) or

AccA overflowed into guard bits and saturated (bit 39 overflow and saturation)

- 4 SR
  - AccB saturated (bit 31 overflow and saturation) or

AccB overflowed into guard bits and saturated (bit 39 overflow and saturation)

- OAB: Logical OR of OA and OB
- 6. SAB: Logical OR of SA and SB

The OA and OB bits are modified each time data passes through the adder/subtracter. When set, they indicate that the most recent operation has overflowed into the accumulator guard bits (bits 32 through 39). The OA and OB bits can also optionally generate an arithmetic warning trap when set and the corresponding overflow trap flag enable bit (OVATE, OVBTE) in the INTCON1 register (refer to Section 8.0 "Interrupts") is set. This allows the user to take immediate action, for example, to correct system gain.

The SA and SB bits are modified each time data passes through the adder/subtracter but can only be cleared by the user. When set, they indicate that the accumulator has overflowed its maximum range (bit 31 for 32-bit saturation or bit 39 for 40-bit saturation) and will be saturated if saturation is enabled. When saturation is not enabled, SA and SB default to bit 39 overflow and, thus, indicate that a catastrophic overflow has occurred. If the COVTE bit in the INTCON1 register is set, SA and SB bits generate an arithmetic warning trap when saturation is disabled.

The overflow and saturation Status bits can optionally be viewed in the STATUS register (SR) as the logical OR of OA and OB (in bit OAB) and the logical OR of SA and SB (in bit SAB). This allows programmers to check one bit in the STATUS register to determine if either accumulator has overflowed, or one bit to determine if either accumulator has saturated. This would be useful for complex number arithmetic which typically uses both the accumulators.

The device supports three saturation and overflow modes:

- 1. Bit 39 Overflow and Saturation:
  - When bit 39 overflow and saturation occurs, the saturation logic loads the maximally positive 9.31 (0x7FFFFFFFFF), or maximally negative 9.31 value (0x8000000000) into the target accumulator. The SA or SB bit is set and remains set until cleared by the user. This is referred to as 'super saturation' and provides protection against erroneous data or unexpected algorithm problems (e.g., gain calculations).
- 2. Bit 31 Overflow and Saturation:
  - When bit 31 overflow and saturation occurs, the saturation logic then loads the maximally positive 1.31 value (0x007FFFFFFF), or maximally negative 1.31 value (0x0080000000) into the target accumulator. The SA or SB bit is set and remains set until cleared by the user. When this Saturation mode is in effect, the guard bits are not used, so the OA, OB or OAB bits are never set.
- 3. Bit 39 Catastrophic Overflow:
  - The bit 39 overflow Status bit from the adder is used to set the SA or SB bit which remain set until cleared by the user. No saturation operation is performed and the accumulator is allowed to overflow (destroying its sign). If the COVTE bit in the INTCON1 register is set, a catastrophic overflow can initiate a trap exception.

#### 2.4.2.2 Accumulator 'Write-Back'

The MAC class of instructions (with the exception of MPY, MPY.N, ED and EDAC) can optionally write a rounded version of the high word (bits 31 through 16) of the accumulator that is not targeted by the instruction into data space memory. The write is performed across the X bus into combined X and Y address space. The following addressing modes are supported:

- 1. W13, Register Direct:
  - The rounded contents of the non-target accumulator are written into W13 as a 1.15 fraction.
- [W13]+=2, Register Indirect with Post-Increment: The rounded contents of the non-target accumulator are written into the address pointed to by W13 as a 1.15 fraction. W13 is then incremented by 2 (for a word write).

#### 2.4.2.3 Round Logic

The round logic is a combinational block which performs a conventional (biased) or convergent (unbiased) round function during an accumulator write (store). The Round mode is determined by the state of the RND bit in the CORCON register. It generates a 16-bit, 1.15 data value, which is passed to the data space write saturation logic. If rounding is not indicated by the instruction, a truncated 1.15 data value is stored and the least significant word (lsw) is simply discarded.

Conventional rounding takes bit 15 of the accumulator, zero-extends it and adds it to the ACCxH word (bits 16 through 31 of the accumulator). If the ACCxL word (bits 0 through 15 of the accumulator) is between 0x8000 and 0xFFFF (0x8000 included), ACCxH is incremented. If ACCxL is between 0x0000 and 0x7FFF, ACCxH is left unchanged. A consequence of this algorithm is that over a succession of random rounding operations, the value tends to be biased slightly positive.

Convergent (or unbiased) rounding operates in the same manner as conventional rounding, except when ACCxL equals 0x8000. If this is the case, the Least Significant bit (LSb) (bit 16 of the accumulator) of ACCxH is examined. If it is '1', ACCxH is incremented. If it is '0', ACCxH is not modified. Assuming that bit 16 is effectively random in nature, this scheme removes any rounding bias that may accumulate.

The SAC and SAC.R instructions store either a truncated (SAC) or rounded (SAC.R) version of the contents of the target accumulator to data memory via the X bus (subject to data saturation, see Section 2.4.2.4 "Data Space Write Saturation"). Note that for the MAC class of instructions, the accumulator write-back operation functions in the same manner, addressing combined MCU (X and Y) data space though the X bus. For this class of instructions, the data is always subject to rounding.

#### 2.4.2.4 Data Space Write Saturation

In addition to adder/subtracter saturation, writes to data space may also be saturated but without affecting the contents of the source accumulator. The data space write saturation logic block accepts a 16-bit, 1.15 fractional value from the round logic block as its input, together with overflow status from the original source (accumulator) and the 16-bit round adder. These are combined and used to select the appropriate 1.15 fractional value as output to write to data space memory.

If the SATDW bit in the CORCON register is set, data (after rounding or truncation) is tested for overflow and adjusted accordingly. For input data greater than 0x007FFF, data written to memory is forced to the maximum positive 1.15 value, 0x7FFF. For input data less than 0xFF8000, data written to memory is forced to the maximum negative 1.15 value, 0x8000. The Most Significant bit (MSb) of the source (bit 39) is used to determine the sign of the operand being tested.

If the SATDW bit in the CORCON register is not set, the input data is always passed through unmodified under all conditions.

#### 2.4.3 BARREL SHIFTER

The barrel shifter is capable of performing up to 16-bit arithmetic or logic right shifts, or up to 16-bit left shifts in a single cycle. The source can be either of the two DSP accumulators, or the X bus (to support multi-bit shifts of register or memory data).

The shifter requires a signed binary value to determine both the magnitude (number of bits) and direction of the shift operation. A positive value shifts the operand right. A negative value shifts the operand left. A value of '0' does not modify the operand.

The barrel shifter is 40 bits wide, thereby obtaining a 40-bit result for DSP shift operations and a 16-bit result for MCU shift operations. Data from the X bus is presented to the barrel shifter between bit positions 16 to 31 for right shifts, and bit positions 0 to 16 for left shifts

NOTES:

#### 3.0 MEMORY ORGANIZATION


Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

#### 3.1 Program Address Space

The program address space is 4M instruction words. It is addressable by a 24-bit value from either the 23-bit PC, table instruction Effective Address (EA) or data space EA, when program space is mapped into data space as defined by Table 3-1. Note that the program space address is incremented by two between successive program words in order to provide compatibility with data space addressing.

FIGURE 3-1: dsPIC30F3014 PROGRAM SPACE MEMORY MAP



User program space access is restricted to the lower 4M instruction word address range (0x000000 to 0x7FFFFE) for all accesses other than TBLRD/TBLWT, which use TBLPAG<7> to determine user or configuration space access. In Table 3-1, bit 23 allows access to the Device ID, the User ID and the Configuration bits; otherwise, bit 23 is always clear.

FIGURE 3-2: dsPIC30F4013 PROGRAM SPACE MEMORY MAP





TABLE 3-1: PROGRAM SPACE ADDRESS CONSTRUCTION

| Access Type              | Access                        | Program Space Address |           |            |               |     |  |  |  |  |  |  |
|--------------------------|-------------------------------|-----------------------|-----------|------------|---------------|-----|--|--|--|--|--|--|
| Access Type              | Space                         | <23>                  | <22:16>   | <15>       | <14:1>        | <0> |  |  |  |  |  |  |
| Instruction Access       | User                          | 0                     |           | PC<22:1> 0 |               |     |  |  |  |  |  |  |
| TBLRD/TBLWT              | User<br>(TBLPAG<7> = 0)       | TBL                   | .PAG<7:0> |            | Data EA<15:0> |     |  |  |  |  |  |  |
| TBLRD/TBLWT              | Configuration (TBLPAG<7> = 1) | TBL                   | .PAG<7:0> |            | Data EA<15:0> |     |  |  |  |  |  |  |
| Program Space Visibility | User                          | 0                     | PSVPAG<   | 7:0>       | Data EA<14:0> |     |  |  |  |  |  |  |

FIGURE 3-3: DATA ACCESS FROM PROGRAM SPACE ADDRESS GENERATION



# 3.1.1 DATA ACCESS FROM PROGRAM MEMORY USING TABLE INSTRUCTIONS

This architecture fetches 24-bit wide program memory. Consequently, instructions are always aligned. However, as the architecture is modified Harvard, data can also be present in program space.

There are two methods by which program space can be accessed: via special table instructions, or through the remapping of a 16K word program space page into the upper half of data space (see Section 3.1.2 "Data Access from Program Memory Using Program Space Visibility"). The TBLRDL and TBLWTL instructions offer a direct method of reading or writing the lsw of any address within program space, without going through data space. The TBLRDH and TBLWTH instructions are the only method whereby the upper 8 bits of a program space word can be accessed as data.


The PC is incremented by two for each successive 24-bit program word. This allows program memory addresses to directly map to data space addresses. Program memory can thus be regarded as two 16-bit word-wide address spaces, residing side by side, each with the same address range. TBLRDL and TBLWTL access the space which contains the least significant data word, and TBLRDH and TBLWTH access the space which contains the MS Data Byte.

Figure 3-3 shows how the EA is created for table operations and data space accesses (PSV = 1). Here, P<23:0> refers to a program space word, whereas D<15:0> refers to a data space word.


A set of table instructions are provided to move byte or word-sized data to and from program space. (See Figure 3-4 and Figure 3-5.)

- TBLRDL: Table Read Low
   Word: Read the lsw of the program address;
   P<15:0> maps to D<15:0>.
   Byte: Read one of the LSBs of the program address;
   P<7:0> maps to the destination byte when byte
  - select = 0;
  - P<15:8> maps to the destination byte when byte select = 1.
- TBLWTL: Table Write Low (refer to Section 5.0
  "Flash Program Memory" for details on Flash
  programming)
- TBLRDH: Table Read High
   Word: Read the most significant word (msw) of
   the program address; P<23:16> maps to D<7:0>;
   D<15:8> will always be = 0.
  - Byte: Read one of the MSBs of the program address;
  - P<23:16> maps to the destination byte when byte select = 0:
  - The destination byte will always be = 0 when byte select = 1.
- TBLWTH: Table Write High (refer to Section 5.0
   "Flash Program Memory" for details on Flash
   Programming)









# 3.1.2 DATA ACCESS FROM PROGRAM MEMORY USING PROGRAM SPACE VISIBILITY

The upper 32 Kbytes of data space may optionally be mapped into any 16K word program space page. This provides transparent access of stored constant data from X data space without the need to use special instructions (i.e., TBLRDL/H, TBLWTL/H instructions).

Program space access through the data space occurs if the MSb of the data space, EA, is set and program space visibility is enabled by setting the PSV bit in the Core Control register (CORCON). The functions of CORCON are discussed in Section 2.4 "DSP Engine".

Data accesses to this area add an additional cycle to the instruction being executed, since two program memory fetches are required.

Note that the upper half of addressable data space is always part of the X data space. Therefore, when a DSP operation uses program space mapping to access this memory region, Y data space should typically contain state (variable) data for DSP operations, whereas X data space should typically contain coefficient (constant) data.

Although each data space address, 0x8000 and higher, maps directly into a corresponding program memory address (see Figure 3-6), only the lower 16 bits of the 24-bit program word are used to contain the data. The upper 8 bits should be programmed to force an illegal instruction to maintain machine robustness. Refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157) for details on instruction encoding.

Note that by incrementing the PC by 2 for each program memory word, the 15 LSbs of data space addresses directly map to the 15 LSbs in the corresponding program space addresses. The remaining bits are provided by the Program Space Visibility Page register, PSVPAG<7:0>, as shown in Figure 3-6.


**Note:** PSV access is temporarily disabled during table reads/writes.

For instructions that use PSV which are executed outside a REPEAT loop:

- The following instructions require one instruction cycle in addition to the specified execution time:
  - MAC class of instructions with data operand prefetch
  - MOV instructions
  - MOV.D instructions
- All other instructions require two instruction cycles in addition to the specified execution time of the instruction.

For instructions that use PSV which are executed inside a REPEAT loop:

- The following instances require two instruction cycles in addition to the specified execution time of the instruction:
  - Execution in the first iteration
  - Execution in the last iteration
  - Execution prior to exiting the loop due to an interrupt
  - Execution upon re-entering the loop after an interrupt is serviced
- Any other iteration of the REPEAT loop allows the instruction accessing data, using PSV, to execute in a single cycle.



© 2010 Microchip Technology Inc.

#### 3.2 Data Address Space

The core has two data spaces. The data spaces can be considered either separate (for some DSP instructions), or as one unified linear address range (for MCU instructions). The data spaces are accessed using two Address Generation Units (AGUs) and separate data paths.

#### 3.2.1 DATA SPACE MEMORY MAP

The data space memory is split into two blocks, X and Y data space. A key element of this architecture is that Y space is a subset of X space, and is fully contained within X space. In order to provide an apparent Linear Addressing space, X and Y spaces have contiguous addresses.

When executing any instruction other than one of the MAC class of instructions, the X block consists of the 64-Kbyte data address space (including all Y addresses). When executing one of the MAC class of instructions, the X block consists of the 64-Kbyte data address space excluding the Y address block (for data reads only). In other words, all other instructions regard the entire data memory as one composite address space. The MAC class instructions extract the Y address space from data space and address it using EAs sourced from W10 and W11. The remaining X data space is addressed using W8 and W9. Both address spaces are concurrently accessed only with the MAC class instructions.

The data space memory map is shown in Figure 3-7.

FIGURE 3-7: dsPIC30F3014/dsPIC30F4013 DATA SPACE MEMORY MAP





FIGURE 3-8: DATA SPACE FOR MCU AND DSP (MAC CLASS) INSTRUCTIONS EXAMPLE



#### 3.2.2 DATA SPACES

The X data space is used by all instructions and supports all addressing modes. There are separate read and write data buses. The X read data bus is the return data path for all instructions that view data space as combined X and Y address space. It is also the X address space data path for the dual operand read instructions (MAC class). The X write data bus is the only write path to data space for all instructions.

The X data space also supports Modulo Addressing for all instructions, subject to addressing mode restrictions. Bit-Reversed Addressing is only supported for writes to X data space.

The Y data space is used in concert with the X data space by the MAC class of instructions (CLR, ED, EDAC, MAC, MOVSAC, MPY, MPY.N and MSC) to provide two concurrent data read paths. No writes occur across the Y bus. This class of instructions dedicates two W register pointers, W10 and W11, to always address Y data space, independent of X data space, whereas W8 and W9 always address X data space. Note that during accumulator write-back, the data address space is considered a combination of X and Y data spaces, so the write occurs across the X bus. Consequently, the write can be to any address in the entire data space.

The Y data space can only be used for the data prefetch operation associated with the MAC class of instructions. It also supports Modulo Addressing for automated circular buffers. Of course, all other instructions can access the Y data address space through the X data path as part of the composite linear space.

The boundary between the X and Y data spaces is defined as shown in Figure 3-7 and is not user-programmable. Should an EA point to data outside its own assigned address space, or to a location outside physical memory, an all zero word/byte is returned. For example, although Y address space is visible by all non-MAC instructions using any addressing mode, an attempt by a MAC instruction to fetch data from that space using W8 or W9 (X Space Pointers) returns 0x0000.

TABLE 3-2: EFFECT OF INVALID MEMORY ACCESSES

| Attempted Operation   | Data Returned |  |  |  |  |  |  |
|---|---------------|--|--|--|--|--|--|
| EA = an unimplemented address                               | 0x0000        |  |  |  |  |  |  |
| W8 or W9 used to access Y data space in a MAC instruction   | 0x0000        |  |  |  |  |  |  |
| W10 or W11 used to access X data space in a MAC instruction | 0x0000        |  |  |  |  |  |  |

All effective addresses are 16 bits wide and point to bytes within the data space. Therefore, the data space address range is 64 Kbytes or 32K words.

#### 3.2.3 DATA SPACE WIDTH

The core data width is 16 bits. All internal registers are organized as 16-bit wide words. Data space memory is organized in byte addressable, 16-bit wide blocks.

#### 3.2.4 DATA ALIGNMENT

To help maintain backward compatibility with PIC® MCU devices and improve data space memory usage efficiency, the dsPIC30F instruction set supports both word and byte operations. Data is aligned in data memory and registers as words, but all data space EAs resolve to bytes. Data byte reads read the complete word which contains the byte, using the LSb of any EA to determine which byte to select. The selected byte is placed onto the LSB of the X data path (no byte accesses are possible from the Y data path as the MAC class of instruction can only fetch words). That is, data memory and registers are organized as two parallel byte-wide entities with shared (word) address decode but separate write lines. Data byte writes only write to the corresponding side of the array or register which matches the byte address.

As a consequence of this byte accessibility, all effective address calculations (including those generated by the DSP operations which are restricted to word-sized data) are internally scaled to step through word-aligned memory. For example, the core would recognize that Post-Modified Register Indirect Addressing mode [Ws++] will result in a value of Ws + 1 for byte operations and Ws + 2 for word operations.

All word accesses must be aligned to an even address. Misaligned word data fetches are not supported so care must be taken when mixing byte and word operations, or translating from 8-bit MCU code. Should a misaligned read or write be attempted, an address error trap is generated. If the error occurred on a read, the instruction underway is completed, whereas if it occurred on a write, the instruction is executed but the write does not occur. In either case, a trap is then executed, allowing the system and/or user to examine the machine state prior to execution of the address Fault.

FIGURE 3-9: DATA ALIGNMENT

| ,    | MSB    | B 7 LSB | )    |
|------|--------|---------|------|
| 0001 | Byte 1 | Byte 0  | 0000 |
| 0003 | Byte 3 | Byte 2  | 0002 |
| 0005 | Byte 5 | Byte 4  | 0004 |
|      | •      |         | _    |

All byte loads into any W register are loaded into the LSB. The MSB is not modified.

A Sign-Extend (SE) instruction is provided to allow users to translate 8-bit signed data to 16-bit signed values. Alternatively, for 16-bit unsigned data, users can clear the MSB of any W register by executing a Zero-Extend (ZE) instruction on the appropriate address.

Although most instructions are capable of operating on word or byte data sizes, it should be noted that some instructions, including the DSP instructions, operate only on words.

#### 3.2.5 NEAR DATA SPACE

An 8-Kbyte 'near' data space is reserved in X address memory space between 0x0000 and 0x1FFF, which is directly addressable via a 13-bit absolute address field within all memory direct instructions. The remaining X address space and all of the Y address space is addressable indirectly. Additionally, the whole of X data space is addressable using MOV instructions, which support memory direct addressing with a 16-bit address field.

#### 3.2.6 SOFTWARE STACK

The dsPIC DSC devices contain a software stack. W15 is used as the Stack Pointer.

The Stack Pointer always points to the first available free word and grows from lower addresses towards higher addresses. It pre-decrements for stack pops and post-increments for stack pushes as shown in Figure 3-10. Note that for a PC push during any CALL instruction, the MSB of the PC is zero-extended before the push, ensuring that the MSB is always clear.


**Note:** A PC push during exception processing concatenates the SRL register to the MSB of the PC prior to the push.

There is a Stack Pointer Limit register (SPLIM) associated with the Stack Pointer. SPLIM is uninitialized at Reset. As is the case for the Stack Pointer, SPLIM<0> is forced to '0' because all stack operations must be word-aligned. Whenever an Effective Address (EA) is generated, using W15 as a source or destination pointer, the address thus generated is compared with the value in SPLIM. If the contents of the Stack Pointer (W15) and the SPLIM register are equal and a push operation is performed, a stack error trap does not occur. The stack error trap occurs on a subsequent push operation. Thus, for example, if it is desirable to cause a stack error trap when the stack grows beyond address 0x2000 in RAM, initialize the SPLIM with the value, 0x1FFE.

Similarly, a Stack Pointer underflow (stack error) trap is generated when the Stack Pointer address is found to be less than 0x0800, thus preventing the stack from interfering with the Special Function Register (SFR) space.

A write to the SPLIM register should not be immediately followed by an indirect read operation using W15.

FIGURE 3-10: CALL STACK FRAME



DS70138G-page 34

TABLE 3-3: CORE REGISTER MAP<sup>(1)</sup>

| SFR Name | Address<br>(Home) | Bit 15 | Bit 14   | Bit 13 | Bit 12     | Bit 11  | Bit 10 | Bit 9 | Bit 8  | Bit 7      | Bit 6 | Bit 5               | Bit 4 | Bit 3 | Bit 2               | Bit 1               | Bit 0 | Reset State         |  |  |
|----------|-------------------|--------|----------|--------|------------|---------|--------|-------|--------|------------|-------|---------------------|-------|-------|---------------------|---------------------|-------|---------------------|--|--|
| W0       | 0000              |        | W0/WREG  |        |            |         |        |       |        |            |       |                     |       |       |                     | 0000 0000 0000 0000 |       |                     |  |  |
| W1       | 0002              |        |          |        |            |         |        |       | W1     |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W2       | 0004              |        |          |        |            |         |        |       | W2     |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W3       | 0006              |        |          |        |            |         |        |       | W3     |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W4       | 8000              |        |          |        |            |         |        |       | W4     |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W5       | 000A              |        |          |        |            |         |        |       | W5     |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W6       | 000C              |        | W6       |        |            |         |        |       |        |            |       |                     |       |       |                     | 0000 0000 0000 0000 |       |                     |  |  |
| W7       | 000E              |        | W7       |        |            |         |        |       |        |            |       |                     |       |       |                     | 0000 0000 0000 0000 |       |                     |  |  |
| W8       | 0010              |        | W8       |        |            |         |        |       |        |            |       |                     |       |       | 0000 0000 0000 0000 |                     |       |                     |  |  |
| W9       | 0012              |        |          |        |            |         |        |       | W9     |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W10      | 0014              |        |          |        |            |         |        |       | W10    |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W11      | 0016              |        |          |        |            |         |        |       | W11    |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W12      | 0018              |        |          |        |            |         |        |       | W12    |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W13      | 001A              |        |          |        |            |         |        |       | W13    |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W14      | 001C              |        |          |        |            |         |        |       | W14    |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| W15      | 001E              |        |          |        |            |         |        |       | W15    |            |       |                     |       |       |                     |                     |       | 0000 1000 0000 0000 |  |  |
| SPLIM    | 0020              |        |          |        |            |         |        |       | SPLIM  | 1          |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| ACCAL    | 0022              |        |          |        |            |         |        |       | ACCAI  | L          |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| ACCAH    | 0024              |        |          |        |            |         |        |       | ACCA   | Н          |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| ACCAU    | 0026              |        |          | Sign E | xtension ( | ACCA<39 | 9>)    |       |        |            |       |                     | ACC   | AU    |                     |                     |       | 0000 0000 0000 0000 |  |  |
| ACCBL    | 0028              |        |          |        |            |         |        |       | ACCBI  | Ĺ          |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| ACCBH    | 002A              |        |          |        |            |         |        |       | ACCBI  | H          |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| ACCBU    | 002C              |        |          | Sign E | xtension ( | ACCB<39 | 9>)    |       |        |            |       |                     | ACC   | BU    |                     |                     |       | 0000 0000 0000 0000 |  |  |
| PCL      | 002E              |        |          |        |            |         |        |       | PCL    |            |       |                     |       |       |                     |                     |       | 0000 0000 0000 0000 |  |  |
| PCH      | 0030              | -      | _        | _      | _          | _       | _      | _     | _      | _          |       |                     |       | PCH   |                     |                     |       | 0000 0000 0000 0000 |  |  |
| TBLPAG   | 0032              | -      | _        | _      | _          | _       | _      | _     | _      |            |       |                     | TBLP  | AG    |                     |                     |       | 0000 0000 0000 0000 |  |  |
| PSVPAG   | 0034              | -      | _        | _      | _          | _       | _      | _     | _      |            |       |                     | PSVF  | AG    |                     |                     |       | 0000 0000 0000 0000 |  |  |
| RCOUNT   | 0036              |        |          |        |            |         |        |       | RCOUN  | NT.        |       |                     |       |       |                     |                     |       | uuuu uuuu uuuu uuuu |  |  |
| DCOUNT   | 0038              |        |          |        |            |         |        |       | DCOUN  | <b>I</b> T |       |                     |       |       |                     |                     |       | uuuu uuuu uuuu uuuu |  |  |
| DOSTARTL | 003A              |        |          |        |            |         |        | DC    | STARTL |            |       |                     |       |       |                     |                     | 0     | uuuu uuuu uuuu uuu0 |  |  |
| DOSTARTH | 003C              | -      | DOSTARTH |        |            |         |        |       |        |            |       |                     |       |       | 0000 0000 0uuu uuuu |                     |       |                     |  |  |
| DOENDL   | 003E              |        | DOENDL 0 |        |            |         |        |       |        |            |       | uuuu uuuu uuuu uuu0 |       |       |                     |                     |       |                     |  |  |
| DOENDH   | 0040              | -      | _        | _      | _          |         | _      | _     | _      | _          |       |                     | D     | OENDH |                     |                     |       | 0000 0000 0uuu uuuu |  |  |
| SR       | 0042              | OA     | ОВ       | SA     | SB         | OAB     | SAB    | DA    | DC     | IPL2       | IPL1  | IPL0                | RA    | N     | OV                  | Z                   | С     | 0000 0000 0000 0000 |  |  |

**Legend:** u = uninitialized bit; — = unimplemented bit, read as '0'

<sup>1:</sup> Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

| <b>TABLE 3-3:</b> | CORE REGISTER MAP <sup>(1)</sup> (CONTINUED) |
|-------------------|--|
|-------------------|--|

| SFR Name | Address<br>(Home) | Bit 15 | Bit 14        | Bit 13 | Bit 12                     | Bit 11 | Bit 10 | Bit 9 | Bit 8   | Bit 7  | Bit 6   | Bit 5 | Bit 4  | Bit 3               | Bit 2               | Bit 1 | Bit 0 | Reset State         |
|----------|-------------------|--------|---------------|--------|----------------------------|--------|--------|-------|---------|--------|---------|-------|--------|---------------------|---------------------|-------|-------|---------------------|
| CORCON   | 0044              | _      | _             | _      | US                         | EDT    | DL2    | DL1   | DL0     | SATA   | SATB    | SATDW | ACCSAT | IPL3                | PSV                 | RND   | IF    | 0000 0000 0010 0000 |
| MODCON   | 0046              | XMODEN | YMODEN        | _      | BWM<3:0> YWM<3:0> XWM<3:0> |        |        |       |         |        |         |       |        |                     | 0000 0000 0000 0000 |       |       |                     |
| XMODSRT  | 0048              |        | XS<15:1> 0    |        |                            |        |        |       |         |        |         |       |        | uuuu uuuu uuu0      |                     |       |       |                     |
| XMODEND  | 004A              |        |               |        |                            |        |        | XE    | <15:1>  |        |         |       |        |                     |                     |       | 1     | uuuu uuuu uuu1      |
| YMODSRT  | 004C              |        |               |        |                            |        |        | YS    | S<15:1> |        |         |       |        |                     |                     |       | 0     | uuuu uuuu uuu0      |
| YMODEND  | 004E              |        | YE<15:1> 1    |        |                            |        |        |       |         |        |         |       |        | uuuu uuuu uuu1      |                     |       |       |                     |
| XBREV    | 0050              | BREN   | BREN XB<14:0> |        |                            |        |        |       |         |        |         |       |        | uuuu uuuu uuuu uuuu |                     |       |       |                     |
| DISICNT  | 0052              | _      | -             |        | •                          |        | •      |       | •       | DISICN | Γ<13:0> | •     |        | •                   | •                   |       |       | 0000 0000 0000 0000 |

Legend:

u = uninitialized bit; — = unimplemented bit, read as '0'
 Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

#### 4.0 ADDRESS GENERATOR UNITS

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

The dsPIC DSC core contains two independent address generator units: the X AGU and Y AGU. The Y AGU supports word-sized data reads for the DSP MAC class of instructions only. The dsPIC DSC AGUs support three types of data addressing:

- · Linear Addressing
- · Modulo (Circular) Addressing
- · Bit-Reversed Addressing

Linear and Modulo Data Addressing modes can be applied to data space or program space. Bit-Reversed Addressing is only applicable to data space addresses.

#### 4.1 Instruction Addressing Modes

The addressing modes in Table 4-1 form the basis of the addressing modes optimized to support the specific features of individual instructions. The addressing modes provided in the MAC class of instructions are somewhat different from those in the other instruction types.

#### 4.1.1 FILE REGISTER INSTRUCTIONS

Most file register instructions use a 13-bit address field (f) to directly address data present in the first 8192 bytes of data memory (near data space). Most file register instructions employ a working register, W0, which is denoted as WREG in these instructions. The destination is typically either the same file register or WREG (with the exception of the MUL instruction), which writes the result to a register or register pair. The MOV instruction allows additional flexibility and can access the entire data space during file register operation.

#### 4.1.2 MCU INSTRUCTIONS

The three-operand MCU instructions are of the form:

Operand 3 = Operand 1 < function > Operand 2

where Operand 1 is always a working register (i.e., the addressing mode can only be Register Direct), which is referred to as Wb. Operand 2 can be a W register, fetched from data memory or a 5-bit literal. The result location can be either a W register or an address location. The following addressing modes are supported by MCU instructions:

- · Register Direct
- Register Indirect
- · Register Indirect Post-Modified
- · Register Indirect Pre-Modified
- 5-bit or 10-bit Literal

**Note:** Not all instructions support all the addressing modes given above. Individual instructions may support different subsets of these addressing modes.

TABLE 4-1: FUNDAMENTAL ADDRESSING MODES SUPPORTED

| Addressing Mode                        | Description  |
|--|--|
| File Register Direct                   | The address of the File register is specified explicitly.  |
| Register Direct                        | The contents of a register are accessed directly.  |
| Register Indirect                      | The contents of Wn forms the EA.   |
| Register Indirect Post-Modified        | The contents of Wn forms the EA. Wn is post-modified (incremented or decremented) by a constant value. |
| Register Indirect Pre-Modified         | Wn is pre-modified (incremented or decremented) by a signed constant value to form the EA.             |
| Register Indirect with Register Offset | The sum of Wn and Wb forms the EA.   |
| Register Indirect with Literal Offset  | The sum of Wn and a literal forms the EA.  |

### 4.1.3 MOVE AND ACCUMULATOR INSTRUCTIONS

Move instructions and the DSP accumulator class of instructions provide a greater degree of addressing flexibility than other instructions. In addition to the addressing modes supported by most MCU instructions, move and accumulator instructions also support Register Indirect with Register Offset Addressing mode, also referred to as Register Indexed mode.

Note:

For the MOV instructions, the addressing mode specified in the instruction can differ for the source and destination EA. However, the 4-bit Wb (register offset) field is shared between both source and destination (but typically only used by one).

In summary, the following addressing modes are supported by move and accumulator instructions:

- · Register Direct
- · Register Indirect
- · Register Indirect Post-Modified
- · Register Indirect Pre-Modified
- Register Indirect with Register Offset (Indexed)
- · Register Indirect with Literal Offset
- 8-bit Literal
- 16-bit Literal

Note:

Not all instructions support all the addressing modes given above. Individual instructions may support different subsets of these addressing modes.

### 4.1.4 MAC INSTRUCTIONS

The dual source operand DSP instructions (CLR, ED, EDAC, MAC, MPY, MPY.N, MOVSAC and MSC), also referred to as MAC instructions, utilize a simplified set of addressing modes to allow the user to effectively manipulate the Data Pointers through register indirect tables.

The two source operand prefetch registers must be a member of the set {W8, W9, W10, W11}. For data reads, W8 and W9 is always directed to the X RAGU, and W10 and W11 are always directed to the Y AGU. The Effective Addresses generated (before and after modification) must, therefore, be valid addresses within X data space for W8 and W9 and Y data space for W10 and W11.

Note:

Register Indirect with Register Offset addressing is only available for W9 (in X space) and W11 (in Y space).

In summary, the following addressing modes are supported by the MAC class of instructions:

- · Register Indirect
- · Register Indirect Post-Modified by 2
- · Register Indirect Post-Modified by 4
- Register Indirect Post-Modified by 6
- Register Indirect with Register Offset (Indexed)

#### 4.1.5 OTHER INSTRUCTIONS

Besides the various addressing modes outlined above, some instructions use literal constants of various sizes. For example, BRA (branch) instructions use 16-bit signed literals to specify the branch destination directly, whereas the DISI instruction uses a 14-bit unsigned literal field. In some instructions, such as ADD Acc, the source of an operand or result is implied by the opcode itself. Certain operations, such as NOP, do not have any operands.

#### 4.2 Modulo Addressing

Modulo Addressing is a method of providing an automated means to support circular data buffers using hardware. The objective is to remove the need for software to perform data address boundary checks when executing tightly looped code, as is typical in many DSP algorithms.

Modulo Addressing can operate in either data or program space (since the data pointer mechanism is essentially the same for both). One circular buffer can be supported in each of the X (which also provides the pointers into program space) and Y data spaces. Modulo Addressing can operate on any W register pointer. However, it is not advisable to use W14 or W15 for Modulo Addressing since these two registers are used as the Stack Frame Pointer and Stack Pointer, respectively.

In general, any particular circular buffer can only be configured to operate in one direction, as there are certain restrictions on the buffer start address (for incrementing buffers), or end address (for decrementing buffers) based upon the direction of the buffer.

The only exception to the usage restrictions is for buffers that have a power-of-2 length. As these buffers satisfy the start and end address criteria, they may operate in a Bidirectional mode (i.e., address boundary checks are performed on both the lower and upper address boundaries).

#### 4.2.1 START AND END ADDRESS

The Modulo Addressing scheme requires that a starting and an ending address be specified and loaded into the 16-bit Modulo Buffer Address registers: XMODSRT, XMODEND, YMODSRT and YMODEND (see Table 3-3).

**Note:** Y space Modulo Addressing EA calculations assume word-sized data (LSb of every EA is always clear).

The length of a circular buffer is not directly specified. It is determined by the difference between the corresponding start and end addresses. The maximum possible length of the circular buffer is 32K words (64 Kbytes).


### 4.2.2 W ADDRESS REGISTER SELECTION

The Modulo and Bit-Reversed Addressing Control register MODCON<15:0> contains enable flags as well as a W register field to specify the W address registers. The XWM and YWM fields select which registers operate with Modulo Addressing. If XWM = 15, X RAGU and X WAGU Modulo Addressing is disabled. Similarly, if YWM = 15, Y AGU Modulo Addressing is disabled.

The X Address Space Pointer W register (XWM), to which Modulo Addressing is to be applied, is stored in MODCON<3:0> (see Table 3-3). Modulo Addressing is enabled for X data space when XWM is set to any value other than '15' and the XMODEN bit is set at MODCON<15>.

The Y Address Space Pointer W register (YWM), to which Modulo Addressing is to be applied, is stored in MODCON<7:4>. Modulo Addressing is enabled for Y data space when YWM is set to any value other than '15' and the YMODEN bit is set at MODCON<14>.

FIGURE 4-1: MODULO ADDRESSING OPERATION EXAMPLE



## 4.2.3 MODULO ADDRESSING APPLICABILITY

Modulo Addressing can be applied to the Effective Address (EA) calculation associated with any W register. It is important to realize that the address boundaries check for addresses less than or greater than the upper (for incrementing buffers) and lower (for decrementing buffers) boundary addresses (not just equal to). Address changes may, therefore, jump beyond boundaries and still be adjusted correctly.

Note: The modulo corrected effective address is written back to the register only when Pre-Modify or Post-Modify Addressing mode is used to compute the effective address. When an address offset (e.g., [W7+W2]) is used, Modulo Addressing correction is performed but the contents of the register remain unchanged.

### 4.3 Bit-Reversed Addressing

Bit-Reversed Addressing is intended to simplify data re-ordering for radix-2 FFT algorithms. It is supported by the X AGU for data writes only.

The modifier, which may be a constant value or register contents, is regarded as having its bit order reversed. The address source and destination are kept in normal order. Thus, the only operand requiring reversal is the modifier.

# 4.3.1 BIT-REVERSED ADDRESSING IMPLEMENTATION

Bit-Reversed Addressing is enabled when:

- BWM (W register selection) in the MODCON register is any value other than '15' (the stack cannot be accessed using Bit-Reversed Addressing) and
- 2. the BREN bit is set in the XBREV register and
- 3. the addressing mode used is Register Indirect with Pre-Increment or Post-Increment.

If the length of a bit-reversed buffer is  $M = 2^N$  bytes, then the last 'N' bits of the data buffer start address must be zeros

XB<14:0> is the bit-reversed address modifier or 'pivot point' which is typically a constant. In the case of an FFT computation, its value is equal to half of the FFT data buffer size.

Note: All bit-reversed EA calculations assume word-sized data (LSb of every EA is always clear). The XB value is scaled accordingly to generate compatible (byte) addresses.

When enabled, Bit-Reversed Addressing is only executed for Register Indirect with Pre-Increment or Post-Increment Addressing and word-sized data writes. It does not function for any other addressing mode or for byte sized data. Normal addresses are generated instead. When Bit-Reversed Addressing is active, the W Address Pointer is always added to the address modifier (XB) and the offset associated with the Register Indirect Addressing mode is ignored. In addition, as word-sized data is a requirement, the LSb of the EA is ignored (and always clear).

Note: Modulo Addressing and Bit-Reversed Addressing should not be enabled together. In the event that the user attempts to do this, Bit-Reversed Addressing assumes priority when active for the X WAGU, and X WAGU Modulo Addressing is disabled. However, Modulo Addressing continues to function in the X RAGU.

If Bit-Reversed Addressing has already been enabled by setting the BREN (XBREV<15>) bit, then a write to the XBREV register should not be immediately followed by an indirect read operation using the W register that has been designated as the Bit-Reversed Pointer.

#### FIGURE 4-2: BIT-REVERSED ADDRESS EXAMPLE




TABLE 4-2: BIT-REVERSED ADDRESS SEQUENCE (16-ENTRY)

|    |    | Norma | al Addres | ss      |    |    | Bit-Rev | ersed Ac | Idress  |
|----|----|-------|-----------|---------|----|----|---------|----------|---------|
| А3 | A2 | A1    | A0        | Decimal | А3 | A2 | A1      | Α0       | Decimal |
| 0  | 0  | 0     | 0         | 0       | 0  | 0  | 0       | 0        | 0       |
| 0  | 0  | 0     | 1         | 1       | 1  | 0  | 0       | 0        | 8       |
| 0  | 0  | 1     | 0         | 2       | 0  | 1  | 0       | 0        | 4       |
| 0  | 0  | 1     | 1         | 3       | 1  | 1  | 0       | 0        | 12      |
| 0  | 1  | 0     | 0         | 4       | 0  | 0  | 1       | 0        | 2       |
| 0  | 1  | 0     | 1         | 5       | 1  | 0  | 1       | 0        | 10      |
| 0  | 1  | 1     | 0         | 6       | 0  | 1  | 1       | 0        | 6       |
| 0  | 1  | 1     | 1         | 7       | 1  | 1  | 1       | 0        | 14      |
| 1  | 0  | 0     | 0         | 8       | 0  | 0  | 0       | 1        | 1       |
| 1  | 0  | 0     | 1         | 9       | 1  | 0  | 0       | 1        | 9       |
| 1  | 0  | 1     | 0         | 10      | 0  | 1  | 0       | 1        | 5       |
| 1  | 0  | 1     | 1         | 11      | 1  | 1  | 0       | 1        | 13      |
| 1  | 1  | 0     | 0         | 12      | 0  | 0  | 1       | 1        | 3       |
| 1  | 1  | 0     | 1         | 13      | 1  | 0  | 1       | 1        | 11      |
| 1  | 1  | 1     | 0         | 14      | 0  | 1  | 1       | 1        | 7       |
| 1  | 1  | 1     | 1         | 15      | 1  | 1  | 1       | 1        | 15      |

TABLE 4-3: BIT-REVERSED ADDRESS MODIFIER VALUES FOR XBREV REGISTER

| Buffer Size (Words) | XB<14:0> Bit-Reversed Address Modifier Value |
|---------------------|--|
| 1024                | 0x0200                                       |
| 512                 | 0x0100                                       |
| 256                 | 0x0080                                       |
| 128                 | 0x0040                                       |
| 64                  | 0x0020                                       |
| 32                  | 0x0010                                       |
| 16                  | 0x0008                                       |
| 8                   | 0x0004                                       |
| 4                   | 0x0002                                       |
| 2                   | 0x0001                                       |

NOTES:

#### 5.0 FLASH PROGRAM MEMORY

Note:

FIGURE 5-1:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU. peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

The dsPIC30F family of devices contains internal program Flash memory for executing user code. There are two methods by which the user can program this memory:

- Run-Time Self-Programming (RTSP)
- In-Circuit Serial Programming™ (ICSP™)

#### 5.1 **In-Circuit Serial Programming** (ICSP)

dsPIC30F devices can be serially programmed while in the end application circuit. This is simply done with two lines for Programming Clock and Programming Data (which are named PGC and PGD, respectively), and three other lines for Power (VDD), Ground (VSS) and Master Clear (MCLR). This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

#### 5.2 **Run-Time Self-Programming** (RTSP)

RTSP is accomplished using TBLRD (table read) and TBLWT (table write) instructions.

With RTSP, the user may erase program memory, 32 instructions (96 bytes) at a time and can write program memory data, 32 instructions (96 bytes) at a time.

#### 5.3 **Table Instruction Operation Summary**


The TBLRDL and the TBLWTL instructions are used to read or write to bits<15:0> of program memory. TBLRDL and TBLWTL can access program memory in Word or Byte mode.

The TBLRDH and TBLWTH instructions are used to read or write to bits<23:16> of program memory. TBLRDH and TBLWTH can access program memory in Word or Byte mode.

A 24-bit program memory address is formed using bits<7:0> of the TBLPAG register and the Effective Address (EA) from a W register specified in the table instruction, as shown in Figure 5-1.



ADDRESSING FOR TABLE AND NVM REGISTERS



#### 5.4 RTSP Operation

The dsPIC30F Flash program memory is organized into rows and panels. Each row consists of 32 instructions or 96 bytes. Each panel consists of 128 rows or 4K x 24 instructions. RTSP allows the user to erase one row (32 instructions) at a time and to program four instructions at one time. RTSP may be used to program multiple program memory panels, but the Table Pointer must be changed at each panel boundary.

Each panel of program memory contains write latches that hold 32 instructions of programming data. Prior to the actual programming operation, the write data must be loaded into the panel write latches. The data to be programmed into the panel is loaded in sequential order into the write latches; instruction 0, instruction 1, etc. The instruction words loaded must always be from a 32 address boundary.

The basic sequence for RTSP programming is to set up a Table Pointer, then do a series of TBLWT instructions to load the write latches. Programming is performed by setting the special bits in the NVMCON register. 32 TBLWTL and four TBLWTH instructions are required to load the 32 instructions. If multiple panel programming is required, the Table Pointer needs to be changed and the next set of multiple write latches written.

All of the table write operations are single-word writes (2 instruction cycles), because only the table latches are written. A programming cycle is required for programming each row.

The Flash program memory is readable, writable and erasable during normal operation over the entire VDD range.

### 5.5 Control Registers

The four SFRs used to read and write the program Flash memory are:

- NVMCON
- NVMADR
- NVMADRU
- NVMKEY

#### 5.5.1 NVMCON REGISTER

The NVMCON register controls which blocks are to be erased, which memory type is to be programmed and the start of the programming cycle.

#### 5.5.2 NVMADR REGISTER

The NVMADR register is used to hold the lower two bytes of the Effective Address. The NVMADR register captures the EA<15:0> of the last table instruction that has been executed and selects the row to write.

#### 5.5.3 NVMADRU REGISTER

The NVMADRU register is used to hold the upper byte of the Effective Address. The NVMADRU register captures the EA<23:16> of the last table instruction that has been executed.

#### 5.5.4 NVMKEY REGISTER

NVMKEY is a write-only register that is used for write protection. To start a programming or erase sequence, the user must consecutively write 0x55 and 0xAA to the NVMKEY register. Refer to **Section 5.6** "**Programming Operations**" for further details.

Note:

The user can also directly write to the NVMADR and NVMADRU registers to specify a program memory address for erasing or programming.

#### 5.6 Programming Operations

A complete programming sequence is necessary for programming or erasing the internal Flash in RTSP mode. A programming operation is nominally 2 msec in duration and the processor stalls (waits) until the operation is finished. Setting the WR bit (NVMCON<15>) starts the operation and the WR bit is automatically cleared when the operation is finished.

# 5.6.1 PROGRAMMING ALGORITHM FOR PROGRAM FLASH

The user can erase or program one row of program Flash memory at a time. The general process is:

- Read one row of program Flash (32 instruction words) and store into data RAM as a data "image".
- Update the data image with the desired new data.
- 3. Erase program Flash row.
  - Set up NVMCON register for multi-word, program Flash, erase, and set WREN bit.
  - Write address of row to be erased into NVMADRU/NVMDR.
  - c) Write 0x55 to NVMKEY.
  - d) Write 0xAA to NVMKEY.
  - e) Set the WR bit. This begins erase cycle.
  - f) CPU stalls for the duration of the erase cycle.
  - g) The WR bit is cleared when erase cycle ends.

- Write 32 instruction words of data from data RAM "image" into the program Flash write latches.
- Program 32 instruction words into program Flash.
  - Set up NVMCON register for multi-word, program Flash, program, and set WREN hit
  - b) Write 0x55 to NVMKEY.
  - c) Write 0xAA to NVMKEY.
  - d) Set the WR bit. This begins program cycle.
  - e) CPU stalls for duration of the program cycle.
  - f) The WR bit is cleared by the hardware when program cycle ends.
- Repeat steps 1 through 5 as needed to program desired amount of program Flash memory.

### 5.6.2 ERASING A ROW OF PROGRAM MEMORY

Example 5-1 shows a code sequence that can be used to erase a row (32 instructions) of program memory.

#### **EXAMPLE 5-1: ERASING A ROW OF PROGRAM MEMORY**

```
; Setup NVMCON for erase operation, multi word write
; program memory selected, and writes enabled
               #0x4041,W0
       MOV
               W0 NVMCON
                                             ; Init NVMCON SFR
; Init pointer to row to be ERASED
               #tblpage(PROG_ADDR),W0
       MOV
       MOV
               W0 NVMADRU
                                             ; Initialize PM Page Boundary SFR
       MOV
               #tbloffset(PROG_ADDR),W0
                                             ; Intialize in-page EA[15:0] pointer
       MOV
               W0, NVMADR
                                             ; Initialize NVMADR SFR
                                             ; Block all interrupts with priority <7 for
       DISI
               #5
                                             ; next 5 instructions
               #0x55,W0
       MOV
               WO NVMKEY
                                             ; Write the 0x55 key
       MOV
       MOV
               #0xAA,W1
               W1 NVMKEY
                                             ; Write the 0xAA key
       MOV
       BSET
               NVMCON, #WR
                                             ; Start the erase sequence
       NOP
                                              ; Insert two NOPs after the erase
       NOP
                                              ; command is asserted
```

#### 5.6.3 LOADING WRITE LATCHES

Example 5-2 shows a sequence of instructions that can be used to load the 96 bytes of write latches. 32 TBLWTL and 32 TBLWTH instructions are needed to load the write latches selected by the Table Pointer.

# 5.6.4 INITIATING THE PROGRAMMING SEQUENCE

For protection, the write initiate sequence for NVMKEY must be used to allow any erase or program operation to proceed. After the programming command has been executed, the user must wait for the programming time until programming is complete. The two instructions following the start of the programming sequence should be NOPs as shown in Example 5-3.

#### **EXAMPLE 5-2: LOADING WRITE LATCHES**

```
; Set up a pointer to the first program memory location to be written
; program memory selected, and writes enabled
              #0x0000,W0
       MOV
       MOV
              W0 TBLPAG
                                                 ; Initialize PM Page Boundary SFR
       MOV
              #0x6000,W0
                                                 ; An example program memory address
; Perform the TBLWT instructions to write the latches
; 0th_program_word
       MOV
              #LOW_WORD_0,W2
       MOV
               #HIGH_BYTE_0,W3
       TBLWTL W2 [W0]
                                                 ; Write PM low word into program latch
       TBLWTH W3 [W0++]
                                                 ; Write PM high byte into program latch
; 1st_program_word
       MOV
              #LOW_WORD_1,W2
              #HIGH_BYTE_1,W3
       MOV
       TBLWTL W2 [W0]
                                                ; Write PM low word into program latch
       TBLWTH W3 [W0++]
                                                ; Write PM high byte into program latch
  2nd_program_word
            #LOW_WORD_2,W2
              #HIGH_BYTE_2,W3
       MOV
       TBLWTL W2 [W0]
                                                ; Write PM low word into program latch
       TBLWTH W3 [W0++]
                                                ; Write PM high byte into program latch
; 31st_program_word
       MOV
              #LOW WORD 31,W2
                                                 ;
       MOV
               #HIGH_BYTE_31,W3
                                                 ;
       TBLWTL W2 [W0]
                                                 ; Write PM low word into program latch
       TBLWTH W3 [W0++]
                                                 ; Write PM high byte into program latch
         In Example 5-2, the contents of the upper byte of W3 has no effect.
 Note:
```

#### EXAMPLE 5-3: INITIATING A PROGRAMMING SEQUENCE

```
DISI
       #5
                                  ; Block all interrupts with priority <7 for
                                  ; next 5 instructions
MOV
       #0x55,W0
MOV
       WO NVMKEY
                                  ; Write the 0x55 key
VOM
       #0xAA,W1
       W1 NVMKEY
                                  ; Write the 0xAA key
MOV
BSET
       NVMCON, #WR
                                  ; Start the erase sequence
NOP
                                  ; Insert two NOPs after the erase
NOP
                                  ; command is asserted
```

#### NVM REGISTER MAP<sup>(1)</sup> **TABLE 5-1:**

| File Name | Addr. | Bit 15 | Bit 14 | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7       | Bit 6         | Bit 5 | Bit 4 | Bit 3               | Bit 2 | Bit 1               | Bit 0               | All Resets          |
|-----------|-------|--------|--------|--------|--------|--------|--------|-------|-------|-------------|---------------|-------|-------|---------------------|-------|---------------------|---------------------|---------------------|
| NVMCON    | 0760  | WR     | WREN   | WRERR  | _      | _      | _      | _     | TWRI  | PROGOP<6:0> |               |       |       | 0000 0000 0000 0000 |       |                     |                     |                     |
| NVMADR    | 0762  |        |        |        |        |        |        |       | NVMAD | R<15:0>     | R<15:0>       |       |       |                     |       | uuuu uuuu uuuu uuuu |                     |                     |
| NVMADRU   | 0764  | 1      | -      | _      | -      |        | 1      | -     | -     |             | NVMADR<23:16> |       |       |                     |       |                     | 0000 0000 uuuu uuuu |                     |
| NVMKEY    | 0766  | _      | 1      | _      | -      |        | 1      | -     | -     |             |               |       | KE)   | /<7:0>              |       |                     |                     | 0000 0000 0000 0000 |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

#### 6.0 DATA EEPROM MEMORY

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

The data EEPROM memory is readable and writable during normal operation over the entire VDD range. The data EEPROM memory is directly mapped in the program memory address space.

The four SFRs used to read and write the program Flash memory are used to access data EEPROM memory as well. As described in **Section 5.5 "Control Registers"**, these registers are:

- NVMCON
- NVMADR
- NVMADRU
- NVMKEY

The EEPROM data memory allows read and write of single words and 16-word blocks. When interfacing to data memory, NVMADR, in conjunction with the NVMADRU register, are used to address the EEPROM location being accessed. TBLRDL and TBLWTL instructions are used to read and write data EEPROM. The dsPIC30F devices have up to 8 Kbytes (4K words) of data EEPROM with an address range from 0x7FF000 to 0x7FFFFE.

A word write operation should be preceded by an erase of the corresponding memory location(s). The write typically requires 2 ms to complete, but the write time varies with voltage and temperature.

A program or erase operation on the data EEPROM does not stop the instruction flow. The user is responsible for waiting for the appropriate duration of time before initiating another data EEPROM write/erase operation. Attempting to read the data EEPROM while a programming or erase operation is in progress results in unspecified data.

Control bit, WR, initiates write operations similar to program Flash writes. This bit cannot be cleared, only set, in software. They are cleared in hardware at the completion of the write operation. The inability to clear the WR bit in software prevents the accidental or premature termination of a write operation.

The WREN bit, when set, allows a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, following Reset, the user can check the WRERR bit and rewrite the location. The address register, NVMADR, remains unchanged.

Note: Interrupt flag bit, NVMIF in the IFS0 register, is set when the write is complete. It must be cleared in software.

### 6.1 Reading the Data EEPROM

A TBLRD instruction reads a word at the current program word address. This example uses W0 as a pointer to data EEPROM. The result is placed in register W4 as shown in Example 6-1.

#### **EXAMPLE 6-1: DATA EEPROM READ**

MOV #LOW\_ADDR\_WORD,W0 ; Init Pointer
MOV #HIGH\_ADDR\_WORD,W1
MOV W1,TBLPAG
TBLRDL [ W0 ], W4 ; read data EEPROM

### 6.2 Erasing Data EEPROM

### 6.2.1 ERASING A BLOCK OF DATA EEPROM

In order to erase a block of data EEPROM, the NVMADRU and NVMADR registers must initially point to the block of memory to be erased. Configure NVMCON for erasing a block of data EEPROM and set the WR and WREN bits in the NVMCON register. Setting the WR bit initiates the erase, as shown in Example 6-2.

# 6.2.2 ERASING A WORD OF DATA EEPROM

The NVMADRU and NVMADR registers must point to the block. Select a block of data Flash and set the WR and WREN bits in the NVMCON register. Setting the WR bit initiates the erase, as shown in Example 6-3.

#### **EXAMPLE 6-2:** DATA EEPROM BLOCK ERASE

```
; Select data EEPROM block, WR, WREN bits
   MOV
           #4045,W0
           W0 NVMCON
                                     ; Initialize NVMCON SFR
   MOV
; Start erase cycle by setting WR after writing key sequence
                                     ; Block all interrupts with priority <7 for
   DISI
                                     ; next 5 instructions
   MOV
           #0x55,W0
          W0 NVMKEY
   MOV
                                     ; Write the 0x55 key
   MOV
           #0xAA,W1
   MOV
          W1 NVMKEY
                                     ; Write the OxAA key
          NVMCON, #WR
   BSET
                                     ; Initiate erase sequence
   NOP
   NOP
; Erase cycle will complete in 2mS. CPU is not stalled for the Data Erase Cycle
; User can poll WR bit, use NVMIF or Timer IRQ to determine erasure complete
```

#### **EXAMPLE 6-3: DATA EEPROM WORD ERASE**

```
; Select data EEPROM word, WR, WREN bits
   MOV
           #4044,W0
   MOV
           W0 NVMCON
; Start erase cycle by setting WR after writing key sequence
   DISI
                                          ; Block all interrupts with priority <7 for
                                         ; next 5 instructions
           #0x55,W0
   MOV
   MOV
           WO NVMKEY
                                         ; Write the 0x55 key
   MOV
           #0xAA,W1
   MOV
           W1 NVMKEY
                                         ; Write the 0xAA key
           NVMCON, #WR
   BSET
                                         ; Initiate erase sequence
   NOP
; Erase cycle will complete in 2mS. CPU is not stalled for the Data Erase Cycle
; User can poll WR bit, use NVMIF or Timer IRQ to determine erasure complete
```

### 6.3 Writing to the Data EEPROM

To write an EEPROM data location, the following sequence must be followed:

- 1. Erase the data EEPROM word.
  - Select the word, data EEPROM erase and set the WREN bit in the NVMCON register.
  - Write the address of word to be erased into NVMADR.
  - c) Enable the NVM interrupt (optional).
  - d) Write 0x55 to NVMKEY.
  - e) Write 0xAA to NVMKEY.
  - f) Set the WR bit. This begins the erase cycle.
  - g) Either poll the NVMIF bit or wait for the NVMIF interrupt.
  - h) The WR bit is cleared when the erase cycle ends.
- Write the data word into data the EEPROM write latches.
- 3. Program 1 data word into the data EEPROM.
  - Select the word, data EEPROM program and set the WREN bit in the NVMCON register.
  - b) Enable the NVM write done interrupt (optional).
  - c) Write 0x55 to NVMKEY.
  - d) Write 0xAA to NVMKEY.
  - e) Set the WR bit. This begins the program cycle.
  - Either poll the NVMIF bit or wait for the NVM interrupt.
  - g) The WR bit is cleared when the write cycle ends.

The write does not initiate if the above sequence is not exactly followed (write 0x55 to NVMKEY, write 0xAA to NVMCON, then set WR bit) for each word. It is strongly recommended that interrupts be disabled during this code segment.

Additionally, the WREN bit in NVMCON must be set to enable writes. This mechanism prevents accidental writes to data EEPROM due to unexpected code execution. The WREN bit should be kept clear at all times except when updating the EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, clearing the WREN bit does not affect the current write cycle. The WR bit is inhibited from being set unless the WREN bit is set. The WREN bit must be set on a previous instruction. Both WR and WREN cannot be set with the same instruction.

At the completion of the write cycle, the WR bit is cleared in hardware and the Nonvolatile Memory Write Complete Interrupt Flag bit (NVMIF) is set. The user may either enable this interrupt or poll this bit. NVMIF must be cleared by software.

### 6.3.1 WRITING A WORD OF DATA EEPROM

Once the user has erased the word to be programmed, then a table write instruction is used to write one write latch, as shown in Example 6-4.

# 6.3.2 WRITING A BLOCK OF DATA EEPROM

To write a block of data EEPROM, write to all sixteen latches first, then set the NVMCON register and program the block, as shown in Example 6-5.

#### **EXAMPLE 6-4:** DATA EEPROM WORD WRITE

```
; Point to data memory
   MOV
               #LOW_ADDR_WORD,W0
                                                  ; Init pointer
   MOV
               #HIGH_ADDR_WORD,W1
   MOV
               W1 TBLPAG
   MOV
               #LOW(WORD), W2
                                                  ; Get data
   TBLWTL
               W2 [ W0]
                                                  ; Write data
; The NVMADR captures last table access address
; Select data EEPROM for 1 word op
               #0x4004,W0
   MOV
   MOV
               W0 NVMCON
; Operate key to allow write operation
                                                  ; Block all interrupts with priority <7 for
               #5
   DIST
                                                  ; next 5 instructions
   MOV
               #0x55,W0
               WO NVMKEY
                                                  ; Write the 0x55 key
   MOV
   MOV
               #0xAA,W1
               W1 NVMKEY
   MOV
                                                  ; Write the OxAA key
   BSET
               NVMCON, #WR
                                                  ; Initiate program sequence
    NOP
    NOP
; Write cycle will complete in 2mS. CPU is not stalled for the Data Write Cycle
; User can poll WR bit, use NVMIF or Timer IRQ to determine write complete
```

#### **EXAMPLE 6-5:** DATA EEPROM BLOCK WRITE

```
MOV
           #LOW_ADDR_WORD, WO ; Init pointer
           #HIGH_ADDR_WORD,W1
VOM
MOV
          W1 TBLPAG
           #data1,W2
MOV
                             ; Get 1st data
          W2 [ W0]++
                             ; write data
TBLWTL
MOV
           #data2,W2
                             ; Get 2nd data
                             ; write data
TRI.WTI.
          W2 [ W0]++
          #data3,W2
                            ; Get 3rd data
MOV
TBLWTL
          W2 [ W0]++
                            ; write data
           #data4,W2
                            ; Get 4th data
TBLWTL
          W2 [ W0]++
                            ; write data
          #data5,W2
                             ; Get 5th data
MOV
          W2 [ W0]++
TRI.WTI.
                             ; write data
MOV
          #data6,W2
                             ; Get 6th data
          W2 [ W0]++
TBLWTL
                             ; write data
MOV
          #data7,W2
                             ; Get 7th data
          W2 [ W0]++
                             ; write data
TRI.WTI.
MOV
          #data8,W2
                            ; Get 8th data
TBLWTL
         W2 [ W0]++
                            ; write data
MOV
          #data9,W2
                            ; Get 9th data
          W2,[ W0]++
                            ; write data
TBLWTL
                            ; Get 10th data
          #data10,W2
VOM
TBLWTL
          W2 [ W0]++
                             ; write data
MOV
           #data11,W2
                             ; Get 11th data
TBLWTL
          W2 [ W0]++
                             ; write data
          #data12,W2
                             ; Get 12th data
VOM
          W2 [ W0]++
                            ; write data
TBLWTL
VOM
          #data13,W2
                            ; Get 13th data
TBLWTL
        W2 [ W0]++
                            ; write data
MOV
          #data14,W2
                            ; Get 14th data
        W2 [ W0]++
                             ; write data
TBLWTL
          #data15,W2
                             ; Get 15th data
MOV
TBLWTL
          W2 [ W0]++
                             ; write data
           #data16,W2
                             ; Get 16th data
MOV
          W2 [ W0]++
                             ; write data. The NVMADR captures last table access address.
TBLWTL
                            ; Select data EEPROM for multi word op
           #0x400A,W0
MOV
          W0 NVMCON
                            ; Operate Key to allow program operation
MOV
       #5
                             ; Block all interrupts with priority <7 for
DISI
                             ; next 5 instructions
MOV
           #0×55.W0
           WO NVMKEY
MOV
                             ; Write the 0x55 key
MOV
           #0xAA,W1
           W1 NVMKEY
                             ; Write the 0xAA key
MOV
BSET
          NVMCON, #WR
                             ; Start write cycle
MOP
NOP
```

### 6.4 Write Verify

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

### 6.5 Protection Against Spurious Write

There are conditions when the device may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built-in. On power-up, the WREN bit is cleared; also, the Power-up Timer prevents EEPROM write.

The write initiate sequence, and the WREN bit together, help prevent an accidental write during brown-out, power glitch or software malfunction.

#### **7.0 I/O PORTS**

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

All of the device pins (except VDD, Vss,  $\overline{MCLR}$  and OSC1/CLKI) are shared between the peripherals and the parallel I/O ports.

All I/O input ports feature Schmitt Trigger inputs for improved noise immunity.

### 7.1 Parallel I/O (PIO) Ports

When a peripheral is enabled and the peripheral is actively driving an associated pin, the use of the pin as a general purpose output pin is disabled. The I/O pin can be read, but the output driver for the parallel port bit is disabled. If a peripheral is enabled but the peripheral is not actively driving a pin, that pin can be driven by a port.

All port pins have three registers directly associated with the operation of the port pin. The Data Direction register (TRISx) determines whether the pin is an input or an output. If the data direction bit is a '1', then the pin is an input. All port pins are defined as inputs after a Reset.

Reads from the latch (LATx), read the latch. Writes to the latch, write the latch (LATx). Reads from the port (PORTx), read the port pins and writes to the port pins, write the latch (LATx).


Any bit and its associated data and control registers that are not valid for a particular device are disabled, which means the corresponding LATx and TRISx registers and the port pin read as zeros.


When a pin is shared with another peripheral or function that is defined as an input only, it is nevertheless regarded as a dedicated port because there is no other competing source of outputs. An example is the INT4 pin.

A Parallel I/O (PIO) port that shares a pin with a peripheral is, in general, subservient to the peripheral. The peripheral's output buffer data and control signals are provided to a pair of multiplexers. The multiplexers select whether the peripheral or the associated port has ownership of the output data and control signals of the I/O pad cell. Figure 7-2 shows how ports are shared with other peripherals and the associated I/O cell (pad) to which they are connected. Table 7-1 shows the formats of the registers for the shared ports, PORTB through PORTF.

**Note:** The actual bits in use vary between devices.

FIGURE 7-1: BLOCK DIAGRAM OF A DEDICATED PORT STRUCTURE





#### **FIGURE 7-2: BLOCK DIAGRAM OF A SHARED PORT STRUCTURE**

#### 7.2 **Configuring Analog Port Pins**

The use of the ADPCFG and TRIS registers control the operation of the A/D port pins. The port pins that are desired as analog inputs must have their corresponding TRIS bit set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) is converted.

When the PORT register is read, all pins configured as analog input channels are read as cleared (a low level).

Pins configured as digital inputs will not convert an analog input. Analog levels on any pin that is defined as a digital input (including the ANx pins) may cause the input buffer to consume current that exceeds the device specifications.

#### 7.2.1 I/O PORT WRITE/READ TIMING

One instruction cycle is required between a port direction change or port write operation and a read operation of the same port. Typically, this instruction would be a NOP.

#### **EXAMPLE 7-1: PORT WRITE/READ EXAMPLE**

```
MOV 0xFF00, W0; Configure PORTB<15:8>
              ; as inputs
MOV W0, TRISB ; and PORTB<7:0> as outputs
NOP
               ; additional instruction
                    cycle
BTSS PORTB, #11; bit test RB11 and skip if set
```

TABLE 7-1: dsPIC30F3014/4013 PORT REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15  | Bit 14  | Bit 13  | Bit 12  | Bit 11  | Bit 10  | Bit 9  | Bit 8  | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2  | Bit 1  | Bit 0  | Reset State         |
|----------|-------|---------|---------|---------|---------|---------|---------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|---------------------|
| TRISA    | 02C0  | _       | _       | _       | _       | TRISA11 | _       | _      | _      | _      | _      | _      | _      | _      | _      | _      | _      | 0000 1000 0000 0000 |
| PORTA    | 02C2  | _       | _       | _       | _       | RA11    | _       | _      | _      | _      | _      | _      | _      | _      | _      | _      | _      | 0000 0000 0000 0000 |
| LATA     | 02C4  | -       | _       | _       | _       | LATA11  | _       | _      | _      | _      | _      | _      | _      | -      | _      | _      | _      | 0000 0000 0000 0000 |
| TRISB    | 02C6  | -       | _       | _       | TRISB12 | TRISB11 | TRISB10 | TRISB9 | TRISB8 | TRISB7 | TRISB6 | TRISB5 | TRISB4 | TRISB3 | TRISB2 | TRISB1 | TRISB0 | 0001 1111 1111 1111 |
| PORTB    | 02C8  | -       | _       | _       | RB12    | RB11    | RB10    | RB9    | RB8    | RB7    | RB6    | RB5    | RB4    | RB3    | RB2    | RB1    | RB0    | 0000 0000 0000 0000 |
| LATB     | 02CB  | -       | _       | _       | LATB12  | LATB11  | LATB10  | LATB9  | LATB8  | LATB7  | LATB6  | LATB5  | LATB4  | LATB3  | LATB2  | LATB1  | LATB0  | 0000 0000 0000 0000 |
| TRISC    | 02CC  | TRISC15 | TRISC14 | TRISC13 | I       |         | _       | _      | _      | -      |        | 1      | 1      | I      | 1      | _      | _      | 1110 0000 0000 0000 |
| PORTC    | 02CE  | RC15    | RC14    | RC13    |         | _       | _       | _      | _      | _      |        | _      | _      | 1      |        | _      | _      | 0000 0000 0000 0000 |
| LATC     | 02D0  | LATC15  | LATC14  | LATC13  | _       | _       | _       | _      | _      | _      | _      | _      | _      | -      | _      | _      | _      | 0000 0000 0000 0000 |
| TRISD    | 02D2  | _       | _       | _       | _       | _       | _       | TRISD9 | TRISD8 | _      | _      | _      | _      | TRISD3 | TRISD2 | TRISD1 | TRISD0 | 0000 0011 0000 1111 |
| PORTD    | 02D4  | _       | _       | _       | _       | _       | _       | RD9    | RD8    | _      | _      | _      | _      | RD3    | RD2    | RD1    | RD0    | 0000 0000 0000 0000 |
| LATD     | 02D6  | _       | _       | _       | _       | _       | _       | LATD9  | LATD8  | _      | _      | _      | _      | LATD3  | LATD2  | LATD1  | LATD0  | 0000 0000 0000 0000 |
| TRISF    | 02DE  | _       | _       | _       | _       | _       | _       | _      | _      | _      | TRISF6 | TRISF5 | TRISF4 | TRISF3 | TRISF2 | TRISF1 | TRISF0 | 0000 0000 0111 1111 |
| PORTF    | 02E0  | -       | _       | _       | 1       | _       | _       | _      | _      | _      | RF6    | RF5    | RF4    | RF3    | RF2    | RF1    | RF0    | 0000 0000 0000 0000 |
| LATF     | 02E2  | -       | _       | _       | 1       | _       | _       | _      | _      | _      | LATF6  | LATF5  | LATF4  | LATF3  | LATF2  | LATF1  | LATF0  | 0000 0000 0000 0000 |

Legend: — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

### 7.3 Input Change Notification Module

The input change notification module provides the dsPIC30F devices the ability to generate interrupt requests to the processor, in response to a Change-Of-State (COS) on selected input pins. This module is capable of detecting input Change-Of-States, even in Sleep mode, when the clocks are disabled. There are up to 10 external signals (CN0 through CN9, CN17 and CN18) that may be selected (enabled) for generating an interrupt request on a Change-Of-State.

TABLE 7-2: INPUT CHANGE NOTIFICATION REGISTER MAP FOR dsPIC30F3014/4013 DEVICES (BITS 15-0)<sup>(1)</sup>

| SFR<br>Name | Addr. | Bit 15 | Bit 14 | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7  | Bit 6  | Bit 5  | Bit 4  | Bit 3  | Bit 2   | Bit 1   | Bit 0  | Reset State         |
|-------------|-------|--------|--------|--------|--------|--------|--------|-------|-------|--------|--------|--------|--------|--------|---------|---------|--------|---------------------|
| CNEN1       | 00C0  | _      | _      | _      | _      | _      | _      |       | _     | CN7IE  | CN6IE  | CN5IE  | CN4IE  | CN3IE  | CN2IE   | CN1IE   | CN0IE  | 0000 0000 0000 0000 |
| CNEN2       | 00C2  | _      | _      | _      | _      | _      | _      | _     | _     | _      | _      | _      | _      |        | CN18IE  | CN17IE  | _      | 0000 0000 0000 0000 |
| CNPU1       | 00C4  | _      | _      | _      | _      | _      | _      | _     | _     | CN7PUE | CN6PUE | CN5PUE | CN4PUE | CN3PUE | CN2PUE  | CN1PUE  | CN0PUE | 0000 0000 0000 0000 |
| CNPU2       | 00C6  | _      | _      | _      | _      | _      | _      | _     | _     | _      | _      | _      | _      |        | CN18PUE | CN17PUE | _      | 0000 0000 0000 0000 |

**Legend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

#### 8.0 INTERRUPTS

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

The dsPIC30F sensor and general purpose families have up to 41 interrupt sources and 4 processor exceptions (traps) which must be arbitrated based on a priority scheme.

The CPU is responsible for reading the Interrupt Vector Table (IVT) and transferring the address contained in the interrupt vector to the program counter. The interrupt vector is transferred from the program data bus into the program counter via a 24-bit wide multiplexer on the input of the program counter.

The Interrupt Vector Table (IVT) and Alternate Interrupt Vector Table (AIVT) are placed near the beginning of program memory (0x000004). The IVT and AIVT are shown in Figure 8-1.

The interrupt controller is responsible for preprocessing the interrupts and processor exceptions prior to them being presented to the processor core. The peripheral interrupts and traps are enabled, prioritized and controlled using centralized Special Function Registers:

- IFS0<15:0>, IFS1<15:0>, IFS2<15:0>
   All interrupt request flags are maintained in these three registers. The flags are set by their respective peripherals or external signals and they are cleared via software.
- IEC0<15:0>, IEC1<15:0>, IEC2<15:0>
   All interrupt enable control bits are maintained in these three registers. These control bits are used to individually enable interrupts from the peripherals or external signals.
- IPC0<15:0>... IPC10<7:0>
   The user-assignable priority level associated with each of these 41 interrupts is held centrally in these eleven registers.
- IPL<3:0>
   The current CPU priority level is explicitly stored in the IPL bits. IPL<3> is present in the CORCON register, whereas IPL<2:0> are present in the

STATUS register (SR) in the processor core.

INTCON1<15:0>, INTCON2<15:0>
 Global interrupt control functions are derived from these two registers. INTCON1 contains the control and status flags for the processor exceptions. The INTCON2 register controls the external interrupt request signal behavior and the use of the alternate vector table.

Note

Interrupt flag bits get set when an interrupt condition occurs, regardless of the state of its corresponding enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

All interrupt sources can be user-assigned to one of 7 priority levels, 1 through 7, via the IPCx registers. Each interrupt source is associated with an interrupt vector, as shown in Table 8-1. Levels 7 and 1 represent the highest and lowest maskable priorities, respectively.

Note:

Assigning a priority level of '0' to an interrupt source is equivalent to disabling that interrupt.

If the NSTDIS bit (INTCON1<15>) is set, nesting of interrupts is prevented. Thus, if an interrupt is currently being serviced, processing of a new interrupt is prevented even if the new interrupt is of higher priority than the one currently being serviced.

Note:

The IPL bits become read-only whenever the NSTDIS bit has been set to '1'.

Certain interrupts have specialized control bits for features like edge or level triggered interrupts, interrupt-on-change, etc. Control of these features remains within the peripheral module which generates the interrupt.

The DISI instruction can be used to disable the processing of interrupts of priorities 6 and lower for a certain number of instructions, during which the DISI bit (INTCON2<14>) remains set.

When an interrupt is serviced, the PC is loaded with the address stored in the vector location in program memory that corresponds to the interrupt. There are 63 different vectors within the IVT (refer to Table 8-1) These vectors are contained in locations 0x000004 through 0x0000FE of program memory (refer to Table 8-1). These locations contain 24-bit addresses. In order to preserve robustness, an address error trap takes place should the PC attempt to fetch any of these words during normal execution. This prevents execution of random data as a result of accidentally decrementing a PC into vector space, accidentally mapping a data space address into vector space or the PC rolling over to 0x000000 after reaching the end of implemented program memory space. Execution of a GOTO instruction to this vector space also generates an address error trap.

#### 8.1 Interrupt Priority

The user-assignable interrupt priority (IP<2:0>) bits for each individual interrupt source are located in the 3 LSbs of each nibble within the IPCx register(s). Bit 3 of each nibble is not used and is read as a '0'. These bits define the priority level assigned to a particular interrupt by the user.

Note: The user-assignable priority levels start at 0 as the lowest priority and Level 7 as the highest priority.

Since more than one interrupt request source may be assigned to a specific user-assigned priority level, a means is provided to assign priority within a given level. This method is called "Natural Order Priority" and is final.

Natural Order Priority is determined by the position of an interrupt in the vector table, and only affects interrupt operation when multiple interrupts with the same user-assigned priority become pending at the same time.

Table 8-1 and Table 8-2 list the interrupt numbers, corresponding interrupt sources and associated vector numbers for the dsPIC30F3014 and dsPIC30F4013 devices, respectively.

- **Note 1:** The natural order priority scheme has 0 as the highest priority and 53 as the lowest priority.
  - **2:** The natural order priority number is the same as the INT number.

The ability for the user to assign every interrupt to one of seven priority levels means that the user can assign a very high overall priority level to an interrupt with a low natural order priority. For example, the PLVD (Programmable Low-Voltage Detect) can be given a priority of 7. The INTO (External Interrupt 0) may be assigned to priority Level 1, thus giving it a very low effective priority.

TABLE 8-1: dsPIC30F3014 INTERRUPT VECTOR TABLE

| INT<br>Number | Vector<br>Number | Interrupt Source                         |
|---------------|------------------|--|
|               | Highest          | Natural Order Priority                   |
| 0             | 8                | INT0 – External Interrupt 0              |
| 1             | 9                | IC1 – Input Capture 1                    |
| 2             | 10               | OC1 – Output Compare 1                   |
| 3             | 11               | T1 – Timer1                              |
| 4             | 12               | IC2 – Input Capture 2                    |
| 5             | 13               | OC2 – Output Compare 2                   |
| 6             | 14               | T2 – Timer2                              |
| 7             | 15               | T3 – Timer3                              |
| 8             | 16               | SPI1                                     |
| 9             | 17               | U1RX – UART1 Receiver                    |
| 10            | 18               | U1TX – UART1 Transmitter                 |
| 11            | 19               | ADC – ADC Convert Done                   |
| 12            | 20               | NVM – NVM Write Complete                 |
| 13            | 21               | SI2C – I <sup>2</sup> C™ Slave Interrupt |
| 14            | 22               | MI2C – I <sup>2</sup> C Master Interrupt |
| 15            | 23               | Input Change Interrupt                   |
| 16            | 24               | INT1 – External Interrupt 1              |
| 17-22         | 25-30            | Reserved                                 |
| 23            | 31               | INT2 – External Interrupt 2              |
| 24            | 32               | U2RX – UART2 Receiver                    |
| 25            | 33               | U2TX – UART2 Transmitter                 |
| 26            | 34               | Reserved                                 |
| 27            | 35               | C1 – Combined IRQ for CAN1               |
| 28-41         | 36-49            | Reserved                                 |
| 42            | 50               | LVD – Low-Voltage Detect                 |
| 43-53         | 51-61            | Reserved                                 |
|               | Lowest           | Natural Order Priority                   |

TABLE 8-2: dsPIC30F4013 INTERRUPT VECTOR TABLE

| Interrupt<br>Number | Vector<br>Number | Interrupt Source                         |  |  |  |  |  |  |  |
|---------------------|------------------|--|--|--|--|--|--|--|--|
|                     | Highest I        | Natural Order Priority                   |  |  |  |  |  |  |  |
| 0                   | 8                | INT0 – External Interrupt 0              |  |  |  |  |  |  |  |
| 1                   | 9                | IC1 – Input Capture 1                    |  |  |  |  |  |  |  |
| 2                   | 10               | OC1 – Output Compare 1                   |  |  |  |  |  |  |  |
| 3                   | 11               | T1 – Timer1                              |  |  |  |  |  |  |  |
| 4                   | 12               | IC2 – Input Capture 2                    |  |  |  |  |  |  |  |
| 5                   | 13               | OC2 – Output Compare 2                   |  |  |  |  |  |  |  |
| 6                   | 14               | T2 V Timer2                              |  |  |  |  |  |  |  |
| 7                   | 15               | T3 – Timer3                              |  |  |  |  |  |  |  |
| 8                   | 16               | SPI1                                     |  |  |  |  |  |  |  |
| 9                   | 17               | U1RX – UART1 Receiver                    |  |  |  |  |  |  |  |
| 10                  | 18               | U1TX – UART1 Transmitter                 |  |  |  |  |  |  |  |
| 11                  | 19               | ADC – ADC Convert Done                   |  |  |  |  |  |  |  |
| 12                  | 20               | NVM – NVM Write Complete                 |  |  |  |  |  |  |  |
| 13                  | 21               | SI2C – I <sup>2</sup> C™ Slave Interrupt |  |  |  |  |  |  |  |
| 14                  | 22               | MI2C – I <sup>2</sup> C Master Interrupt |  |  |  |  |  |  |  |
| 15                  | 23               | Input Change Interrupt                   |  |  |  |  |  |  |  |
| 16                  | 24               | INT1 – External Interrupt 1              |  |  |  |  |  |  |  |
| 17                  | 25               | IC7 – Input Capture 7                    |  |  |  |  |  |  |  |
| 18                  | 26               | IC8 – Input Capture 8                    |  |  |  |  |  |  |  |
| 19                  | 27               | OC3 – Output Compare 3                   |  |  |  |  |  |  |  |
| 20                  | 28               | OC4 – Output Compare 4                   |  |  |  |  |  |  |  |
| 21                  | 29               | T4 – Timer4                              |  |  |  |  |  |  |  |
| 22                  | 30               | T5 – Timer5                              |  |  |  |  |  |  |  |
| 23                  | 31               | INT2 – External Interrupt 2              |  |  |  |  |  |  |  |
| 24                  | 32               | U2RX – UART2 Receiver                    |  |  |  |  |  |  |  |
| 25                  | 33               | U2TX – UART2 Transmitter                 |  |  |  |  |  |  |  |
| 26                  | 34               | Reserved                                 |  |  |  |  |  |  |  |
| 27                  | 35               | C1 – Combined IRQ for CAN1               |  |  |  |  |  |  |  |
| 28-40               | 36-48            | Reserved                                 |  |  |  |  |  |  |  |
| 41                  | 49               | DCI – CODEC Transfer Done                |  |  |  |  |  |  |  |
| 42                  | 50               | LVD – Low-Voltage Detect                 |  |  |  |  |  |  |  |
| 43-53               | 51-61            | Reserved                                 |  |  |  |  |  |  |  |
|                     | Lowest N         | Natural Order Priority                   |  |  |  |  |  |  |  |

#### 8.2 Reset Sequence

A Reset is not a true exception because the interrupt controller is not involved in the Reset process. The processor initializes its registers in response to a Reset which forces the PC to zero. The processor then begins program execution at location 0x000000. A GOTO instruction is stored in the first program memory location immediately followed by the address target for the GOTO instruction. The processor executes the GOTO to the specified address and then begins operation at the specified target (start) address.

#### 8.2.1 RESET SOURCES

In addition to external Reset and Power-on Reset (POR), these sources of error conditions 'trap' to the Reset vector:

- Watchdog Time-out:
   The watchdog has timed out, indicating that the processor is no longer executing the correct flow of code.
- Uninitialized W Register Trap:
   An attempt to use an uninitialized W register as an Address Pointer causes a Reset.
- Illegal Instruction Trap:
   Attempted execution of any unused opcodes results in an illegal instruction trap. Note that a fetch of an illegal instruction does not result in an illegal instruction trap if that instruction is flushed prior to execution due to a flow change.
- Brown-out Reset (BOR):
   A momentary dip in the power supply to the device has been detected which may result in malfunction.
- Trap Lockout:
   Occurrence of multiple trap conditions simultaneously causes a Reset.

### 8.3 Traps

Traps can be considered as non-maskable interrupts, indicating a software or hardware error, which adhere to a predefined priority as shown in Figure 8-1. They are intended to provide the user a means to correct erroneous operation during debug and when operating within the application.

Note:

If the user does not intend to take corrective action in the event of a trap error condition, these vectors must be loaded with the address of a default handler that simply contains the RESET instruction. If, on the other hand, one of the vectors containing an invalid address is called, an address error trap is generated.

Note that many of these trap conditions can only be detected when they occur. Consequently, the questionable instruction is allowed to complete prior to trap exception processing. If the user chooses to recover from the error, the result of the erroneous action that caused the trap may have to be corrected.

There are 8 fixed priority levels for traps: Level 8 through Level 15, which means that the IPL3 is always set during processing of a trap.

If the user is not currently executing a trap, and he sets the IPL<3:0> bits to a value of '0111' (Level 7), then all interrupts are disabled, but traps can still be processed.

#### 8.3.1 TRAP SOURCES

The following traps are provided with increasing priority. However, since all traps can be nested, priority has little effect.

#### Math Error Trap:

The math error trap executes under these circumstances:

- Should an attempt be made to divide by zero, the divide operation aborts on a cycle boundary and the trap is taken.
- If enabled, a math error trap is taken when an arithmetic operation on either accumulator A or B causes an overflow from bit 31 and the accumulator guard bits are not utilized.
- 3. If enabled, a math error trap is taken when an arithmetic operation on either accumulator A or B causes a catastrophic overflow from bit 39 and all saturation is disabled.
- If the shift amount specified in a shift instruction is greater than the maximum allowed shift amount, a trap occurs.

#### Address Error Trap:

This trap is initiated when any of the following circumstances occurs:

- 1. A misaligned data word access is attempted.
- A data fetch from our unimplemented data memory location is attempted.
- 3. A data access of an unimplemented program memory location is attempted.
- 4. An instruction fetch from vector space is attempted.

Note: In the MAC class of instructions, wherein the data space is split into X and Y data space, unimplemented X space includes all of Y space, and unimplemented Y space includes all of X space.

- Execution of a "BRA #literal" instruction or a "GOTO #literal" instruction, where literal is an unimplemented program memory address.
- Executing instructions after modifying the PC to point to unimplemented program memory addresses. The PC may be modified by loading a value into the stack and executing a RETURN instruction.

#### Stack Error Trap:

This trap is initiated under the following conditions:

- The Stack Pointer is loaded with a value which is greater than the (user-programmable) limit value written into the SPLIM register (stack overflow).
- The Stack Pointer is loaded with a value which is less than 0x0800 (simple stack underflow).

#### Oscillator Fail Trap:

This trap is initiated if the external oscillator fails and operation becomes reliant on an internal RC backup.

#### 8.3.2 HARD AND SOFT TRAPS

It is possible that multiple traps can become active within the same cycle (e.g., a misaligned word stack write to an overflowed address). In such a case, the fixed priority shown in Figure 8-2 is implemented, which may require the user to check if other traps are pending, in order to completely correct the Fault.


'Soft' traps include exceptions of priority Level 8 through Level 11, inclusive. The arithmetic error trap (Level 11) falls into this category of traps.

'Hard' traps include exceptions of priority Level 12 through Level 15, inclusive. The address error (Level 12), stack error (Level 13) and oscillator error (Level 14) traps fall into this category.

Each hard trap that occurs must be Acknowledged before code execution of any type may continue. If a lower priority hard trap occurs while a higher priority trap is pending, Acknowledged, or is being processed, a hard trap conflict occurs.

The device is automatically Reset in a hard trap conflict condition. The TRAPR status bit (RCON<15>) is set when the Reset occurs so that the condition may be detected in software.

FIGURE 8-1: TRAP VECTORS




#### 8.4 Interrupt Sequence

All interrupt event flags are sampled in the beginning of each instruction cycle by the IFSx registers. A pending Interrupt Request (IRQ) is indicated by the flag bit being equal to a '1' in an IFSx register. The IRQ causes an interrupt to occur if the corresponding bit in the Interrupt Enable (IECx) register is set. For the remainder of the instruction cycle, the priorities of all pending interrupt requests are evaluated.

If there is a pending IRQ with a priority level greater than the current processor priority level in the IPL bits, the processor is interrupted.

The processor then stacks the current program counter and the low byte of the processor STATUS register (SRL), as shown in Figure 8-2. The low byte of the STATUS register contains the processor priority level at the time prior to the beginning of the interrupt cycle. The processor then loads the priority level for this interrupt into the STATUS register. This action disables all lower priority interrupts until the completion of the Interrupt Service Routine.

FIGURE 8-2: INTERRUPT STACK FRAME



- Note 1: The user can always lower the priority level by writing a new value into SR. The Interrupt Service Routine must clear the interrupt flag bits in the IFSx register before lowering the processor interrupt priority, in order to avoid recursive interrupts.
  - 2: The IPL3 bit (CORCON<3>) is always clear when interrupts are being processed. It is set only during execution of traps.

The RETFIE (return from interrupt) instruction unstacks the program counter and STATUS registers to return the processor to its state prior to the interrupt sequence.

#### 8.5 Alternate Vector Table

In program memory, the Interrupt Vector Table (IVT) is followed by the Alternate Interrupt Vector Table (AIVT), as shown in Figure 8-1. Access to the alternate vector table is provided by the ALTIVT bit in the INTCON2 register. If the ALTIVT bit is set, all interrupt and exception processes use the alternate vectors instead of the default vectors. The alternate vectors are organized in the same manner as the default vectors. The AIVT supports emulation and debugging efforts by providing a means to switch between an application and a support environment without requiring the interrupt vectors to be reprogrammed. This feature also enables switching between applications for evaluation of different software algorithms at run time.

If the AIVT is not required, the program memory allocated to the AIVT may be used for other purposes. AIVT is not a protected section and may be freely programmed by the user.

### 8.6 Fast Context Saving

A context saving option is available using shadow registers. Shadow registers are provided for the DC, N, OV, Z and C bits in SR, and the registers, W0 through W3. The shadows are only one level deep. The shadow registers are accessible using the PUSH.S and POP.S instructions only.

When the processor vectors to an interrupt, the PUSH.S instruction can be used to store the current value of the aforementioned registers into their respective shadow registers.

If an ISR of a certain priority uses the PUSH.S and POP.S instructions for fast context saving, then a higher priority ISR should not include the same instructions. Users must save the key registers in software during a lower priority interrupt if the higher priority ISR uses fast context saving.

#### 8.7 External Interrupt Requests

The interrupt controller supports up to five external interrupt request signals, INT0-INT4. These inputs are edge sensitive; they require a low-to-high or a high-to-low transition to generate an interrupt request. The INTCON2 register has three bits, INT0EP-INT2EP, that select the polarity of the edge detection circuitry.

#### 8.8 Wake-up from Sleep and Idle

The interrupt controller may be used to wake-up the processor from either Sleep or Idle mode, if Sleep or Idle mode is active when the interrupt is generated.

If an enabled interrupt request of sufficient priority is received by the interrupt controller, then the standard interrupt request is presented to the processor. At the same time, the processor wakes up from Sleep or Idle and begins execution of the Interrupt Service Routine (ISR) needed to process the interrupt request.

TABLE 8-3: dsPIC30F3014 INTERRUPT CONTROLLER REGISTER MAP<sup>(1)</sup>

| SFR<br>Name | ADR  | Bit 15 | Bit 14 | Bit 13    | Bit 12 | Bit 11 | Bit 10 | Bit 9      | Bit 8  | Bit 7  | Bit 6 | Bit 5   | Bit 4   | Bit 3   | Bit 2  | Bit 1       | Bit 0  | Reset State         |
|-------------|------|--------|--------|-----------|--------|--------|--------|------------|--------|--------|-------|---------|---------|---------|--------|-------------|--------|---------------------|
| INTCON1     | 0080 | NSTDIS | _      | _         | _      | _      | OVATE  | OVBTE      | COVTE  | _      | _     | _       | MATHERR | ADDRERR | STKERR | OSCFAIL     | _      | 0000 0000 0000 0000 |
| INTCON2     | 0082 | ALTIVT | DISI   | _         | _      | _      | _      | _          | _      | _      | _     | _       | _       | _       | INT2EP | INT1EP      | INT0EP | 0000 0000 0000 0000 |
| IFS0        | 0084 | CNIF   | MI2CIF | SI2CIF    | NVMIF  | ADIF   | U1TXIF | U1RXIF     | SPI1IF | T3IF   | T2IF  | OC2IF   | IC2IF   | T1IF    | OC1IF  | IC1IF       | INT0IF | 0000 0000 0000 0000 |
| IFS1        | 0086 | _      | _      | _         | _      | C1IF   | _      | U2TXIF     | U2RXIF | INT2IF | _     | _       | _       | _       | _      | _           | INT1IF | 0000 0000 0000 0000 |
| IFS2        | 0088 | _      | _      | _         | _      | _      | LVDIF  | 1          | _      |        | _     | _       | _       | _       | _      | _           | _      | 0000 0000 0000 0000 |
| IEC0        | 008C | CNIE   | MI2CIE | SI2CIE    | NVMIE  | ADIE   | U1TXIE | U1RXIE     | SPI1IE | T3IE   | T2IE  | OC2IE   | IC2IE   | T1IE    | OC1IE  | IC1IE       | INT0IE | 0000 0000 0000 0000 |
| IEC1        | 008E | _      | _      | _         | _      | C1IE   | _      | U2TXIE     | U2RXIE | INT2IE | _     | _       | _       | _       | _      | _           | INT1IE | 0000 0000 0000 0000 |
| IEC2        | 0090 | _      | _      | _         | _      | _      | LVDIE  | _          | _      | _      | _     | _       | _       | _       | _      | _           | _      | 0000 0000 0000 0000 |
| IPC0        | 0094 | _      |        | T1IP<2:0> | •      | _      | C      | C1IP<2:0   | >      | _      |       | IC1IP<  | 2:0>    | _       | I      | NT0IP<2:0>  | •      | 0100 0100 0100 0100 |
| IPC1        | 0096 | _      | ٦      | Γ31P<2:0  | >      | _      |        | T2IP<2:0>  | •      | _      |       | OC2IP<  | :2:0>   | _       |        | IC2IP<2:0>  |        | 0100 0100 0100 0100 |
| IPC2        | 0098 | _      | A      | ADIP<2:0  | >      | _      | U      | 1TXIP<2:0  | )>     | _      |       | U1RXIP  | <2:0>   | _       | 5      | SPI1IP<2:0> | >      | 0100 0100 0100 0100 |
| IPC3        | 009A | _      | (      | CNIP<2:0: | >      | _      | N      | II2CIP<2:0 | )>     | _      |       | SI2CIP< | <2:0>   | _       | ١      | NVMIP<2:0>  | >      | 0100 0100 0100 0100 |
| IPC4        | 009C | _      | _      | _         | _      | _      | _      | _          | _      | _      | _     | _       | _       | _       | I      | NT1IP<2:0>  | >      | 0100 0100 0100 0100 |
| IPC5        | 009E | _      | II.    | NT2IP<2:0 | )>     | _      | _      | _          | _      | _      | -     | _       | _       | _       | _      | _           | _      | 0100 0100 0100 0100 |
| IPC6        | 00A0 | _      | (      | C1IP<2:0> | >      | _      | _      | _          | _      |        |       | U2TXIP  | <2:0>   | _       | U      | J2RXIP<2:0  | >      | 0100 0100 0100 0100 |
| IPC7        | 00A2 | _      | _      | _         | _      | _      | _      | _          | _      | _      | _     | _       | _       | _       | _      | _           | _      | 0100 0100 0100 0100 |
| IPC8        | 00A4 | _      | _      | _         | _      | _      | _      | _          | _      | _      | -     | _       | _       | _       | _      | _           | _      | 0100 0100 0100 0100 |
| IPC9        | 00A6 | _      | _      | _         | _      | _      | _      | _          | _      | _      | -     | _       | _       | _       | _      | _           | _      | 0000 0100 0100 0100 |
| IPC10       | 00A8 | _      | _      | _         | _      | _      | L      | VDIP<2:0   | >      | _      |       | DCIIP<  | 2:0>    | _       | _      | _           | _      | 0000 0100 0100 0000 |

**Legend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

TABLE 8-4: dsPIC30F4013 INTERRUPT CONTROLLER REGISTER MAP<sup>(1)</sup>

| SFR<br>Name | ADR  | Bit 15 | Bit 14 | Bit 13    | Bit 12 | Bit 11 | Bit 10 | Bit 9      | Bit 8  | Bit 7  | Bit 6 | Bit 5   | Bit 4   | Bit 3   | Bit 2  | Bit 1      | Bit 0  | Reset State         |
|-------------|------|--------|--------|-----------|--------|--------|--------|------------|--------|--------|-------|---------|---------|---------|--------|------------|--------|---------------------|
| INTCON1     | 0080 | NSTDIS | _      | _         | _      |        | OVATE  | OVBTE      | COVTE  | -      | _     | _       | MATHERR | ADDRERR | STKERR | OSCFAIL    | _      | 0000 0000 0000 0000 |
| INTCON2     | 0082 | ALTIVT | DISI   | _         | _      | _      | _      | _          | _      | _      | _     | _       | _       | _       | INT2EP | INT1EP     | INT0EP | 0000 0000 0000 0000 |
| IFS0        | 0084 | CNIF   | MI2CIF | SI2CIF    | NVMIF  | ADIF   | U1TXIF | U1RXIF     | SPI1IF | T3IF   | T2IF  | OC2IF   | IC2IF   | T1IF    | OC1IF  | IC1IF      | INT0IF | 0000 0000 0000 0000 |
| IFS1        | 0086 | _      | _      | _         | _      | C1IF   | _      | U2TXIF     | U2RXIF | INT2IF | T5IF  | T4IF    | OC4IF   | OC3IF   | IC8IF  | IC7IF      | INT1IF | 0000 0000 0000 0000 |
| IFS2        | 0088 | _      | _      | _         | _      | -      | LVDIF  | DCIIF      | I      | 1      | 1     | _       | _       | _       | _      | _          | _      | 0000 0000 0000 0000 |
| IEC0        | 008C | CNIE   | MI2CIE | SI2CIE    | NVMIE  | ADIE   | U1TXIE | U1RXIE     | SPI1IE | T3IE   | T2IE  | OC2IE   | IC2IE   | T1IE    | OC1IE  | IC1IE      | INT0IE | 0000 0000 0000 0000 |
| IEC1        | 008E | _      | _      | _         | _      | C1IE   | _      | U2TXIE     | U2RXIE | INT2IE | T5IE  | T4IE    | OC4IE   | OC3IE   | IC8IE  | IC7IE      | INT1IE | 0000 0000 0000 0000 |
| IEC2        | 0090 | _      | _      | _         | _      | _      | LVDIE  | DCIIE      | -      | _      | _     | _       | _       | _       | _      | _          | _      | 0000 0000 0000 0000 |
| IPC0        | 0094 | _      | Т      | Γ1IP<2:0> | ,      | _      | C      | OC1IP<2:0  | >      | _      |       | IC1IP<  | 2:0>    | _       | I      | NT0IP<2:0  | >      | 0100 0100 0100 0100 |
| IPC1        | 0096 | _      | Т      | 31P<2:0>  | •      | _      |        | T2IP<2:0>  | •      | _      |       | OC2IP<  | :2:0>   | _       |        | IC2IP<2:0> |        | 0100 0100 0100 0100 |
| IPC2        | 0098 | _      | Δ      | DIP<2:0>  | •      | _      | U      | 1TXIP<2:0  | )>     | _      |       | U1RXIP  | <2:0>   | _       | 5      | SPI1IP<2:0 | >      | 0100 0100 0100 0100 |
| IPC3        | 009A | _      | C      | NIP<2:0>  | •      | _      | N      | 112CIP<2:0 | )>     | _      |       | SI2CIP< | :2:0>   | _       | 1      | NVMIP<2:0  | >      | 0100 0100 0100 0100 |
| IPC4        | 009C | _      | 0      | C3IP<2:0  | >      | _      | I      | IC8IP<2:0> | >      | _      |       | IC7IP<  | 2:0>    | _       | I      | NT1IP<2:0  | >      | 0100 0100 0100 0100 |
| IPC5        | 009E | _      | IN     | IT2IP<2:0 | >      | _      |        | T5IP<2:0>  | •      | 1      |       | T4IP<2  | 2:0>    | _       | (      | OC4IP<2:0> | >      | 0100 0100 0100 0100 |
| IPC6        | 00A0 | _      | C      | C1IP<2:0> |        | _      | S      | SPI2IP<2:0 | >      | _      |       | U2TXIP  | <2:0>   | _       | U      | 12RXIP<2:0 | >      | 0100 0100 0100 0100 |
| IPC7        | 00A2 | _      | _      | _         | _      | -      | _      | I          | I      | 1      | 1     | _       | _       | _       | _      | _          | _      | 0100 0100 0100 0100 |
| IPC8        | 00A4 | _      | _      | _         | _      | _      | _      | _          | 1      | _      | _     | _       | _       | _       | _      | _          | _      | 0100 0100 0100 0100 |
| IPC9        | 00A6 | _      | _      | _         | _      | _      | _      | _          | 1      | _      | _     | _       | _       | _       | _      | _          | _      | 0000 0100 0100 0100 |
| IPC10       | 8A00 | _      | _      | _         | _      | _      | L      | VDIP<2:0:  | >      | _      |       | DCIIP<  | 2:0>    | _       | _      | _          | _      | 0000 0100 0100 0000 |

**\_egend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

#### 9.0 TIMER1 MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

This section describes the 16-bit general purpose Timer1 module and associated operational modes. Figure 9-1 depicts the simplified block diagram of the 16-bit Timer1 module.

The following sections provide a detailed description including setup and control registers, along with associated block diagrams for the operational modes of the timers.

The Timer1 module is a 16-bit timer which can serve as the time counter for the Real-Time Clock (RTC), or operate as a free-running interval timer/counter. The 16-bit timer has the following modes:

- 16-bit Timer
- 16-bit Synchronous Counter
- 16-bit Asynchronous Counter

Further, the following operational characteristics are supported:

- · Timer gate operation
- · Selectable prescaler settings
- Timer operation during CPU Idle and Sleep modes
- Interrupt on 16-bit Period register match or falling edge of external gate signal

These operating modes are determined by setting the appropriate bit(s) in the 16-bit SFR, T1CON. Figure 9-1 presents a block diagram of the 16-bit timer module.

**16-Bit Timer Mode:** In the 16-Bit Timer mode, the timer increments on every instruction cycle up to a match value preloaded into the Period register, PR1, then resets to '0' and continues to count.

When the CPU goes into the Idle mode, the timer stops incrementing unless the TSIDL (T1CON<13>) bit = 0. If TSIDL = 1, the timer module logic resumes the incrementing sequence upon termination of the CPU Idle mode.


**16-Bit Synchronous Counter Mode:** In the 16-Bit Synchronous Counter mode, the timer increments on the rising edge of the applied external clock signal which is synchronized with the internal phase clocks. The timer counts up to a match value preloaded in PR1, then resets to '0' and continues.

When the CPU goes into the Idle mode, the timer stops incrementing unless the respective TSIDL bit = 0. If TSIDL = 1, the timer module logic resumes the incrementing sequence upon termination of the CPU Idle mode.

**16-Bit Asynchronous Counter Mode:** In the 16-Bit Asynchronous Counter mode, the timer increments on every rising edge of the applied external clock signal. The timer counts up to a match value preloaded in PR1, then resets to '0' and continues.

When the timer is configured for the Asynchronous mode of operation and the CPU goes into the Idle mode, the timer stops incrementing if TSIDL = 1.

#### FIGURE 9-1: 16-BIT TIMER1 MODULE BLOCK DIAGRAM



### 9.1 Timer Gate Operation

The 16-bit timer can be placed in the Gated Time Accumulation mode. This mode allows the internal Tcy to increment the respective timer when the gate input signal (T1CK pin) is asserted high. Control bit, TGATE (T1CON<6>), must be set to enable this mode. The timer must be enabled (TON = 1) and the timer clock source set to internal (TCS = 0).

When the CPU goes into the Idle mode, the timer stops incrementing unless TSIDL = 0. If TSIDL = 1, the timer resumes the incrementing sequence upon termination of the CPU Idle mode.

#### 9.2 Timer Prescaler

The input clock (Fosc/4 or external clock) to the 16-bit Timer has a prescale option of 1:1, 1:8, 1:64 and 1:256, selected by control bits, TCKPS<1:0> (T1CON<5:4>). The prescaler counter is cleared when any of the following occurs:

- a write to the TMR1 register
- a write to the T1CON register
- · device Reset, such as POR and BOR

However, if the timer is disabled (TON = 0), then the timer prescaler cannot be reset since the prescaler clock is halted.

TMR1 is not cleared when T1CON is written. It is cleared by writing to the TMR1 register.

# 9.3 Timer Operation During Sleep Mode

During CPU Sleep mode, the timer operates if:

- The timer module is enabled (TON = 1) and
- The timer clock source is selected as external (TCS = 1) and
- The TSYNC bit (T1CON<2>) is asserted to a logic '0' which defines the external clock source as asynchronous.

When all three conditions are true, the timer continues to count up to the Period register and is reset to 0x0000.

When a match between the timer and the Period register occurs, an interrupt can be generated if the respective timer interrupt enable bit is asserted.

#### 9.4 Timer Interrupt

The 16-bit timer has the ability to generate an interrupton-period match. When the timer count matches the Period register, the T1IF bit is asserted and an interrupt is generated, if enabled. The T1IF bit must be cleared in software. The Timer Interrupt Flag, T1IF, is located in the IFS0 Control register in the interrupt controller.

When the Gated Time Accumulation mode is enabled, an interrupt is also generated on the falling edge of the gate signal (at the end of the accumulation cycle).

Enabling an interrupt is accomplished via the respective timer interrupt enable bit, T1IE. The timer interrupt enable bit is located in the IEC0 Control register in the interrupt controller.


#### 9.5 Real-Time Clock

Timer1, when operating in Real-Time Clock (RTC) mode, provides time of day and event time-stamping capabilities. Key operational features of the RTC are:

- · Operation from 32 kHz LP oscillator
- 8-bit prescaler
- · Low power
- · Real-Time Clock interrupts

These operating modes are determined by setting the appropriate bit(s) in the T1CON Control register.

# FIGURE 9-2: RECOMMENDED COMPONENTS FOR TIMER1 LP OSCILLATOR RTC



#### 9.5.1 RTC OSCILLATOR OPERATION

When the TON = 1, TCS = 1 and TGATE = 0, the timer increments on the rising edge of the 32 kHz LP oscillator output signal, up to the value specified in the Period register and is then reset to  $^{\circ}$ 0'.

The TSYNC bit must be asserted to a logic '0' (Asynchronous mode) for correct operation.

Enabling LPOSCEN (OSCCON<1>) disables the normal Timer and Counter modes and enable a timer carry-out wake-up event.

When the CPU enters Sleep mode, the RTC continues to operate, provided the 32 kHz external crystal oscillator is active and the control bits have not been changed. The TSIDL bit should be cleared to '0' in order for RTC to continue operation in Idle mode.

#### 9.5.2 RTC INTERRUPTS

When an interrupt event occurs, the respective interrupt flag, T1IF, is asserted and an interrupt is generated, if enabled. The T1IF bit must be cleared in software. The respective Timer Interrupt Flag, T1IF, is located in the IFS0 register in the interrupt controller.

Enabling an interrupt is accomplished via the respective timer interrupt enable bit, T1IE. The timer interrupt enable bit is located in the IEC0 Control register in the interrupt controller.

#### dsPIC30F3014/4013 TIMER1 REGISTER MAP(1) **TABLE 9-1:**

| SFR Name | Addr. | Bit 15 | Bit 14          | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7        | Bit 6 | Bit 5  | Bit 4          | Bit 3 | Bit 2 | Bit 1 | Bit 0 | Reset State         |
|----------|-------|--------|-----------------|--------|--------|--------|--------|-------|-------|--------------|-------|--------|----------------|-------|-------|-------|-------|---------------------|
| TMR1     | 0100  |        | Timer1 Register |        |        |        |        |       |       |              |       |        | uuuu uuuu uuuu |       |       |       |       |                     |
| PR1      | 0102  |        |                 |        |        |        |        |       | Pe    | riod Registe | er 1  |        |                |       |       |       |       | 1111 1111 1111 1111 |
| T1CON    | 0104  | TON    | _               | TSIDL  | _      | _      | _      | _     |       | _            | TGATE | TCKPS1 | TCKPS0         | _     | TSYNC | TCS   | _     | 0000 0000 0000 0000 |

dsPIC30F3014/4013

u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

#### 10.0 TIMER2/3 MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

This section describes the 32-bit general purpose timer module (Timer2/3) and associated operational modes. Figure 10-1 depicts the simplified block diagram of the 32-bit Timer2/3 module. Figure 10-2 and Figure 10-3 show Timer2/3 configured as two independent 16-bit timers, Timer2 and Timer3, respectively.

The Timer2/3 module is a 32-bit timer (which can be configured as two 16-bit timers) with selectable operating modes. These timers are utilized by other peripheral modules, such as:

- · Input Capture
- Output Compare/Simple PWM

The following sections provide a detailed description, including setup and control registers, along with associated block diagrams for the operational modes of the timers.

The 32-bit timer has the following modes:

- Two independent 16-bit timers (Timer2 and Timer3) with all 16-bit operating modes (except Asynchronous Counter mode)
- Single 32-bit timer operation
- Single 32-bit synchronous counter

Further, the following operational characteristics are supported:

- · ADC event trigger
- · Timer gate operation
- · Selectable prescaler settings
- · Timer operation during Idle and Sleep modes
- Interrupt on a 32-bit Period register match

These operating modes are determined by setting the appropriate bit(s) in the 16-bit T2CON and T3CON SFRs.

For 32-bit timer/counter operation, Timer2 is the Isw and Timer3 is the msw of the 32-bit timer.

Note:

For 32-bit timer operation, T3CON control bits are ignored. Only T2CON control bits are used for setup and control. Timer2 clock and gate inputs are utilized for the 32-bit timer module, but an interrupt is generated with the Timer3 Interrupt Flag (T3IF) and the interrupt is enabled with the Timer3 interrupt enable bit (T3IE).

**16-Bit Timer Mode:** In the 16-bit mode, Timer2 and Timer3 can be configured as two independent 16-bit timers. Each timer can be set up in either 16-bit Timer mode or 16-bit Synchronous Counter mode. See **Section 9.0 "Timer1 Module"** for details on these two operating modes.

The only functional difference between Timer2 and Timer3 is that Timer2 provides synchronization of the clock prescaler output. This is useful for high-frequency external clock inputs.

**32-Bit Timer Mode:** In the 32-Bit Timer mode, the timer increments on every instruction cycle, up to a match value preloaded into the combined 32-bit Period register, PR3/PR2, then resets to '0' and continues to count.

For synchronous 32-bit reads of the Timer2/Timer3 pair, reading the lsw (TMR2 register) causes the msw to be read and latched into a 16-bit holding register, termed TMR3HLD.

For synchronous 32-bit writes, the holding register (TMR3HLD) must first be written to. When followed by a write to the TMR2 register, the contents of TMR3HLD is transferred and latched into the MSB of the 32-bit timer (TMR3).

**32-Bit Synchronous Counter Mode:** In the 32-Bit Synchronous Counter mode, the timer increments on the rising edge of the applied external clock signal which is synchronized with the internal phase clocks. The timer counts up to a match value preloaded in the combined 32-bit Period register, PR3/PR2, then resets to '0' and continues.

When the timer is configured for the Synchronous Counter mode of operation and the CPU goes into the Idle mode, the timer stops incrementing unless the TSIDL (T2CON<13>) bit = 0. If TSIDL = 1, the timer module logic resumes the incrementing sequence upon termination of the CPU Idle mode.

#### FIGURE 10-1: 32-BIT TIMER2/3 BLOCK DIAGRAM




FIGURE 10-2: 16-BIT TIMER2 BLOCK DIAGRAM





FIGURE 10-3: 16-BIT TIMER3 BLOCK DIAGRAM



## 10.1 Timer Gate Operation

The 32-bit timer can be placed in the Gated Time Accumulation mode. This mode allows the internal TcY to increment the respective timer when the gate input signal (T2CK pin) is asserted high. Control bit, TGATE (T2CON<6>), must be set to enable this mode. When in this mode, Timer2 is the originating clock source. The TGATE setting is ignored for Timer3. The timer must be enabled (TON = 1) and the timer clock source set to internal (TCS = 0).

The falling edge of the external signal terminates the count operation but does not reset the timer. The user must reset the timer in order to start counting from zero.

## 10.2 ADC Event Trigger

When a match occurs between the 32-bit timer (TMR3/TMR2) and the 32-bit combined Period register (PR3/PR2), a special ADC trigger event signal is generated by Timer3.

#### 10.3 Timer Prescaler

The input clock (Fosc/4 or external clock) to the timer has a prescale option of 1:1, 1:8, 1:64 and 1:256, selected by control bits, TCKPS<1:0> (T2CON<5:4> and T3CON<5:4>). For the 32-bit timer operation, the originating clock source is Timer2. The prescaler operation for Timer3 is not applicable in this mode. The prescaler counter is cleared when any of the following occurs:

- · a write to the TMR2/TMR3 register
- a write to the T2CON/T3CON register
- · device Reset, such as POR and BOR

However, if the timer is disabled (TON = 0), then the Timer2 prescaler cannot be reset since the prescaler clock is halted.

TMR2/TMR3 is not cleared when T2CON/T3CON is written.

## 10.4 Timer Operation During Sleep Mode

During CPU Sleep mode, the timer does not operate because the internal clocks are disabled.

## 10.5 Timer Interrupt

The 32-bit timer module can generate an interrupt-onperiod match or on the falling edge of the external gate signal. When the 32-bit timer count matches the respective 32-bit Period register, or the falling edge of the external "gate" signal is detected, the T3IF bit (IFSO<7>) is asserted and an interrupt is generated, if enabled. In this mode, the T3IF interrupt flag is used as the source of the interrupt. The T3IF bit must be cleared in software.

Enabling an interrupt is accomplished via the respective timer interrupt enable bit, T3IE (IEC0<7>).

## TABLE 10-1: dsPIC30F3014/4013 TIMER2/3 REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15 | Bit 14   | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7        | Bit 6 | Bit 5               | Bit 4 | Bit 3 | Bit 2 | Bit 1 | Bit 0               | Reset State         |
|----------|-------|--------|--|--------|--------|--------|--------|-------|-------|--------------|-------|---------------------|-------|-------|-------|-------|---------------------|---------------------|
| TMR2     | 0106  |        |  |        |        |        |        |       | Tir   | mer2 Regist  | er    |                     |       |       |       |       |                     | uuuu uuuu uuuu uuuu |
| TMR3HLD  | 0108  |        | Timer3 Holding Register (for 32-bit timer operations only) |        |        |        |        |       |       |              |       |                     |       |       |       |       |                     | uuuu uuuu uuuu uuuu |
| TMR3     | 010A  |        | Timer3 Register  |        |        |        |        |       |       |              |       |                     |       |       |       |       |                     | uuuu uuuu uuuu uuuu |
| PR2      | 010C  |        |  |        |        |        |        |       | Pe    | riod Registe | r 2   |                     |       |       |       |       |                     | 1111 1111 1111 1111 |
| PR3      | 010E  |        |  |        |        |        |        |       | Pe    | riod Registe | r 3   |                     |       |       |       |       |                     | 1111 1111 1111 1111 |
| T2CON    | 0110  | TON    |  |        |        |        |        |       |       |              |       |                     |       |       |       |       | 0000 0000 0000 0000 |                     |
| T3CON    | 0112  |        |  |        |        |        |        |       |       |              |       | 0000 0000 0000 0000 |       |       |       |       |                     |                     |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

## 11.0 TIMER4/5 MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the dsPIC30F Family Reference Manual (DS70046).

This section describes the second 32-bit general purpose timer module (Timer4/5) and associated operational modes. Figure 11-1 depicts the simplified block diagram of the 32-bit Timer4/5 module. Figure 11-2 and Figure 11-3 show Timer4/5 configured as two independent 16-bit timers, Timer4 and Timer5, respectively.

The Timer4/5 module is similar in operation to the Timer2/3 module. However, there are some differences:

- The Timer4/5 module does not support the ADC event trigger feature
- Timer4/5 can not be utilized by other peripheral modules, such as input capture and output compare

The operating modes of the Timer4/5 module are determined by setting the appropriate bit(s) in the 16-bit T4CON and T5CON SFRs.

For 32-bit timer/counter operation, Timer4 is the Isw and Timer5 is the msw of the 32-bit timer.

Note:

For 32-bit timer operation, T5CON control bits are ignored. Only T4CON control bits are used for setup and control. Timer4 clock and gate inputs are utilized for the 32-bit timer module but an interrupt is generated with the Timer5 Interrupt Flag (T5IF) and the interrupt is enabled with the Timer5 interrupt enable bit (T5IE).

FIGURE 11-1: 32-BIT TIMER4/5 BLOCK DIAGRAM




FIGURE 11-2: 16-BIT TIMER4 BLOCK DIAGRAM





FIGURE 11-3: 16-BIT TIMER5 BLOCK DIAGRAM



## TABLE 11-1: dsPIC30F4013 TIMER4/5 REGISTER MAP<sup>(1)</sup>

|          |       |   |  |        |        |        |        |       |       |              |       |        |        |       |                     |       |                     | 1                   |
|----------|-------|---|--|--------|--------|--------|--------|-------|-------|--------------|-------|--------|--------|-------|---------------------|-------|---------------------|---------------------|
| SFR Name | Addr. | Bit 15                                    | Bit 14   | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7        | Bit 6 | Bit 5  | Bit 4  | Bit 3 | Bit 2               | Bit 1 | Bit 0               | Reset State         |
| TMR4     | 0114  |   |  |        |        |        |        |       | Tir   | mer4 Regis   | ter   |        |        |       |                     |       |                     | uuuu uuuu uuuu      |
| TMR5HLD  | 0116  |   | Timer5 Holding Register (for 32-bit operations only) |        |        |        |        |       |       |              |       |        |        |       |                     |       |                     | uuuu uuuu uuuu uuuu |
| TMR5     | 0118  |   | Timer5 Register                                      |        |        |        |        |       |       |              |       |        |        |       |                     |       | uuuu uuuu uuuu uuuu |                     |
| PR4      | 011A  |   |  |        |        |        |        |       | Pe    | riod Registe | er 4  |        |        |       |                     |       |                     | 1111 1111 1111 1111 |
| PR5      | 011C  |   |  |        |        |        |        |       | Pe    | riod Registe | er 5  |        |        |       |                     |       |                     | 1111 1111 1111 1111 |
| T4CON    | 011E  | TON - TSIDL TGATE TCKPS1 TCKPS0 T32 - TCS |  |        |        |        |        |       |       |              |       |        |        | _     | 0000 0000 0000 0000 |       |                     |                     |
| T5CON    | 0120  | TON                                       | _  | TSIDL  | _      | _      | _      | _     | _     | _            | TGATE | TCKPS1 | TCKPS0 |       | _                   | TCS   | _                   | 0000 0000 0000 0000 |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

## 12.0 INPUT CAPTURE MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

This section describes the input capture module and associated operational modes. The features provided by this module are useful in applications requiring frequency (period) and pulse measurement. Figure 12-1 depicts a block diagram of the input capture module. Input capture is useful for such modes as:

- Frequency/Period/Pulse Measurements
- · Additional Sources of External Interrupts

The key operational features of the input capture module are:

- Simple Capture Event mode
- Timer2 and Timer3 mode selection
- · Interrupt on input capture event

These operating modes are determined by setting the appropriate bits in the ICxCON register (where x = 1,2,...,N). The dsPIC DSC devices contain up to 8 capture channels (i.e., the maximum value of N is 8). The dsPIC30F3014 device contains 2 capture channels while the dsPIC30F4013 device contains 4 capture channels.

## 12.1 Simple Capture Event Mode

The simple capture events in the dsPIC30F product family are:


- · Capture every falling edge
- · Capture every rising edge
- · Capture every 4th rising edge
- · Capture every 16th rising edge
- Capture every rising and falling edge

These simple Input Capture modes are configured by setting the appropriate bits, ICM<2:0> (ICxCON<2:0>).

## 12.1.1 CAPTURE PRESCALER

There are four input capture prescaler settings specified by bits, ICM<2:0> (ICxCON<2:0>). Whenever the capture channel is turned off, the prescaler counter is cleared. In addition, any Reset clears the prescaler counter.

FIGURE 12-1: INPUT CAPTURE MODE BLOCK DIAGRAM



#### 12.1.2 CAPTURE BUFFER OPERATION

Each capture channel has an associated FIFO buffer which is four 16-bit words deep. There are two status flags which provide status on the FIFO buffer:

- ICBNE Input Capture Buffer Not Empty
- ICOV Input Capture Overflow

The ICBFNE is set on the first input capture event and remain set until all capture events have been read from the FIFO. As each word is read from the FIFO, the remaining words are advanced by one position within the buffer.

In the event that the FIFO is full with four capture events and a fifth capture event occurs prior to a read of the FIFO, an overflow condition occurs and the ICOV bit is set to a logic '1'. The fifth capture event is lost and is not stored in the FIFO. No additional events are captured until all four events have been read from the buffer.

If a FIFO read is performed after the last read and no new capture event has been received, the read will yield indeterminate results.

## 12.1.3 TIMER2 AND TIMER3 SELECTION MODE

The input capture module consists of up to 8 input capture channels. Each channel can select between one of two timers for the time base, Timer2 or Timer3.

Selection of the timer resource is accomplished through SFR bit, ICTMR (ICxCON<7>). Timer3 is the default timer resource available for the input capture module.

### 12.1.4 HALL SENSOR MODE

When the input capture module is set for capture on every edge, rising and falling, ICM<2:0> = 001, the following operations are performed by the input capture logic:

- The input capture interrupt flag is set on every edge, rising and falling.
- The interrupt on Capture mode setting bits, ICI<1:0>, is ignored since every capture generates an interrupt.
- A capture overflow condition is not generated in this mode.

## 12.2 Input Capture Operation During Sleep and Idle Modes

An input capture event generates a device wake-up or interrupt, if enabled, if the device is in CPU Idle or Sleep mode.

Independent of the timer being enabled, the input capture module wakes up from the CPU Sleep or Idle mode when a capture event occurs if ICM<2:0> = 111 and the interrupt enable bit is asserted. The same wake-up can generate an interrupt if the conditions for processing the interrupt have been satisfied. The wake-up feature is useful as a method of adding extra external pin interrupts.

## 12.2.1 INPUT CAPTURE IN CPU SLEEP MODE

CPU Sleep mode allows input capture module operation with reduced functionality. In the CPU Sleep mode, the ICI<1:0> bits are not applicable and the input capture module can only function as an external interrupt source.

The capture module must be configured for interrupt only on rising edge (ICM<2:0> = 111) in order for the input capture module to be used while the device is in Sleep mode. The prescale settings of 4:1 or 16:1 are not applicable in this mode.

## 12.2.2 INPUT CAPTURE IN CPU IDLE MODE

CPU Idle mode allows input capture module operation with full functionality. In the CPU Idle mode, the Interrupt mode selected by the ICI<1:0> bits is applicable, as well as the 4:1 and 16:1 capture prescale settings which are defined by control bits, ICM<2:0>. This mode requires the selected timer to be enabled. Moreover, the ICSIDL bit must be asserted to a logic '0'.

If the input capture module is defined as ICM<2:0> = 111 in CPU Idle mode, the input capture pin serves only as an external interrupt pin.

## 12.3 Input Capture Interrupts

The input capture channels have the ability to generate an interrupt based upon the selected number of capture events. The selection number is set by control bits, ICI<1:0> (ICxCON<6:5>).

Each channel provides an interrupt flag (ICxIF) bit. The respective capture channel interrupt flag is located in the corresponding IFSx register.

Enabling an interrupt is accomplished via the respective Input Capture Channel Interrupt Enable (ICxIE) bit. The capture interrupt enable bit is located in the corresponding IEC Control register.

## TABLE 12-1: dsPIC30F3014 INPUT CAPTURE REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15 | Bit 14 | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8        | Bit 7      | Bit 6 | Bit 5 | Bit 4 | Bit 3 | Bit 2       | Bit 1 | Bit 0 | Reset State         |
|----------|-------|--------|--------|--------|--------|--------|--------|-------|--------------|------------|-------|-------|-------|-------|-------------|-------|-------|---------------------|
| IC1BUF   | 0140  |        |        |        |        |        |        | Inpu  | ıt 1 Capture | e Register |       |       |       |       |             |       |       | uuuu uuuu uuuu uuuu |
| IC1CON   | 0142  | _      | _      | ICSIDL | _      |        | -      | _     | _            | ICTMR      | ICI<  | 1:0>  | ICOV  | ICBNE | ICM<2:0>    |       |       | 0000 0000 0000 0000 |
| IC2BUF   | 0144  |        |        |        |        |        |        | Inpu  | ıt 2 Capture | Register   |       |       |       |       |             |       |       | uuuu uuuu uuuu      |
| IC2CON   | 0146  | _      | _      | ICSIDL | _      | _      |        | _     |              | ICTMR      | ICI<  | 1:0>  | ICOV  | ICBNE | NE ICM<2:0> |       |       | 0000 0000 0000 0000 |

**Legend:** u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

## TABLE 12-2: dsPIC30F4013 INPUT CAPTURE REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15                   | Bit 14 | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8        | Bit 7      | Bit 6 | Bit 5               | Bit 4 | Bit 3               | Bit 2      | Bit 1   | Bit 0 | Reset State         |
|----------|-------|--------------------------|--------|--------|--------|--------|--------|-------|--------------|------------|-------|---------------------|-------|---------------------|------------|---------|-------|---------------------|
| IC1BUF   | 0140  |                          |        |        |        |        |        | Inpu  | ut 1 Capture | e Register |       |                     |       |                     |            |         |       | uuuu uuuu uuuu uuuu |
| IC1CON   | 0142  | -                        | _      | ICSIDL |        |        | _      | -     | _            | ICTMR      | ICI<  | 1:0>                | ICOV  | ICBNE               | I          | CM<2:0> | i     | 0000 0000 0000 0000 |
| IC2BUF   | 0144  | Input 2 Capture Register |        |        |        |        |        |       |              |            |       |                     |       | uuuu uuuu uuuu uuuu |            |         |       |                     |
| IC2CON   | 0146  | _                        | _      | ICSIDL | -      | -      | _      | _     | _            | ICTMR      | ICI<  | 1:0>                | ICOV  | ICBNE               | ı          | CM<2:0> |       | 0000 0000 0000 0000 |
| IC7BUF   | 0158  |                          |        |        |        |        |        | Inpu  | ut 7 Capture | e Register |       |                     |       |                     |            |         |       | uuuu uuuu uuuu uuuu |
| IC7CON   | 015A  |                          |        |        |        |        |        |       |              |            |       | 0000 0000 0000 0000 |       |                     |            |         |       |                     |
| IC8BUF   | 015C  |                          |        |        |        |        |        | Inpu  | ut 8 Capture | e Register |       |                     |       |                     |            |         |       | uuuu uuuu uuuu uuuu |
| IC8CON   | 015E  | _                        | _      | ICSIDL | _      | _      | _      | _     | _            | ICTMR      | ICI<  | 1:0>                | ICOV  | ICBNE               | E ICM<2:0> |         |       | 0000 0000 0000 0000 |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

## 13.0 OUTPUT COMPARE MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

This section describes the output compare module and associated operational modes. The features provided by this module are useful in applications requiring operational modes, such as:

- · Generation of Variable Width Output Pulses
- Power Factor Correction

Figure 13-1 depicts a block diagram of the output compare module.

The key operational features of the output compare module include:

- Timer2 and Timer3 Selection mode
- · Simple Output Compare Match mode
- Dual Output Compare Match mode
- Simple PWM mode
- · Output Compare During Sleep and Idle modes
- Interrupt on Output Compare/PWM Event

These operating modes are determined by setting the appropriate bits in the 16-bit OCxCON SFR (where x = 1,2,3,...,N). The dsPIC DSC devices contain up to 8 compare channels (i.e., the maximum value of N is 8). The dsPIC30F3014 device contains 2 compare channels while the dsPIC30F4013 device contains 4 compare channels.


OCxRS and OCxR in Figure 13-1 represent the Dual Compare registers. In the Dual Compare mode, the OCxR register is used for the first compare and OCxRS is used for the second compare.

### 13.1 Timer2 and Timer3 Selection Mode

Each output compare channel can select between one of two 16-bit timers: Timer2 or Timer3.

The selection of the timers is controlled by the OCTSEL bit (OCxCON<3>). Timer2 is the default timer resource for the output compare module.

### FIGURE 13-1: OUTPUT COMPARE MODE BLOCK DIAGRAM



## 13.2 Simple Output Compare Match Mode

When control bits, OCM<2:0> (OCxCON<2:0>) = 001, 010 or 011, the selected output compare channel is configured for one of three simple Output Compare Match modes:

- · Compare forces I/O pin low
- · Compare forces I/O pin high
- · Compare toggles I/O pin

The OCxR register is used in these modes. The OCxR register is loaded with a value and is compared to the selected incrementing timer count. When a compare occurs, one of these Compare Match modes occurs. If the counter resets to zero before reaching the value in OCxR, the state of the OCx pin remains unchanged.

## 13.3 Dual Output Compare Match Mode

When control bits, OCM<2:0> (OCxCON<2:0>) = 100 or 101, the selected output compare channel is configured for one of two Dual Output Compare modes, which are:

- Single Output Pulse mode
- · Continuous Output Pulse mode

### 13.3.1 SINGLE PULSE MODE

For the user to configure the module for the generation of a single output pulse, the following steps are required (assuming timer is off):

- · Determine instruction cycle time, Tcy.
- Calculate desired pulse width value based on Tcy.
- Calculate time to Start pulse from timer start value of 0x0000.
- Write pulse-width start and stop times into OCxR and OCxRS Compare registers (x denotes channel 1, 2, ...,N).
- Set Timer Period register to value equal to or greater than value in OCxRS Compare register.
- Set OCM<2:0> = 100.
- Enable timer, TON (TxCON<15>) = 1.

To initiate another single pulse, issue another write to set OCM<2:0> = 100.

#### 13.3.2 CONTINUOUS PULSE MODE

For the user to configure the module for the generation of a continuous stream of output pulses, the following steps are required:

- Determine instruction cycle time, Tcy.
- · Calculate desired pulse value based on Tcy.
- Calculate timer to Start pulse width from timer start value of 0x0000.
- Write pulse-width Start and Stop times into OCxR and OCxRS (x denotes channel 1, 2, ...,N)
   Compare registers, respectively.
- Set Timer Period register to value equal to or greater than value in OCxRS Compare register.
- Set OCM<2:0> = 101.
- Enable timer, TON (TxCON<15>) = 1.

## 13.4 Simple PWM Mode

When control bits, OCM<2:0> (OCxCON<2:0>) = 110 or 111, the selected output compare channel is configured for the PWM mode of operation. When configured for the PWM mode of operation, OCxR is the main latch (read-only) and OCxRS is the secondary latch. This enables glitchless PWM transitions.

The user must perform the following steps in order to configure the output compare module for PWM operation:

- Set the PWM period by writing to the appropriate Period register.
- 2. Set the PWM duty cycle by writing to the OCxRS register.
- Configure the output compare module for PWM operation.
- Set the TMRx prescale value and enable the timer, TON (TxCON<15>) = 1.

## 13.4.1 INPUT PIN FAULT PROTECTION FOR PWM

When control bits, OCM<2:0> (OCxCON<2:0>) = 111, the selected output compare channel is again configured for the PWM mode of operation with the additional feature of input Fault protection. While in this mode, if a logic '0' is detected on the OCFA/B pin, the respective PWM output pin is placed in the high-impedance input state. The OCFLT bit (OCxCON<4>) indicates whether a Fault condition has occurred. This state is maintained until both of the following events have occurred:

- The external Fault condition has been removed.
- The PWM mode has been re-enabled by writing to the appropriate control bits.

### 13.4.2 PWM PERIOD

The PWM period is specified by writing to the PRx register. The PWM period can be calculated using Equation 13-1.

### **EQUATION 13-1:**

PWM period = 
$$[(PRx) + 1] \cdot 4 \cdot TOSC \cdot$$
  
(TMRx prescale value)


PWM frequency is defined as 1/[PWM period].

When the selected TMRx is equal to its respective Period register, PRx, the following four events occur on the next increment cycle:

- · TMRx is cleared.
- The OCx pin is set.
  - Exception 1: If PWM duty cycle is 0x0000, the OCx pin remains low.
  - Exception 2: If duty cycle is greater than PRx, the pin remains high.
- The PWM duty cycle is latched from OCxRS into OCxR.
- The corresponding timer interrupt flag is set.

See Figure 13-2 for key PWM period comparisons. Timer3 is referred to in Figure 13-2 for clarity.

## FIGURE 13-2: PWM OUTPUT TIMING



## 13.5 Output Compare Operation During CPU Sleep Mode

When the CPU enters Sleep mode, all internal clocks are stopped. Therefore, when the CPU enters the Sleep state, the output compare channel drives the pin to the active state that was observed prior to entering the CPU Sleep state.

For example, if the pin was high when the CPU entered the Sleep state, the pin remains high. Likewise, if the pin was low when the CPU entered the Sleep state, the pin remains low. In either case, the output compare module resumes operation when the device wakes up.

## 13.6 Output Compare Operation During CPU Idle Mode

When the CPU enters the Idle mode, the output compare module can operate with full functionality.

The output compare channel operates during the CPU Idle mode if the OCSIDL bit (OCxCON<13>) is at logic '0' and the selected time base (Timer2 or Timer3) is enabled and the TSIDL bit of the selected timer is set to logic '0'.

## 13.7 Output Compare Interrupts

The output compare channels have the ability to generate an interrupt on a compare match for whichever Match mode has been selected.

For all modes, except the PWM mode, when a compare event occurs, the respective interrupt flag (OCxIF) is asserted and an interrupt is generated, if enabled. The OCxIF bit is located in the corresponding IFSx register and must be cleared in software. The interrupt is enabled via the respective compare interrupt enable (OCxIE) bit located in the corresponding IEC register.

For the PWM mode, when an event occurs, the respective Timer Interrupt Flag (T2IF or T3IF) is asserted and an interrupt is generated, if enabled. The TxIF bit is located in the IFS0 register and must be cleared in software. The interrupt is enabled via the respective timer interrupt enable bit (T2IE or T3IE) located in the IEC0 register. The output compare interrupt flag is never set during the PWM mode of operation.

|             |                                      | (1) |
|-------------|--------------------------------------|-----|
| TABLE 13-1: | dsPIC30F3014 OUTPUT COMPARE REGISTER | MAP |

| SFR Name | Addr. | Bit 15   | Bit 14                              | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7 | Bit 6               | Bit 5               | Bit 4 | Bit 3  | Bit 2               | Bit 1               | Bit 0 | Reset State         |
|----------|-------|--|-------------------------------------|--------|--------|--------|--------|-------|-------|-------|---------------------|---------------------|-------|--------|---------------------|---------------------|-------|---------------------|
| OC1RS    | 0180  | and the first for the second of the second o |                                     |        |        |        |        |       |       |       |                     | 0000 0000 0000 0000 |       |        |                     |                     |       |                     |
| OC1R     | 0182  | Output Compare 1 Main Register   |                                     |        |        |        |        |       |       |       |                     |                     |       |        | 0000 0000 0000 0000 |                     |       |                     |
| OC1CON   | 0184  | _  | _                                   | OCSIDL |        |        | _      | _     | _     | -     | -                   | _                   | OCFLT | OCTSEL |                     | OCM<2:0>            | •     | 0000 0000 0000 0000 |
| OC2RS    | 0186  |  | Output Compare 2 Secondary Register |        |        |        |        |       |       |       | 0000 0000 0000 0000 |                     |       |        |                     |                     |       |                     |
| OC2R     | 0188  |  | Output Compare 2 Main Register      |        |        |        |        |       |       |       |                     |                     |       |        |                     | 0000 0000 0000 0000 |       |                     |
| OC2CON   | 018A  | _  | _                                   | OCSIDL | _      | _      | _      | ı     | _     |       |                     | _                   | OCFLT | OCTSE  | ·                   | OCM<2:0>            |       | 0000 0000 0000 0000 |

Legend: — = unimplemented bit, read as '0'
Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

## TABLE 13-2: dsPIC30F4013 OUTPUT COMPARE REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15                       | Bit 14   | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8     | Bit 7     | Bit 6               | Bit 5 | Bit 4 | Bit 3  | Bit 2               | Bit 1    | Bit 0               | Reset State         |
|----------|-------|------------------------------|--|--------|--------|--------|--------|-------|-----------|-----------|---------------------|-------|-------|--------|---------------------|----------|---------------------|---------------------|
| OC1RS    | 0180  |                              |  |        |        |        |        | Outp  | ut Compar | e 1 Secon | dary Regi           | ster  |       |        |                     |          |                     | 0000 0000 0000 0000 |
| OC1R     | 0182  |                              |  |        |        |        |        | 0     | utput Com | pare 1 Ma | in Registe          | r     |       |        |                     |          |                     | 0000 0000 0000 0000 |
| OC1CON   | 0184  | _                            | OCSIDL OCFLT OCTSEL OCM<2:0>                                       |        |        |        |        |       |           |           |                     |       |       |        |                     | >        | 0000 0000 0000 0000 |                     |
| OC2RS    | 0186  |                              | Output Compare 2 Secondary Register                                |        |        |        |        |       |           |           |                     |       |       |        | 0000 0000 0000 0000 |          |                     |                     |
| OC2R     | 0188  |                              | Output Compare 2 Main Register                                     |        |        |        |        |       |           |           |                     |       |       |        | 0000 0000 0000 0000 |          |                     |                     |
| OC2CON   | 018A  | _                            | I  | OCSIDL | _      | ı      | _      | _     | _         | _         | _                   | _     | OCFLT | OCTSE  |                     | OCM<2:0  | >                   | 0000 0000 0000 0000 |
| OC3RS    | 018C  |                              |  |        |        |        |        | Outp  | ut Compar | e 3 Secon | dary Regi           | ster  |       |        |                     |          |                     | 0000 0000 0000 0000 |
| OC3R     | 018E  |                              |  |        |        |        |        | 0     | utput Com | pare 3 Ma | in Registe          | r     |       |        |                     |          |                     | 0000 0000 0000 0000 |
| OC3CON   | 0190  | OCSIDL OCFLT OCTSEL OCM<2:0> |  |        |        |        |        |       |           | >         | 0000 0000 0000 0000 |       |       |        |                     |          |                     |                     |
| OC4RS    | 0192  |                              | Output Compare 4 Secondary Register                                |        |        |        |        |       |           |           |                     |       |       |        | 0000 0000 0000 0000 |          |                     |                     |
| OC4R     | 0194  |                              | Output Compare 4 Secondary Register Output Compare 4 Main Register |        |        |        |        |       |           |           |                     |       |       |        | •                   | •        | 0000 0000 0000 0000 |                     |
| OC4CON   | 0196  | _                            | _  | OCSIDL |        | _      | _      | _     | _         | _         | _                   | _     | OCFLT | OCTSEL |                     | OCM<2:0> | >                   | 0000 0000 0000 0000 |

Legend: — = unimplemented bit, read as '0'

Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields. Note 1:

NOTES:

## 14.0 I<sup>2</sup>C™ MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the 'dsPIC30F Family Reference Manual (DS70046).

The Inter-Integrated Circuit ( $I^2C^{TM}$ ) module provides complete hardware support for both Slave and Multi-Master modes of the  $I^2C$  serial communication standard with a 16-bit interface.

This module offers the following key features:

- I<sup>2</sup>C interface supporting both master and slave operation.
- I<sup>2</sup>C Slave mode supports 7-bit and 10-bit addressing.
- I<sup>2</sup>C Master mode supports 7-bit and 10-bit addressing.
- I<sup>2</sup>C port allows bidirectional transfers between master and slaves.
- Serial clock synchronization for I<sup>2</sup>C port can be used as a handshake mechanism to suspend and resume serial transfer (SCLREL control).
- I<sup>2</sup>C supports multi-master operation; detects bus collision and arbitrates accordingly.

## 14.1 Operating Function Description

The hardware fully implements all the master and slave functions of the  $I^2C$  Standard and Fast mode specifications, as well as 7 and 10-bit addressing.

Thus, the  $I^2C$  module can operate either as a slave or a master on an  $I^2C$  bus.

### 14.1.1 VARIOUS I<sup>2</sup>C MODES

The following types of I<sup>2</sup>C operation are supported:

- I<sup>2</sup>C slave operation with 7-bit addressing
- I<sup>2</sup>C slave operation with 10-bit addressing
- I<sup>2</sup>C master operation with 7-bit or 10-bit addressing See the I<sup>2</sup>C programmer's model in Figure 14-1.

### 14.1.2 PIN CONFIGURATION IN I<sup>2</sup>C MODE

 $I^2C$  has a 2-pin interface: the SCL pin is clock and the SDA pin is data.

## 14.1.3 I<sup>2</sup>C REGISTERS

I2CCON and I2CSTAT are control and status registers, respectively. The I2CCON register is readable and writable. The lower 6 bits of I2CSTAT are read-only. The remaining bits of the I2CSTAT are read/write.

I2CRSR is the shift register used for shifting data, whereas I2CRCV is the buffer register to which data bytes are written, or from which data bytes are read. I2CRCV is the receive buffer as shown in Figure 14-1. I2CTRN is the transmit register to which bytes are written during a transmit operation, as shown in Figure 14-2.

The I2CADD register holds the slave address. A status bit, ADD10, indicates 10-Bit Addressing mode. The I2CBRG acts as the Baud Rate Generator reload value


In receive operations, I2CRSR and I2CRCV together form a double-buffered receiver. When I2CRSR receives a complete byte, it is transferred to I2CRCV and an interrupt pulse is generated. During transmission, the I2CTRN is not double-buffered.

**Note:** Following a Restart condition in 10-bit mode, the user only needs to match the first 7-bit address.

#### FIGURE 14-1: PROGRAMMER'S MODEL

|        | Bit 7 | Bit 0 | I2CRCV (8 bits)   |
|--------|-------|-------|-------------------|
|        | Bit 7 | Bit 0 | I2CTRN (8 bits)   |
|        | Bit 8 | Bit 0 | I2CBRG (9 bits)   |
| Bit 15 |       | Bit 0 | I2CCON (16 bits)  |
|        |       |       | I2CSTAT (16 bits) |
| Bit 15 |       | Bit 0 | I2CADD (10 bits)  |
|        | Bit 9 | Bit 0 |                   |

FIGURE 14-2: I<sup>2</sup>C™ BLOCK DIAGRAM



## 14.2 I<sup>2</sup>C Module Addresses

The I2CADD register contains the Slave mode addresses. The register is a 10-bit register.

If the A10M bit (I2CCON<10>) is '0', the address is interpreted by the module as a 7-bit address. When an address is received, it is compared to the 7 LSbs of the I2CADD register.

If the A10M bit is '1', the address is assumed to be a 10-bit address. When an address is received, it is compared with the binary value, '11110 A9 A8' (where A9 and A8 are two Most Significant bits of I2CADD). If that value matches, the next address is compared with the Least Significant 8 bits of I2CADD, as specified in the 10-bit addressing protocol.

TABLE 14-1: 7-BIT I<sup>2</sup>C™ SLAVE ADDRESSES SUPPORTED BY dsPIC30F

| 0x00      | General Call Address or Start Byte    |
|-----------|---------------------------------------|
| 0x01-0x03 | Reserved                              |
| 0x04-0x07 | HS mode Master Codes                  |
| 0x08-0x77 | Valid 7-Bit Addresses                 |
| 0x78-0x7b | Valid 10-Bit Addresses (lower 7 bits) |
| 0x7c-0x7f | Reserved                              |

## 14.3 I<sup>2</sup>C 7-Bit Slave Mode Operation

Once enabled (I2CEN = 1), the slave module waits for a Start bit to occur (i.e., the  $I^2C$  module is 'Idle'). Following the detection of a Start bit, 8 bits are shifted into I2CRSR, and the address is compared against I2CADD. In 7-bit mode (A10M = 0), bits I2CADD<6:0> are compared against I2CRSR<7:1> and I2CRSR<0> is the R\_W bit. All incoming bits are sampled on the rising edge of SCL.

If an address match occurs, an Acknowledgement is sent and the Slave Event Interrupt Flag (SI2CIF) is set on the falling edge of the ninth (ACK) bit. The address match does not affect the contents of the I2CRCV buffer or the RBF bit.

## 14.3.1 SLAVE TRANSMISSION

If the R\_W bit received is a '1', the serial port goes into Transmit mode. It sends an ACK on the ninth bit and then holds SCL to '0' until the CPU responds by writing to I2CTRN. SCL is released by setting the SCLREL bit, and 8 bits of data are shifted out. Data bits are shifted out on the falling edge of SCL, such that SDA is valid during SCL high. The interrupt pulse is sent on the falling edge of the ninth clock pulse, regardless of the status of the ACK received from the master.

#### 14.3.2 SLAVE RECEPTION

If the R\_W bit received is a '0' during an address match, then Receive mode is initiated. Incoming bits are sampled on the rising edge of SCL. After 8 bits are received, if I2CRCV is not full or I2COV is not set, I2CRSR is transferred to I2CRCV. ACK is sent on the ninth clock.

If the RBF flag is set, indicating that I2CRCV is still holding data from a previous operation (RBF = 1), then  $\overline{ACK}$  is not sent; however, the interrupt pulse is generated. In the case of an overflow, the contents of the I2CRSR are not loaded into the I2CRCV.

Note: The I2CRCV is loaded if the I2COV bit = 1 and the RBF flag = 0. In this case, a read of the I2CRCV was performed but the user did not clear the state of the I2COV bit before the next receive occurred. The acknowledgement is not sent (ACK = 1)

## 14.4 I<sup>2</sup>C 10-Bit Slave Mode Operation

and the I2CRCV is updated.

In 10-bit mode, the basic receive and transmit operations are the same as in the 7-bit mode. However, the criteria for address match is more complex.

The I<sup>2</sup>C specification dictates that a slave must be addressed for a write operation with two address bytes following a Start bit.

The A10M bit is a control bit that signifies that the address in I2CADD is a 10-bit address rather than a 7-bit address. The address detection protocol for the first byte of a message address is identical for 7-bit and 10-bit messages, but the bits being compared are different.

I2CADD holds the entire 10-bit address. Upon receiving an address following a Start bit, I2CRSR <7:3> is compared against a literal '11110' (the default 10-bit address) and I2CRSR<2:1> are compared against I2CADD<9:8>. If a match occurs and if  $R_W=0$ , the interrupt pulse is sent. The ADD10 bit is cleared to indicate a partial address match. If a match fails or  $R_W=1$ , the ADD10 bit is cleared and the module returns to the Idle state.

The low byte of the address is then received and compared with I2CADD<7:0>. If an address match occurs, the interrupt pulse is generated and the ADD10 bit is set, indicating a complete 10-bit address match. If an address match did not occur, the ADD10 bit is cleared and the module returns to the Idle state.

#### 14.4.1 10-BIT MODE SLAVE TRANSMISSION

Once a slave is addressed in this fashion with the full 10-bit address (we refer to this state as "PRIOR\_ADDR\_MATCH"), the master can begin sending data bytes for a slave reception operation.

### 14.4.2 10-BIT MODE SLAVE RECEPTION

Once addressed, the master can generate a Repeated Start, reset the high byte of the address and set the R\_W bit without generating a Stop bit, thus initiating a slave transmit operation.

### 14.5 Automatic Clock Stretch

In the Slave modes, the module can synchronize buffer reads and write to the master device by clock stretching.

#### 14.5.1 TRANSMIT CLOCK STRETCHING

Both 10-Bit and 7-Bit Transmit modes implement clock stretching by asserting the SCLREL bit after the falling edge of the ninth clock, if the TBF bit is cleared, indicating the buffer is empty.

In Slave Transmit modes, clock stretching is always performed irrespective of the STREN bit.

Clock synchronization takes place following the ninth clock of the transmit sequence. If the device samples an  $\overline{ACK}$  on the falling edge of the ninth clock and if the TBF bit is still clear, then the SCLREL bit is automatically cleared. The SCLREL being cleared to '0' asserts the SCL line low. The user's ISR must set the SCLREL bit before transmission is allowed to continue. By holding the SCL line low, the user has time to service the ISR and load the contents of the I2CTRN before the master device can initiate another transmit sequence.

- Note 1: If the user loads the contents of I2CTRN, setting the TBF bit before the falling edge of the ninth clock, the SCLREL bit is not be cleared and clock stretching does not occur.
  - **2:** The SCLREL bit can be set in software, regardless of the state of the TBF bit.

### 14.5.2 RECEIVE CLOCK STRETCHING

The STREN bit in the I2CCON register can be used to enable clock stretching in Slave Receive mode. When the STREN bit is set, the SCL pin is held low at the end of each data receive sequence.

## 14.5.3 CLOCK STRETCHING DURING 7-BIT ADDRESSING (STREN = 1)

When the STREN bit is set in Slave Receive mode, the SCL line is held low when the buffer register is full. The method for stretching the SCL output is the same for both 7 and 10-Bit Addressing modes.

Clock stretching takes place following the ninth clock of the receive sequence. On the falling edge of the ninth clock at the end of the  $\overline{ACK}$  sequence, if the RBF bit is set, the SCLREL bit is automatically cleared, forcing the SCL output to be held low. The user's ISR must set the SCLREL bit before reception is allowed to continue. By holding the SCL line low, the user has time to service the ISR and read the contents of the I2CRCV before the master device can initiate another receive sequence. This prevents buffer overruns from occurring.

- Note 1: If the user reads the contents of the I2CRCV, clearing the RBF bit before the falling edge of the ninth clock, the SCLREL bit is not cleared and clock stretching does not occur.
  - 2: The SCLREL bit can be set in software regardless of the state of the RBF bit. The user should be careful to clear the RBF bit in the ISR before the next receive sequence in order to prevent an overflow condition.

## 14.5.4 CLOCK STRETCHING DURING 10-BIT ADDRESSING (STREN = 1)

Clock stretching takes place automatically during the addressing sequence. Because this module has a register for the entire address, it is not necessary for the protocol to wait for the address to be updated.

After the address phase is complete, clock stretching occurs on each data receive or transmit sequence, as described earlier.

## 14.6 Software Controlled Clock Stretching (STREN = 1)

When the STREN bit is '1', the SCLREL bit can be cleared by software to allow software to control the clock stretching. Program logic synchronizes writes to the SCLREL bit with the SCL clock. Clearing the SCLREL bit does not assert the SCL output until the module detects a falling edge on the SCL output and SCL is sampled low. If the SCLREL bit is cleared by the user while the SCL line has been sampled low, the SCL output is asserted (held low). The SCL output remains low until the SCLREL bit is set and all other devices on the I<sup>2</sup>C bus have deasserted SCL. This ensures that a write to the SCLREL bit does not violate the minimum high time requirement for SCL.

If the STREN bit is '0', a software write to the SCLREL bit is disregarded and has no effect on the SCLREL bit.

## 14.7 Interrupts

The I<sup>2</sup>C module generates two interrupt flags, MI2CIF (I<sup>2</sup>C Master Interrupt Flag) and SI2CIF (I<sup>2</sup>C Slave Interrupt Flag). The MI2CIF interrupt flag is activated on completion of a master message event. The SI2CIF interrupt flag is activated on detection of a message directed to the slave.

## 14.8 Slope Control

The I<sup>2</sup>C standard requires slope control on the SDA and SCL signals for Fast mode (400 kHz). The control bit, DISSLW, enables the user to disable slew rate control if desired. It is necessary to disable the slew rate control for 1 MHz mode.

## 14.9 IPMI Support

The control bit, IPMIEN, enables the module to support Intelligent Peripheral Management Interface (IPMI). When this bit is set, the module accepts and acts upon all addresses.

## 14.10 General Call Address Support

The general call address can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledgement.

The general call address is one of eight addresses reserved for specific purposes by the  $I^2C$  protocol. It consists of all '0's with  $R_W = 0$ .

The general call address is recognized when the General Call Enable (GCEN) bit is set (I2CCON<7> = 1). Following a Start bit detection, 8 bits are shifted into I2CRSR and the address is compared with I2CADD, and is also compared with the general call address which is fixed in hardware.

If a general call address match occurs, the I2CRSR is transferred to the I2CRCV after the eighth clock, the RBF flag is set and on the falling edge of the ninth bit (ACK bit), the Master Event Interrupt Flag (MI2CIF) is set

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the I2CRCV to determine if the address was device-specific or a general call address.

## 14.11 I<sup>2</sup>C Master Support

As a master device, six operations are supported:

- · Assert a Start condition on SDA and SCL.
- · Assert a Restart condition on SDA and SCL.
- Write to the I2CTRN register initiating transmission of data/address.
- · Generate a Stop condition on SDA and SCL.
- Configure the I<sup>2</sup>C port to receive data.
- Generate an ACK condition at the end of a received byte of data.

## 14.12 I<sup>2</sup>C Master Operation

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I<sup>2</sup>C bus is not released.

In Master Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the slave address of the receiving device (7 bits) and the data direction bit. In this case, the data direction bit (R\_W) is logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an  $\overline{ACK}$  bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the data direction bit. In this case, the data direction bit (R\_W) is logic '1'. Thus, the first byte transmitted is a 7-bit slave address, followed by a '1' to indicate the receive bit. Serial data is received via SDA while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an ACK bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

#### 14.12.1 I<sup>2</sup>C MASTER TRANSMISSION

Transmission of a data byte, a 7-bit address or the second half of a 10-bit address, is accomplished by simply writing a value to I2CTRN register. The user should only write to I2CTRN when the module is in a Wait state. This action sets the Buffer Full Flag (TBF) and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data is shifted out onto the SDA pin after the falling edge of SCL is asserted. The Transmit Status Flag, TRSTAT (I2CSTAT<14>), indicates that a master transmit is in progress.

## 14.12.2 I<sup>2</sup>C MASTER RECEPTION

Master mode reception is enabled by programming the Receive Enable bit, RCEN (I2CCON<3>). The  $\rm I^2C$  module must be Idle before the RCEN bit is set; otherwise, the RCEN bit is disregarded. The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin  $\overline{\rm ACK}$  and data are shifted into the I2CRSR on the rising edge of each clock.

#### 14.12.3 BAUD RATE GENERATOR

In I<sup>2</sup>C Master mode, the reload value for the BRG is located in the I2CBRG register. When the BRG is loaded with this value, the BRG counts down to '0' and stops until another reload has taken place. If clock arbitration is taking place, for instance, the BRG is reloaded when the SCL pin is sampled high.

As per the I<sup>2</sup>C standard, FSCK may be 100 kHz or 400 kHz. However, the user can specify any baud rate up to 1 MHz. I2CBRG values of '0' or '1' are illegal.

### **EQUATION 14-1: SERIAL CLOCK RATE**

$$I2CBRG = \left(\frac{FCY}{FSCK} - \frac{FCY}{1,111,111}\right) - 1$$

### 14.12.4 CLOCK ARBITRATION

Clock arbitration occurs when the master deasserts the SCL pin (SCL allowed to float high) during any receive, transmit, or Restart/Stop condition. When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of I2CBRG and begins counting. This ensures that the SCL high time is always at least one BRG rollover count in the event that the clock is held low by an external device.

## 14.12.5 MULTI-MASTER COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-master operation support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA by letting SDA float high while another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin = 0, then a bus collision has taken place. The master sets the MI2CIF pulse and resetS the master portion of the  $I^2C$  port to its Idle state.

If a transmit was in progress when the bus collision occurred, the transmission is halted, the TBF flag is cleared, the SDA and SCL lines are deasserted and a value can now be written to I2CTRN. When the user services the  $\rm I^2C$  master event Interrupt Service Routine, if the  $\rm I^2C$  bus is free (i.e., the P bit is set), the user can resume communication by asserting a Start condition.

If a Start, Restart, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the I2CCON register are cleared to '0'. When the user services the bus collision Interrupt Service Routine, and if the I<sup>2</sup>C bus is free, the user can resume communication by asserting a Start condition.

The master continues to monitor the SDA and SCL pins, and if a Stop condition occurs, the MI2CIF bit is set.

A write to the I2CTRN starts the transmission of data at the first data bit, regardless of where the transmitter left off when bus collision occurred.

In a multi-master environment, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the  $I^2C$  bus can be taken when the P bit is set in the I2CSTAT register, or the bus is Idle and the S and P bits are cleared.

## 14.13 I<sup>2</sup>C Module Operation During CPU Sleep and Idle Modes

## 14.13.1 I<sup>2</sup>C OPERATION DURING CPU SLEEP MODE

When the device enters Sleep mode, all clock sources to the module are shut down and stay at logic '0'. If Sleep occurs in the middle of a transmission and the state machine is partially into a transmission as the clocks stop, then the transmission is aborted. Similarly, if Sleep occurs in the middle of a reception, then the reception is aborted.

## 14.13.2 I<sup>2</sup>C OPERATION DURING CPU IDLE MODE

For the  $I^2C$ , the I2CSIDL bit determines if the module stops or continues on Idle. If I2CSIDL = 0, the module continues operation on assertion of the Idle mode. If I2CSIDL = 1, the module stops on Idle.

| SFR Name | Addr. | Bit 15  | Bit 14 | Bit 13  | Bit 12 | Bit 11 | Bit 10 | Bit 9  | Bit 8 | Bit 7                          | Bit 6 | Bit 5 | Bit 4               | Bit 3   | Bit 2 | Bit 1 | Bit 0 | Reset State         |
|----------|-------|---------|--------|---------|--------|--------|--------|--------|-------|--------------------------------|-------|-------|---------------------|---------|-------|-------|-------|---------------------|
| I2CRCV   | 0200  | _       | _      | 1       | _      | _      | _      | _      | _     |                                |       |       | Receive R           | egister |       |       |       | 0000 0000 0000 0000 |
| I2CTRN   | 0202  | -       |        | _       | _      | _      | _      | _      | _     |                                |       |       | 0000 0000 1111 1111 |         |       |       |       |                     |
| I2CBRG   | 0204  | -       |        | _       | _      | _      | _      | _      |       |                                |       |       | 0000 0000 0000 0000 |         |       |       |       |                     |
| I2CCON   | 0206  | I2CEN   |        | I2CSIDL | SCLREL | IPMIEN | A10M   | DISSLW | SMEN  | GCEN                           | STREN | ACKDT | ACKEN               | RCEN    | PEN   | RSEN  | SEN   | 0001 0000 0000 0000 |
| I2CSTAT  | 0208  | ACKSTAT | TRSTAT | _       | _      | _      | BCL    | GCSTAT | ADD10 | 10 IWCOL I2COV D_A P S R_W RBF |       |       |                     |         |       |       | TBF   | 0000 0000 0000 0000 |
| I2CADD   | 020A  | _       | _      | _       | _      | _      | _      |        |       |                                |       |       | 0000 0000 0000 0000 |         |       |       |       |                     |

Legend: — = unimplemented bit, read as '0'
Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

### 15.0 SPI MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

The Serial Peripheral Interface (SPI) module is a synchronous serial interface. It is useful for communicating with other peripheral devices, such as EEPROMs, shift registers, display drivers and A/D converters, or other microcontrollers. It is compatible with Motorola's SPI and SIOP interfaces. The dsPIC30F3014 and dsPIC30F4013 devices feature one SPI module, SPI1.

## 15.1 Operating Function Description

Each SPI module consists of a 16-bit shift register, SPIxSR (where x = 1 or 2), used for shifting data in and out, and a buffer register, SPIxBUF. A control register, SPIxCON, configures the module. Additionally, a status register, SPIxSTAT, indicates various status conditions.

The serial interface consists of 4 pins: SDIx (Serial Data Input), SDOx (Serial Data Output), SCKx (Shift Clock Input or Output), and  $\overline{SSx}$  (Active-Low Slave Select).

In Master mode operation, SCKx is a clock output but in Slave mode, it is a clock input.

A series of eight (8) or sixteen (16) clock pulses shift out bits from the SPIxSR to SDOx pin and simultaneously shift in data from SDIx pin. An interrupt is generated when the transfer is complete and the corresponding interrupt flag bit (SPI1IF or SPI2IF) is set. This interrupt can be disabled through an interrupt enable bit (SPI1IE or SPI2IE).

The receive operation is double-buffered. When a complete byte is received, it is transferred from SPIxSR to SPIxBUF.

If the receive buffer is full when new data is being transferred from SPIxSR to SPIxBUF, the module sets the SPIROV bit, indicating an overflow condition. The transfer of the data from SPIxSR to SPIxBUF is not completed and new data is lost. The module does not respond to SCL transitions while SPIROV is '1', effectively disabling the module until SPIxBUF is read by user software.

Transmit writes are also double-buffered. The user writes to SPIxBUF. When the master or slave transfer is completed, the contents of the shift register (SPIxSR) are moved to the receive buffer. If any transmit data has been written to the buffer register, the contents of the transmit buffer are moved to SPIxSR. The received data is thus placed in SPIxBUF and the transmit data in SPIxSR is ready for the next transfer.

Note:

Both the transmit buffer (SPIxTXB) and the receive buffer (SPIxRXB) are mapped to the same register address, SPIxBUF.

In Master mode, the clock is generated by prescaling the system clock. Data is transmitted as soon as a value is written to SPIxBUF. The interrupt is generated at the middle of the transfer of the last bit.

In Slave mode, data is transmitted and received as external clock pulses appear on SCKx. Again, the interrupt is generated when the last bit is latched. If  $\overline{SSx}$  control is enabled, then transmission and reception are enabled only when  $\overline{SSx} = \underline{low}$ . The SDOx output is disabled in  $\overline{SSx}$  mode with  $\overline{SSx}$  high.

The clock provided to the module is (Fosc/4). This clock is then prescaled by the primary (PPRE<1:0>) and the secondary (SPRE<2:0>) prescale factors. The CKE bit determines whether transmit occurs on transition from active clock state to Idle clock state, or vice versa. The CKP bit selects the Idle state (high or low) for the clock.

## 15.1.1 WORD AND BYTE COMMUNICATION

A control bit, MODE16 (SPIxCON<10>), allows the module to communicate in either 16-bit or 8-bit mode. 16-bit operation is identical to 8-bit operation except that the number of bits transmitted is 16 instead of 8.

The user software must disable the module prior to changing the MODE16 bit. The SPI module is reset when the MODE16 bit is changed by the user.

A basic difference between 8-bit and 16-bit operation is that the data is transmitted out of bit 7 of the SPIxSR for 8-bit operation, and data is transmitted out of bit 15 of the SPIxSR for 16-bit operation. In both modes, data is shifted into bit 0 of the SPIxSR.

### 15.1.2 SDOx DISABLE

A control bit, DISSDO, is provided to the SPIxCON register to allow the SDOx output to be disabled. This allows the SPI module to be connected in an input-only configuration. SDOx can also be used for general purpose I/O.

## 15.2 Framed SPI Support

The module supports a basic framed SPI protocol in Master or Slave mode. The control bit, FRMEN, enables framed SPI support and causes the SSx pin to perform the Frame Synchronization pulse (FSYNC) function. The control bit, SPIFSD, determines whether

the SSx pin is an input or an output (i.e., whether the module receives or generates the Frame Synchronization pulse). The frame pulse is an active-high pulse for a single SPI clock cycle. When Frame Synchronization is enabled, the data transmission starts only on the subsequent transmit edge of the SPI clock.

FIGURE 15-1: SPI BLOCK DIAGRAM





FIGURE 15-2: SPI MASTER/SLAVE CONNECTION



## 15.3 Slave Select Synchronization

The  $\overline{SSx}$  pin allows a Synchronous Slave mode. The SPI must be configured in SPI Slave mode with  $\overline{SSx}$  pin control enabled (SSEN = 1). When the  $\overline{SSx}$  pin is low, transmission and reception are enabled and the SDOx pin is driven. When  $\overline{SSx}$  pin goes high, the SDOx pin is no longer driven. Also, the SPI module is resynchronized, and all counters/control circuitry are reset. Therefore, when the  $\overline{SSx}$  pin is asserted low again, transmission/reception begins at the MSb even if  $\overline{SSx}$  had been deasserted in the middle of a transmit/receive.

## 15.4 SPI Operation During CPU Sleep Mode

During Sleep mode, the SPI module is shut down. If the CPU enters Sleep mode while an SPI transaction is in progress, then the transmission and reception is aborted.

The transmitter and receiver stop in Sleep mode. However, register contents are not affected by entering or exiting Sleep mode.

## 15.5 SPI Operation During CPU Idle Mode

When the device enters Idle mode, all clock sources remain functional. The SPISIDL bit (SPIxSTAT<13>) determines if the SPI module stops or continues on Idle. If SPISIDL = 0, the module continues to operate when the CPU enters Idle mode. If SPISIDL = 1, the module stops when the CPU enters Idle mode.

## TABLE 15-1: dsPIC30F3014/4013 SPI1 REGISTER MAP

| SFR<br>Name | Addr. | Bit 15 | Bit 14   | Bit 13  | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7 | Bit 6  | Bit 5 | Bit 4 | Bit 3 | Bit 2 | Bit 1  | Bit 0  | Reset State         |
|-------------|-------|--------|--|---------|--------|--------|--------|-------|-------|-------|--------|-------|-------|-------|-------|--------|--------|---------------------|
| SPI1STAT    | 0220  | SPIEN  | _  | SPISIDL | _      | _      | _      | _     | _     | _     | SPIROV | _     | _     | _     | _     | SPITBF | SPIRBF | 0000 0000 0000 0000 |
| SPI1CON     | 0222  | _      | FRMEN  | SPIFSD  | _      | DISSDO | MODE16 | SMP   | CKE   | SSEN  | CKP    | MSTEN | SPRE2 | SPRE1 | SPRE0 | PPRE1  | PPRE0  | 0000 0000 0000 0000 |
| SPI1BUF     | 0224  |        | FRMEN   SPIFSD   —   DISSDO   MODE16   SMP   CKE   SSEN   CKP   MSTEN   SPRE2   SPRE1   SPRE0   PPRE1  Transmit and Receive Buffer |         |        |        |        |       |       |       |        |       |       |       |       |        |        | 0000 0000 0000 0000 |

dsPIC30F3014/4013

**Legend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

# 16.0 UNIVERSAL ASYNCHRONOUS RECEIVER TRANSMITTER (UART) MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).


This section describes the Universal Asynchronous Receiver/Transmitter Communications module.


### 16.1 UART Module Overview

The key features of the UART module are:

- Full-duplex, 8 or 9-bit data communication
- Even, odd or no parity options (for 8-bit data)
- · One or two Stop bits
- Fully integrated Baud Rate Generator with 16-bit prescaler
- Baud rates range from 38 bps to 1.875 Mbps at a 30 MHz instruction rate
- 4-word deep transmit data buffer
- 4-word deep receive data buffer
- Parity, framing and buffer overrun error detection
- Support for interrupt only on address detect (9th bit = 1)
- · Separate transmit and receive interrupts
- · Loopback mode for diagnostic support
- Two choices of TX/RX pins on UART1 module

FIGURE 16-1: UART TRANSMITTER BLOCK DIAGRAM





## 16.2 Enabling and Setting Up UART

### 16.2.1 ENABLING THE UART

The UART module is enabled by setting the UARTEN bit in the UxMODE register (where x = 1 or 2). Once enabled, the UxTX and UxRX pins are configured as an output and an input, respectively, overriding the TRIS and LAT register bit settings for the corresponding I/O port pins. The UxTX pin is at logic '1' when no transmission is taking place.

### 16.2.2 DISABLING THE UART

The UART module is disabled by clearing the UARTEN bit in the UxMODE register. This is the default state after any Reset. If the UART is disabled, all I/O pins operate as port pins under the control of the LAT and TRIS bits of the corresponding port pins.

Disabling the UART module resets the buffers to empty states. Any data characters in the buffers are lost and the baud rate counter is reset.

All error and status flags associated with the UART module are reset when the module is disabled. The URXDA, OERR, FERR, PERR, UTXEN, UTXBRK and UTXBF bits are cleared, whereas RIDLE and TRMT are set. Other control bits, including ADDEN, URXISEL<1:0>, UTXISEL, as well as the UxMODE and UxBRG registers, are not affected.

Clearing the UARTEN bit while the UART is active aborts all pending transmissions and receptions and resets the module, as defined above. Re-enabling the UART restarts the UART in the same configuration.

### 16.2.3 ALTERNATE I/O

The alternate I/O function is enabled by setting the ALTIO bit (UxMODE<10>). If ALTIO = 1, the UxATX and UxARX pins (alternate transmit and alternate receive pins, respectively) are used by the UART module instead of the UxTX and UxRX pins. If ALTIO = 0, the UxTX and UxRX pins are used by the UART module.

## 16.2.4 SETTING UP DATA, PARITY AND STOP BIT SELECTIONS

Control bits, PDSEL<1:0> in the UxMODE register, are used to select the data length and parity used in the transmission. The data length may either be 8 bits with even, odd or no parity, or 9 bits with no parity.

The STSEL bit determines whether one or two Stop bits are used during data transmission.

The default (power-on) setting of the UART is 8 bits, no parity and 1 Stop bit (typically represented as 8, N, 1).

## 16.3 Transmitting Data

## 16.3.1 TRANSMITTING IN 8-BIT DATA MODE

The following steps must be performed in order to transmit 8-bit data:

#### 1. Set up the UART:

First, the data length, parity and number of Stop bits must be selected. Then, the transmit and receive interrupt enable and priority bits are set up in the UxMODE and UxSTA registers. Also, the appropriate baud rate value must be written to the UxBRG register.

- 2. Enable the UART by setting the UARTEN bit (UxMODE<15>).
- 3. Set the UTXEN bit (UxSTA<10>), thereby enabling a transmission.
- 4. Write the byte to be transmitted to the lower byte of UxTXREG. The value is transferred to the Transmit Shift register (UxTSR) immediately, and the serial bit stream starts shifting out during the next rising edge of the baud clock. Alternatively, the data byte can be written while UTXEN = 0, following which, the user can set UTXEN. This causes the serial bit stream to begin immediately because the baud clock starts from a cleared state.
- A transmit interrupt is generated, depending on the value of the interrupt control bit, UTXISEL (UxSTA<15>).

## 16.3.2 TRANSMITTING IN 9-BIT DATA MODE

The sequence of steps involved in the transmission of 9-bit data is similar to 8-bit transmission, except that a 16-bit data word (of which the upper 7 bits are always clear) must be written to the UxTXREG register.

### 16.3.3 TRANSMIT BUFFER (UXTXB)

The transmit buffer is 9 bits wide and 4 characters deep. Including the Transmit Shift register (UxTSR), the user effectively has a 5-deep FIFO (First-In, First-Out) buffer. The UTXBF status bit (UxSTA<9>) indicates whether the transmit buffer is full.

If a user attempts to write to a full buffer, the new data is not accepted into the FIFO, and no data shift occurs within the buffer. This enables recovery from a buffer overrun condition.

The FIFO is reset during any device Reset but is not affected when the device enters or wakes up from a power-saving mode.

#### 16.3.4 TRANSMIT INTERRUPT

The transmit interrupt flag (U1TXIF or U2TXIF) is located in the corresponding interrupt flag register.

The transmitter generates an edge to set the UxTXIF bit. The condition for generating the interrupt depends on the UTXISEL control bit:

- a) If UTXISEL = 0, an interrupt is generated when a word is transferred from the transmit buffer to the Transmit Shift register (UxTSR). This means that the transmit buffer has at least one empty word.
- b) If UTXISEL = 1, an interrupt is generated when a word is transferred from the transmit buffer to the Transmit Shift register (UxTSR) and the transmit buffer is empty.

Switching between the two Interrupt modes during operation is possible and sometimes offers more flexibility.

#### 16.3.5 TRANSMIT BREAK

Setting the UTXBRK bit (UxSTA<11>) causes the UxTX line to be driven to logic '0'. The UTXBRK bit overrides all transmission activity. Therefore, the user should generally wait for the transmitter to be Idle before setting UTXBRK.

To send a Break character, the UTXBRK bit must be set by software and must remain set for a minimum of 13 baud clock cycles. The UTXBRK bit is then cleared by software to generate Stop bits. The user must wait for a duration of at least one or two baud clock cycles in order to ensure a valid Stop bit(s) before reloading the UxTXB, or starting other transmitter activity. Transmission of a Break character does not generate a transmit interrupt.

## 16.4 Receiving Data

## 16.4.1 RECEIVING IN 8-BIT OR 9-BIT DATA MODE

The following steps must be performed while receiving 8-bit or 9-bit data:

- 1. Set up the UART (see Section 16.3.1 "Transmitting in 8-Bit Data Mode").
- 2. Enable the UART (see Section 16.3.1 "Transmitting in 8-Bit Data Mode").
- A receive interrupt is generated when one or more data words have been received, depending on the receive interrupt settings specified by the URXISEL bits (UxSTA<7:6>).
- Read the OERR bit to determine if an overrun error has occurred. The OERR bit must be reset in software.
- Read the received data from UxRXREG. The act of reading UxRXREG moves the next word to the top of the receive FIFO, and the PERR and FERR values are updated.

### 16.4.2 RECEIVE BUFFER (UxRXB)

The receive buffer is 4 words deep. Including the Receive Shift register (UxRSR), the user effectively has a 5-word deep FIFO buffer.

URXDA (UxSTA<0>) = 1 indicates that the receive buffer has data available. URXDA = 0 means that the buffer is empty. If a user attempts to read an empty buffer, the old values in the buffer are read and no data shift occurs within the FIFO.

The FIFO is reset during any device Reset. It is not affected when the device enters or wakes up from a power-saving mode.

#### 16.4.3 RECEIVE INTERRUPT

The receive interrupt flag (U1RXIF or U2RXIF) can be read from the corresponding interrupt flag register. The interrupt flag is set by an edge generated by the receiver. The condition for setting the receive interrupt flag depends on the settings specified by the URXISEL<1:0> (UxSTA<7:6>) control bits.

- a) If URXISEL<1:0> = 00 or 01, an interrupt is generated every time a data word is transferred from the Receive Shift register (UxRSR) to the receive buffer. There may be one or more characters in the receive buffer.
- b) If URXISEL<1:0> = 10, an interrupt is generated when a word is transferred from the Receive Shift register (UxRSR) to the receive buffer, which as a result of the transfer, contains 3 characters.
- c) If URXISEL<1:0> = 11, an interrupt is set when a word is transferred from the Receive Shift register (UxRSR) to the receive buffer, which as a result of the transfer, contains 4 characters (i.e., becomes full).

Switching between the Interrupt modes during operation is possible, though generally not advisable during normal operation.

## 16.5 Reception Error Handling

## 16.5.1 RECEIVE BUFFER OVERRUN ERROR (OERR BIT)

The OERR bit (UxSTA<1>) is set if all of the following conditions occur:

- a) The receive buffer is full.
- b) The Receive Shift register is full, but unable to transfer the character to the receive buffer.
- c) The Stop bit of the character in the UxRSR is detected, indicating that the UxRSR needs to transfer the character to the buffer.

Once OERR is set, no further data is shifted in UxRSR (until the OERR bit is cleared in software or a Reset occurs). The data held in UxRSR and UxRXREG remains valid.

### 16.5.2 FRAMING ERROR (FERR)

The FERR bit (UxSTA<2>) is set if a '0' is detected instead of a Stop bit. If two Stop bits are selected, both Stop bits must be '1'; otherwise, FERR is set. The readonly FERR bit is buffered along with the received data; it is cleared on any Reset.

### 16.5.3 PARITY ERROR (PERR)

The PERR bit (UxSTA<3>) is set if the parity of the received word is incorrect. This error bit is applicable only if a Parity mode (odd or even) is selected. The read-only PERR bit is buffered along with the received data bytes; it is cleared on any Reset.

#### 16.5.4 IDLE STATUS

When the receiver is active (i.e., between the initial detection of the Start bit and the completion of the Stop bit), the RIDLE bit (UxSTA<4>) is '0'. Between the completion of the Stop bit and detection of the next Start bit, the RIDLE bit is '1', indicating that the UART is Idle.

#### 16.5.5 RECEIVE BREAK

The receiver counts and expects a certain number of bit times based on the values programmed in the PDSEL (UxMODE<2:1>) and STSEL (UxMODE<0>) bits.

If the break is longer than 13 bit times, the reception is considered complete after the number of bit times specified by PDSEL and STSEL. The URXDA bit is set, FERR is set, zeros are loaded into the receive FIFO, interrupts are generated if appropriate, and the RIDLE bit is set.

When the module receives a long Break signal and the receiver has detected the Start bit, the data bits and the invalid Stop bit (which sets the FERR), the receiver must wait for a valid Stop bit before looking for the next Start bit. It cannot assume that the Break condition on the line is the next Start bit.

Break is regarded as a character containing all '0's with the FERR bit set. The Break character is loaded into the buffer. No further reception can occur until a Stop bit is received. Note that RIDLE goes high when the Stop bit has not yet been received.

### 16.6 Address Detect Mode

Setting the ADDEN bit (UxSTA<5>) enables this special mode in which a 9th bit (URX8) value of '1' identifies the received word as an address, rather than data. This mode is only applicable for 9-bit data communication. The URXISEL control bit does not have any impact on interrupt generation in this mode since an interrupt (if enabled) is generated every time the received word has the 9th bit set.

## 16.7 Loopback Mode

Setting the LPBACK bit enables this special mode in which the UxTX pin is internally connected to the UxRX pin. When configured for the Loopback mode, the UxRX pin is disconnected from the internal UART receive logic. However, the UxTX pin still functions as in a normal operation.

To select this mode:

- a) Configure UART for desired mode of operation.
- b) Set LPBACK = 1 to enable Loopback mode.
- c) Enable transmission as defined in Section 16.3 "Transmitting Data".

### 16.8 Baud Rate Generator

The UART has a 16-bit Baud Rate Generator to allow maximum flexibility in baud rate generation. The Baud Rate Generator register (UxBRG) is readable and writable. The baud rate is computed as follows:

BRG = 16-bit value held in UxBRG register (0 through 65535)

Fcy = Instruction Clock Rate (1/Tcy)

The Baud Rate is given by Equation 16-1.

### **EQUATION 16-1: BAUD RATE**

Baud Rate = FCY/(16\*(BRG+1))

Therefore, the maximum baud rate possible is:

FCY/16 (if BRG = 0),

and the minimum baud rate possible is:

Fcy/(16 \* 65536).

With a full 16-bit Baud Rate Generator at 30 MIPS operation, the minimum baud rate achievable is 28.5 bps.

## 16.9 Auto-Baud Support

To allow the system to determine baud rates of received characters, the input can be optionally linked to a capture input (IC1 for UART1, IC2 for UART2). To enable this mode, the user must program the input capture module to detect the falling and rising edges of the Start bit.

## 16.10 UART Operation During CPU Sleep and Idle Modes

## 16.10.1 UART OPERATION DURING CPU SLEEP MODE

When the device enters Sleep mode, all clock sources to the module are shut down and stay at logic '0'. If entry into Sleep mode occurs while a transmission is in progress, then the transmission is aborted. The UxTX pin is driven to logic '1'. Similarly, if entry into Sleep mode occurs while a reception is in progress, then the reception is aborted. The UxSTA, UxMODE, transmit and receive registers and buffers, and the UxBRG register are not affected by Sleep mode.

If the WAKE bit (UxMODE<7>) is set before the device enters Sleep mode, a falling edge on the UxRX pin generates a receive interrupt. The Receive Interrupt Select mode bit (URXISEL) has no effect for this function. If the receive interrupt is enabled, this wakes the device up from Sleep. The UARTEN bit must be set in order to generate a wake-up interrupt.

## 16.10.2 UART OPERATION DURING CPU IDLE MODE

For the UART, the USIDL bit determines if the module stops or continues operation when the device enters Idle mode. If USIDL=0, the module continues operation during Idle mode. If USIDL=1, the module stops on Idle.

#### TABLE 16-1: dsPIC30F3014/4013 UART1 REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15  | Bit 14                        | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7    | Bit 6    | Bit 5 | Bit 4               | Bit 3 | Bit 2               | Bit 1  | Bit 0 | Reset State         |
|----------|-------|---------|-------------------------------|--------|--------|--------|--------|-------|-------|----------|----------|-------|---------------------|-------|---------------------|--------|-------|---------------------|
| U1MODE   | 020C  | UARTEN  | _                             | USIDL  | _      | _      | ALTIO  | _     | _     | WAKE     | LPBACK   | ABAUD | _                   | _     | PDSEL1              | PDSEL0 | STSEL | 0000 0000 0000 0000 |
| U1STA    | 020E  | UTXISEL | -                             | _      | _      | UTXBRK | UTXEN  | UTXBF | TRMT  | URXISEL1 | URXISEL0 | ADDEN | RIDLE               | PERR  | FERR                | OERR   | URXDA | 0000 0001 0001 0000 |
| U1TXREG  | 0210  | -       | _                             | _      | _      | _      |        | _     | UTX8  |          |          |       | 0000 000u uuuu uuuu |       |                     |        |       |                     |
| U1RXREG  | 0212  | -       | _                             | _      | _      | _      |        | _     | URX8  |          |          |       | 0000 0000 0000 0000 |       |                     |        |       |                     |
| U1BRG    | 0214  |         | Baud Rate Generator Prescaler |        |        |        |        |       |       |          |          |       |                     |       | 0000 0000 0000 0000 |        |       |                     |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

#### TABLE 16-2: dsPIC30F3014/4013 UART2 REGISTER MAP<sup>(1)</sup>

| SFR<br>Name | Addr. | Bit 15  | Bit 14 | Bit 13 | Bit 12 | Bit 11 | Bit 10 | Bit 9 | Bit 8 | Bit 7    | Bit 6    | Bit 5               | Bit 4               | Bit 3 | Bit 2  | Bit 1               | Bit 0 | Reset State         |
|-------------|-------|---------|--------|--------|--------|--------|--------|-------|-------|----------|----------|---------------------|---------------------|-------|--------|---------------------|-------|---------------------|
| U2MODE      | 0216  | UARTEN  | _      | USIDL  | _      | _      | _      | _     | _     | WAKE     | LPBACK   | ABAUD               | _                   | _     | PDSEL1 | PDSEL0              | STSEL | 0000 0000 0000 0000 |
| U2STA       | 0218  | UTXISEL | _      | _      | _      | UTXBRK | UTXEN  | UTXBF | TRMT  | URXISEL1 | URXISEL0 | 0000 0001 0001 0000 |                     |       |        |                     |       |                     |
| U2TXREG     | 021A  | _       | _      | _      | _      | _      | -      | _     | UTX8  |          |          |                     | 0000 000u uuuu uuuu |       |        |                     |       |                     |
| U2RXREG     | 021C  | _       | _      | _      | _      | _      | -      | _     | URX8  |          |          |                     | 0000 0000 0000 0000 |       |        |                     |       |                     |
| U2BRG       | 021E  |         |        |        |        |        |        |       |       |          |          |                     |                     |       |        | 0000 0000 0000 0000 |       |                     |

u = uninitialized bit; — = unimplemented bit, read as '0'

Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

#### 17.0 CAN MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

#### 17.1 Overview

The Controller Area Network (CAN) module is a serial interface, useful for communicating with other CAN modules or microcontroller devices. This interface/protocol was designed to allow communications within noisy environments.

The CAN module is a communication controller implementing the CAN 2.0 A/B protocol, as defined in the BOSCH specification. The module supports CAN 1.2, CAN 2.0A, CAN 2.0B Passive, and CAN 2.0B Active versions of the protocol. The module implementation is a full CAN system. The CAN specification is not covered within this data sheet. The reader may refer to the BOSCH CAN specification for further details.

The module features are as follows:

- Implementation of the CAN protocol CAN 1.2, CAN 2.0A and CAN 2.0B
- · Standard and extended data frames
- · 0-8 bytes data length
- Programmable bit rate up to 1 Mbit/sec
- · Support for remote frames
- Double-buffered receiver with two prioritized received message storage buffers (each buffer may contain up to 8 bytes of data)
- 6 full (standard/extended identifier), acceptance filters, 2 associated with the high-priority receive buffer and 4 associated with the low-priority receive buffer
- 2 full, acceptance filter masks, one each associated with the high and low-priority receive buffers
- Three transmit buffers with application specified prioritization and abort capability (each buffer may contain up to 8 bytes of data)
- Programmable wake-up functionality with integrated low-pass filter
- Programmable Loopback mode supports self-test operation
- Signaling via interrupt capabilities for all CAN receiver and transmitter error states
- · Programmable clock source
- Programmable link to input capture module (IC2, for both CAN1 and CAN2) for time-stamping and network synchronization
- · Low-power Sleep and Idle mode

The CAN bus module consists of a protocol engine and message buffering/control. The CAN protocol engine handles all functions for receiving and transmitting messages on the CAN bus. Messages are transmitted by first loading the appropriate data registers. Status and errors can be checked by reading the appropriate registers. Any message detected on the CAN bus is checked for errors and then matched against filters to see if it should be received and stored in one of the receive registers.

#### 17.2 Frame Types

The CAN module transmits various types of frames which include data messages or remote transmission requests, initiated by the user, as other frames that are automatically generated for control purposes. The following frame types are supported:

#### • Standard Data Frame:

A standard data frame is generated by a node when the node wishes to transmit data. It includes an 11-bit Standard Identifier (SID) but not an 18-bit Extended Identifier (EID).

#### Extended Data Frame:

An extended data frame is similar to a standard data frame but includes an extended identifier as well.

#### • Remote Frame:

It is possible for a destination node to request the data from the source. For this purpose, the destination node sends a remote frame with an identifier that matches the identifier of the required data frame. The appropriate data source node then sends a data frame as a response to this remote request.

#### · Error Frame:


An error frame is generated by any node that detects a bus error. An error frame consists of 2 fields: an error flag field and an error delimiter field.

#### Overload Frame:

An overload frame can be generated by a node as a result of 2 conditions. First, the node detects a dominant bit during interframe space which is an illegal condition. Second, due to internal conditions, the node is not yet able to start reception of the next message. A node may generate a maximum of 2 sequential overload frames to delay the start of the next message.

#### • Interframe Space:

Interframe space separates a proceeding frame (of whatever type) from a following data or remote frame.



CAN BUFFERS AND PROTOCOL ENGINE BLOCK DIAGRAM **FIGURE 17-1:** 

#### 17.3 Modes of Operation

The CAN module can operate in one of several operation modes selected by the user. These modes include:

- · Initialization mode
- Disable mode
- · Normal Operation mode
- · Listen Only mode
- · Loopback mode
- · Error Recognition mode

Modes are requested by setting the REQOP<2:0> bits (CiCTRL<10:8>). Entry into a mode is Acknowledged by monitoring the OPMODE<2:0> bits (CiCTRL<7:5>). The module does not change the mode and the OPMODE bits until a change in mode is acceptable, generally during bus Idle time which is defined as at least 11 consecutive recessive bits.

#### 17.3.1 INITIALIZATION MODE

In the Initialization mode, the module does not transmit or receive. The error counters are cleared and the interrupt flags remain unchanged. The programmer has access to Configuration registers that are access restricted in other modes. The module protects the user from accidentally violating the CAN protocol through programming errors. All registers that control the configuration of the module can not be modified while the module is on-line. The CAN module is not allowed to enter the Configuration mode while a transmission is taking place. The Configuration mode serves as a lock to protect the following registers.

- All Module Control registers
- Baud Rate and Interrupt Configuration registers
- · Bus Timing registers
- · Identifier Acceptance Filter registers
- · Identifier Acceptance Mask registers

#### 17.3.2 DISABLE MODE

In Disable mode, the module does not transmit or receive. The module has the ability to set the WAKIF bit due to bus activity, however, any pending interrupts remain and the error counters retain their value.

If the REQOP<2:0> bits (CiCTRL<10:8>) = 001, the module enters the Module Disable mode. If the module is active, the module waits for 11 recessive bits on the CAN bus, detects that condition as an Idle bus, and then accepts the module disable command. When the OPMODE<2:0> bits (CiCTRL<7:5>) = 001, that indicates whether the module successfully went into Module Disable mode. The I/O pins revert to normal I/O function when the module is in the Module Disable mode.

The module can be programmed to apply a low-pass filter function to the CiRX input line while the module or the CPU is in Sleep mode. The WAKFIL bit (CiCFG2<14>) enables or disables the filter.

Typically, if the CAN module is allowed to transmit in a particular mode of operation and a transmission is requested immediately after the CAN module has been placed in that mode of operation, the module waits for 11 consecutive recessive bits on the bus before starting transmission. If the user switches to Disable mode within this 11-bit period, then this transmission is aborted and the corresponding TXABT bit is set and TXREQ bit is cleared.

#### 17.3.3 NORMAL OPERATION MODE

Normal Operating mode is selected when REQOP<2:0> = 000. In this mode, the module is activated and the I/O pins assume the CAN bus functions. The module transmits and receives CAN bus messages via the CxTX and CxRX pins.

#### 17.3.4 LISTEN ONLY MODE

Note:

If the Listen Only mode is activated, the module on the CAN bus is passive. The transmitter buffers revert to the port I/O function. The receive pins remain inputs. For the receiver, no error flags or Acknowledge signals are sent. The error counters are deactivated in this state. The Listen Only mode can be used for detecting the baud rate on the CAN bus. To use this, it is necessary that there are at least two further nodes that communicate with each other.

#### 17.3.5 LISTEN ALL MESSAGES MODE

The module can be set to ignore all errors and receive any message. The Listen All Messages mode is activated by setting the REQOP<2:0> bits to '111'. In this mode, the data which is in the message assembly buffer until the time an error occurred, is copied in the receive buffer and can be read via the CPU interface.

#### 17.3.6 LOOPBACK MODE

If the Loopback mode is activated, the module connects the internal transmit signal to the internal receive signal at the module boundary. The transmit and receive pins revert to their port I/O function.

#### 17.4 Message Reception

#### 17.4.1 RECEIVE BUFFERS

The CAN bus module has 3 receive buffers. However, one of the receive buffers is always committed to monitoring the bus for incoming messages. This buffer is called the Message Assembly Buffer (MAB). So there are 2 receive buffers visible, denoted as RXB0 and RXB1, that can essentially instantaneously receive a complete message from the protocol engine.

All messages are assembled by the MAB and are transferred to the RXBn buffers only if the acceptance filter criterion are met. When a message is received, the RXnIF flag (CilNRF<0> or CilNRF<1>) is set. This bit can only be set by the module when a message is received. The bit is cleared by the CPU when it has completed processing the message in the buffer. If the RXnIE bit (CilNTE<0> or CilNTE<1>) is set, an interrupt is generated when a message is received.

RXF0 and RXF1 filters with RXM0 mask are associated with RXB0. The filters RXF2, RXF3, RXF4 and RXF5, and the mask RXM1 are associated with RXB1.

#### 17.4.2 MESSAGE ACCEPTANCE FILTERS

The message acceptance filters and masks are used to determine if a message in the message assembly buffer should be loaded into either of the receive buffers. Once a valid message has been received into the Message Assembly Buffer (MAB), the identifier fields of the message are compared to the filter values. If there is a match, that message is loaded into the appropriate receive buffer.

The acceptance filter looks at incoming messages for the RXIDE bit (CiRXnSID<0>) to determine how to compare the identifiers. If the RXIDE bit is clear, the message is a standard frame and only filters with the EXIDE bit (CiRXFnSID<0>) clear are compared. If the RXIDE bit is set, the message is an extended frame and only filters with the EXIDE bit set are compared.

### 17.4.3 MESSAGE ACCEPTANCE FILTER MASKS

The mask bits essentially determine which bits to apply the filter to. If any mask bit is set to a zero, that bit is automatically accepted regardless of the filter bit. There are two programmable acceptance filter masks associated with the receive buffers, one for each buffer.

#### 17.4.4 RECEIVE OVERRUN

An overrun condition occurs when the Message Assembly Buffer (MAB) has assembled a valid received message, the message is accepted through the acceptance filters, and when the receive buffer associated with the filter has not been designated as clear of the previous message.

The overrun error flag, RXnOVR (CiINTF<15> or CiINTF<14>), and the ERRIF bit (CiINTF<5>) are set and the message in the MAB is discarded.

If the DBEN bit is clear, RXB1 and RXB0 operate independently. When this is the case, a message intended for RXB0 is not diverted into RXB1 if RXB0 contains an unread message, and the RX0OVR bit is set.

If the DBEN bit is set, the overrun for RXB0 is handled differently. If a valid message is received for RXB0 and RXFUL = 1 it indicates that RXB0 is full and RXFUL = 0 indicates that RXB1 is empty, the message for RXB0 is loaded into RXB1. An overrun error is not generated for RXB0. If a valid message is received for RXB0 and RXFUL = 1, indicates that both RXB0 and RXB1 are full, the message is lost and an overrun is indicated for RXB1.

#### 17.4.5 RECEIVE ERRORS

The CAN module detects the following receive errors:

- Cyclic Redundancy Check (CRC) error
- Bit Stuffing error
- Invalid Message Receive Error

The receive error counter is incremented by one in case one of these errors occur. The RXWAR bit (CiINTF<9>) indicates that the receive error counter has reached the CPU warning limit of 96 and an interrupt is generated.

#### 17.4.6 RECEIVE INTERRUPTS

Receive interrupts can be divided into 3 major groups, each including various conditions that generate interrupts:

• Receive Interrupt:

A message has been successfully received and loaded into one of the receive buffers. This interrupt is activated immediately after receiving the End-of-Frame (EOF) field. Reading the RXnIF flag indicates which receive buffer caused the interrupt.

• Wake-up Interrupt:

The CAN module has woken up from Disable mode or the device has woken up from Sleep mode.

#### · Receive Error Interrupts:

A receive error interrupt is indicated by the ERRIF bit. This bit shows that an error condition occurred. The source of the error can be determined by checking the bits in the CAN Interrupt register, CilNTF.

#### - Invalid Message Received:

If any type of error occurred during reception of the last message, an error is indicated by the IVRIF bit.

#### - Receiver Overrun:

The RXnOVR bit indicates that an overrun condition occurred.

#### - Receiver Warning:

The RXWAR bit indicates that the Receive Error Counter (RERRCNT<7:0>) has reached the warning limit of 96.

#### - Receiver Error Passive:

The RXEP bit indicates that the Receive Error Counter has exceeded the error passive limit of 127 and the module has gone into error passive state.

#### 17.5 Message Transmission

#### 17.5.1 TRANSMIT BUFFERS

The CAN module has three transmit buffers. Each of the three buffers occupies 14 bytes of data. Eight of the bytes are the maximum 8 bytes of the transmitted message. Five bytes hold the standard and extended identifiers and other message arbitration information.

#### 17.5.2 TRANSMIT MESSAGE PRIORITY

Transmit priority is a prioritization within each node of the pending transmittable messages. There are 4 levels of transmit priority. If TXPRI<1:0> (CiTXnCON<1:0>, where  $n=0,\,1$  or 2, represents a particular transmit buffer) for a particular message buffer is set to '11', that buffer has the highest priority. If TXPRI<1:0> for a particular message buffer is set to '10' or '01', that buffer has an intermediate priority. If TXPRI<1:0> for a particular message buffer is '00', that buffer has the lowest priority.

#### 17.5.3 TRANSMISSION SEQUENCE

To initiate transmission of the message, the TXREQ bit (CiTXnCON<3>) must be set. The CAN bus module resolves any timing conflicts between setting of the TXREQ bit and the Start-of-Frame (SOF), ensuring that if the priority was changed, it is resolved correctly before the SOF occurs. When TXREQ is set, the TXABT (CiTXnCON<6>), TXLARB (CiTXnCON<5>) and TXERR (CiTXnCON<4>) flag bits are automatically cleared.

Setting TXREQ bit simply flags a message buffer as enqueued for transmission. When the module detects an available bus, it begins transmitting the message which has been determined to have the highest priority.

If the transmission completes successfully on the first attempt, the TXREQ bit is cleared automatically and an interrupt is generated if TX1IE was set.

If the message transmission fails, one of the error condition flags is set, and the TXREQ bit remains set, indicating that the message is still pending for transmission. If the message encountered an error condition during the transmission attempt, the TXERR bit is set, and the error condition may cause an interrupt. If the message loses arbitration during the transmission attempt, the TXLARB bit is set. No interrupt is generated to signal the loss of arbitration.

### 17.5.4 ABORTING MESSAGE TRANSMISSION

The system can also abort a message by clearing the TXREQ bit associated with each message buffer. Setting the ABAT bit (CiCTRL<12>) requests an abort of all pending messages. If the message has not yet started transmission, or if the message started but is interrupted by loss of arbitration or an error, the abort is processed. The abort is indicated when the module sets the TXABT bit and the TXnIF flag is not automatically set.

#### 17.5.5 TRANSMISSION ERRORS

The CAN module detects the following transmission errors:

- Acknowledge error
- Form error
- · Bit error

These transmission errors do not necessarily generate an interrupt but are indicated by the transmission error counter. However, each of these errors causes the transmission error counter to be incremented by one. Once the value of the error counter exceeds the value of 96, the ERRIF (CiINTF<5>) and the TXWAR bit (CiINTF<10>) are set. Once the value of the error counter exceeds the value of 96, an interrupt is generated and the TXWAR bit in the Error Flag register is set.

#### 17.5.6 TRANSMIT INTERRUPTS

Transmit interrupts can be divided into 2 major groups, each including various conditions that generate interrupts:

#### • Transmit Interrupt:

At least one of the three transmit buffers is empty (not scheduled) and can be loaded to schedule a message for transmission. The TXnIF flags are read to determine which transmit buffer is available and caused the interrupt.

#### Transmit Error Interrupts:

A transmission error interrupt is indicated by the ERRIF flag. This flag shows that an error condition occurred. The source of the error can be determined by checking the error flags in the CAN Interrupt register, CilNTF. The flags in this register are related to receive and transmit errors.

Transmitter Warning Interrupt:
 The TXWAR bit indicates that the Transmit Error
 Counter has reached the CPU warning limit of 96.

#### - Transmitter Error Passive:

The TXEP bit (CilNTF<12>) indicates that the Transmit Error Counter has exceeded the error passive limit of 127 and the module has gone to error passive state.

#### - Bus Off:

The TXBO bit (CilNTF<13>) indicates that the Transmit Error Counter (TERRCNT<7:0>) has exceeded 255 and the module has gone to the bus off state.

#### 17.6 Baud Rate Setting

All nodes on any particular CAN bus must have the same nominal bit rate. In order to set the baud rate, the following parameters have to be initialized:

- · Synchronization Jump Width
- · Baud Rate Prescaler
- Phase Segments
- Length determination of Phase Segment 2
- · Sample Point
- Propagation Segment bits

#### 17.6.1 BIT TIMING


All controllers on the CAN bus must have the same baud rate and bit length. However, different controllers are not required to have the same master oscillator clock. At different clock frequencies of the individual controllers, the baud rate has to be adjusted by adjusting the number of time quanta in each segment.

The nominal bit time can be thought of as being divided into separate non-overlapping time segments. These segments are shown in Figure 17-2.

- Synchronization Segment (Sync Seg)
- · Propagation Time Segment (Prop Seg)
- Phase Segment 1 (Phase1 Seg)
- Phase Segment 2 (Phase2 Seg)

The time segments and also the nominal bit time are made up of integer units of time called time quanta or TQ. By definition, the nominal bit time has a minimum of 8 TQ and a maximum of 25 TQ. Also, by definition, the minimum nominal bit time is 1  $\mu$ sec corresponding to a maximum bit rate of 1 MHz.

#### FIGURE 17-2: CAN BIT TIMING



#### 17.6.2 PRESCALER SETTING

There is a programmable prescaler with integral values ranging from 1 to 64 in addition to a fixed divide-by-2 for clock generation. The Time Quantum (TQ) is a fixed unit of time derived from the oscillator period, shown in Equation 17-1, where FCAN is FCY (if the CANCKS bit is set) or 4FCY (if CANCKS is clear).

**Note:** FCAN must not exceed 30 MHz. If CANCKS = 0, then FCY must not exceed 7.5 MHz.

### EQUATION 17-1: TIME QUANTUM FOR CLOCK GENERATION

 $T_0 = 2 (BRP < 5:0 > + 1)/FCAN$ 

#### 17.6.3 PROPAGATION SEGMENT

This part of the bit time is used to compensate physical delay times within the network. These delay times consist of the signal propagation time on the bus line and the internal delay time of the nodes. The propagation segment can be programmed from 1 TQ to 8 TQ by setting the PRSEG<2:0> bits (CiCFG2<2:0>).

#### 17.6.4 PHASE SEGMENTS

The phase segments are used to optimally locate the sampling of the received bit within the transmitted bit time. The sampling point is between Phase1 Seg and Phase2 Seg. These segments are lengthened or shortened by resynchronization. The end of the Phase1 Seg determines the sampling point within a bit period. The segment is programmable from 1 TQ to 8 TQ. Phase2 Seg provides delay to the next transmitted data transition. The segment is programmable from 1 TQ to 8 TQ, or it may be defined to be equal to the greater of Phase1 Seg or the information processing time (2 TQ). The Phase1 Seg is initialized by setting bits SEG1PH<2:0> (CiCFG2<5:3>), and Phase2 Seg is initialized by setting SEG2PH<2:0> (CiCFG2<10:8>).

The following requirement must be fulfilled while setting the lengths of the phase segments:

Prop Seg + Phase1 Seg > = Phase2 Seg

#### 17.6.5 SAMPLE POINT

The sample point is the point of time at which the bus level is read and interpreted as the value of that respective bit. The location is at the end of Phase1 Seg. If the bit timing is slow and contains many TQ, it is possible to specify multiple sampling of the bus line at the sample point. The level determined by the CAN bus then corresponds to the result from the majority decision of three values. The majority samples are taken at the sample point and twice before with a distance of TQ/2. The CAN module allows the user to choose between sampling three times at the same point, or once at the same point by setting or clearing the SAM bit (CiCFG2<6>).

Typically, the sampling of the bit should take place at about 60-70% through the bit time depending on the system parameters.

#### 17.6.6 SYNCHRONIZATION

To compensate for phase shifts between the oscillator frequencies of the different bus stations, each CAN controller must be able to synchronize to the relevant signal edge of the incoming signal. When an edge in the transmitted data is detected, the logic compares the location of the edge to the expected time (synchronous segment). The circuit then adjusts the values of Phase1 Seg and Phase2 Seg. There are two mechanisms used to synchronize.

#### 17.6.6.1 Hard Synchronization

Hard synchronization is only done when there is a recessive to dominant edge during bus Idle, indicating the start of a message. After hard synchronization, the bit-time counters are restarted with the synchronous segment. Hard synchronization forces the edge which has caused the hard synchronization to lie within the synchronization segment of the restarted bit time. If a hard synchronization is done, there will not be a resynchronization within that bit time.

#### 17.6.6.2 Resynchronization

As a result of resynchronization, Phase1 Seg may be lengthened or Phase2 Seg may be shortened. The amount of lengthening or shortening of the phase buffer segment has an upper bound known as the synchronization jump width, and is specified by the SJW<1:0> bits (CiCFG1<7:6>). The value of the synchronization jump width is added to Phase1 Seg or subtracted from Phase2 Seg. The resynchronization jump width is programmable between 1 TQ and 4 TQ.

The following requirement must be fulfilled while setting the SJW<1:0> bits:

Phase 2 Seg > Synchronization Jump Width

DS70138G-page 118

TABLE 17-1: dsPIC30F4013 CAN1 REGISTER MAP<sup>(1)</sup>

| SFR Name   | Addr. | Bit 15      | Bit 14  | Bit 13        | Bit 12        | Bit 11       | Bit 10 | Bit 9     | Bit 8      | Bit 7          | Bit 6          | Bit 5        | Bit 4       | Bit 3         | Bit 2               | Bit 1 | Bit 0   | Reset State         |
|------------|-------|-------------|---|---------------|---------------|--------------|--------|-----------|------------|----------------|----------------|--------------|-------------|---------------|---------------------|-------|---------|---------------------|
| C1RXF0SID  | 0300  | _           | _   | _             |               |              |        | Receive A | cceptance  | Filter 0 Stand | dard Identi    | fier<10:0>   |             |               |                     | _     | EXIDE   | 000u uuuu uuuu uu0u |
| C1RXF0EIDH | 0302  | _           |   | _             | _             |              |        |           | Rece       | ive Acceptanc  | e Filter 0 I   | Extended l   | dentifier<1 | 7:6>          |                     | 1     |         | 0000 uuuu uuuu uuuu |
| C1RXF0EIDL | 0304  | Rece        | eive Accepta  | ance Filter ( | 0 Extended    | dentifier<5: | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1RXF1SID  | 0308  | _           | _   | _             |               |              |        | Receive A | cceptance  | Filter 1 Stand | dard Identi    | fier<10:0>   |             |               | •                   | _     | EXIDE   | 000u uuuu uuuu uu0u |
| C1RXF1EIDH | 030A  | _           |   | _             | _             |              |        |           | Rece       | ive Acceptanc  | e Filter 1 E   | Extended l   | dentifier<1 | 7:6>          |                     | 1     |         | 0000 uuuu uuuu uuuu |
| C1RXF1EIDL | 030C  | Rece        | eive Accepta  | ance Filter 1 | 1 Extended    | dentifier<5: | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1RXF2SID  | 0310  | _           | _   | _             |               |              |        | Receive A | cceptance  | Filter 2 Stand | dard Identi    | fier<10:0>   |             |               | •                   | _     | EXIDE   | 000u uuuu uuuu uu0u |
| C1RXF2EIDH | 0312  | _           |   | _             | _             |              |        |           | Rece       | ive Acceptanc  | e Filter 2 I   | Extended l   | dentifier<1 | 7:6>          |                     | •     |         | 0000 uuuu uuuu uuuu |
| C1RXF2EIDL | 0314  | Rece        | eive Accepta  | ance Filter 2 | 2 Extended    | dentifier<5: | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1RXF3SID  | 0318  | _           | _   | _             |               |              |        | Receive A | cceptance  | Filter 3 Stand | dard Identi    | fier<10:0>   | •           |               | •                   | _     | EXIDE   | 000u uuuu uuuu uu0u |
| C1RXF3EIDH | 031A  | _           |   | _             | _             |              |        |           | Rece       | ive Acceptanc  | e Filter 3 l   | Extended l   | dentifier<1 | 7:6>          |                     |       |         | 0000 uuuu uuuu uuuu |
| C1RXF3EIDL | 031C  | Rece        | eive Accepta  | ance Filter 3 | 3 Extended    | dentifier<5: | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1RXF4SID  | 0320  | _           | _   | _             |               |              |        | Receive A | cceptance  | Filter 4 Stand | dard Identi    | fier<10:0>   | •           |               | •                   | _     | EXIDE   | 000u uuuu uuuu uu0u |
| C1RXF4EIDH | 0322  | _           |   | _             | _             |              |        |           | Rece       | ive Acceptanc  | e Filter 4 B   | Extended l   | dentifier<1 | 7:6>          |                     | 1     |         | 0000 uuuu uuuu uuuu |
| C1RXF4EIDL | 0324  | Rece        | eive Accepta  | ance Filter 4 | 4 Extended    | dentifier<5: | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     |         | uuuu uu00 0000 0000 |
| C1RXF5SID  | 0328  | _           | _   | _             |               |              |        | Receive A | cceptance  | Filter 5 Stand | dard Identi    | fier<10:0>   | •           |               | •                   | _     | EXIDE   | 000u uuuu uuuu uu0u |
| C1RXF5EIDH | 032A  | _           |   | _             | _             |              |        |           | Rece       | ive Acceptanc  | e Filter 5 B   | Extended l   | dentifier<1 | 7:6>          |                     |       |         | 0000 uuuu uuuu uuuu |
| C1RXF5EIDL | 032C  | Rece        | eive Accepta  | ance Filter 5 | 5 Extended    | dentifier<5: | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1RXM0SID  | 0330  | _           | _   | _             |               |              |        | Receive A | cceptance  | Mask 0 Stand   | dard Identi    | fier<10:0>   |             |               | •                   | _     | MIDE    | 000u uuuu uuuu uu0u |
| C1RXM0EIDH | 0332  | _           |   | _             | _             |              |        |           | Recei      | ive Acceptanc  | e Mask 0       | Extended I   | dentifier<  | 17:6>         |                     |       |         | 0000 uuuu uuuu uuuu |
| C1RXM0EIDL | 0334  | Rece        | eive Accepta  | ance Mask     | 0 Extended    | Identifier<5 | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1RXM1SID  | 0338  | _           | _   | _             |               |              |        | Receive A | cceptance  | Mask 1 Stand   | dard Identi    | fier<10:0>   | •           |               | •                   | _     | MIDE    | 000u uuuu uuuu uu0u |
| C1RXM1EIDH | 033A  | _           |   | _             | _             |              |        |           | Recei      | ive Acceptanc  | e Mask 1       | Extended I   | dentifier<  | 17:6>         |                     |       |         | 0000 uuuu uuuu uuuu |
| C1RXM1EIDL | 033C  | Rece        | eive Accepta  | ance Mask     | 1 Extended    | Identifier<5 | :0>    | _         | _          | _              | _              | _            | _           | _             | _                   | _     | _       | uuuu uu00 0000 0000 |
| C1TX2SID   | 0340  | Trans       | smit Buffer 2                                       | 2 Standard    | Identifier<10 | ):6>         | _      | _         | _          | Т              | ransmit Bu     | uffer 2 Star | dard Iden   | tifier<5:0>   | •                   | SRR   | TXIDE   | uuuu u000 uuuu uuuu |
| C1TX2EID   | 0342  | Transmit B  | uffer 2 Exter                                       | nded Identif  | fier<17:14>   | _            | _      | _         | _          |                | Tra            | nsmit Buff   | er 2 Exter  | ded Identifie | r<13:6>             |       |         | uuuu 0000 uuuu uuuu |
| C1TX2DLC   | 0344  |             | Transmit B  | uffer 2 Exte  | ended Identi  | fier<5:0>    |        | TXRTR     | TXRB1      | TXRB0          |                | DLO          | C<3:0>      |               | _                   | _     | _       | uuuu uuuu uuuu u000 |
| C1TX2B1    | 0346  |             |   | Tra           | ansmit Buffe  | r 2 Byte 1   |        | •         | •          |                |                | Trai         | nsmit Buff  | er 2 Byte 0   | •                   |       |         | uuuu uuuu uuuu uuuu |
| C1TX2B2    | 0348  |             |   | Tra           | ansmit Buffe  | r 2 Byte 3   |        |           |            |                |                | Trai         | nsmit Buff  | er 2 Byte 2   |                     |       |         | uuuu uuuu uuuu uuuu |
| C1TX2B3    | 034A  |             | Transmit Buffer 2 Byte 5                            |               |               |              |        |           |            |                |                | Trai         | nsmit Buff  | er 2 Byte 4   |                     |       |         | uuuu uuuu uuuu uuuu |
| C1TX2B4    | 034C  |             |   | Tra           | ansmit Buffe  | r 2 Byte 7   |        |           |            |                |                | Trai         | nsmit Buff  | er 2 Byte 6   |                     |       |         | uuuu uuuu uuuu uuuu |
| C1TX2CON   | 034E  | _           | _   | _             | _             | _            | _      | _         | _          | _              | TXABT          | TXLARB       | TXERR       | TXREQ         | _                   | TXPR  | RI<1:0> | 0000 0000 0000 0000 |
| C1TX1SID   | 0350  | Tran        | smit Buffer 1                                       | 1 Standard    | Identifier<10 | ):6>         | _      | _         | _          | Т              | ransmit Bu     | uffer 1 Star | dard Iden   | tifier<5:0>   | •                   | SRR   | TXIDE   | uuuu u000 uuuu uuuu |
| C1TX1EID   | 0352  | Transmit Bu | uffer 1 Exter                                       | nded Identif  | fier<17:14>   | _            |        | Tra       | nsmit Buff | er 1 Exter     | ided Identifie | r<13:6>      | •           | •             | uuuu 0000 uuuu uuuu |       |         |                     |
| C1TX1DLC   | 0354  |             | Transmit Buffer 1 Extended Identifier<5:0> TXRTR TX |               |               |              |        |           | TXRB1      | TXRB0          |                | DLO          | C<3:0>      |               | _                   | _     | _       | uuuu uuuu uuuu u000 |

**Legend:** u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

DS70138G-page 119

TABLE 17-1: dsPIC30F4013 CAN1 REGISTER MAP<sup>(1)</sup> (CONTINUED)

| .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, |       | 4000         | 00.0          | <b>O</b> 7   |              |            | . , , , | • |             |                                     |             |              |            |                 |         |          |         |         |           |         |
|---|-------|--------------|---------------|--------------|--------------|------------|---------|---|-------------|-------------------------------------|-------------|--------------|------------|-----------------|---------|----------|---------|---------|-----------|---------|
| SFR Name                                | Addr. | Bit 15       | Bit 14        | Bit 13       | Bit 12       | Bit 11     | Bit 10  | Bit 9                                   | Bit 8       | Bit 7                               | Bit 6       | Bit 5        | Bit 4      | Bit 3           | Bit 2   | Bit 1    | Bit 0   |         | Reset Sta | ite     |
| C1TX1B1                                 | 0356  |              |               | Tra          | nsmit Buffe  | r 1 Byte 1 |         |   |             |                                     |             | Tra          | nsmit Buff | er 1 Byte 0     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX1B2                                 | 0358  |              |               | Tra          | nsmit Buffe  | r 1 Byte 3 |         |   |             |                                     |             | Tra          | nsmit Buff | er 1 Byte 2     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX1B3                                 | 035A  |              |               | Tra          | nsmit Buffe  | r 1 Byte 5 |         |   |             |                                     |             | Tra          | nsmit Buff | er 1 Byte 4     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX1B4                                 | 035C  |              |               | Tra          | nsmit Buffe  | r 1 Byte 7 |         |   |             |                                     |             | Tra          | nsmit Buff | er 1 Byte 6     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX1CON                                | 035E  | 1            |               |              | I            | _          | -       | _                                       | _           | _                                   | TXABT       | TXLARB       | TXERR      | TXREQ           |         | TXPR     | RI<1:0> | 0000    | 0000 00   | 00 0000 |
| C1TX0SID                                | 0360  | Tran         | smit Buffer ( | ) Standard I | dentifier<10 | ):6>       | -       | _                                       | _           | Tr                                  | ransmit Bu  | uffer 0 Star | idard Iden | tifier <5:0>    |         | SRR      | TXIDE   | uuuu    | u000 uu   | uu uuuu |
| C1TX0EID                                | 0362  | Transmit Bu  | uffer 0 Exten | ded Identifi | er <17:14>   | _          | -       | _                                       | _           |                                     | Tra         | ansmit Buff  | er 0 Exter | nded Identifier | <13:6>  |          |         | uuuu    | 0000 uu   | uu uuuu |
| C1TX0DLC                                | 0364  |              | Transmit B    | uffer 0 Exte | nded Identi  | fier<5:0>  |         | TXRTR                                   | TXRB1       | TXRB0                               |             | DL           | C<3:0>     |                 |         | _        | _       | uuuu    | uuuu uu   | uu u000 |
| C1TX0B1                                 | 0366  |              |               | Tra          | nsmit Buffe  | r 0 Byte 1 |         |   |             |                                     |             | Tra          | nsmit Buff | er 0 Byte 0     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX0B2                                 | 0368  |              |               | Tra          | nsmit Buffe  | r 0 Byte 3 |         |   |             |                                     |             | Tra          | nsmit Buff | er 0 Byte 2     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX0B3                                 | 036A  |              |               | Tra          | nsmit Buffe  | r 0 Byte 5 |         |   |             |                                     |             | Tra          | nsmit Buff | er 0 Byte 4     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX0B4                                 | 036C  |              |               | Tra          | nsmit Buffe  | r 0 Byte 7 |         |   |             |                                     |             | Tra          | nsmit Buff | er 0 Byte 6     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1TX0CON                                | 036E  | _            |               |              |              |            |         |   |             | _                                   | TXABT       | TXLARB       | TXERR      | TXREQ           | _       | TXPR     | RI<1:0> | 0000    | 0000 00   | 00 0000 |
| C1RX1SID                                | 0370  | _            |               | _            |              |            |         | Rece                                    | eive Buffer | 1 Standard Id                       | lentifier<1 | 0:0>         |            |                 |         | SRR      | RXIDE   | 000u    | uuuu uu   | uu uuuu |
| C1RX1EID                                | 0372  | _            | _             | _            |              |            |         | Receive Buffe                           | r 1 Extend  | ded Identifi                        | er <17:6>   |              |            |                 |         | 0000     | uuuu uu | uu uuuu |           |         |
| C1RX1DLC                                | 0374  |              | Receive B     | RXRB1        | _            | _          | _       | RXRB0                                   |             | DLC<3                               | 3:0>        |              | uuuu       | uuuu 00         | 0u uuuu |          |         |         |           |         |
| C1RX1B1                                 | 0376  |              |               | Re           | ceive Buffe  | r 1 Byte 1 |         |   |             |                                     |             | Re           | ceive Buff | er 1 Byte 0     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX1B2                                 | 0378  |              |               | Re           | ceive Buffe  | r 1 Byte 3 |         |   |             |                                     |             | Re           | ceive Buff | er 1 Byte 2     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX1B3                                 | 037A  |              |               | Re           | ceive Buffe  | r 1 Byte 5 |         |   |             |                                     |             | Re           | ceive Buff | er 1 Byte 4     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX1B4                                 | 037C  |              |               | Re           | ceive Buffe  | r 1 Byte 7 |         |   |             |                                     |             | Re           | ceive Buff | er 1 Byte 6     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX1CON                                | 037E  | _            | _             | _            | _            | _          | _       | _                                       | _           | RXFUL                               | _           | _            | _          | RXRTRRO         | F       | ILHIT<2: | 0>      | 0000    | 0000 00   | 00 0000 |
| C1RX0SID                                | 0380  |              |               |              |              | •          |         | Rece                                    | eive Buffer | 0 Standard Id                       | lentifier<1 | 0:0>         | •          |                 |         | SRR      | RXIDE   | 000u    | uuuu uu   | uu uuuu |
| C1RX0EID                                | 0382  |              |               |              | _            |            |         |   |             | Receive Buffe                       | er 0 Extend | ded Identif  | er<17:6>   |                 |         |          | •       | 0000    | uuuu uu   | uu uuuu |
| C1RX0DLC                                | 0384  |              | Receive B     | uffer 0 Exte | nded Identif | ier<5:0>   |         | RXRTR                                   | RXRB1       | _                                   | _           | _            | RXRB0      |                 | DLC<3   | 3:0>     |         | uuuu    | uuuu 00   | 0u uuuu |
| C1RX0B1                                 | 0386  |              |               | Re           | ceive Buffe  | r 0 Byte 1 |         |   |             |                                     |             | Re           | ceive Buff | er 0 Byte 0     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX0B2                                 | 0388  |              |               | Re           | ceive Buffe  | r 0 Byte 3 |         |   |             |                                     |             | Re           | ceive Buff | er 0 Byte 2     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX0B3                                 | 038A  |              |               | Re           | ceive Buffe  | r 0 Byte 5 |         |   |             |                                     |             | Re           | ceive Buff | er 0 Byte 4     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX0B4                                 | 038C  |              |               | Re           | ceive Buffe  | r 0 Byte 7 |         |   |             |                                     |             | Re           | ceive Buff | er 0 Byte 6     |         |          |         | uuuu    | uuuu uu   | uu uuuu |
| C1RX0CON                                | 038E  | -            | _             | _            | _            | _          | _       | _                                       | _           | RXFUL                               | _           | _            | _          | RXRTRRO         | DBEN    | JTOFF    | FILHIT0 | 0000    | 0000 00   | 00 0000 |
| C1CTRL                                  | 0390  | CANCAP       | _             | CSIDL        | ABAT         | CANCKS     | R       | EQOP<2:                                 | 0>          | OPM                                 | 10DE<2:0    | )>           | _          | ICOI            | DE<2:0> |          | _       | 0000    | 0100 10   | 00 0000 |
| C1CFG1                                  | 0392  | -            | _             | _            | _            | _          | _       | _                                       | _           | SJW<1                               | :0>         |              | •          | BRP<5:0         | )>      |          |         | 0000    | 0000 00   | 00 0000 |
| C1CFG2                                  | 0394  | _            | WAKFIL        | _            | _            | _          | SE      | G2PH<2:                                 | 0>          | SEG2PHTS SAM SEG1PH<2:0> PRSEG<2:0> |             |              |            |                 | :0>     | 0u00     | 0uuu uu | uu uuuu |           |         |
| C1INTF                                  | 0396  | RX00VR       | RX10VR        | TXBO         | TXEP         | RXEP       | TXWAR   | RXWAR                                   | EWARN       | IVRIF                               | WAKIF       | ERRIF        | TX2IF      | TX1IF           | TX0IF   | RX1IF    | RX0IF   | 0000    | 0000 00   | 00 0000 |
| C1INTE                                  | 0398  | -            | _             | _            | _            | _          | _       | _                                       | _           | IVRIE                               | WAKIE       | ERRIE        | TX2IE      | TX1IE           | TX0IE   | RX1IE    | RX0IE   | 0000    | 0000 00   | 00 0000 |
| C1EC                                    | 039A  | TERRCNT<7:0> |               |              |              |            |         |   |             |                                     | •           | •            | RERRCN     | T<7:0>          |         |          |         | 0000    | 0000 00   | 00 0000 |
| Logondi                                 |       |              | TERRCNT<7:0>  |              |              |            |         |   |             | l .                                 |             |              |            |                 |         |          |         |         |           |         |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

## 18.0 DATA CONVERTER INTERFACE (DCI) MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

#### 18.1 Module Introduction

The dsPIC30F Data Converter Interface (DCI) module allows simple interfacing of devices, such as audio coder/decoders (Codecs), A/D converters and D/A converters. The following interfaces are supported:

- Framed Synchronous Serial Transfer (single or multichannel)
- Inter-IC Sound (I2S) Interface
- · AC-Link Compliant mode

The DCI module provides the following general features:

- Programmable word size up to 16 bits
- Support for up to 16 time slots, for a maximum frame size of 256 bits
- Data buffering for up to 4 samples without CPU overhead

#### 18.2 Module I/O Pins

There are four I/O pins associated with the module. When enabled, the module controls the data direction of each of the four pins.

#### 18.2.1 CSCK PIN

The CSCK pin provides the serial clock for the DCI module. The CSCK pin may be configured as an input or output using the CSCKD control bit in the DCICON1 SFR. When configured as an output, the serial clock is provided by the dsPIC30F. When configured as an input, the serial clock must be provided by an external device.

#### 18.2.2 CSDO PIN

The serial data output (CSDO) pin is configured as an output only pin when the module is enabled. The CSDO pin drives the serial bus whenever data is to be transmitted. The CSDO pin is tri-stated or driven to '0' during CSCK periods when data is not transmitted, depending on the state of the CSDOM control bit. This allows other devices to place data on the serial bus during transmission periods not used by the DCI module.

#### 18.2.3 CSDI PIN

The serial data input (CSDI) pin is configured as an input only pin when the module is enabled.

#### 18.2.3.1 COFS PIN

The Codec Frame Synchronization (COFS) pin is used to synchronize data transfers that occur on the CSDO and CSDI pins. The COFS pin may be configured as an input or an output. The data direction for the COFS pin is determined by the COFSD control bit in the DCICON1 register.

The DCI module accesses the shadow registers while the CPU is in the process of accessing the memory mapped buffer registers.

#### 18.2.4 BUFFER DATA ALIGNMENT

Data values are always stored left justified in the buffers since most Codec data is represented as a signed 2's complement fractional number. If the received word length is less than 16 bits, the unused LSbs in the receive buffer registers are set to '0' by the module. If the transmitted word length is less than 16 bits, the unused LSbs in the transmit buffer register are ignored by the module. The word length setup is described in subsequent sections of this document.

### 18.2.5 TRANSMIT/RECEIVE SHIFT REGISTER

The DCI module has a 16-bit shift register for shifting serial data in and out of the module. Data is shifted in/out of the shift register MSb first, since audio PCM data is transmitted in signed 2's complement format.

#### 18.2.6 DCI BUFFER CONTROL

The DCI module contains a buffer control unit for transferring data between the shadow buffer memory and the serial shift register. The buffer control unit is a simple 2-bit address counter that points to word locations in the shadow buffer memory. For the receive memory space (high address portion of DCI buffer memory), the address counter is concatenated with a '0' in the MSb location to form a 3-bit address. For the transmit memory space (high portion of DCI buffer memory), the address counter is concatenated with a '1' in the MSb location.

Note:

The DCI buffer control unit always accesses the same relative location in the transmit and receive buffers, so only one address counter is provided.

**FIGURE 18-1: DCI MODULE BLOCK DIAGRAM** BCG Control bits SCKD Sample Rate CSCK Fosc/4 Generator FSD Word-Size Selection bits-Frame COFS Frame Length Selection bits Synchronization Generator DCI Mode Selection bits 16-Bit Data Bus Receive Buffer Registers w/Shadow DCI Buffer Control Unit 0 Transmit Buffer DCI Shift Register X CSDI Registers w/Shadow X CSDO

#### 18.3 DCI Module Operation

#### 18.3.1 MODULE ENABLE

The DCI module is enabled or disabled by setting/ clearing the DCIEN control bit in the DCICON1 SFR. Clearing the DCIEN control bit has the effect of resetting the module. In particular, all counters associated with CSCK generation, Frame Sync, and the DCI buffer control unit are reset.

The DCI clocks are shut down when the DCIEN bit is cleared

When enabled, the DCI controls the data direction for the four I/O pins associated with the module. The port, LAT and TRIS register values for these I/O pins are overridden by the DCI module when the DCIEN bit is set.

It is also possible to override the CSCK pin separately when the bit clock generator is enabled. This permits the bit clock generator to operate without enabling the rest of the DCI module.

#### 18.3.2 WORD-SIZE SELECTION BITS

The WS<3:0> word-size selection bits in the DCICON2 SFR determine the number of bits in each DCI data word. Essentially, the WS<3:0> bits determine the counting period for a 4-bit counter clocked from the CSCK signal.

Any data length, up to 16 bits, may be selected. The value loaded into the WS<3:0> bits is one less the desired word length. For example, a 16-bit data word size is selected when WS<3:0> = 1111.

Note:

These WS<3:0> control bits are used only in the Multichannel and I<sup>2</sup>S modes. These bits have no effect in AC-Link mode since the data slot sizes are fixed by the protocol.

#### 18.3.3 FRAME SYNC GENERATOR

The Frame Sync generator (COFSG) is a 4-bit counter that sets the frame length in data words. The Frame Sync generator is incremented each time the word-size counter is reset (refer to **Section 18.3.2** "Word-Size **Selection Bits**"). The period for the Frame Synchronization generator is set by writing the COFSG<3:0> control bits in the DCICON2 SFR. The COFSG period in clock cycles is determined by the following formula:

#### **EQUATION 18-1: COFSG PERIOD**

Frame Length = Word Length • (FSG Value + 1)

Frame lengths, up to 16 data words, may be selected. The frame length in CSCK periods can vary up to a maximum of 256 depending on the word size that is selected.

Note:

The COFSG control bits have no effect in AC-Link mode since the frame length is set to 256 CSCK periods by the protocol.

### 18.3.4 FRAME SYNC MODE CONTROL BITS

The type of Frame Sync signal is selected using the Frame Synchronization mode control bits (COFSM<1:0>) in the DCICON1 SFR. The following operating modes can be selected:

- Multichannel mode
- I<sup>2</sup>S mode
- AC-Link mode (16-bit)
- AC-Link mode (20-bit)

The operation of the COFSM control bits depends on whether the DCI module generates the Frame Sync signal as a master device, or receives the Frame Sync signal as a slave device.

The master device in a DSP/Codec pair is the device that generates the Frame Sync signal. The Frame Sync signal initiates data transfers on the CSDI and CSDO pins and usually has the same frequency as the data sample rate (COFS).

The DCI module is a Frame Sync master if the COFSD control bit is cleared and is a Frame Sync slave if the COFSD control bit is set.

### 18.3.5 MASTER FRAME SYNC OPERATION

When the DCI module is operating as a Frame Sync master device (COFSD = 0), the COFSM mode bits determine the type of Frame Sync pulse that is generated by the Frame Sync generator logic.

A new COFS signal is generated when the Frame Sync generator resets to '0'.

In the Multichannel mode, the Frame Sync pulse is driven high for the CSCK period to initiate a data transfer. The number of CSCK cycles between successive Frame Sync pulses depends on the word size and Frame Sync generator control bits. A timing diagram for the Frame Sync signal in Multichannel mode is shown in Figure 18-2.

In the AC-Link mode of operation, the Frame Sync signal has a fixed period and duty cycle. The AC-Link Frame Sync signal is high for 16 CSCK cycles and is low for 240 CSCK cycles. A timing diagram with the timing details at the start of an AC-Link frame is shown in Figure 18-3.

In the I<sup>2</sup>S mode, a Frame Sync signal having a 50% duty cycle is generated. The period of the I<sup>2</sup>S Frame Sync signal in CSCK cycles is determined by the word

size and Frame Sync generator control bits. A new I<sup>2</sup>S data transfer boundary is marked by a high-to-low or a low-to-high transition edge on the COFS pin.

#### 18.3.6 SLAVE FRAME SYNC OPERATION


When the DCI module is operating as a Frame Sync slave (COFSD = 1), data transfers are controlled by the Codec device attached to the DCI module. The COFSM control bits control how the DCI module responds to incoming COFS signals.

In the Multichannel mode, a new data frame transfer begins one CSCK cycle after the COFS pin is sampled high (see Figure 18-2). The pulse on the COFS pin resets the Frame Sync generator logic. In the I<sup>2</sup>S mode, a new data word is transferred one CSCK cycle after a low-to-high or a high-to-low transition is sampled on the COFS pin. A rising or falling edge on the COFS pin resets the Frame Sync generator logic.


In the AC-Link mode, the tag slot and subsequent data slots for the next frame is transferred one CSCK cycle after the COFS pin is sampled high.

The COFSG and WS bits must be configured to provide the proper frame length when the module is operating in the Slave mode. Once a valid Frame Sync pulse has been sampled by the module on the COFS pin, an entire data frame transfer takes place. The module will not respond to further Frame Sync pulses until the data frame transfer has completed.


#### FIGURE 18-2: FRAME SYNC TIMING, MULTICHANNEL MODE



#### FIGURE 18-3: FRAME SYNC TIMING, AC-LINK START-OF-FRAME



#### FIGURE 18-4: I<sup>2</sup>S INTERFACE FRAME SYNC TIMING



#### 18.3.7 BIT CLOCK GENERATOR

The DCI module has a dedicated 12-bit time base that produces the bit clock. The bit clock rate (period) is set by writing a non-zero 12-bit value to the BCG<11:0> control bits in the DCICON3 SFR.

When the BCG<11:0> bits are set to zero, the bit clock is disabled. If the BCG<11:0> bits are set to a non-zero value, the bit clock generator is enabled. These bits should be set to '0' and the CSCKD bit set to '1' if the serial clock for the DCI is received from an external device

The formula for the bit clock frequency is given in Equation 18-2.

#### **EQUATION 18-2: BIT CLOCK FREQUENCY**

$$FBCK = \frac{FCY}{2 \bullet (BCG + 1)}$$

The required bit clock frequency is determined by the system sampling rate and frame size. Typical bit clock frequencies range from 16x to 512x the converter sample rate depending on the data converter and the communication protocol that is used.

To achieve bit clock frequencies associated with common audio sampling rates, the user needs to select a crystal frequency that has an 'even' binary value. Examples of such crystal frequencies are listed in Table 18-1.

TABLE 18-1: DEVICE FREQUENCIES FOR COMMON CODEC CSCK FREQUENCIES

| Fs (kHz) | Fcsck/Fs | Fcsck (MHz) <sup>(1)</sup> | Fosc (MHz) | PLL | Fcy (MIPS) | BCG <sup>(2)</sup> |
|----------|----------|----------------------------|------------|-----|------------|--------------------|
| 8        | 256      | 2.048                      | 8.192      | 4   | 8.192      | 1                  |
| 12       | 256      | 3.072                      | 6.144      | 8   | 12.288     | 1                  |
| 32       | 32       | 1.024                      | 8.192      | 8   | 16.384     | 7                  |
| 44.1     | 32       | 1.4112                     | 5.6448     | 8   | 11.2896    | 3                  |
| 48       | 64       | 3.072                      | 6.144      | 16  | 24.576     | 3                  |

- Note 1: When the CSCK signal is applied externally (CSCKD = 1), the BCG<11:0> bits have no effect on the operation of the DCI module.
  - 2: When the CSCK signal is applied externally (CSCKD = 1), the external clock high and low times must meet the device timing requirements.

### 18.3.8 SAMPLE CLOCK EDGE CONTROL BIT

The sample clock edge (CSCKE) control bit determines the sampling edge for the CSCK signal. If the CSCK bit is cleared (default), data is sampled on the falling edge of the CSCK signal. The AC-Link protocols and most multichannel formats require that data be sampled on the falling edge of the CSCK signal. If the CSCK bit is set, data is sampled on the rising edge of CSCK. The I<sup>2</sup>S protocol requires that data be sampled on the rising edge of the CSCK signal.

### 18.3.9 DATA JUSTIFICATION CONTROL BIT

In most applications, the data transfer begins one CSCK cycle after the COFS signal is sampled active. This is the default configuration of the DCI module. An alternate data alignment can be selected by setting the DJST control bit in the DCICON1 SFR. When DJST = 1, data transfers begin during the same CSCK cycle when the COFS signal is sampled active.

#### 18.3.10 TRANSMIT SLOT ENABLE BITS

The TSCON SFR has control bits that are used to enable up to 16 time slots for transmission. These control bits are the TSE<15:0> bits. The size of each time slot is determined by the WS<3:0> word-size selection bits and can vary up to 16 bits.

If a transmit time slot is enabled via one of the TSE bits (TSEx = 1), the contents of the current transmit shadow buffer location is loaded into the CSDO Shift register and the DCI buffer control unit is incremented to point to the next location.

During an unused transmit time slot, the CSDO pin drives '0's or is tri-stated during all disabled time slots depending on the state of the CSDOM bit in the DCICON1 SFR.

The data frame size in bits is determined by the chosen data word size and the number of data word elements in the frame. If the chosen frame size has less than 16 elements, the additional slot enable bits have no effect.

Each transmit data word is written to the 16-bit transmit buffer as left justified data. If the selected word size is less than 16 bits, then the LSbs of the transmit buffer memory have no effect on the transmitted data. The user should write '0's to the unused LSbs of each transmit buffer location.

#### 18.3.11 RECEIVE SLOT ENABLE BITS

The RSCON SFR contains control bits that are used to enable up to 16 time slots for reception. These control bits are the RSE<15:0> bits. The size of each receive time slot is determined by the WS<3:0> word-size selection bits and can vary from 1 to 16 bits.

If a receive time slot is enabled via one of the RSE bits (RSEx = 1), the shift register contents are written to the current DCI receive shadow buffer location and the buffer control unit is incremented to point to the next buffer location.

Data is not packed in the receive memory buffer locations if the selected word size is less than 16 bits. Each received slot data word is stored in a separate 16-bit buffer location. Data is always stored in a left justified format in the receive memory buffer.

### 18.3.12 SLOT ENABLE BITS OPERATION WITH FRAME SYNC

The TSE and RSE control bits operate in concert with the DCI Frame Sync generator. In the Master mode, a COFS signal is generated whenever the Frame Sync generator is reset. In the Slave mode, the Frame Sync generator is reset whenever a COFS pulse is received.

The TSE and RSE control bits allow up to 16 consecutive time slots to be enabled for transmit or receive. After the last enabled time slot has been transmitted/received, the DCI stops buffering data until the next occurring COFS pulse.

### 18.3.13 SYNCHRONOUS DATA TRANSFERS

The DCI buffer control unit is incremented by one word location whenever a given time slot has been enabled for transmission or reception. In most cases, data input and output transfers are synchronized, which means that a data sample is received for a given channel at the same time a data sample is transmitted. Therefore, the transmit and receive buffers are filled with equal amounts of data when a DCI interrupt is generated.

In some cases, the amount of data transmitted and received during a data frame may not be equal. As an example, assume a two-word data frame is used. Furthermore, assume that data is only received during slot #0 but is transmitted during slot #0 and slot #1. In this case, the buffer control unit counter would be incremented twice during a data frame but only one receive register location would be filled with data.

#### 18.3.14 BUFFER LENGTH CONTROL

The amount of data that is buffered between interrupts is determined by the buffer length (BLEN<1:0>) control bits in the DCICON2 SFR. The size of the transmit and receive buffers may be varied from 1 to 4 data words using the BLEN control bits. The BLEN control bits are compared to the current value of the DCI buffer control unit address counter. When the two LSbs of the DCI address counter match the BLEN<1:0> value, the buffer control unit is reset to '0'. In addition, the contents of the receive shadow registers are transferred to the receive buffer registers and the contents of the transmit buffer registers are transferred to the transmit shadow registers.

### 18.3.15 BUFFER ALIGNMENT WITH DATA FRAMES

There is no direct coupling between the position of the AGU Address Pointer and the data frame boundaries. This means that there is an implied assignment of each transmit and receive buffer that is a function of the BLEN control bits and the number of enabled data slots via the TSE and RSE control bits.

As an example, assume that a 4-word data frame is chosen and that we want to transmit on all four time slots in the frame. This configuration would be established by setting the TSE0, TSE1, TSE2, and TSE3 control bits in the TSCON SFR. With this module setup, the TXBUF0 register would be naturally assigned to slot #0, the TXBUF1 register would be naturally assigned to slot #1, and so on.

Note:

When more than four time slots are active within a data frame, the user code must keep track of which time slots are to be read/written at each interrupt. In some cases, the alignment between transmit/receive buffers and their respective slot assignments could be lost. Examples of such cases include an emulation breakpoint or a hardware trap. In these situations, the user should poll the SLOT status bits to determine what data should be loaded into the buffer registers to resynchronize the software with the DCI module.

#### 18.3.16 TRANSMIT STATUS BITS

There are two transmit status bits in the DCISTAT SFR.

The TMPTY bit is set when the contents of the transmit buffer registers are transferred to the transmit shadow registers. The TMPTY bit may be polled in software to determine when the transmit buffer registers may be written. The TMPTY bit is cleared automatically by the hardware when a write to one of the four transmit buffers occurs.

The TUNF bit is read-only and indicates that a transmit underflow has occurred for at least one of the transmit buffer registers that is in use. The TUNF bit is set at the time the transmit buffer registers are transferred to the transmit shadow registers. The TUNF status bit is cleared automatically when the buffer register that underflowed is written by the CPU.

Note:

The transmit status bits only indicate status for buffer locations that are used by the module. If the buffer length is set to less than four words, for example, the unused buffer locations do not affect the transmit status bits.

#### 18.3.17 RECEIVE STATUS BITS

There are two receive status bits in the DCISTAT SFR.

The RFUL status bit is read-only and indicates that new data is available in the receive buffers. The RFUL bit is cleared automatically when all receive buffers in use have been read by the CPU.

The ROV status bit is read-only and indicates that a receive overflow has occurred for at least one of the receive buffer locations. A receive overflow occurs when the buffer location is not read by the CPU before new data is transferred from the shadow registers. The ROV status bit is cleared automatically when the buffer register that caused the overflow is read by the CPU.

When a receive overflow occurs for a specific buffer location, the old contents of the buffer are overwritten.

Note:

The receive status bits only indicate status for buffer locations that are used by the module. If the buffer length is set to less than four words, for example, the unused buffer locations do not affect the transmit status bits.

#### 18.3.18 SLOT STATUS BITS

The SLOT<3:0> status bits in the DCISTAT SFR indicate the current active time slot. These bits correspond to the value of the Frame Sync generator counter. The user may poll these status bits in software when a DCI interrupt occurs to determine what time slot data was last received and which time slot data should be loaded into the TXBUF registers.

#### 18.3.19 CSDO MODE BIT

The CSDOM control bit controls the behavior of the CSDO pin during unused transmit slots. A given transmit time slot is unused if it's corresponding TSEx bit in the TSCON SFR is cleared.

If the CSDOM bit is cleared (default), the CSDO pin is low during unused time slot periods. This mode is used when there are only two devices attached to the serial bus.

If the CSDOM bit is set, the CSDO pin is tri-stated during unused time slot periods. This mode allows multiple devices to share the same CSDO line in a multichannel application. Each device on the CSDO line is configured so that it only transmits data during specific time slots. No two devices transmit data during the same time slot.

#### 18.3.20 DIGITAL LOOPBACK MODE

Digital Loopback mode is enabled by setting the DLOOP control bit in the DCICON1 SFR. When the DLOOP bit is set, the module internally connects the CSDO signal to CSDI. The actual data input on the CSDI I/O pin is ignored in Digital Loopback mode.

#### 18.3.21 UNDERFLOW MODE CONTROL BIT

When an underflow occurs, one of two actions may occur depending on the state of the Underflow mode (UNFM) control bit in the DCICON1 SFR. If the UNFM bit is cleared (default), the module transmits '0's on the CSDO pin during the active time slot for the buffer location. In this operating mode, the Codec device attached to the DCI module is simply fed digital 'silence'. If the UNFM control bit is set, the module transmits the last data written to the buffer location. This operating mode permits the user to send continuous data to the Codec device without consuming CPU overhead.

#### 18.4 DCI Module Interrupts

The frequency of DCI module interrupts is dependent on the BLEN<1:0> control bits in the DCICON2 SFR. An interrupt to the CPU is generated each time the set buffer length has been reached and a shadow register transfer takes place. A shadow register transfer is defined as the time when the previously written TXBUF values are transferred to the transmit shadow registers and new received values in the receive shadow registers are transferred into the RXBUF registers.

#### 18.5 DCI Module Operation During CPU Sleep and Idle Modes

### 18.5.1 DCI MODULE OPERATION DURING CPU SLEEP MODE

The DCI module has the ability to operate while in Sleep mode and wake the CPU when the CSCK signal is supplied by an external device (CSCKD = 1). The DCI module generates an asynchronous interrupt when a DCI buffer transfer has completed and the CPU is in Sleep mode.

### 18.5.2 DCI MODULE OPERATION DURING CPU IDLE MODE

If the DCISIDL control bit is cleared (default), the module continues to operate normally even in Idle mode. If the DCISIDL bit is set, the module halts when Idle mode is asserted.

#### 18.6 AC-Link Mode Operation

The AC-Link protocol is a 256-bit frame with one 16-bit data slot, followed by twelve 20-bit data slots. The DCI module has two operating modes for the AC-Link protocol. These operating modes are selected by the COFSM<1:0> control bits in the DCICON1 SFR. The first AC-Link mode is called '16-bit AC-Link mode' and is selected by setting COFSM<1:0> = 10. The second AC-Link mode is called '20-bit AC-Link mode' and is selected by setting COFSM<1:0> = 11.

#### 18.6.1 16-BIT AC-LINK MODE

In the 16-bit AC-Link mode, data word lengths are restricted to 16 bits. Note that this restriction only affects the 20-bit data time slots of the AC-Link protocol. For received time slots, the incoming data is simply truncated to 16 bits. For outgoing time slots, the 4 LSbs of the data word are set to '0' by the module. This truncation of the time slots limits the A/D and DAC data to 16 bits but permits proper data alignment in the TXBUF and RXBUF registers. Each RXBUF and TXBUF register contains one data time slot value.

#### 18.6.2 20-BIT AC-LINK MODE

The 20-bit AC-Link mode allows all bits in the data time slots to be transmitted and received but does not maintain data alignment in the TXBUF and RXBUF registers.

The 20-bit AC-Link mode functions similar to the Multichannel mode of the DCI module, except for the duty cycle of the Frame Synchronization signal. The AC-Link Frame Synchronization signal should remain high for 16 CSCK cycles and should be low for the following 240 cycles.

The 20-bit mode treats each 256-bit AC-Link frame as sixteen, 16-bit time slots. In the 20-bit AC-Link mode, the module operates as if COFSG<3:0> = 1111 and WS<3:0> = 1111. The data alignment for 20-bit data slots is ignored. For example, an entire AC-Link data frame can be transmitted and received in a packed fashion by setting all bits in the TSCON and RSCON SFRs. Since the total available buffer length is 64 bits, it would take 4 consecutive interrupts to transfer the AC-Link frame. The application software must keep track of the current AC-Link frame segment.

#### 18.7 I<sup>2</sup>S Mode Operation

The DCI module is configured for I<sup>2</sup>S mode by writing a value of '01' to the COFSM<1:0> control bits in the DCICON1 SFR. When operating in the I<sup>2</sup>S mode, the DCI module generates Frame Synchronization signals with a 50% duty cycle. Each edge of the Frame Synchronization signal marks the boundary of a new data word transfer.

The user must also select the frame length and data word size using the COFSG and WS control bits in the DCICON2 SFR.

### 18.7.1 I<sup>2</sup>S FRAME AND DATA WORD LENGTH SELECTION

The WS and COFSG control bits are set to produce the period for one half of an I<sup>2</sup>S data frame. That is, the frame length is the total number of CSCK cycles required for a left or a right data word transfer.

The BLEN bits must be set for the desired buffer length. Setting BLEN<1:0> = 01 produces a CPU interrupt, once per  $I^2$ S frame.

#### 18.7.2 I<sup>2</sup>S DATA JUSTIFICATION

As per the I<sup>2</sup>S specification, a data word transfer, by default, begins one CSCK cycle after a transition of the WS signal. A 'MSb left justified' option can be selected using the DJST control bit in the DCICON1 SFR.

If DJST = 1, the I<sup>2</sup>S data transfers are MSb left justified. The MSb of the data word is presented on the CSDO pin during the same CSCK cycle as the rising or falling edge of the COFS signal. The CSDO pin is tri-stated after the data word has been sent.

TABLE 18-2: dsPIC30F3014/4013 DCI REGISTER MAP<sup>(1)</sup>

| SFR Name | Addr. | Bit 15 | Bit 14                          | Bit 13  | Bit 12                         | Bit 11 | Bit 10    | Bit 9      | Bit 8       | Bit 7     | Bit 6  | Bit 5 | Bit 4 | Bit 3 | Bit 2    | Bit 1   | Bit 0    | Res      | et State | ,    |
|----------|-------|--------|---------------------------------|---------|--------------------------------|--------|-----------|------------|-------------|-----------|--------|-------|-------|-------|----------|---------|----------|----------|----------|------|
| DCICON1  | 0240  | DCIEN  | _                               | DCISIDL | _                              | DLOOP  | CSCKD     | CSCKE      | COFSD       | UNFM      | CSDOM  | DJST  | _     | _     | _        | COFSM1  | COFSM0   | 0000 000 | 0 0000   | 0000 |
| DCICON2  | 0242  | _      | _                               | 1       | _                              | BLEN1  | BLEN0     | _          |             | COFS      | G<3:0> |       | _     |       | ١        | VS<3:0> |          | 0000 000 | 0 0000   | 0000 |
| DCICON3  | 0244  | _      | _                               | 1       | _                              |        | BCG<11:0> |            |             |           |        |       |       |       | 0000 000 | 0 0000  | 0000     |          |          |      |
| DCISTAT  | 0246  | _      |                                 | I       | _                              | SLOT3  | SLOT2     | SLOT1      | SLOT0       |           | I      | _     | _     | ROV   | RFUL     | TUNF    | TMPTY    | 0000 000 | 0 0000   | 0000 |
| TSCON    | 0248  | TSE15  | TSE14                           | TSE13   | TSE12                          | TSE11  | TSE10     | TSE9       | TSE8        | TSE7      | TSE6   | TSE5  | TSE4  | TSE3  | TSE2     | TSE1    | TSE0     | 0000 000 | 0 0000   | 0000 |
| RSCON    | 024C  | RSE15  | RSE14                           | RSE13   | RSE12                          | RSE11  | RSE10     | RSE9       | RSE8        | RSE7      | RSE6   | RSE5  | RSE4  | RSE3  | RSE2     | RSE1    | RSE0     | 0000 000 | 0 0000   | 0000 |
| RXBUF0   | 0250  |        |                                 |         | Receive Buffer 0 Data Register |        |           |            |             |           |        |       |       |       |          |         | 0000 000 | 0 0000   | 0000     |      |
| RXBUF1   | 0252  |        |                                 |         |                                |        |           | Receive E  | Buffer 1 Da | ata Regis | ter    |       |       |       |          |         |          | 0000 000 | 0 0000   | 0000 |
| RXBUF2   | 0254  |        |                                 |         |                                |        |           | Receive E  | Buffer 2 Da | ata Regis | ter    |       |       |       |          |         |          | 0000 000 | 0 0000   | 0000 |
| RXBUF3   | 0256  |        |                                 |         |                                |        |           | Receive E  | Buffer 3 Da | ata Regis | ter    |       |       |       |          |         |          | 0000 000 | 0 0000   | 0000 |
| TXBUF0   | 0258  |        |                                 |         |                                |        |           | Transmit E | Buffer 0 Da | ata Regis | ter    |       |       |       |          |         |          | 0000 000 | 0 0000   | 0000 |
| TXBUF1   | 025A  |        | Transmit Buffer 1 Data Register |         |                                |        |           |            |             |           |        |       |       |       | 0000 000 | 0 0000  | 0000     |          |          |      |
| TXBUF2   | 025C  |        | Transmit Buffer 2 Data Register |         |                                |        |           |            |             |           |        |       |       | •     | 0000 000 | 0 0000  | 0000     |          |          |      |
| TXBUF3   | 025E  |        | •                               |         |                                |        | •         | Transmit E | Buffer 3 Da | ata Regis | ter    | •     |       |       | •        |         | •        | 0000 000 | 0 0000   | 0000 |

**Legend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

## 19.0 12-BIT ANALOG-TO-DIGITAL CONVERTER (ADC) MODULE

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046).

The 12-bit Analog-to-Digital Converter (ADC) allows conversion of an analog input signal to a 12-bit digital number. This module is based on a Successive Approximation Register (SAR) architecture and provides a maximum sampling rate of 200 ksps. The A/D module has up to 16 analog inputs which are multiplexed into a sample and hold amplifier. The output of the sample and hold is the input into the converter which generates the result. The analog reference voltage is software selectable to either the device supply voltage (AVDD/AVSS) or the voltage level on the (VREF+/VREF-) pin. The A/D converter has a unique feature of being able to operate while the device is in Sleep mode with RC oscillator selection.

The A/D module has six 16-bit registers:

- A/D Control Register 1 (ADCON1)
- A/D Control Register 2 (ADCON2)
- A/D Control Register 3 (ADCON3)
- A/D Input Select Register (ADCHS)
- A/D Port Configuration Register (ADPCFG)
- A/D Input Scan Selection Register (ADCSSL)


The ADCON1, ADCON2 and ADCON3 registers control the operation of the A/D module. The ADCHS register selects the input channels to be converted. The ADPCFG register configures the port pins as analog inputs or as digital I/O. The ADCSSL register selects inputs for scanning.

Note:

The SSRC<2:0>, ASAM, SMPI<3:0>, BUFM and ALTS bits, as well as the ADCON3 and ADCSSL registers, must not be written to while ADON = 1. This would lead to indeterminate results.

The block diagram of the 12-bit A/D module is shown in Figure 19-1.

FIGURE 19-1: 12-BIT A/D FUNCTIONAL BLOCK DIAGRAM



#### 19.1 A/D Result Buffer

The module contains a 16-word, dual port read-only buffer, called ADCBUFO...ADCBUFF, to buffer the A/D results. The RAM is 12 bits wide but the data obtained is represented in one of four different 16-bit data formats. The contents of the sixteen A/D Conversion Result Buffer registers, ADCBUFO through ADCBUFF, cannot be written by user software.

#### 19.2 Conversion Operation

After the A/D module has been configured, the sample acquisition is started by setting the SAMP bit. Various sources, such as a programmable bit, timer time-outs and external events, terminate acquisition and start a conversion. When the A/D conversion is complete, the result is loaded into ADCBUFO...ADCBUFF, and the DONE bit and the A/D Interrupt Flag, ADIF, are set after the number of samples specified by the SMPI bit. The ADC module can be configured for different interrupt rates as described in Section 19.3 "Selecting the Conversion Sequence".

The following steps should be followed for doing an A/D conversion:

- 1. Configure the A/D module:
  - Configure analog pins, voltage reference and digital I/O
  - · Select A/D input channels
  - Select A/D conversion clock
  - Select A/D conversion trigger
  - Turn on A/D module
- 2. Configure A/D interrupt (if required):
  - Clear ADIF bit
  - Select A/D interrupt priority
  - Set ADIE bit (for ISR processing)
- 3. Start sampling
- 4. Wait the required acquisition time
- 5. Trigger acquisition end, start conversion:
- 6. Wait for A/D conversion to complete, by either:
  - · Waiting for the A/D interrupt, or
  - Waiting for the DONE bit to get set.
- 7. Read A/D result buffer, clear ADIF if required

#### 19.3 Selecting the Conversion Sequence

Several groups of control bits select the sequence in which the A/D connects inputs to the sample/hold channel, converts a channel, writes the buffer memory and generates interrupts.

The sequence is controlled by the sampling clocks.

The SMPI bits select the number of acquisition/conversion sequences that would be performed before an interrupt occurs. This can vary from 1 sample per interrupt to 16 samples per interrupt.

The BUFM bit splits the 16-word results buffer into two 8-word groups. Writing to the 8-word buffers is alternated on each interrupt event.

Use of the BUFM bit depends on how much time is available for moving the buffers after the interrupt.

If the processor can quickly unload a full buffer within the time it takes to acquire and convert one channel, the BUFM bit can be '0' and up to 16 conversions (corresponding to the 16 input channels) may be done per interrupt. The processor has one acquisition and conversion time to move the sixteen conversions.

If the processor cannot unload the buffer within the acquisition and conversion time, the BUFM bit should be '1'. For example, if SMPI<3:0> (ADCON2<5:2>) = 0111, then eight conversions are loaded into 1/2 of the buffer, following which an interrupt occurs. The next eight conversions are loaded into the other 1/2 of the buffer. The processor has the entire time between interrupts to move the eight conversions.

The ALTS bit can be used to alternate the inputs selected during the sampling sequence. The input multiplexer has two sets of sample inputs: MUX A and MUX B. If the ALTS bit is '0', only the MUX A inputs are selected for sampling. If the ALTS bit is '1' and SMPI<3:0> = 0000 on the first sample/convert sequence, the MUX A inputs are selected and on the next acquire/convert sequence, the MUX B inputs are selected.

The CSCNA bit (ADCON2<10>) allows the S/H input to be sequentially scanned across a selected number of analog inputs for the MUX A group. The inputs are selected by the ADCSSL register. If a particular bit in the ADCSSL register is '1', the corresponding input is selected. The inputs are always scanned from lower to higher numbered inputs, starting after each interrupt. If the number of inputs selected is greater than the number of samples taken per interrupt, the higher numbered inputs are unused.

Note:

The ADCHS, ADPCFG and ADCSSL registers allow the application to configure AN13-AN15 as analog input pins. Since these pins are not physically present on the device, conversion results from these pins read '0'.

## 19.4 Programming the Start of Conversion Trigger

The conversion trigger terminates acquisition and starts the requested conversions.

The SSRC<2:0> bits select the source of the conversion trigger. The SSRC bits provide for up to 4 alternate sources of conversion trigger.

When SSRC<2:0> = 000, the conversion trigger is under software control. Clearing the SAMP bit causes the conversion trigger.

When SSRC<2:0> = 111 (Auto-Convert mode), the conversion trigger is under A/D clock control. The SAMC bits select the number of A/D clocks between the start of acquisition and the start of conversion. This provides the fastest conversion rates on multiple channels. The SAMC bits must always be at least one clock cycle.

Other trigger sources can come from timer modules or external interrupts.

#### 19.5 Aborting a Conversion

Clearing the ADON bit during a conversion aborts the current conversion and stops the sampling sequencing until the next sampling trigger. The ADCBUF is not updated with the partially completed A/D conversion sample. That is, the ADCBUF will continue to contain the value of the last completed conversion (or the last value written to the ADCBUF register).

If clearing of the ADON bit coincides with an auto-start, the clearing has a higher priority and a new conversion does not start.

### 19.6 Selecting the ADC Conversion Clock

The ADC conversion requires 14 TAD. The source of the ADC conversion clock is software selected, using a 6-bit counter. There are 64 possible options for TAD.

### EQUATION 19-1: ADC CONVERSION CLOCK

TAD = TCY \* (0.5\*(ADCS < 5:0 > + 1))

The internal RC oscillator is selected by setting the ADRC bit.

For correct ADC conversions, the ADC conversion clock (TAD) must be selected to ensure a minimum TAD time of 334 nsec (for VDD = 5V). Refer to **Section 23.0** "**Electrical Characteristics**" for minimum TAD under other operating conditions.

Example 19-1 shows a sample calculation for the ADCS<5:0> bits, assuming a device operating speed of 30 MIPS.

# EXAMPLE 19-1: ADC CONVERSION CLOCK AND SAMPLING RATE CALCULATION

TCY = 33.33 nsec (30 MIPS)

ADCS<5:0> = 2 
$$\frac{\text{TAD}}{\text{TCY}} - 1$$
= 2 •  $\frac{334 \text{ nsec}}{33.33 \text{ nsec}} - 1$ 

Minimum TAD = 334 nsec

Therefore, Set ADCS<5:0> = 19

Actual TAD = 
$$\frac{\text{TCY}}{2}$$
 (ADCS<5:0> + 1)  
=  $\frac{33.33 \text{ nsec}}{2}$  (19 + 1)  
= 334 nsec

If SSRC<2:0> = 111 and SAMC<4:0> = 00001

Since,

Sampling Time = Acquisition Time + Conversion Time = 1 TAD + 14 TAD = 15 x 334 nsec

Therefore, Sampling Rate =  $\frac{1}{(15 \text{ x } 334 \text{ nsec})}$ =  $\sim 200 \text{ kHz}$ 

#### 19.7 ADC Speeds

The dsPIC30F 12-bit ADC specifications permit a maximum of 200 ksps sampling rate. The table below summarizes the conversion speeds for the dsPIC30F 12-bit ADC and the required operating conditions.


TABLE 19-1: 12-BIT ADC EXTENDED CONVERSION RATES

|                               | dsPIC30F 12-Bit ADC Conversion Rates |                      |                    |                 |                 |                           |  |  |  |  |  |  |  |  |
|-------------------------------|--------------------------------------|----------------------|--------------------|-----------------|-----------------|---------------------------|--|--|--|--|--|--|--|--|
| Speed                         | T <sub>AD</sub><br>Minimum           | Sampling<br>Time Min | R <sub>s</sub> Max | VDD             | Temperature     | Channels Configuration    |  |  |  |  |  |  |  |  |
| Up to 200 ksps <sup>(1)</sup> | 334 ns                               | 1 TAD                | 2.5 kΩ             | 4.5V to<br>5.5V | -40°C to +85°C  | ANX CHX ADC               |  |  |  |  |  |  |  |  |
| Up to 100<br>ksps             | 668 ns                               | 1 TAD                | 2.5 kΩ             | 3.0V to<br>5.5V | -40°C to +125°C | ANX CHX ADC  ANX OF VREF- |  |  |  |  |  |  |  |  |

Note 1: External VREF+ pins must be used for correct operation. See Figure 19-2 for recommended circuit.

Figure 19-2 depicts the recommended circuit for the conversion rates above 200 ksps. The dsPIC30F3014 is shown as an example.

FIGURE 19-2: ADC VOLTAGE REFERENCE SCHEMATIC



The configuration procedures below give the required setup values for the conversion speeds above 100 ksps.

## 19.7.1 200 ksps CONFIGURATION GUIDELINE

The following configuration items are required to achieve a 200 ksps conversion rate.

- Comply with conditions provided in Table 19-2.
- Connect external VREF+ and VREF- pins following the recommended circuit shown in Figure 19-2.
- Set SSRC<2.0> = 111 in the ADCON1 register to enable the auto-convert option.
- Enable automatic sampling by setting the ASAM control bit in the ADCON1 register.
- Write the SMPI<3.0> control bits in the ADCON2 register for the desired number of conversions between interrupts.

• Configure the ADC clock period to be:


$$\frac{1}{(14+1) \times 200,000} = 334 \text{ ns}$$

by writing to the ADCS<5:0> control bits in the ADCON3 register.

• Configure the sampling time to be 1 TAD by writing: SAMC<4:0> = 00001.

The following figure shows the timing diagram of the ADC running at 200 ksps. The TAD selection in conjunction with the guidelines described above allows a conversion speed of 200 ksps. See Example 19-1 for code example.

FIGURE 19-3: CONVERTING 1 CHANNEL AT 200 ksps, AUTO-SAMPLE START, 1 TAD SAMPLING TIME




#### 19.8 A/D Acquisition Requirements

The analog input model of the 12-bit A/D converter is shown in Figure 19-4. The total sampling time for the A/D is a function of the internal amplifier settling time and the holding capacitor charge time.

For the A/D converter to meet its specified accuracy, the Charge Holding Capacitor (CHOLD) must be allowed to fully charge to the voltage level on the analog input pin. The Source Impedance (Rs), the Interconnect Impedance (RIC) and the Internal Sampling Switch (Rss) Impedance combine to directly

affect the time required to charge the capacitor, CHOLD. The combined impedance of the analog sources must therefore be small enough to fully charge the holding capacitor within the chosen sample time. To minimize the effects of pin leakage currents on the accuracy of the A/D converter, the maximum recommended source impedance, Rs, is 2.5 k $\Omega$ . After the analog input channel is selected (changed), this sampling function must be completed prior to starting the conversion. The internal holding capacitor will be in a discharged state prior to each sample operation.

FIGURE 19-4: 12-BIT A/D CONVERTER ANALOG INPUT MODEL



#### 19.9 Module Power-Down Modes

The module has two internal power modes.

When the ADON bit is '1', the module is in Active mode; it is fully powered and functional.

When ADON is '0', the module is in Off mode. The digital and analog portions of the circuit are disabled for maximum current savings.

In order to return to the Active mode from Off mode, the user must wait for the ADC circuitry to stabilize. The time required to stabilize is specified in **Section 23.0** "Electrical Characteristics".

### 19.10 A/D Operation During CPU Sleep and Idle Modes

#### 19.10.1 A/D OPERATION DURING CPU SLEEP MODE

When the device enters Sleep mode, all clock sources to the module are shut down and stay at logic '0'.

If Sleep occurs in the middle of a conversion, the conversion is aborted. The converter does not continue with a partially completed conversion on exit from Sleep mode.

Register contents are not affected by the device entering or leaving Sleep mode.

The A/D module can operate during Sleep mode if the A/D clock source is set to RC (ADRC = 1). When the RC clock source is selected, the A/D module waits one instruction cycle before starting the conversion. This allows the SLEEP instruction to be executed which eliminates all digital switching noise from the conversion. (When the conversion sequence is complete, the DONE bit is set.)

If the A/D interrupt is enabled, the device wakes up from Sleep. If the A/D interrupt is not enabled, the A/D module is then turned off, although the ADON bit remains set.

### 19.10.2 A/D OPERATION DURING CPU IDLE MODE

The ADSIDL bit determines if the module stops or continues on Idle. If ADSIDL = 0, the module continues operation on assertion of Idle mode. If ADSIDL = 1, the module stops on Idle.

#### 19.11 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the A/D module to be turned off, and any conversion and sampling sequence is aborted. The values that are in the ADCBUF registers are not modified. The A/D Result register contains unknown data after a Power-on Reset.

#### 19.12 Output Formats

The A/D result is 12 bits wide. The data buffer RAM is also 12 bits wide. The 12-bit data can be read in one of four different formats. The FORM<1:0> bits select the format. Each of the output formats translates to a 16-bit result on the data bus. Write data is always in right-justified (integer) format.

#### FIGURE 19-5: A/D OUTPUT DATA FORMATS

| 1100KL 19-3. A/D C | OII OI DAIAI OKMAIS                     |                         |
|--------------------|---|-------------------------|
| RAM Contents:      | d11 d10 d09 d08 d07 d06                 | d05 d04 d03 d02 d01 d00 |
| Read to Bus:       |   |                         |
| Signed Fractional  |   | d01 d00 0 0 0 0         |
|                    |   |                         |
| Fractional         | d11 d10 d09 d08 d07 d06 d05 d04 d03 d02 | d01 d00 0 0 0 0         |
|                    |   |                         |
| Signed Integer     |   | d05 d04 d03 d02 d01 d00 |
|                    |   |                         |
| Integer            | 0 0 0 0 d11 d10 d09 d08 d07 d06         | d05 d04 d03 d02 d01 d00 |
|                    |   |                         |

#### 19.13 Configuring Analog Port Pins

The use of the ADPCFG and TRIS registers control the operation of the A/D port pins. The port pins that are desired as analog inputs must have their corresponding TRIS bit set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) is converted.

The A/D operation is independent of the state of the CH0SA<3:0>/CH0SB<3:0> bits and the TRIS bits.

When reading the PORT register, all pins configured as analog input channels are read as cleared.

Pins configured as digital inputs will not convert an analog input. Analog levels on any pin that is defined as a digital input (including the ANx pins) may cause the input buffer to consume current that exceeds the device specifications.

#### 19.14 Connection Considerations

The analog inputs have diodes to VDD and VSS as ESD protection. This requires that the analog input be between VDD and VSS. If the input voltage exceeds this range by greater than 0.3V (either direction), one of the diodes becomes forward biased and it may damage the device if the input current specification is exceeded.

An external RC filter is sometimes added for antialiasing of the input signal. The R component should be selected to ensure that the sampling time requirements are satisfied. Any external components connected (via high-impedance) to an analog input pin (capacitor, Zener diode, etc.) should have very little leakage current at the pin.

DS70138G-page 139

TABLE 19-2: A/D CONVERTER REGISTER MAP<sup>(1)</sup>

| Addr. | Bit 15   | Bit 14   | Bit 13   | Bit 12   | Bit 11  | Bit 10            | Bit 9 | Bit 8  | Bit 7 | Bit 6    | Bit 5       | Bit 4   | Bit 3               | Bit 2 | Bit 1               | Bit 0               | Reset State         |
|-------|--|--|--|--|---|-------------------|-------|--------|-------|----------|-------------|---|---------------------|-------|---------------------|---------------------|---------------------|
| 0280  | _  | _  | _  | _  |   |                   |       |        |       | ADC Dat  | ta Buffer 0 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0282  | _  | _  | _  | _  |   |                   |       |        |       | ADC Dat  | ta Buffer 1 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0284  | _  | _  | _  | _  |   |                   |       |        |       | ADC Dat  | ta Buffer 2 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0286  |  | I  | _  | 1  |   |                   |       |        |       | ADC Dat  | ta Buffer 3 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0288  |  | I  | _  | 1  |   |                   |       |        |       | ADC Dat  | ta Buffer 4 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 028A  |  | I  | _  | 1  |   |                   |       |        |       | ADC Dat  | ta Buffer 5 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 028C  |  | I  | _  | 1  |   | ADC Data Buffer 6 |       |        |       |          |             |   |                     |       |                     | 0000 uuuu uuuu uuuu |                     |
| 028E  |  | I  | _  | 1  |   | ADC Data Buffer 7 |       |        |       |          |             |   |                     |       | 0000 uuuu uuuu uuuu |                     |                     |
| 0290  |  | I  | _  | 1  |   | ADC Data Buffer 8 |       |        |       |          |             |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0292  |  | I  | _  | 1  |   |                   |       |        |       | ADC Dat  | ta Buffer 9 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0294  |  | I  | _  | 1  |   |                   |       |        |       | ADC Data | a Buffer 10 | )   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0296  |  | I  | _  | 1  |   |                   |       |        |       | ADC Data | a Buffer 11 |   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 0298  |  | I  | _  | 1  |   |                   |       |        |       | ADC Data | a Buffer 12 | 2   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 029A  |  | 1  | _  | 1  |   |                   |       |        |       | ADC Data | a Buffer 13 | 3   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 029C  |  | 1  | _  | 1  |   |                   |       |        |       | ADC Data | a Buffer 14 | 1   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 029E  | _  | -  | _  | -  |   |                   |       |        |       | ADC Data | a Buffer 15 | 5   |                     |       |                     |                     | 0000 uuuu uuuu uuuu |
| 02A0  | ADON   | -  | ADSIDL   | -  | _   | _                 | FORM  | 1<1:0> | S     | SRC<2:0: | >           | _   | _                   | ASAM  | SAMP                | DONE                | 0000 0000 0000 0000 |
| 02A2  | V  | CFG<2:0>   | >  | -  | _   | CSCNA             | _     | _      | BUFS  | _        |             | SMPI  | <3:0>               |       | BUFM                | ALTS                | 0000 0000 0000 0000 |
| 02A4  | _  | _  | _  |  | SAMC<4:0> ADRC — ADCS<5:0>  |                   |       |        |       |          |             |   | 0000 0000 0000 0000 |       |                     |                     |                     |
| 02A6  | _  | _  | _  | CH0NB  |   | CH0SB-            | <3:0> |        |       | _        | _           | CH0NA   |                     | CH0S  | SA<3:0>             |                     | 0000 0000 0000 0000 |
| 02A8  | PCFG15   | PCFG14   | PCFG13   | PCFG12   | PCFG11  | PCFG10            | PCFG9 | PCFG8  | PCFG7 | PCFG6    | PCFG5       | PCFG4   | PCFG3               | PCFG2 | PCFG1               | PCFG0               | 0000 0000 0000 0000 |
| 02AA  | CSSL15   | CSSL14   | CSSL13   | CSSL12   | CSSL11  | CSSL10            | CSSL9 | CSSL8  | CSSL7 | CSSL6    | CSSL5       | CSSL4   | CSSL3               | CSSL2 | CSSL1               | CSSL0               | 0000 0000 0000 0000 |
| ŀ     | 0280<br>0284<br>0288<br>0288<br>0288<br>028C<br>028E<br>0290<br>0292<br>0294<br>0296<br>0298<br>0298<br>029C<br>029E<br>02A0<br>02A2 | 0280 — 0282 — 0284 — 0286 — 0288 — 028A — 028C — 028E — 0290 — 0292 — 0294 — 0296 — 0298 — 029A — 029C — 029E — 02AO ADON 02A2 V 02A4 — 02A6 — | 0280         —         —           0282         —         —           0284         —         —           0286         —         —           0288         —         —           028A         —         —           028C         —         —           029C         —         —           0292         —         —           0294         —         —           0296         —         —           0298         —         —           029A         —         —           029C         —         —           029E         —         —           02A0         ADON         —           02A2         VCFG<<2:0x | 0280     —     —       0282     —     —       0284     —     —       0286     —     —       0288     —     —       028A     —     —       028E     —     —       0290     —     —       0292     —     —       0294     —     —       0298     —     —       029A     —     —       029C     —     —       02A0     ADON     —       02A2     VCFG<2:0>       02A4     —     —       02A8     PCFG15     PCFG14     PCFG13 | 0280         —         —         —         —           0282         —         —         —         —           0284         —         —         —         —           0286         —         —         —         —           0288         —         —         —         —           028A         —         —         —         —           028E         —         —         —         —           0290         —         —         —         —           0291         —         —         —         —           0292         —         —         —         —           0294         —         —         —         —           0294         —         —         —         —           0298         —         —         —         —           0298         —         —         —         —           0299         —         —         —         —           0290         —         —         —         —           0291         —         —         —         —           0292         — | 0280              | 0280  | 0280   | 0280  | 0280     | 0280        | 0280       —       —       —       ADC Data Buffer 0         0282       —       —       —       ADC Data Buffer 1         0284       —       —       —       ADC Data Buffer 2         0286       —       —       —       ADC Data Buffer 3         0288       —       —       —       ADC Data Buffer 4         028A       —       —       —       ADC Data Buffer 4         028E       —       —       —       ADC Data Buffer 6         028E       —       —       —       ADC Data Buffer 7         0290       —       —       —       ADC Data Buffer 8         0292       —       —       —       ADC Data Buffer 9         0294       —       —       —       ADC Data Buffer 10         0296       —       —       —       ADC Data Buffer 11         0298       —       —       —       ADC Data Buffer 11         029A       —       —       —       ADC Data Buffer 12         029C       —       —       —       ADC Data Buffer 12         029C       —       —       —       ADC Data Buffer 12         029C       —       — </td <td>0280</td> <td>  Q280</td> <td>0280</td> <td>0280</td> <td>0280</td> | 0280                | Q280  | 0280                | 0280                | 0280                |

Legend: u = uninitialized bit; — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

NOTES:

#### 20.0 SYSTEM INTEGRATION

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

There are several features intended to maximize system reliability, minimize cost through elimination of external components, provide power-saving operating modes and offer code protection:

- · Oscillator Selection
- Reset
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Programmable Brown-out Reset (BOR)
- Watchdog Timer (WDT)
- Low-Voltage Detect
- Power-Saving modes (Sleep and Idle)
- · Code Protection
- · Unit ID Locations
- In-Circuit Serial Programming (ICSP)

dsPIC30F devices have a Watchdog Timer which is permanently enabled via the Configuration bits or can be software controlled. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable. The other is the Power-up Timer (PWRT) which provides a delay on power-up only, designed to keep the part in Reset while the power supply stabilizes. With these two timers onchip, most applications need no external Reset circuitry.

Sleep mode is designed to offer a very low-current Power-Down mode. The user can wake-up from Sleep through external Reset, Watchdog Timer wake-up, or through an interrupt. Several oscillator options are also made available to allow the part to fit a wide variety of applications. In the Idle mode, the clock sources are still active but the CPU is shut off. The RC oscillator option saves system cost while the LP crystal option saves power.

#### 20.1 Oscillator System Overview

The dsPIC30F oscillator system has the following modules and features:

- Various external and internal oscillator options as clock sources
- An on-chip PLL to boost internal operating frequency
- A clock switching mechanism between various clock sources
- Programmable clock postscaler for system power savings
- A Fail-Safe Clock Monitor (FSCM) that detects clock failure and takes fail-safe measures
- Clock Control register (OSCCON)
- · Configuration bits for main oscillator selection

Configuration bits determine the clock source upon Power-on Reset (POR) and Brown-out Reset (BOR). Thereafter, the clock source can be changed between permissible clock sources. The OSCCON register controls the clock switching and reflects system clock related status bits.

Table 20-1 provides a summary of the dsPIC30F oscillator operating modes. A simplified diagram of the oscillator system is shown in Figure 20-1.


TABLE 20-1: OSCILLATOR OPERATING MODES

| Oscillator Mode | Description   |
|-----------------|---|
| XTL             | 400 kHz-4 MHz crystal on OSC1:OSC2  |
| XT              | 4 MHz-10 MHz crystal on OSC1:OSC2   |
| XT w/PLL 4x     | 4 MHz-10 MHz crystal on OSC1:OSC2, 4x PLL enabled                                 |
| XT w/PLL 8x     | 4 MHz-10 MHz crystal on OSC1:OSC2, 8x PLL enabled                                 |
| XT w/PLL 16x    | 4 MHz-7.5 MHz crystal on OSC1:OSC2, 16x PLL enabled <sup>(1)</sup>                |
| LP              | 32 kHz crystal on SOSCO:SOSCI <sup>(2)</sup>                                      |
| HS              | 10 MHz-25 MHz crystal   |
| HS/2 w/PLL 4x   | 10 MHz-20 MHz crystal, divide by 2, 4x PLL enabled                                |
| HS/2 w/PLL 8x   | 10 MHz-20 MHz crystal, divide by 2, 8x PLL enabled                                |
| HS/2 w/PLL 16x  | 10 MHz-15 MHz crystal, divide by 2, 16x PLL enabled                               |
| HS/3 w/PLL 4x   | 12 MHz-25 MHz crystal, divide by 3, 4x PLL enabled                                |
| HS/3 w/PLL 8x   | 12 MHz-25 MHz crystal, divide by 3, 8x PLL enabled                                |
| HS/3 w/PLL 16x  | 12 MHz-22.5 MHz crystal, divide by 3, 16x PLL enabled                             |
| EC              | External clock input (0-40 MHz)   |
| ECIO            | External clock input (0-40 MHz), OSC2 pin is I/O                                  |
| EC w/PLL 4x     | External clock input (4-10 MHz), OSC2 pin is I/O, 4x PLL enabled <sup>(1)</sup>   |
| EC w/PLL 8x     | External clock input (4-10 MHz), OSC2 pin is I/O, 8x PLL enabled <sup>(1)</sup>   |
| EC w/PLL 16x    | External clock input (4-7.5 MHz), OSC2 pin is I/O, 16x PLL enabled <sup>(1)</sup> |
| ERC             | External RC oscillator, OSC2 pin is Fosc/4 output <sup>(3)</sup>                  |
| ERCIO           | External RC oscillator, OSC2 pin is I/O <sup>(3)</sup>                            |
| FRC             | 7.37 MHz internal RC oscillator   |
| FRC w/PLL 4x    | 7.37 MHz Internal RC oscillator, 4x PLL enabled                                   |
| FRC w/PLL 8x    | 7.37 MHz Internal RC oscillator, 8x PLL enabled                                   |
| FRC w/PLL 16x   | 7.37 MHz Internal RC oscillator, 16x PLL enabled                                  |
| LPRC            | 512 kHz internal RC oscillator  |

**Note 1:** dsPIC30F maximum operating frequency of 120 MHz must be met.

<sup>2:</sup> LP oscillator can be conveniently shared as system clock, as well as Real-Time Clock for Timer1.

<sup>3:</sup> Requires external R and C. Frequency operation up to 4 MHz.



#### 20.2 Oscillator Configurations

### 20.2.1 INITIAL CLOCK SOURCE SELECTION

While coming out of Power-on Reset or Brown-out Reset, the device selects its clock source based on:

- a) FOS<2:0> Configuration bits that select one of four oscillator groups,
- b) and FPR<4:0> Configuration bits that select one of 13 oscillator choices within the primary group.

The selection is as shown in Table 20-2.

### 20.2.2 OSCILLATOR START-UP TIMER (OST)

In order to ensure that a crystal oscillator (or ceramic resonator) has started and stabilized, an Oscillator Start-up Timer is included. It is a simple 10-bit counter that counts 1024 Tosc cycles before releasing the oscillator clock to the rest of the system. The time-out period is designated as Tost. The Tost time is involved every time the oscillator has to restart (i.e., on POR, BOR and wake-up from Sleep). The Oscillator Start-up Timer is applied to the LP, XT, XTL and HS Oscillator modes (upon wake-up from Sleep, POR and BOR) for the primary oscillator.

TABLE 20-2: CONFIGURATION BIT VALUES FOR CLOCK SELECTION

| Oscillator Mode | Oscillator<br>Source | F | OS<2:0 | > |   | F | PR<4:0 | )> |   | OSC2<br>Function |
|-----------------|----------------------|---|--------|---|---|---|--------|----|---|------------------|
| ECIO w/PLL 4x   | PLL                  | 1 | 1      | 1 | 0 | 1 | 1      | 0  | 1 | I/O              |
| ECIO w/PLL 8x   | PLL                  | 1 | 1      | 1 | 0 | 1 | 1      | 1  | 0 | I/O              |
| ECIO w/PLL 16x  | PLL                  | 1 | 1      | 1 | 0 | 1 | 1      | 1  | 1 | I/O              |
| FRC w/PLL 4x    | PLL                  | 1 | 1      | 1 | 0 | 0 | 0      | 0  | 1 | I/O              |
| FRC w/PLL 8x    | PLL                  | 1 | 1      | 1 | 0 | 1 | 0      | 1  | 0 | I/O              |
| FRC w/PLL 16x   | PLL                  | 1 | 1      | 1 | 0 | 0 | 0      | 1  | 1 | I/O              |
| XT w/PLL 4x     | PLL                  | 1 | 1      | 1 | 0 | 0 | 1      | 0  | 1 | OSC2             |
| XT w/PLL 8x     | PLL                  | 1 | 1      | 1 | 0 | 0 | 1      | 1  | 0 | OSC2             |
| XT w/PLL 16x    | PLL                  | 1 | 1      | 1 | 0 | 0 | 1      | 1  | 1 | OSC2             |
| HS2 w/PLL 4x    | PLL                  | 1 | 1      | 1 | 1 | 0 | 0      | 0  | 1 | OSC2             |
| HS2 w/PLL 8x    | PLL                  | 1 | 1      | 1 | 1 | 0 | 0      | 1  | 0 | OSC2             |
| HS2 w/PLL 16x   | PLL                  | 1 | 1      | 1 | 1 | 0 | 0      | 1  | 1 | OSC2             |
| HS3 w/PLL 4x    | PLL                  | 1 | 1      | 1 | 1 | 0 | 1      | 0  | 1 | OSC2             |
| HS3 w/PLL 8x    | PLL                  | 1 | 1      | 1 | 1 | 0 | 1      | 1  | 0 | OSC2             |
| HS3 w/PLL 16x   | PLL                  | 1 | 1      | 1 | 1 | 0 | 1      | 1  | 1 | OSC2             |
| ECIO            | External             | 0 | 1      | 1 | 0 | 1 | 1      | 0  | 0 | I/O              |
| XT              | External             | 0 | 1      | 1 | 0 | 0 | 1      | 0  | 0 | OSC2             |
| HS              | External             | 0 | 1      | 1 | 0 | 0 | 0      | 1  | 0 | OSC2             |
| EXT             | External             | 0 | 1      | 1 | 0 | 1 | 0      | 1  | 1 | CLKO             |
| ERC             | External             | 0 | 1      | 1 | 0 | 1 | 0      | 0  | 1 | CLKO             |
| ERCIO           | External             | 0 | 1      | 1 | 0 | 1 | 0      | 0  | 0 | I/O              |
| XTL             | External             | 0 | 1      | 1 | 0 | 0 | 0      | 0  | 0 | OSC2             |
| LP              | Secondary            | 0 | 0      | 0 | Х | Х | Х      | Х  | Х | (Notes 1, 2)     |
| FRC             | Internal FRC         | 0 | 0      | 1 | Х | Х | Х      | Х  | Х | (Notes 1, 2)     |
| LPRC            | Internal LPRC        | 0 | 1      | 0 | Х | Х | Х      | Х  | Х | (Notes 1, 2)     |

**Note 1:** The OSC2 pin is either usable as a general purpose I/O pin functionality only depending on the Primary Oscillator mode selection (FPR<4:0>).

<sup>2:</sup> Note that OSC1 pin cannot be used as an I/O pin even if the secondary oscillator or an internal clock source is selected at all times.

#### 20.2.3 LP OSCILLATOR CONTROL

Enabling the LP oscillator is controlled with two elements:

- The current oscillator group bits, COSC<2:0>.
- The LPOSCEN bit (OSCCON register).

The LP oscillator is on (even during Sleep mode) if LPOSCEN = 1. The LP oscillator is the device clock if:

- COSC<2:0> = 00 (LP selected as main osc.) and
- LPOSCEN = 1

Keeping the LP oscillator on at all times allows for a fast switch to the 32 kHz system clock for lower power operation. Returning to the faster main oscillator still requires a start-up time

#### 20.2.4 PHASE LOCKED LOOP (PLL)

The PLL multiplies the clock which is generated by the primary oscillator. The PLL is selectable to have either gains of x4, x8 and x16. Input and output frequency ranges are summarized in Table 20-3.

TABLE 20-3: PLL FREQUENCY RANGE

| Fin           | PLL<br>Multiplier | Fouт           |
|---------------|-------------------|----------------|
| 4 MHz-10 MHz  | x4                | 16 MHz-40 MHz  |
| 4 MHz-10 MHz  | x8                | 32 MHz-80 MHz  |
| 4 MHz-7.5 MHz | x16               | 64 MHz-120 MHz |

The PLL features a lock output which is asserted when the PLL enters a phase locked state. Should the loop fall out of lock (e.g., due to noise), the lock signal is rescinded. The state of this signal is reflected in the read-only LOCK bit in the OSCCON register.

#### 20.2.5 FAST RC OSCILLATOR (FRC)

The FRC oscillator is a fast (7.37 MHz ±2% nominal) internal RC oscillator. This oscillator is intended to provide reasonable device operating speeds without the use of an external crystal, ceramic resonator, or RC network. The FRC oscillator can be used with the PLL to obtain higher clock frequencies.

The dsPIC30F operates from the FRC oscillator whenever the current oscillator selection control bits in the OSCCON register (OSCCON<14:12>) are set to '001'.

The four-bit field specified by TUN<3:0> (OSCTUN<3:0>) allows the user to tune the internal fast RC oscillator (nominal 7.37 MHz). The user can tune the FRC oscillator within a range of +10.5% (840 kHz) and -12% (960 kHz) in steps of 1.50% around the factory-calibrated setting (see Table 20-4).

Note: OSCTUN functionality has been provided to help customers compensate for temperature effects on the FRC frequency over a wide range of temperatures. The tuning step size is an approximation and is neither characterized nor tested.

If OSCCON<14:12> are set to '111' and FPR<4:0> are set to '00101', '00110' or '00111', then a PLL multiplier of 4, 8 or 16 (respectively) is applied.

Note: When a 16x PLL is used, the FRC frequency must not be tuned to a frequency greater than 7.5 MHz.

TABLE 20-4: FRC TUNING

| TUN<3:0><br>Bits | FRC Frequency  |
|------------------|--|
| 0111             | +10.5%   |
| 0110             | +9.0%  |
| 0101             | +7.5%  |
| 0100             | +6.0%  |
| 0011             | +4.5%  |
| 0010             | +3.0%  |
| 0001             | +1.5%  |
| 0000             | Center Frequency (oscillator is running at calibrated frequency) |
| 1111             | -1.5%  |
| 1110             | -3.0%  |
| 1101             | -4.5%  |
| 1100             | -6.0%  |
| 1011             | -7.5%  |
| 1010             | -9.0%  |
| 1001             | -10.5%   |
| 1000             | -12.0%   |

#### 20.2.6 LOW-POWER RC OSCILLATOR (LPRC)

The LPRC oscillator is a component of the Watchdog Timer (WDT) and oscillates at a nominal frequency of 512 kHz. The LPRC oscillator is the clock source for the Power-up Timer (PWRT) circuit, WDT and clock monitor circuits. It may also be used to provide a low-frequency clock source option for applications where power consumption is critical and timing accuracy is not required.

The LPRC oscillator is always enabled at a Power-on Reset because it is the clock source for the PWRT. After the PWRT expires, the LPRC oscillator remains on if one of the following is TRUE:

- The Fail-Safe Clock Monitor is enabled
- The WDT is enabled
- The LPRC oscillator is selected as the system clock via the COSC<2:0> control bits in the OSCCON register

If one of the above conditions is not true, the LPRC shuts off after the PWRT expires.

- Note 1: OSC2 pin function is determined by the Primary Oscillator mode selection (FPR<4:0>).
  - OSC1 pin cannot be used as an I/O pin even if the secondary oscillator or an internal clock source is selected at all times.

#### 20.2.7 FAIL-SAFE CLOCK MONITOR

The Fail-Safe Clock Monitor (FSCM) allows the device to continue to operate even in the event of an oscillator failure. The FSCM function is enabled by appropriately programming the FCKSM Configuration bits (clock switch and monitor selection bits) in the FOSC Device Configuration register. If the FSCM function is enabled, the LPRC internal oscillator runs at all times (except during Sleep mode) and is not subject to control by the SWDTEN bit.

In the event of an oscillator failure, the FSCM generates a clock failure trap event and switches the system clock over to the FRC oscillator. The user then has the option to either attempt to restart the oscillator or execute a controlled shutdown. The user may decide to treat the trap as a warm Reset by simply loading the Reset address into the oscillator fail trap vector. In this event, the CF (Clock Fail) status bit (OSCCON<3>) is also set whenever a clock failure is recognized.

In the event of a clock failure, the WDT is unaffected and continues to run on the LPRC clock.

If the oscillator has a very slow start-up time coming out of POR, BOR or Sleep, it is possible that the PWRT timer will expire before the oscillator has started. In such cases, the FSCM is activated and the FSCM initiates a clock failure trap, and the COSC<2:0> bits are loaded with FRC oscillator selection. This effectively shuts off the original oscillator that was trying to start.

The user may detect this situation and restart the oscillator in the clock fail trap ISR.

Upon a clock failure detection, the FSCM module initiates a clock switch to the FRC oscillator as follows:

- 1. The COSC bits (OSCCON<14:12>) are loaded with the FRC oscillator selection value.
- 2. CF bit is set (OSCCON<3>).
- 3. OSWEN control bit (OSCCON<0>) is cleared.

For the purpose of clock switching, the clock sources are sectioned into four groups:

- Primary
- Secondary
- Internal FRC
- Internal LPRC

The user can switch between these functional groups but cannot switch between options within a group. If the primary group is selected, then the choice within the group is always determined by the FPR<4:0> Configuration bits.

The OSCCON register holds the control and status bits related to clock switching.

 COSC<2:0>: Read-only status bits always reflect the current oscillator group in effect.

- NOSC<2:0>: Control bits which are written to indicate the new oscillator group of choice.
  - On POR and BOR, COSC<2:0> and NOSC<2:0> are both loaded with the Configuration bit values, FOS<2:0>.
- LOCK: The LOCK status bit indicates a PLL lock.
- CF: Read-only status bit indicating if a clock fail detect has occurred.
- OSWEN: Control bit changes from a '0' to a '1' when a clock transition sequence is initiated.
   Clearing the OSWEN control bit aborts a clock transition in progress (used for hang-up situations).

If Configuration bits, FCKSM<1:0> = 1x, then the clock switching and Fail-Safe Clock Monitor functions are disabled. This is the default Configuration bit setting.

If clock switching is disabled, then the FOS<2:0> and FPR<4:0> bits directly control the oscillator selection and the COSC<2:0> bits do not control the clock selection. However, these bits reflect the clock source selection.

#### Note:

The application should not attempt to switch to a clock of frequency lower than 100 kHz when the Fail-Safe Clock Monitor is enabled. If such clock switching is performed, the device may generate an oscillator fail trap and switch to the Fast RC oscillator.

### 20.2.8 PROTECTION AGAINST ACCIDENTAL WRITES TO OSCCON

A write to the OSCCON register is intentionally made difficult because it controls clock switching and clock scaling.

To write to the OSCCON low byte, the following code sequence must be executed without any other instructions in between:

```
Byte Write 0x46 to OSCCON low Byte Write 0x57 to OSCCON low
```

Byte write is allowed for one instruction cycle. Write the desired value or use bit manipulation instruction.

To write to the OSCCON high byte, the following instructions must be executed without any other instructions in between:

```
Byte Write 0x78 to OSCCON high
Byte Write 0x9A to OSCCON high
```

Byte write is allowed for one instruction cycle. Write the desired value or use bit manipulation instruction.

#### 20.3 Oscillator Control Registers

The oscillators are controlled with two SFRs, OSCCON and OSCTUN and one Configuration register, FOSC.

Note: The description of the OSCCON and OSCTUN SFRs, as well as the FOSC Configuration register provided in this section are applicable only to the dsPIC30F3014 and dsPIC30F4013 devices in the dsPIC30F product family.

#### REGISTER 20-1: OSCCON: OSCILLATOR CONTROL REGISTER

| U-0    | R-y | R-y       | R-y | U-0 | R/W-y | R/W-y     | R/W-y |  |  |  |
|--------|-----|-----------|-----|-----|-------|-----------|-------|--|--|--|
| _      |     | COSC<2:0> |     | _   |       | NOSC<2:0> |       |  |  |  |
| bit 15 |     |           |     |     |       |           | bit 8 |  |  |  |

| R/W-0 | R/W-0          | R-0 | U-0 | R/W-0 | U-0 | R/W-0   | R/W-0 |
|-------|----------------|-----|-----|-------|-----|---------|-------|
| POST  | POST<1:0> LOCK |     | _   | CF    | _   | LPOSCEN | OSWEN |
| bit 7 |                |     |     |       |     |         | bit 0 |

| Legend:           |                  |                             |                    |
|-------------------|------------------|-----------------------------|--------------------|
| R = Readable bit  | W = Writable bit | U = Unimplemented bit, read | l as '0'           |
| -n = Value at POR | '1' = Bit is set | '0' = Bit is cleared        | x = Bit is unknown |

bit 15 **Unimplemented:** Read as '0'

bit 14-12 COSC<2:0>: Current Oscillator Group Selection bits (read-only)

111 = PLL oscillator; PLL source selected by FPR<4:0> bits

011 = External oscillator; OSC1/OSC2 pins; external oscillator configuration selected by FPR<4:0> bits

010 = LPRC internal low-power RC

001 = FRC internal fast RC

000 = LP crystal oscillator; SOSCI/SOSCO pins

Set to FOS<2:0> values on POR or BOR. Loaded with NOSC<2:0> at the completion of a successful clock switch. Set to FRC value when FSCM detects a failure and switches clock to FRC.

bit 11 Unimplemented: Read as '0'

bit 10-8 NOSC<2:0>: New Oscillator Group Selection bits

111 = PLL Oscillator; PLL source selected by FPR<4:0> bits

011 = External oscillator; OSC1/OSC2 pins; external oscillator configuration selected by FPR<4:0> bits

010 = LPRC internal low-power RC

001 = FRC internal fast RC

000 = LP crystal oscillator; SOSCI/SOSCO pins

Set to FOS<2:0> values on POR or BOR.

bit 7-6 **POST<1:0>:** Oscillator Postscaler Selection bits

11 = Oscillator postscaler divides clock by 64

10 = Oscillator postscaler divides clock by 16

01 = Oscillator postscaler divides clock by 4

00 = Oscillator postscaler does not alter clock

#### REGISTER 20-1: OSCCON: OSCILLATOR CONTROL REGISTER (CONTINUED)

bit 5 LOCK: PLL Lock Status bit (read-only)

1 = Indicates that PLL is in lock

0 = Indicates that PLL is out of lock (or disabled)

Reset on POR or BOR. Reset when a valid clock switching sequence is initiated. Set when PLL lock is achieved after a PLL start. Reset when lock is lost. Read zero when PLL is not selected as a system

clock

bit 4 Unimplemented: Read as '0'

bit 3 **CF:** Clock Fail Detect bit (read/clearable by application)

1 = FSCM has detected clock failure 0 = FSCM has NOT detected clock failure

Reset on POR or BOR. Reset when a valid clock switching sequence is initiated. Set when clock fail

detected

bit 2 **Unimplemented:** Read as '0'

bit 1 LPOSCEN: 32 kHz Secondary (LP) Oscillator Enable bit

1 = Secondary oscillator is enabled0 = Secondary oscillator is disabled

Reset on POR or BOR.

bit 0 OSWEN: Oscillator Switch Enable bit

1 = Request oscillator switch to selection specified by NOSC<2:0> bits

0 = Oscillator switch is complete

Reset on POR or BOR. Reset after a successful clock switch. Reset after a redundant clock switch.

Reset after FSCM switches the oscillator to (Group 1) FRC.

#### REGISTER 20-2: OSCTUN: FRC OSCILLATOR TUNING REGISTER

| U-0    | U-0 | U-0 | U-0 | U-0 | U-0 | U-0 | U-0   |
|--------|-----|-----|-----|-----|-----|-----|-------|
| _      | _   | _   | _   | _   | _   | _   | _     |
| bit 15 |     |     |     |     |     |     | bit 8 |

| U-0   | U-0 | U-0 | U-0 | R/W-0 R/W-0 R/W-0 R/W- |  |  |       |  |  |  |
|-------|-----|-----|-----|------------------------|--|--|-------|--|--|--|
| _     | _   | _   | _   | TUN<3:0>               |  |  |       |  |  |  |
| bit 7 |     |     |     |                        |  |  | bit 0 |  |  |  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 15-4 **Unimplemented:** Read as '0'

bit 3-0 TUN<3:0>: TUN Field Lower Two bits

The four-bit field specified by TUN<3:0> specifies the user tuning capability for the internal fast RC oscillator (nominal 7.37 MHz).

0111 = Maximum frequency

0110 =

0101 =

0100 =

0011 =

0010 =

0001 =

0000 = Center frequency, oscillator is running at calibrated frequency

1111 =

1110 =

1101 =

1100 =

1011 =

1010 =

1001 =

1000 = Minimum frequency

#### REGISTER 20-3: FOSC: OSCILLATOR CONFIGURATION REGISTER

| U      | U | U | U | U | U | U | U      |  |
|--------|---|---|---|---|---|---|--------|--|
| _      | _ | _ | _ | _ | _ | _ | _      |  |
| bit 23 |   |   |   |   |   |   | bit 16 |  |

| R/P    | R/P    | U | U | U | R/P      | R/P R/P |  |  |  |  |
|--------|--------|---|---|---|----------|---------|--|--|--|--|
| FCKSM  | Л<1:0> | _ | _ | _ | FOS<2:0> |         |  |  |  |  |
| bit 15 |        |   |   |   |          | bit 8   |  |  |  |  |

| U     | U | U | R/P      | R/P | R/P | R/P | R/P   |  |  |
|-------|---|---|----------|-----|-----|-----|-------|--|--|
| _     | _ | _ | FPR<4:0> |     |     |     |       |  |  |
| bit 7 |   |   |          |     |     |     | bit 0 |  |  |

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 23-16 **Unimplemented:** Read as '0'

bit 15-14 FCKSM<1:0>: Clock Switching and Monitor Selection Configuration bits

1x = Clock switching is disabled, Fail-Safe Clock Monitor is disabled

01 = Clock switching is enabled, Fail-Safe Clock Monitor is disabled

00 = Clock switching is enabled, Fail-Safe Clock Monitor is enabled

bit 13-11 **Unimplemented:** Read as '0'

bit 10-8 **FOS<2:0>:** Oscillator Group Selection on POR bits

111 = PLL oscillator; PLL source selected by FPR<4:0> bits (see Table 20-2)

011 = EXT: External Oscillator; OSC1/OSC2 pins; external oscillator configuration selected by

FPR<4:0> bits

010 = LPRC: Internal Low-Power RC

001 = FRC: Internal Fast RC

000 = LPOSC: Low-Power Crystal Oscillator; SOSCI/SOSCO pins

bit 7-5 **Unimplemented:** Read as '0'

bit 4-0 FPR<4:0>: Oscillator Selection within Primary Group bits (see Table 20-2)

#### 20.4 Reset

The dsPIC30F3014/4013 differentiates between various kinds of Reset:

- a) Power-on Reset (POR)
- b) MCLR Reset during normal operation
- c) MCLR Reset during Sleep
- d) Watchdog Timer (WDT) Reset (during normal operation)
- e) Programmable Brown-out Reset (BOR)
- f) RESET Instruction
- g) Reset caused by trap lockup (TRAPR)
- Reset caused by illegal opcode or by using an uninitialized W register as an Address Pointer (IOPUWR)


Different registers are affected in different ways by various Reset conditions. Most registers are not affected by a WDT wake-up since this is viewed as the resumption of normal operation. Status bits from the RCON register are set or cleared differently in different Reset situations, as indicated in Table 20-5. These bits are used in software to determine the nature of the Reset.

A block diagram of the On-Chip Reset Circuit is shown in Figure 20-2.

A MCLR noise filter is provided in the MCLR Reset path. The filter detects and ignores small pulses.

Internally generated Resets do not drive MCLR pin low.

#### FIGURE 20-2: RESET SYSTEM BLOCK DIAGRAM



#### 20.4.1 POR: POWER-ON RESET

A power-on event generates an internal POR pulse when a VDD rise is detected. The Reset pulse occurs at the POR circuit threshold voltage (VPOR) which is nominally 1.85V. The device supply voltage characteristics must meet specified starting voltage and rise rate requirements. The POR pulse resets a POR timer and places the device in the Reset state. The POR also selects the device clock source identified by the oscillator configuration fuses.

The POR circuit inserts a small delay, TPOR, which is nominally 10  $\mu s$  and ensures that the device bias circuits are stable. Furthermore, a user-selected power-up time-out (TPWRT) is applied. The TPWRT parameter is based on device Configuration bits and can be 0 ms (no delay), 4 ms, 16 ms, or 64 ms. The total delay is at device power-up, TPOR + TPWRT. When these delays have expired,  $\overline{SYSRST}$  is negated on the next leading edge of the Q1 clock and the PC jumps to the Reset vector.

The timing for the SYSRST signal is shown in Figure 20-3 through Figure 20-5.

FIGURE 20-3: TIME-OUT SEQUENCE ON POWER-UP (MCLR TIED TO VDD)




FIGURE 20-4: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 1





FIGURE 20-5: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2



## 20.4.1.1 POR with Long Crystal Start-up Time (with FSCM Enabled)

The oscillator start-up circuitry is not linked to the POR circuitry. Some crystal circuits (especially low-frequency crystals) have a relatively long start-up time. Therefore, one or more of the following conditions is possible after the POR timer and the PWRT have expired:

- The oscillator circuit has not begun to oscillate.
- The Oscillator Start-up Timer has not expired (if a crystal oscillator is used).
- The PLL has not achieved a LOCK (if PLL is used).

If the FSCM is enabled and one of the above conditions is true, a clock failure trap occurs. The device automatically switches to the FRC oscillator and the user can switch to the desired crystal oscillator in the trap ISR.

#### 20.4.1.2 Operating without FSCM and PWRT

If the FSCM is disabled and the Power-up Timer (PWRT) is also disabled, then the device exits rapidly from Reset on power-up. If the clock source is FRC, LPRC, ERC or EC, it will be active immediately.

If the FSCM is disabled and the system clock has not started, the device will be in a frozen state at the Reset vector until the system clock starts. From the user's perspective, the device appears to be in Reset until a system clock is available.

# 20.4.2 BOR: PROGRAMMABLE BROWN-OUT RESET

The BOR (Brown-out Reset) module is based on an internal voltage reference circuit. The main purpose of the BOR module is to generate a device Reset when a brown-out condition occurs. Brown-out conditions are generally caused by glitches on the AC mains (i.e., missing portions of the AC cycle waveform due to bad power transmission lines, or voltage sags due to excessive current draw when a large inductive load is turned on).

The BOR module allows selection of one of the following voltage trip points (see Table 23-11):

- 2.6V-2.71V
- 4.1V-4.4V
- 4.58V-4.73V

Note: The BOR voltage trip points indicated here are nominal values provided for design guidance only. Refer to the Electrical Specifications in the specific device data sheet for BOR voltage limit specifications.


A BOR generates a Reset pulse, which resets the device. The BOR selects the clock source based on the device Configuration bit values (FOS<2:0> and FPR<4:0>). Furthermore, if an oscillator mode is selected, the BOR activates the Oscillator Start-up Timer (OST). The system clock is held until OST expires. If the PLL is used, then the clock is held until the LOCK bit (OSCCON<5>) is '1'.

Concurrently, the POR time-out (TPOR) and the PWRT time-out (TPWRT) are applied before the internal Reset is released. If TPWRT = 0 and a crystal oscillator is being used, then a nominal delay of TFSCM = 100  $\mu$ s is applied. The total delay in this case is (TPOR + TFSCM).

The BOR status bit (RCON<1>) is set to indicate that a BOR has occurred. The BOR circuit, if enabled, continues to operate while in Sleep or Idle modes and resets the device should VDD fall below the BOR threshold voltage.

#### FIGURE 20-6:

#### EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)



- Note 1: External Power-on Reset circuit is required only if the VDD power-up slope is too slow.

  The diode D helps discharge the capacitor quickly when VDD powers down.
  - 2: R should be suitably chosen so as to make sure that the voltage drop across R does not violate the device's electrical specifications.
  - R1 should be suitably chosen so as to limit any current flowing into MCLR from external capacitor C, in the event of MCLR/VPP pin breakdown due to Electrostatic Discharge (ESD), or Electrical Overstress (EOS).

Note:

Dedicated supervisory devices, such as the MCP1XX and MCP8XX, may also be used as an external Power-on Reset circuit.

Table 20-5 shows the Reset conditions for the RCON register. Since the control bits within the RCON register are R/W, the information in the table means that all the bits are negated prior to the action specified in the condition column.

TABLE 20-5: INITIALIZATION CONDITION FOR RCON REGISTER: CASE 1

| Condition                              | Program<br>Counter    | TRAPR | IOPUWR | EXTR | SWR | WDTO | IDLE | SLEEP | POR | BOR |
|--|-----------------------|-------|--------|------|-----|------|------|-------|-----|-----|
| Power-on Reset                         | 0x000000              | 0     | 0      | 0    | 0   | 0    | 0    | 0     | 1   | 1   |
| Brown-out Reset                        | 0x000000              | 0     | 0      | 0    | 0   | 0    | 0    | 0     | 0   | 1   |
| MCLR Reset during normal operation     | 0x000000              | 0     | 0      | 1    | 0   | 0    | 0    | 0     | 0   | 0   |
| Software Reset during normal operation | 0x000000              | 0     | 0      | 0    | 1   | 0    | 0    | 0     | 0   | 0   |
| MCLR Reset during Sleep                | 0x000000              | 0     | 0      | 1    | 0   | 0    | 0    | 1     | 0   | 0   |
| MCLR Reset during Idle                 | 0x000000              | 0     | 0      | 1    | 0   | 0    | 1    | 0     | 0   | 0   |
| WDT Time-out Reset                     | 0x000000              | 0     | 0      | 0    | 0   | 1    | 0    | 0     | 0   | 0   |
| WDT Wake-up                            | PC + 2                | 0     | 0      | 0    | 0   | 1    | 0    | 1     | 0   | 0   |
| Interrupt Wake-up from Sleep           | PC + 2 <sup>(1)</sup> | 0     | 0      | 0    | 0   | 0    | 0    | 1     | 0   | 0   |
| Clock Failure Trap                     | 0x000004              | 0     | 0      | 0    | 0   | 0    | 0    | 0     | 0   | 0   |
| Trap Reset                             | 0x000000              | 1     | 0      | 0    | 0   | 0    | 0    | 0     | 0   | 0   |
| Illegal Operation Trap                 | 0x000000              | 0     | 1      | 0    | 0   | 0    | 0    | 0     | 0   | 0   |

**Legend:** u = unchanged, x = unknown, -= unimplemented bit, read as '0'

Note 1: When the wake-up is due to an enabled interrupt, the PC is loaded with the corresponding interrupt vector.

Table 20-6 shows a second example of the bit conditions for the RCON register. In this case, it is not assumed the user has set/cleared specific bits prior to action specified in the condition column.

TABLE 20-6: INITIALIZATION CONDITION FOR RCON REGISTER: CASE 2

| Condition                              | Program<br>Counter    | TRAPR | IOPUWR | EXTR | SWR | WDTO | IDLE | SLEEP | POR | BOR |
|--|-----------------------|-------|--------|------|-----|------|------|-------|-----|-----|
| Power-on Reset                         | 0x000000              | 0     | 0      | 0    | 0   | 0    | 0    | 0     | 1   | 1   |
| Brown-out Reset                        | 0x000000              | u     | u      | u    | u   | u    | u    | u     | 0   | 1   |
| MCLR Reset during normal operation     | 0x000000              | u     | u      | 1    | 0   | 0    | 0    | 0     | u   | u   |
| Software Reset during normal operation | 0x000000              | u     | u      | 0    | 1   | 0    | 0    | 0     | u   | u   |
| MCLR Reset during Sleep                | 0x000000              | u     | u      | 1    | u   | 0    | 0    | 1     | u   | u   |
| MCLR Reset during Idle                 | 0x000000              | u     | u      | 1    | u   | 0    | 1    | 0     | u   | u   |
| WDT Time-out Reset                     | 0x000000              | u     | u      | 0    | 0   | 1    | 0    | 0     | u   | u   |
| WDT Wake-up                            | PC + 2                | u     | u      | u    | u   | 1    | u    | 1     | u   | u   |
| Interrupt Wake-up from Sleep           | PC + 2 <sup>(1)</sup> | u     | u      | u    | u   | u    | u    | 1     | u   | u   |
| Clock Failure Trap                     | 0x000004              | u     | u      | u    | u   | u    | u    | u     | u   | u   |
| Trap Reset                             | 0x000000              | 1     | u      | u    | u   | u    | u    | u     | u   | u   |
| Illegal Operation Reset                | 0x000000              | u     | 1      | u    | u   | u    | u    | u     | u   | u   |

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, read as '0'

**Note 1:** When the wake-up is due to an enabled interrupt, the PC is loaded with the corresponding interrupt vector.

#### 20.5 Watchdog Timer (WDT)

#### 20.5.1 WATCHDOG TIMER OPERATION

The primary function of the Watchdog Timer (WDT) is to reset the processor in the event of a software malfunction. The WDT is a free-running timer that runs off an on-chip RC oscillator, requiring no external component. Therefore, the WDT timer continues to operate even if the main processor clock (e.g., the crystal oscillator) fails.

### 20.5.2 ENABLING AND DISABLING THE WDT

The Watchdog Timer can be "Enabled" or "Disabled" only through a Configuration bit (FWDTEN) in the Configuration register, FWDT.

Setting FWDTEN = 1 enables the Watchdog Timer. The enabling is done when programming the device. By default, after chip erase, FWDTEN bit = 1. Any device programmer capable of programming dsPIC30F devices allows programming of this and other Configuration bits.

If enabled, the WDT increments until it overflows or "times out". A WDT time-out forces a device Reset (except during Sleep). To prevent a WDT time-out, the user must clear the Watchdog Timer using a CLRWDT instruction.

If a WDT times out during Sleep, the device wakes up. The WDTO bit in the RCON register is cleared to indicate a wake-up resulting from a WDT time-out.

Setting FWDTEN = 0 allows user software to enable/ disable the Watchdog Timer via the SWDTEN (RCON<5>) control bit.

#### 20.6 Low-Voltage Detect

The Low-Voltage Detect (LVD) module is used to detect when the VDD of the device drops below a threshold value, VLVD, which is determined by the LVDL<3:0> bits (RCON<11:8>) and is thus user programmable. The internal voltage reference circuitry requires a nominal amount of time to stabilize, and the BGST bit (RCON<13>) indicates when the voltage reference has stabilized.

In some devices, the LVD threshold voltage may be applied externally on the LVDIN pin.

The LVD module is enabled by setting the LVDEN bit (RCON<12>).

#### 20.7 Power-Saving Modes

There are two power-saving states that can be entered through the execution of a special instruction, PWRSAV; these are Sleep and Idle.

The format of the PWRSAV instruction is as follows:

#### 20.7.1 SLEEP MODE

In Sleep mode, the clock to the CPU and peripherals is shut down. If an on-chip oscillator is being used, it is shut down

The Fail-Safe Clock Monitor is not functional during Sleep since there is no clock to monitor. However, the LPRC clock remains active if WDT is operational during Sleep.

The brown-out protection circuit and the Low-Voltage Detect (LVD) circuit, if enabled, remains functional during Sleep.

The processor wakes up from Sleep if at least one of the following conditions has occurred:

- any interrupt that is individually enabled and meets the required priority level
- any Reset (POR, BOR and MCLR)
- WDT time-out

On waking up from Sleep mode, the processor restarts the same clock that was active prior to entry into Sleep mode. When clock switching is enabled, bits, COSC<2:0>, determine the oscillator source to be used on wake-up. If clock switch is disabled, then there is only one system clock.

**Note:** If a POR or BOR occurred, the selection of the oscillator is based on the FOS<2:0> and FPR<4:0> Configuration bits.

If the clock source is an oscillator, the clock to the device is held off until OST times out (indicating a stable oscillator). If PLL is used, the system clock is held off until LOCK = 1 (indicating that the PLL is stable). In either case, TPOR, TLOCK and TPWRT delays are applied.

If EC, FRC, LPRC or ERC oscillators are used, then a delay of TPOR ( $\sim 10~\mu$ s) is applied. This is the smallest delay possible on wake-up from Sleep.

Moreover, if the LP oscillator was active during Sleep and LP is the oscillator used on wake-up, then the start-up delay is equal to TPOR. PWRT delay and OST timer delay are not applied. In order to have the smallest possible start-up delay when waking up from Sleep, one of these faster wake-up options should be selected before entering Sleep.

Any interrupt that is individually enabled (using the corresponding IE bit) and meets the prevailing priority level can wake-up the processor. The processor processes the interrupt and branch to the ISR. The SLEEP status bit in the RCON register is set upon wake-up.

Note:

In spite of various delays applied (TPOR, TLOCK and TPWRT), the crystal oscillator (and PLL) may not be active at the end of the time-out (e.g., for low-frequency crystals). In such cases, if FSCM is enabled, the device detects this as a clock failure and processes the clock failure trap, the FRC oscillator is enabled and the user will have to re-enable the crystal oscillator. If FSCM is not enabled, the device simply suspends execution of code until the clock is stable and remain in Sleep until the oscillator clock has started.

All Resets wake up the processor from Sleep mode. Any Reset, other than POR, sets the Sleep status bit. In a POR, the SLEEP bit is cleared.

If the Watchdog Timer is enabled, the processor wakes up from Sleep mode upon WDT time-out. The SLEEP and WDTO status bits are both set.

#### 20.7.2 IDLE MODE

In Idle mode, the clock to the CPU is shut down while peripherals keep running. Unlike Sleep mode, the clock source remains active.

Several peripherals have a control bit in each module that allows them to operate during Idle.

The LPRC fail-safe clock remains active if clock failure detect is enabled.

The processor wakes up from Idle if at least one of the following conditions has occurred:

- any interrupt that is individually enabled (IE bit is '1') and meets the required priority level
- any Reset (POR, BOR, MCLR)
- · WDT time-out

Upon wake-up from Idle mode, the clock is re-applied to the CPU and instruction execution begins immediately, starting with the instruction following the PWRSAV instruction.

Any interrupt that is individually enabled (using the IE bit) and meets the prevailing priority level is able to wake up the processor. The processor processes the interrupt and branches to the ISR. The IDLE status bit in the RCON register is set upon wake-up.

Any Reset other than POR sets the IDLE status bit. On a POR, the IDLE bit is cleared.

If Watchdog Timer is enabled, the processor wakes up from Idle mode upon WDT time-out. The Idle and WDTO status bits are both set.

Unlike wake-up from Sleep, there are no time delays involved in wake-up from Idle.

#### 20.8 Device Configuration Registers

The Configuration bits in each device Configuration register specify some of the device modes and are programmed by a device programmer, or by using the In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) feature of the device. Each device Configuration register is a 24-bit register, but only the lower 16 bits of each register are used to hold configuration data. There are five device Configuration registers available to the user:

- FOSC (0xF80000): Oscillator Configuration Register
- FWDT (0xF80002): Watchdog Timer Configuration Register
- FBORPOR (0xF80004): BOR and POR Configuration Register
- 4. FGS (0xF8000A): General Code Segment Configuration Register
- 5. FICD (0xF8000C): Debug Configuration Register

The placement of the Configuration bits is automatically handled when you select the device in your device programmer. The desired state of the Configuration bits may be specified in the source code (dependent on the language tool used), or through the programming interface. After the device has been programmed, the application software may read the Configuration bit values through the table read instructions. For additional information, please refer to the Programming Specifications of the device.

Note:

If the code protection Configuration fuse bits (FGS<GCP> and FGS<GWRP>) have been programmed, an erase of the entire code-protected device is only possible at voltages  $VDD \ge 4.5V$ .

# 20.9 Peripheral Module Disable (PMD) Registers

The Peripheral Module Disable (PMD) registers provide a method to disable a peripheral module by stopping all clock sources supplied to that module. When a peripheral is disabled via the appropriate PMD control bit, the peripheral is in a minimum power consumption state. The control and status registers associated with the peripheral are also disabled so writes to those registers have no effect and read values are invalid.

A peripheral module is only enabled if both the associated bit in the PMD register is cleared and the peripheral is supported by the specific dsPIC DSC variant. If the peripheral is present in the device, it is enabled in the PMD register by default.

- Note 1: If a PMD bit is set, the corresponding module is disabled after a delay of 1 instruction cycle. Similarly, if a PMD bit is cleared, the corresponding module is enabled after a delay of 1 instruction cycle (assuming the module control registers are already configured to enable module operation).
  - 2: In the dsPIC30F3014 device, the T4MD, T5MD, IC7MD, IC8MD, OC3MD, OC4MD and DCIMD are readable and writable, and are read as "1" when set.

#### 20.10 In-Circuit Debugger

When MPLAB<sup>®</sup> ICD 2 is selected as a debugger, the incircuit debugging functionality is enabled. This function allows simple debugging functions when used with MPLAB IDE. When the device has this feature enabled, some of the resources are not available for general use. These resources include the first 80 bytes of data RAM and two I/O pins.

One of four pairs of debug I/O pins may be selected by the user using configuration options in MPLAB IDE. These pin pairs are named EMUD/EMUC, EMUD1/ EMUC1, EMUD2/EMUC2 and MUD3/EMUC3.

In each case, the selected EMUD pin is the Emulation/Debug Data line, and the EMUC pin is the Emulation/Debug Clock line. These pins interface to the MPLAB ICD 2 module available from Microchip. The selected pair of debug I/O pins is used by MPLAB ICD 2 to send commands and receive responses, as well as to send and receive data. To use the in-circuit debugger function of the device, the design must implement ICSP connections to MCLR, VDD, VSS, PGC, PGD and the selected EMUDx/EMUCx pin pair.

This gives rise to two possibilities:

- If EMUD/EMUC is selected as the debug I/O pin pair, then only a 5-pin interface is required, as the EMUD and EMUC pin functions are multiplexed with the PGD and PGC pin functions in all dsPIC30F devices.
- If EMUD1/EMUC1, EMUD2/EMUC2 or EMUD3/ EMUC3 is selected as the debug I/O pin pair, then a 7-pin interface is required, as the EMUDx/EMUCx pin functions (x = 1, 2 or 3) are not multiplexed with the PGD and PGC pin functions.

#### TABLE 20-7: SYSTEM INTEGRATION REGISTER MAP(1)

| SFR<br>Name | Addr. | Bit 15               | Bit 14               | Bit 13  | Bit 12 | Bit 11 | Bit 10    | Bit 9    | Bit 8                | Bit 7 | Bit 6  | Bit 5 | Bit 4 | Bit 3                | Bit 2                | Bit 1   | Bit 0    | Reset State         |  |
|-------------|-------|----------------------|----------------------|---------|--------|--------|-----------|----------|----------------------|-------|--------|-------|-------|----------------------|----------------------|---------|----------|---------------------|--|
| RCON        | 0740  | TRAPR                | IOPUWR               | BGST    | LVDEN  |        | LVDL<3:0> |          | EXTR                 | SWR   | SWDTEN | WDTO  | SLEEP | IDLE                 | BOR                  | POR     | (Note 2) |                     |  |
| OSCCON      | 0742  | _                    | CC                   | SC<2:0> | >      | _      |           | NOSC<2:0 | >                    | POST  | <1:0>  | LOCK  | _     | CF                   | -                    | LPOSCEN | OSWEN    | (Note 3)            |  |
| OSCTUN      | 0744  | _                    | -                    | _       | _      | _      | _         |          | _                    | -     | 1      | _     | _     | TUN3                 | TUN2                 | TUN1    | TUN0     | 0000 0000 0000 0000 |  |
| PMD1        | 0770  | T5MD <sup>(4)</sup>  | T4MD <sup>(4)</sup>  | T3MD    | T2MD   | T1MD   | _         | _        | DCIMD <sup>(4)</sup> | I2CMD | U2MD   | U1MD  | _     | SPI1MD               |                      | C1MD    | ADCMD    | 0000 0000 0000 0000 |  |
| PMD2        | 0772  | IC8MD <sup>(4)</sup> | IC7MD <sup>(4)</sup> | _       | _      | _      | _         | IC2MD    | IC1MD                | _     | _      | _     | _     | OC4MD <sup>(4)</sup> | OC3MD <sup>(4)</sup> | OC2MD   | OC1MD    | 0000 0000 0000 0000 |  |

dsPIC30F3014/4013

**Legend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

2: Reset state depends on type of Reset.

3: Reset state depends on Configuration bits.

4: These bits are not available in dsPIC30F3014 devices.

#### TABLE 20-8: DEVICE CONFIGURATION REGISTER MAP<sup>(1)</sup>

| Name    | Address | Bit 15 | Bit 14 | Bit 13 | Bit 12             | Bit 11 | Bit 10                | Bit 9               | Bit 8                   | Bit 7 | Bit 6 | Bit 5 | Bit 4  | Bit 3      | Bit 2                   | Bit 1             | Bit 0  |
|---------|---------|--------|--------|--------|--------------------|--------|-----------------------|---------------------|-------------------------|-------|-------|-------|--------|------------|-------------------------|-------------------|--------|
| FOSC    | F80000  | FCKSM  | 1<1:0> | _      | _                  | _      |                       | FOS<2:0>            |                         | _     | _     | _     |        | FPR<4:0>   |                         |                   |        |
| FWDT    | F80002  | FWDTEN | _      | _      | _                  | _      | _                     | _                   | _                       | -     | _     | FWPS  | A<1:0> | FWPSB<3:0> |                         |                   |        |
| FBORPOR | F80004  | MCLREN | _      | _      | _                  | _      | PWMPIN <sup>(2)</sup> | HPOL <sup>(2)</sup> | LPOL <sup>(2)</sup>     | BOREN | _     | BORV  | /<1:0> | _          | — — FPWF                |                   | Γ<1:0> |
| FBS     | F80006  | _      | _      | Reser  | ved <sup>(3)</sup> | _      | _                     | _                   | Reserved <sup>(3)</sup> | -     | _     | _     | _      |            | Reserv                  | ed <sup>(3)</sup> |        |
| FSS     | F80008  | _      | _      | Reser  | ved <sup>(3)</sup> | _      | _                     | Rese                | erved <sup>(3)</sup>    | -     | _     | _     | _      |            | Reserv                  | ed <sup>(3)</sup> |        |
| FGS     | F8000A  | _      | _      | _      | _                  | _      | _                     | _                   | _                       | -     | _     | _     | _      | _          | Reserved <sup>(4)</sup> | GCP               | GWRP   |
| FICD    | F8000C  | BKBUG  | COE    |        | _                  | _      | _                     | _                   | _                       |       | _     |       |        | IC         |                         | ICS<              | 1:0>   |

**Legend:** — = unimplemented bit, read as '0'

Note 1: Refer to the "dsPIC30F Family Reference Manual" (DS70046) for descriptions of register bit fields.

2: These bits are reserved (read as '1' and must be programmed as '1').

3: Reserved bits read as '1' and must be programmed as '1'.

4: The FGS<2> bit is a read-only copy of the GCP bit (FGS<1>).

#### 21.0 INSTRUCTION SET SUMMARY

Note:

This data sheet summarizes features of this group of dsPIC30F devices and is not intended to be a complete reference source. For more information on the CPU, peripherals, register descriptions and general device functionality, refer to the "dsPIC30F Family Reference Manual" (DS70046). For more information on the device instruction set and programming, refer to the "16-bit MCU and DSC Programmer's Reference Manual" (DS70157).

The dsPIC30F instruction set adds many enhancements to the previous PIC® MCU instruction sets, while maintaining an easy migration from PIC MCU instruction sets.

Most instructions are a single program memory word (24 bits). Only three instructions require two program memory locations.

Each single-word instruction is a 24-bit word divided into an 8-bit opcode which specifies the instruction type, and one or more operands which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into five basic categories:

- · Word or byte-oriented operations
- · Bit-oriented operations
- · Literal operations
- · DSP operations
- · Control operations

Table 21-1 shows the general symbols used in describing the instructions.

The dsPIC30F instruction set summary in Table 21-2 lists all the instructions, along with the status flags affected by each instruction.

Most word or byte-oriented W register instructions (including barrel shift instructions) have three operands:

- The first source operand which is typically a register 'Wb' without any address modifier
- The second source operand which is typically a register 'Ws' with or without an address modifier
- The destination of the result which is typically a register 'Wd' with or without an address modifier

However, word or byte-oriented file register instructions have two operands:

- The file register specified by the value 'f'
- The destination, which could either be the file register 'f' or the W0 register, which is denoted as 'WREG'

Most bit-oriented instructions (including simple rotate/shift instructions) have two operands:

- The W register (with or without an address modifier) or file register (specified by the value of 'Ws' or 'f')
- The bit in the W register or file register (specified by a literal value or indirectly by the contents of register 'Wb')

The literal instructions that involve data movement may use some of the following operands:

- A literal value to be loaded into a W register or file register (specified by the value of 'k')
- The W register or file register where the literal value is to be loaded (specified by 'Wb' or 'f')

However, literal instructions that involve arithmetic or logical operations use some of the following operands:

- The first source operand which is a register 'Wb' without any address modifier
- The second source operand which is a literal value
- The destination of the result (only if not the same as the first source operand) which is typically a register 'Wd' with or without an address modifier

The MAC class of DSP instructions may use some of the following operands:

- The accumulator (A or B) to be used (required operand)
- The W registers to be used as the two operands
- The X and Y address space prefetch operations
- The X and Y address space prefetch destinations
- The accumulator write-back destination

The other DSP instructions do not involve any multiplication, and may include:

- The accumulator to be used (required)
- The source or destination operand (designated as Wso or Wdo, respectively) with or without an address modifier
- The amount of shift specified by a W register 'Wn' or a literal value

The control instructions may use some of the following operands:

- · A program memory address
- The mode of the table read and table write instructions

All instructions are a single word, except for certain double word instructions, which were made double word instructions so that all the required information is available in these 48 bits. In the second word, the 8 MSbs are '0's. If this second word is executed as an instruction (by itself), it executes as a NOP.

Most single-word instructions are executed in a single instruction cycle, unless a conditional test is true or the program counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles with the additional instruction cycle(s) executed as a NOP. Notable exceptions are the BRA (unconditional/computed branch), indirect CALL/GOTO, all table reads and writes, and RETURN/RETFIE instructions, which are single-word instructions but take two or three cycles. Certain instruction require either

two or three cycles if the skip is performed, depending on whether the instruction being skipped is a singleword or two-word instruction. Moreover, double-word moves require two cycles. The double-word instructions execute in two instruction cycles.

**Note:** For more details on the instruction set, refer to the "16-bit DSC and MCU Programmer's Reference Manual" (DS70157).

TABLE 21-1: SYMBOLS USED IN OPCODE DESCRIPTIONS

| Field           | Description   |
|-----------------|---|
| #text           | Means literal defined by "text"   |
| (text)          | Means "content of text"   |
| [text]          | Means "the location addressed by text"                                      |
| { }             | Optional field or operation   |
| <n:m></n:m>     | Register bit field  |
| .b              | Byte mode selection   |
| .d              | Double-Word mode selection  |
| .S              | Shadow register select  |
| .w              | Word mode selection (default)   |
| Acc             | One of two accumulators {A, B}  |
| AWB             | Accumulator Write-Back Destination Address register ∈ {W13, [W13]+=2}       |
| bit4            | 4-bit bit selection field (used in word addressed instructions) ∈ {015}     |
| C, DC, N, OV, Z | MCU Status bits: Carry, Digit Carry, Negative, Overflow, Sticky Zero        |
| Expr            | Absolute address, label or expression (resolved by the linker)              |
| f               | File register address ∈ {0x00000x1FFF}                                      |
| lit1            | 1-bit unsigned literal ∈ {0,1}  |
| lit4            | 4-bit unsigned literal ∈ {015}  |
| lit5            | 5-bit unsigned literal ∈ {031}  |
| lit8            | 8-bit unsigned literal ∈ {0255}   |
| lit10           | 10-bit unsigned literal $\in$ {0255} for Byte mode, {0:1023} for Word mode  |
| lit14           | 14-bit unsigned literal ∈ {016384}  |
| lit16           | 16-bit unsigned literal ∈ {065535}  |
| lit23           | 23-bit unsigned literal ∈ {08388608}; LSB must be 0                         |
| None            | Field does not require an entry, may be blank                               |
| OA, OB, SA, SB  | DSP Status bits: AccA Overflow, AccB Overflow, AccA Saturate, AccB Saturate |
| PC              | Program Counter   |
| Slit10          | 10-bit signed literal ∈ {-512511}   |
| Slit16          | 16-bit signed literal ∈ {-3276832767}                                       |
| Slit6           | 6-bit signed literal ∈ {-1616}  |

TABLE 21-1: SYMBOLS USED IN OPCODE DESCRIPTIONS (CONTINUED)

| Field | Description   |
|-------|---|
| Wb    | Base W register ∈ {W0W15}   |
| Wd    | Destination W register ∈ { Wd, [Wd], [Wd++], [Wd], [++Wd], [Wd] }   |
| Wdo   | Destination W register ∈ { Wnd, [Wnd], [Wnd++], [Wnd], [++Wnd], [Wnd], [Wnd+Wb] }   |
| Wm,Wn | Dividend, Divisor Working register pair (direct addressing)   |
| Wm*Wm | Multiplicand and Multiplier working register pair for Square instructions ∈ {W4*W4,W5*W5,W6*W6,W7*W7}   |
| Wm*Wn | Multiplicand and Multiplier working register pair for DSP instructions ∈ {W4*W5,W4*W6,W4*W7,W5*W6,W5*W7,W6*W7}  |
| Wn    | One of 16 working registers ∈ {W0W15}   |
| Wnd   | One of 16 destination working registers ∈ {W0W15}   |
| Wns   | One of 16 source working registers ∈ {W0W15}  |
| WREG  | W0 (working register used in file register instructions)  |
| Ws    | Source W register ∈ { Ws, [Ws], [Ws++], [Ws], [++Ws], [Ws] }  |
| Wso   | Source W register ∈ { Wns, [Wns], [Wns++], [Wns], [++Wns], [Wns], [Wns+Wb] }  |
| Wx    | X data space prefetch address register for DSP instructions  { [W8]+=6, [W8]+=4, [W8]+=2, [W8], [W8]-=6, [W8]-=4, [W8]-=2, [W9]+=6, [W9]+=4, [W9]+=2, [W9], [W9]-=6, [W9]-=4, [W9]-=2, [W9+W12],none}                 |
| Wxd   | X data space prefetch destination register for DSP instructions ∈ {W4W7}  |
| Wy    | Y data space prefetch address register for DSP instructions ∈ {[W10]+=6, [W10]+=4, [W10]+=2, [W10], [W10]-=6, [W10]-=4, [W10]-=2, [W11]+=6, [W11]+=4, [W11]+=2, [W11], [W11]-=6, [W11]-=4, [W11]-=2, [W11+W12], none} |
| Wyd   | Y data space prefetch destination register for DSP instructions ∈ {W4W7}  |

TABLE 21-2: INSTRUCTION SET OVERVIEW

| Base<br>Instr<br># | Assembly<br>Mnemoni<br>c |       | Assembly Syntax      | Description                                      | # of<br>Words | # of<br>Cycles                                   | Status Flags<br>Affected |
|--------------------|--------------------------|-------|----------------------|--|---------------|--|--------------------------|
| 1                  | ADD                      | ADD   | Acc                  | Add Accumulators                                 | 1             | 1  | OA,OB,SA,SB              |
|                    |                          | ADD   | f                    | f = f + WREG                                     | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADD   | f,WREG               | WREG = f + WREG                                  | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADD   | #lit10,Wn            | Wd = lit10 + Wd                                  | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADD   | Wb,Ws,Wd             | Wd = Wb + Ws                                     | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADD   | Wb,#lit5,Wd          | Wd = Wb + lit5                                   | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADD   | Wso,#Slit4,Acc       | 16-bit Signed Add to Accumulator                 | 1             | 1  | OA,OB,SA,SB              |
| 2                  | ADDC                     | ADDC  | f                    | f = f + WREG + (C)                               | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADDC  | f,WREG               | WREG = f + WREG + (C)                            | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADDC  | #lit10,Wn            | Wd = lit10 + Wd + (C)                            | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADDC  | Wb,Ws,Wd             | Wd = Wb + Ws + (C)                               | 1             | 1  | C,DC,N,OV,Z              |
|                    |                          | ADDC  | Wb,#lit5,Wd          | Wd = Wb + lit5 + (C)                             | 1             | 1  | C,DC,N,OV,Z              |
| 3                  | AND                      | AND   | f                    | f = f .AND. WREG                                 | 1             | 1  | N,Z                      |
|                    |                          | AND   | f,WREG               | WREG = f .AND. WREG                              | 1             | 1  | N,Z                      |
|                    |                          | AND   | #lit10,Wn            | Wd = lit10 .AND. Wd                              | 1             | 1  | N,Z                      |
|                    |                          | AND   | Wb,Ws,Wd             | Wd = Wb .AND. Ws                                 | 1             | 1  | N,Z                      |
|                    |                          | AND   | Wb,#lit5,Wd          | Wd = Wb .AND. lit5                               | 1             | 1  | N,Z                      |
| 4                  | ASR                      | ASR   | f                    | f = Arithmetic Right Shift f                     | 1             | 1  | C,N,OV,Z                 |
|                    |                          | ASR   | f,WREG               | WREG = Arithmetic Right Shift f                  | 1             | 1  | C,N,OV,Z                 |
|                    |                          | ASR   | Ws,Wd                | Wd = Arithmetic Right Shift Ws                   | 1             | 1  | C,N,OV,Z                 |
|                    |                          | ASR   | Wb, Wns, Wnd         | Wnd = Arithmetic Right Shift Wb by Wns           | 1             | 1  | N,Z                      |
|                    |                          | ASR   | Wb,#lit5,Wnd         | Wnd = Arithmetic Right Shift Wb by lit5          | 1             | 1  | N,Z                      |
| 5                  | BCLR                     | BCLR  | f,#bit4              | Bit Clear f                                      | 1             | 1  | None                     |
|                    | 2021                     | BCLR  | Ws,#bit4             | Bit Clear Ws                                     | 1             | 1  | None                     |
| 6                  | BRA                      | BRA   | C,Expr               | Branch if Carry                                  | 1             | 1 (2)  | None                     |
| J                  | Ditti                    | BRA   | GE, Expr             | Branch if Greater than or Equal                  | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | GEU, Expr            | Branch if Unsigned Greater than or Equal         | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | GT, Expr             | Branch if Greater than                           | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | GTU, Expr            | Branch if Unsigned Greater than                  | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | LE, Expr             | Branch if Less than or Equal                     | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | LEU, Expr            | Branch if Unsigned Less than or Equal            | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | LT, Expr             | Branch if Less than                              | 1             | 1 (2)  | None                     |
|                    |                          | BRA   |                      |  | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | LTU, Expr            | Branch if Unsigned Less than  Branch if Negative | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | N, Expr              | Branch if Not Carry                              | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | NC, Expr<br>NN, Expr | Branch if Not Negative                           | 1             | 1 (2)  | None                     |
|                    |                          |       | <del>_</del>         |  | 1             | <del>                                     </del> |                          |
|                    |                          | BRA   | NOV, Expr            | Branch if Not Overflow                           | +             | 1 (2)  | None                     |
|                    |                          | BRA   | NZ,Expr              | Branch if Acquirellator A Quartley               | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | OA, Expr             | Branch if Accumulator A Overflow                 | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | OB, Expr             | Branch if Accumulator B Overflow                 | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | OV,Expr              | Branch if Overflow                               | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | SA, Expr             | Branch if Accumulator A Saturated                | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | SB,Expr              | Branch if Accumulator B Saturated                | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | Expr                 | Branch Unconditionally                           | 1             | 2  | None                     |
|                    |                          | BRA   | Z,Expr               | Branch if Zero                                   | 1             | 1 (2)  | None                     |
|                    |                          | BRA   | Wn                   | Computed Branch                                  | 1             | 2  | None                     |
| 7                  | BSET                     | BSET  | f,#bit4              | Bit Set f  | 1             | 1  | None                     |
|                    |                          | BSET  | Ws,#bit4             | Bit Set Ws                                       | 1             | 1  | None                     |
| 8                  | BSW                      | BSW.C | Ws,Wb                | Write C bit to Ws <wb></wb>                      | 1             | 1  | None                     |
|                    |                          | BSW.Z | Ws,Wb                | Write Z bit to Ws <wb></wb>                      | 1             | 1  | None                     |

| Base<br>Instr<br># | Assembly<br>Mnemoni<br>c |         | Assembly Syntax            | Description                                   | # of<br>Words | # of<br>Cycles | Status Flags<br>Affected |
|--------------------|--------------------------|---------|----------------------------|---|---------------|----------------|--------------------------|
| 9                  | BTG                      | BTG     | f,#bit4                    | Bit Toggle f                                  | 1             | 1              | None                     |
|                    |                          | BTG     | Ws,#bit4                   | Bit Toggle Ws                                 | 1             | 1              | None                     |
| 10                 | BTSC                     | BTSC    | f,#bit4                    | Bit Test f, Skip if Clear                     | 1             | 1<br>(2 or 3)  | None                     |
|                    |                          | BTSC    | Ws,#bit4                   | Bit Test Ws, Skip if Clear                    | 1             | 1<br>(2 or 3)  | None                     |
| 11                 | BTSS                     | BTSS    | f,#bit4                    | Bit Test f, Skip if Set                       | 1             | 1<br>(2 or 3)  | None                     |
|                    |                          | BTSS    | Ws,#bit4                   | Bit Test Ws, Skip if Set                      | 1             | 1<br>(2 or 3)  | None                     |
| 12                 | BTST                     | BTST    | f,#bit4                    | Bit Test f                                    | 1             | 1              | Z                        |
|                    |                          | BTST.C  | Ws,#bit4                   | Bit Test Ws to C                              | 1             | 1              | С                        |
|                    |                          | BTST.Z  | Ws,#bit4                   | Bit Test Ws to Z                              | 1             | 1              | Z                        |
|                    |                          | BTST.C  | Ws,Wb                      | Bit Test Ws <wb> to C</wb>                    | 1             | 1              | С                        |
|                    |                          | BTST.Z  | Ws,Wb                      | Bit Test Ws <wb> to Z</wb>                    | 1             | 1              | Z                        |
| 13                 | BTSTS                    | BTSTS   | f,#bit4                    | Bit Test then Set f                           | 1             | 1              | Z                        |
|                    |                          | BTSTS.C | Ws,#bit4                   | Bit Test Ws to C, then Set                    | 1             | 1              | С                        |
|                    |                          | BTSTS.Z | Ws,#bit4                   | Bit Test Ws to Z, then Set                    | 1             | 1              | Z                        |
| 14                 | CALL                     | CALL    | lit23                      | Call Subroutine                               | 2             | 2              | None                     |
|                    |                          | CALL    | Wn                         | Call Indirect Subroutine                      | 1             | 2              | None                     |
| 15                 | CLR                      | CLR     | f                          | f = 0x0000                                    | 1             | 1              | None                     |
|                    |                          | CLR     | WREG                       | WREG = 0x0000                                 | 1             | 1              | None                     |
|                    |                          | CLR     | Ws                         | Ws = 0x0000                                   | 1             | 1              | None                     |
|                    |                          | CLR     | Acc, Wx, Wxd, Wy, Wyd, AWB | Clear Accumulator                             | 1             | 1              | OA,OB,SA,SB              |
| 16                 | CLRWDT                   | CLRWDT  |                            | Clear Watchdog Timer                          | 1             | 1              | WDTO, Sleep              |
| 17                 | COM                      | COM     | f                          | $f = \overline{f}$                            | 1             | 1              | N,Z                      |
|                    |                          | COM     | f,WREG                     | WREG = $\overline{f}$                         | 1             | 1              | N,Z                      |
|                    |                          | COM     | Ws,Wd                      | $Wd = \overline{Ws}$                          | 1             | 1              | N,Z                      |
| 18                 | CP                       | CP      | f                          | Compare f with WREG                           | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | CP      | Wb,#lit5                   | Compare Wb with lit5                          | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | CP      | Wb,Ws                      | Compare Wb with Ws (Wb – Ws)                  | 1             | 1              | C,DC,N,OV,Z              |
| 19                 | CP0                      | CP0     | f                          | Compare f with 0x0000                         | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | CP0     | Ws                         | Compare Ws with 0x0000                        | 1             | 1              | C,DC,N,OV,Z              |
| 20                 | CPB                      | CPB     | f                          | Compare f with WREG, with Borrow              | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | CPB     | Wb,#lit5                   | Compare Wb with lit5, with Borrow             | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | CPB     | Wb,Ws                      | Compare Wb with Ws, with Borrow (Wb – Ws – C) | 1             | 1              | C,DC,N,OV,Z              |
| 21                 | CPSEQ                    | CPSEQ   | Wb, Wn                     | Compare Wb with Wn, Skip if =                 | 1             | 1<br>(2 or 3)  | None                     |
| 22                 | CPSGT                    | CPSGT   | Wb, Wn                     | Compare Wb with Wn, Skip if >                 | 1             | 1<br>(2 or 3)  | None                     |
| 23                 | CPSLT                    | CPSLT   | Wb, Wn                     | Compare Wb with Wn, Skip if <                 | 1             | 1<br>(2 or 3)  | None                     |
| 24                 | CPSNE                    | CPSNE   | Wb, Wn                     | Compare Wb with Wn, Skip if ≠                 | 1             | 1<br>(2 or 3)  | None                     |
| 25                 | DAW                      | DAW     | Wn                         | Wn = Decimal Adjust Wn                        | 1             | 1              | С                        |
| 26                 | DEC                      | DEC     | f                          | f = f - 1                                     | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | DEC     | f,WREG                     | WREG = f - 1                                  | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | DEC     | Ws,Wd                      | Wd = Ws - 1                                   | 1             | 1              | C,DC,N,OV,Z              |
| 27                 | DEC2                     | DEC2    | f                          | f = f - 2                                     | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | DEC2    | f,WREG                     | WREG = f - 2                                  | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | DEC2    | Ws,Wd                      | Wd = Ws - 2                                   | 1             | 1              | C,DC,N,OV,Z              |
| 28                 | DISI                     | DISI    | #lit14                     | Disable Interrupts for k Instruction Cycles   | 1             | 1              | None                     |

| IABLI              | E 21-2:                  | INSTRUCTION SET OVERVIEW (CONTINUED) |                              |  |               |                |                          |  |  |  |  |  |
|--------------------|--------------------------|--------------------------------------|------------------------------|--|---------------|----------------|--------------------------|--|--|--|--|--|
| Base<br>Instr<br># | Assembly<br>Mnemoni<br>c |                                      | Assembly Syntax              | Description                            | # of<br>Words | # of<br>Cycles | Status Flags<br>Affected |  |  |  |  |  |
| 29                 | DIV                      | DIV.S                                | Wm,Wn                        | Signed 16/16-Bit Integer Divide        | 1             | 18             | N,Z,C,OV                 |  |  |  |  |  |
|                    |                          | DIV.SD                               | Wm,Wn                        | Signed 32/16-Bit Integer Divide        | 1             | 18             | N,Z,C,OV                 |  |  |  |  |  |
|                    |                          | DIV.U                                | Wm,Wn                        | Unsigned 16/16-Bit Integer Divide      | 1             | 18             | N,Z,C,OV                 |  |  |  |  |  |
|                    |                          | DIV.UD                               | Wm,Wn                        | Unsigned 32/16-Bit Integer Divide      | 1             | 18             | N,Z,C,OV                 |  |  |  |  |  |
| 30                 | DIVF                     | DIVF                                 | Wm,Wn                        | Signed 16/16-bit Fractional Divide     | 1             | 18             | N,Z,C,OV                 |  |  |  |  |  |
| 31                 | DO                       | DO                                   | #lit14,Expr                  | Do Code to PC+Expr, lit14 + 1 Times    | 2             | 2              | None                     |  |  |  |  |  |
|                    |                          | DO                                   | Wn,Expr                      | Do Code to PC+Expr, (Wn) + 1 Times     | 2             | 2              | None                     |  |  |  |  |  |
| 32                 | ED                       | ED                                   | Wm*Wm,Acc,Wx,Wy,Wxd          | Euclidean Distance (no accumulate)     | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |  |  |  |  |  |
| 33                 | EDAC                     | EDAC                                 | Wm*Wm,Acc,Wx,Wy,Wxd          | Euclidean Distance                     | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |  |  |  |  |  |
| 34                 | EXCH                     | EXCH                                 | Wns,Wnd                      | Swap Wns with Wnd                      | 1             | 1              | None                     |  |  |  |  |  |
| 35                 | FBCL                     | FBCL                                 | Ws,Wnd                       | Find Bit Change from Left (MSb) Side   | 1             | 1              | С                        |  |  |  |  |  |
| 36                 | FF1L                     | FF1L                                 | Ws,Wnd                       | Find First One from Left (MSb) Side    | 1             | 1              | С                        |  |  |  |  |  |
| 37                 | FF1R                     | FF1R                                 | Ws,Wnd                       | Find First One from Right (LSb) Side   | 1             | 1              | С                        |  |  |  |  |  |
| 38                 | GOTO                     | GOTO                                 | Expr                         | Go to address                          | 2             | 2              | None                     |  |  |  |  |  |
|                    |                          | GOTO                                 | Wn                           | Go to indirect                         | 1             | 2              | None                     |  |  |  |  |  |
| 39                 | INC                      | INC                                  | f                            | f = f + 1                              | 1             | 1              | C,DC,N,OV,Z              |  |  |  |  |  |
|                    |                          | INC                                  | f,WREG                       | WREG = f + 1                           | 1             | 1              | C,DC,N,OV,Z              |  |  |  |  |  |
|                    |                          | INC                                  | Ws,Wd                        | Wd = Ws + 1                            | 1             | 1              | C,DC,N,OV,Z              |  |  |  |  |  |
| 40                 | INC2                     | INC2                                 | f                            | f = f + 2                              | 1             | 1              | C,DC,N,OV,Z              |  |  |  |  |  |
|                    |                          | INC2                                 | f,WREG                       | WREG = f + 2                           | 1             | 1              | C,DC,N,OV,Z              |  |  |  |  |  |
|                    |                          | INC2                                 | Ws,Wd                        | Wd = Ws + 2                            | 1             | 1              | C,DC,N,OV,Z              |  |  |  |  |  |
| 41                 | IOR                      | IOR                                  | f                            | f = f .IOR. WREG                       | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | IOR                                  | f,WREG                       | WREG = f .IOR. WREG                    | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | IOR                                  | #lit10,Wn                    | Wd = lit10 .IOR. Wd                    | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | IOR                                  | Wb,Ws,Wd                     | Wd = Wb .IOR. Ws                       | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | IOR                                  | Wb,#lit5,Wd                  | Wd = Wb .IOR. lit5                     | 1             | 1              | N,Z                      |  |  |  |  |  |
| 42                 | LAC                      | LAC                                  | Wso,#Slit4,Acc               | Load Accumulator                       | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |  |  |  |  |  |
| 43                 | LNK                      | LNK                                  | #lit14                       | Link Frame Pointer                     | 1             | 1              | None                     |  |  |  |  |  |
| 44                 | LSR                      | LSR                                  | f                            | f = Logical Right Shift f              | 1             | 1              | C,N,OV,Z                 |  |  |  |  |  |
|                    |                          | LSR                                  | f,WREG                       | WREG = Logical Right Shift f           | 1             | 1              | C,N,OV,Z                 |  |  |  |  |  |
|                    |                          | LSR                                  | Ws,Wd                        | Wd = Logical Right Shift Ws            | 1             | 1              | C,N,OV,Z                 |  |  |  |  |  |
|                    |                          | LSR                                  | Wb, Wns, Wnd                 | Wnd = Logical Right Shift Wb by Wns    | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | LSR                                  | Wb,#lit5,Wnd                 | Wnd = Logical Right Shift Wb by lit5   | 1             | 1              | N,Z                      |  |  |  |  |  |
| 45                 | MAC                      | MAC                                  | Wm*Wn,Acc,Wx,Wxd,Wy,Wyd,     | Multiply and Accumulate                | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |  |  |  |  |  |
|                    |                          | MAC                                  | Wm*Wm, Acc, Wx, Wxd, Wy, Wyd | Square and Accumulate                  | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |  |  |  |  |  |
| 46                 | MOV                      | MOV                                  | f,Wn                         | Move f to Wn                           | 1             | 1              | None                     |  |  |  |  |  |
|                    |                          | MOV                                  | f                            | Move f to f                            | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | MOV                                  | f,WREG                       | Move f to WREG                         | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | MOV                                  | #lit16,Wn                    | Move 16-Bit Literal to Wn              | 1             | 1              | None                     |  |  |  |  |  |
|                    |                          | MOV.b                                | #lit8,Wn                     | Move 8-Bit Literal to Wn               | 1             | 1              | None                     |  |  |  |  |  |
|                    |                          | MOV                                  | Wn,f                         | Move Wn to f                           | 1             | 1              | None                     |  |  |  |  |  |
|                    |                          | MOV                                  | Wso,Wdo                      | Move Ws to Wd                          | 1             | 1              | None                     |  |  |  |  |  |
|                    |                          | MOV                                  | WREG, f                      | Move WREG to f                         | 1             | 1              | N,Z                      |  |  |  |  |  |
|                    |                          | MOV.D                                | Wns,Wd                       | Move Double from W(ns):W(ns+1) to Wd   | 1             | 2              | None                     |  |  |  |  |  |
|                    |                          | MOV.D                                | Ws, Wnd                      | Move Double from Ws to W(nd+1):W(nd)   | 1             | 2              | None                     |  |  |  |  |  |
|                    |                          | MOV.D                                | WS, WILL                     | INIOVE DOUBLE HOTH WS to W(Hu+1).W(Hu) | ļ !           |                | INOTIC                   |  |  |  |  |  |

| Base<br>Instr<br># | Assembly<br>Mnemoni<br>c |                   | Assembly Syntax                          | Description                                  | # of<br>Words | # of<br>Cycles | Status Flags<br>Affected |
|--------------------|--------------------------|-------------------|--|--|---------------|----------------|--------------------------|
| 48                 | MPY                      | MPY<br>Wm*Wn,Ad   | cc,Wx,Wxd,Wy,Wyd                         | Multiply Wm by Wn to Accumulator             | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
|                    |                          | MPY<br>Wm*Wm,Ad   | cc,Wx,Wxd,Wy,Wyd                         | Square Wm to Accumulator                     | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
| 49                 | MPY.N                    | MPY.N<br>Wm*Wn,Ad | cc,Wx,Wxd,Wy,Wyd                         | -(Multiply Wm by Wn) to Accumulator          | 1             | 1              | None                     |
| 50                 | MSC                      | MSC               | Wm*Wm, Acc, Wx, Wxd, Wy, Wyd<br>,<br>AWB | Multiply and Subtract from Accumulator       | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
| 51                 | MUL                      | MUL.SS            | Wb, Ws, Wnd                              | {Wnd+1, Wnd} = Signed(Wb) * Signed(Ws)       | 1             | 1              | None                     |
|                    |                          | MUL.SU            | Wb,Ws,Wnd                                | {Wnd+1, Wnd} = Signed(Wb) *<br>Unsigned(Ws)  | 1             | 1              | None                     |
|                    |                          | MUL.US            | Wb,Ws,Wnd                                | {Wnd+1, Wnd} = Unsigned(Wb) * Signed(Ws)     | 1             | 1              | None                     |
|                    |                          | MUL.UU            | Wb,Ws,Wnd                                | {Wnd+1, Wnd} = Unsigned(Wb) * Unsigned(Ws)   | 1             | 1              | None                     |
|                    |                          | MUL.SU            | Wb,#lit5,Wnd                             | {Wnd+1, Wnd} = Signed(Wb) * Unsigned(lit5)   | 1             | 1              | None                     |
|                    |                          | MUL.UU            | Wb,#lit5,Wnd                             | {Wnd+1, Wnd} = Unsigned(Wb) * Unsigned(lit5) | 1             | 1              | None                     |
|                    |                          | MUL               | f  | W3:W2 = f * WREG                             | 1             | 1              | None                     |
| 52                 | NEG                      | NEG               | Acc                                      | Negate Accumulator                           | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
|                    |                          | NEG               | f  | $f = \overline{f} + 1$                       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | NEG               | f,WREG                                   | WREG = $\overline{f}$ + 1                    | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | NEG               | Ws,Wd                                    | $Wd = \overline{Ws} + 1$                     | 1             | 1              | C,DC,N,OV,Z              |
| 53                 | NOP                      | NOP               |  | No Operation                                 | 1             | 1              | None                     |
|                    |                          | NOPR              |  | No Operation                                 | 1             | 1              | None                     |
| 54                 | POP                      | POP               | f  | Pop f from Top-of-Stack (TOS)                | 1             | 1              | None                     |
|                    |                          | POP               | Wdo                                      | Pop from Top-of-Stack (TOS) to Wdo           | 1             | 1              | None                     |
|                    |                          | POP.D             | Wnd                                      | Pop from Top-of-Stack (TOS) to W(nd):W(nd+1) | 1             | 2              | None                     |
|                    |                          | POP.S             |  | Pop Shadow Registers                         | 1             | 1              | All                      |
| 55                 | PUSH                     | PUSH              | f  | Push f to Top-of-Stack (TOS)                 | 1             | 1              | None                     |
|                    |                          | PUSH              | Wso                                      | Push Wso to Top-of-Stack (TOS)               | 1             | 1              | None                     |
|                    |                          | PUSH.D            | Wns                                      | Push W(ns):W(ns+1) to Top-of-Stack (TOS)     | 1             | 2              | None                     |
|                    |                          | PUSH.S            |  | Push Shadow Registers                        | 1             | 1              | None                     |
| 56                 | PWRSAV                   | PWRSAV            | #lit1                                    | Go into Sleep or Idle mode                   | 1             | 1              | WDTO, Sleep              |
| 57                 | RCALL                    | RCALL             | Expr                                     | Relative Call                                | 1             | 2              | None                     |
|                    |                          | RCALL             | Wn                                       | Computed Call                                | 1             | 2              | None                     |
| 58                 | REPEAT                   | REPEAT            | #lit14                                   | Repeat Next Instruction lit14+1 Times        | 1             | 1              | None                     |
|                    |                          | REPEAT            | Wn                                       | Repeat Next Instruction (Wn)+1 Times         | 1             | 1              | None                     |
| 59                 | RESET                    | RESET             |  | Software Device Reset                        | 1             | 1              | None                     |
| 60                 | RETFIE                   | RETFIE            |  | Return from Interrupt                        | 1             | 3 (2)          | None                     |
| 61                 | RETLW                    | RETLW             | #lit10,Wn                                | Return with Literal in Wn                    | 1             | 3 (2)          | None                     |
| 62                 | RETURN                   | RETURN            |  | Return from Subroutine                       | 1             | 3 (2)          | None                     |
| 63                 | RLC                      | RLC               | f  | f = Rotate Left through Carry f              | 1             | 1              | C,N,Z                    |
|                    |                          | RLC               | f,WREG                                   | WREG = Rotate Left through Carry f           | 1             | 1              | C,N,Z                    |
|                    |                          | RLC               | Ws,Wd                                    | Wd = Rotate Left through Carry Ws            | 1             | 1              | C,N,Z                    |
| 64                 | RLNC                     | RLNC              | f  | f = Rotate Left (No Carry) f                 | 1             | 1              | N,Z                      |
|                    |                          | RLNC              | f,WREG                                   | WREG = Rotate Left (No Carry) f              | 1             | 1              | N,Z                      |
|                    |                          | RLNC              | Ws,Wd                                    | Wd = Rotate Left (No Carry) Ws               | 1             | 1              | N,Z                      |
| 65                 | RRC                      | RRC               | f  | f = Rotate Right through Carry f             | 1             | 1              | C,N,Z                    |
|                    |                          | RRC               | f,WREG                                   | WREG = Rotate Right through Carry f          | 1             | 1              | C,N,Z                    |
|                    |                          | RRC               | Ws,Wd                                    | Wd = Rotate Right through Carry Ws           | 1             | 1              | C,N,Z                    |

| IADL               | E 21-2:                  | INSTR  | UCTION SET OVER | RVIEW (CONTINUED)                     |               |                |                          |
|--------------------|--------------------------|--------|-----------------|---------------------------------------|---------------|----------------|--------------------------|
| Base<br>Instr<br># | Assembly<br>Mnemoni<br>c |        | Assembly Syntax | Description                           | # of<br>Words | # of<br>Cycles | Status Flags<br>Affected |
| 66                 | RRNC                     | RRNC   | f               | f = Rotate Right (No Carry) f         | 1             | 1              | N,Z                      |
|                    |                          | RRNC   | f,WREG          | WREG = Rotate Right (No Carry) f      | 1             | 1              | N,Z                      |
|                    |                          | RRNC   | Ws,Wd           | Wd = Rotate Right (No Carry) Ws       | 1             | 1              | N,Z                      |
| 67                 | SAC                      | SAC    | Acc,#Slit4,Wdo  | Store Accumulator                     | 1             | 1              | None                     |
|                    |                          | SAC.R  | Acc,#Slit4,Wdo  | Store Rounded Accumulator             | 1             | 1              | None                     |
| 68                 | SE                       | SE     | Ws,Wnd          | Wnd = Sign-Extended Ws                | 1             | 1              | C,N,Z                    |
| 69                 | SETM                     | SETM   | f               | f = 0xFFFF                            | 1             | 1              | None                     |
|                    |                          | SETM   | WREG            | WREG = 0xFFFF                         | 1             | 1              | None                     |
|                    |                          | SETM   | Ws              | Ws = 0xFFFF                           | 1             | 1              | None                     |
| 70                 | SFTAC                    | SFTAC  | Acc, Wn         | Arithmetic Shift Accumulator by (Wn)  | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
|                    |                          | SFTAC  | Acc,#Slit6      | Arithmetic Shift Accumulator by Slit6 | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
| 71                 | SL                       | SL     | f               | f = Left Shift f                      | 1             | 1              | C,N,OV,Z                 |
|                    |                          | SL     | f,WREG          | WREG = Left Shift f                   | 1             | 1              | C,N,OV,Z                 |
|                    |                          | SL     | Ws,Wd           | Wd = Left Shift Ws                    | 1             | 1              | C,N,OV,Z                 |
|                    |                          | SL     | Wb,Wns,Wnd      | Wnd = Left Shift Wb by Wns            | 1             | 1              | N,Z                      |
|                    |                          | SL     | Wb,#lit5,Wnd    | Wnd = Left Shift Wb by lit5           | 1             | 1              | N,Z                      |
| 72                 | SUB                      | SUB    | Acc             | Subtract Accumulators                 | 1             | 1              | OA,OB,OAB,<br>SA,SB,SAB  |
|                    |                          | SUB    | f               | f = f - WREG                          | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUB    | f,WREG          | WREG = f - WREG                       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUB    | #lit10,Wn       | Wn = Wn - lit10                       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUB    | Wb,Ws,Wd        | Wd = Wb - Ws                          | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUB    | Wb,#lit5,Wd     | Wd = Wb - Iit5                        | 1             | 1              | C,DC,N,OV,Z              |
| 73                 | SUBB                     | SUBB   | f               | $f = f - WREG - (\overline{C})$       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBB   | f,WREG          | $WREG = f - WREG - (\overline{C})$    | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBB   | #lit10,Wn       | $Wn = Wn - lit10 - (\overline{C})$    | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBB   | Wb,Ws,Wd        | $Wd = Wb - Ws - (\overline{C})$       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBB   | Wb,#lit5,Wd     | $Wd = Wb - lit5 - (\overline{C})$     | 1             | 1              | C,DC,N,OV,Z              |
| 74                 | SUBR                     | SUBR   | f               | f = WREG - f                          | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBR   | f,WREG          | WREG = WREG- f                        | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBR   | Wb,Ws,Wd        | Wd = Ws - Wb                          | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBR   | Wb,#lit5,Wd     | Wd = lit5 - Wb                        | 1             | 1              | C,DC,N,OV,Z              |
| 75                 | SUBBR                    | SUBBR  | f               | $f = WREG - f - (\overline{C})$       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBBR  | f,WREG          | WREG = WREG – f – $(\overline{C})$    | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBBR  | Wb,Ws,Wd        | $Wd = Ws - Wb - (\overline{C})$       | 1             | 1              | C,DC,N,OV,Z              |
|                    |                          | SUBBR  | Wb,#lit5,Wd     | $Wd = lit5 - Wb - (\overline{C})$     | 1             | 1              | C,DC,N,OV,Z              |
| 76                 | SWAP                     | SWAP.b | Wn              | Wn = Nibble Swap Wn                   | 1             | 1              | None                     |
|                    |                          | SWAP   | Wn              | Wn = Byte Swap Wn                     | 1             | 1              | None                     |
| 77                 | TBLRDH                   | TBLRDH | Ws,Wd           | Read Prog<23:16> to Wd<7:0>           | 1             | 2              | None                     |
| 78                 | TBLRDL                   | TBLRDL | Ws,Wd           | Read Prog<15:0> to Wd                 | 1             | 2              | None                     |
| 79                 | TBLWTH                   | TBLWTH | Ws,Wd           | Write Ws<7:0> to Prog<23:16>          | 1             | 2              | None                     |
| 80                 | TBLWTL                   | TBLWTL | Ws,Wd           | Write Ws to Prog<15:0>                | 1             | 2              | None                     |
| 81                 | ULNK                     | ULNK   |                 | Unlink Frame Pointer                  | 1             | 1              | None                     |
| 82                 | XOR                      | XOR    | f               | f = f .XOR. WREG                      | 1             | 1              | N,Z                      |
|                    |                          | XOR    | f,WREG          | WREG = f .XOR. WREG                   | 1             | 1              | N,Z                      |
|                    |                          | XOR    | #lit10,Wn       | Wd = lit10 .XOR. Wd                   | 1             | 1              | N,Z                      |
|                    |                          | XOR    | Wb,Ws,Wd        | Wd = Wb .XOR. Ws                      | 1             | 1              | N,Z                      |
|                    |                          | XOR    | Wb,#lit5,Wd     | Wd = Wb .XOR. lit5                    | 1             | 1              | N,Z                      |
| 83                 | ZE                       | ZE     | Ws, Wnd         | Wnd = Zero-Extend Ws                  | 1             | 1              | C,Z,N                    |

#### 22.0 DEVELOPMENT SUPPORT

The PIC® microcontrollers and dsPIC® digital signal controllers are supported with a full range of software and hardware development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Compilers/Assemblers/Linkers
  - MPLAB C Compiler for Various Device Families
  - HI-TECH C for Various Device Families
  - MPASM<sup>TM</sup> Assembler
  - MPLINK<sup>TM</sup> Object Linker/ MPLIB<sup>TM</sup> Object Librarian
  - MPLAB Assembler/Linker/Librarian for Various Device Families
- Simulators
  - MPLAB SIM Software Simulator
- Emulators
  - MPLAB REAL ICE™ In-Circuit Emulator
- · In-Circuit Debuggers
  - MPLAB ICD 3
  - PICkit™ 3 Debug Express
- Device Programmers
  - PICkit™ 2 Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration/Development Boards, Evaluation Kits, and Starter Kits

## 22.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16/32-bit microcontroller market. The MPLAB IDE is a Windows® operating system-based application that contains:

- A single graphical interface to all debugging tools
  - Simulator
  - Programmer (sold separately)
  - In-Circuit Emulator (sold separately)
  - In-Circuit Debugger (sold separately)
- · A full-featured editor with color-coded context
- A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- Mouse over variable inspection
- Drag and drop variables from source to watch windows
- · Extensive on-line help
- Integration of select third party tools, such as IAR C Compilers

The MPLAB IDE allows you to:

- Edit your source files (either C or assembly)
- One-touch compile or assemble, and download to emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - Source files (C or assembly)
  - Mixed C and assembly
  - Machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost-effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increased flexibility and power.

## 22.2 MPLAB C Compilers for Various Device Families

The MPLAB C Compiler code development systems are complete ANSI C compilers for Microchip's PIC18, PIC24 and PIC32 families of microcontrollers and the dsPIC30 and dsPIC33 families of digital signal controllers. These compilers provide powerful integration capabilities, superior code optimization and ease of use.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

# 22.3 HI-TECH C for Various Device Families

The HI-TECH C Compiler code development systems are complete ANSI C compilers for Microchip's PIC family of microcontrollers and the dsPIC family of digital signal controllers. These compilers provide powerful integration capabilities, omniscient code generation and ease of use.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

The compilers include a macro assembler, linker, preprocessor, and one-step driver, and can run on multiple platforms.

#### 22.4 MPASM Assembler

The MPASM Assembler is a full-featured, universal macro assembler for PIC10/12/16/18 MCUs.

The MPASM Assembler generates relocatable object files for the MPLINK Object Linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM Assembler features include:

- · Integration into MPLAB IDE projects
- User-defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

#### 22.5 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK Object Linker combines relocatable objects created by the MPASM Assembler and the MPLAB C18 C Compiler. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB Object Librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

# 22.6 MPLAB Assembler, Linker and Librarian for Various Device Families

MPLAB Assembler produces relocatable machine code from symbolic assembly language for PIC24, PIC32 and dsPIC devices. MPLAB C Compiler uses the assembler to produce its object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- · Support for the entire device instruction set
- · Support for fixed-point and floating-point data
- · Command line interface
- · Rich directive set
- · Flexible macro language
- MPLAB IDE compatibility

#### 22.7 MPLAB SIM Software Simulator

The MPLAB SIM Software Simulator allows code development in a PC-hosted environment by simulating the PIC MCUs and dsPIC® DSCs on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a comprehensive stimulus controller. Registers can be logged to files for further run-time analysis. The trace buffer and logic analyzer display extend the power of the simulator to record and track program execution, actions on I/O, most peripherals and internal registers.

The MPLAB SIM Software Simulator fully supports symbolic debugging using the MPLAB C Compilers, and the MPASM and MPLAB Assemblers. The software simulator offers the flexibility to develop and debug code outside of the hardware laboratory environment, making it an excellent, economical software development tool.

#### 22.8 MPLAB REAL ICE In-Circuit Emulator System

MPLAB REAL ICE In-Circuit Emulator System is Microchip's next generation high-speed emulator for Microchip Flash DSC and MCU devices. It debugs and programs PIC<sup>®</sup> Flash MCUs and dsPIC<sup>®</sup> Flash DSCs with the easy-to-use, powerful graphical user interface of the MPLAB Integrated Development Environment (IDE), included with each kit.

The emulator is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with either a connector compatible with incircuit debugger systems (RJ11) or with the new high-speed, noise tolerant, Low-Voltage Differential Signal (LVDS) interconnection (CAT5).

The emulator is field upgradable through future firmware downloads in MPLAB IDE. In upcoming releases of MPLAB IDE, new devices will be supported, and new features will be added. MPLAB REAL ICE offers significant advantages over competitive emulators including low-cost, full-speed emulation, run-time variable watches, trace analysis, complex breakpoints, a ruggedized probe interface and long (up to three meters) interconnection cables.

# 22.9 MPLAB ICD 3 In-Circuit Debugger System

MPLAB ICD 3 In-Circuit Debugger System is Microchip's most cost effective high-speed hardware debugger/programmer for Microchip Flash Digital Signal Controller (DSC) and microcontroller (MCU) devices. It debugs and programs PIC® Flash microcontrollers and dsPIC® DSCs with the powerful, yet easy-to-use graphical user interface of MPLAB Integrated Development Environment (IDE).

The MPLAB ICD 3 In-Circuit Debugger probe is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with a connector compatible with the MPLAB ICD 2 or MPLAB REAL ICE systems (RJ-11). MPLAB ICD 3 supports all MPLAB ICD 2 headers.

# 22.10 PICkit 3 In-Circuit Debugger/ Programmer and PICkit 3 Debug Express

The MPLAB PICkit 3 allows debugging and programming of PIC<sup>®</sup> and dsPIC<sup>®</sup> Flash microcontrollers at a most affordable price point using the powerful graphical user interface of the MPLAB Integrated Development Environment (IDE). The MPLAB PICkit 3 is connected to the design engineer's PC using a full speed USB interface and can be connected to the target via an Microchip debug (RJ-11) connector (compatible with MPLAB ICD 3 and MPLAB REAL ICE). The connector uses two device I/O pins and the reset line to implement in-circuit debugging and In-Circuit Serial Programming<sup>™</sup>.

The PICkit 3 Debug Express include the PICkit 3, demo board and microcontroller, hookup cables and CDROM with user's guide, lessons, tutorial, compiler and MPLAB IDE software.

# 22.11 PICkit 2 Development Programmer/Debugger and PICkit 2 Debug Express

The PICkit™ 2 Development Programmer/Debugger is a low-cost development tool with an easy to use interface for programming and debugging Microchip's Flash families of microcontrollers. The full featured Windows® programming interface supports baseline (PIC10F, PIC12F5xx, PIC16F5xx), midrange (PIC12F6xx, PIC16F), PIC18F, PIC24, dsPIC30, dsPIC33, and PIC32 families of 8-bit, 16-bit, and 32-bit microcontrollers, and many Microchip Serial EEPROM products. With Microchip's powerful MPLAB Integrated Development Environment (IDE) the PICkit™ 2 enables in-circuit debugging on most PIC® microcontrollers. In-Circuit-Debugging runs, halts and single steps the program while the PIC microcontroller is embedded in the application. When halted at a breakpoint, the file registers can be examined and modified.

The PICkit 2 Debug Express include the PICkit 2, demo board and microcontroller, hookup cables and CDROM with user's guide, lessons, tutorial, compiler and MPLAB IDE software.

#### 22.12 MPLAB PM3 Device Programmer

The MPLAB PM3 Device Programmer is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular, detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 Device Programmer can read, verify and program PIC devices without a PC connection. It can also set code protection in this mode. The MPLAB PM3 connects to the host PC via an RS-232 or USB cable. The MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an MMC card for file storage and data applications.

#### 22.13 Demonstration/Development Boards, Evaluation Kits, and Starter Kits

A wide variety of demonstration, development and evaluation boards for various PIC MCUs and dsPIC DSCs allows quick application development on fully functional systems. Most boards include prototyping areas for adding custom circuitry and provide application firmware and source code for examination and modification.

The boards support a variety of features, including LEDs, temperature sensors, switches, speakers, RS-232 interfaces, LCD displays, potentiometers and additional EEPROM memory.

The demonstration and development boards can be used in teaching environments, for prototyping custom circuits and for learning about various microcontroller applications.

In addition to the PICDEM<sup>TM</sup> and dsPICDEM<sup>TM</sup> demonstration/development board series of circuits, Microchip has a line of evaluation kits and demonstration software for analog filter design, Keeloq® security ICs, CAN, IrDA®, PowerSmart battery management, Seevaluation system, Sigma-Delta ADC, flow rate sensing, plus many more.

Also available are starter kits that contain everything needed to experience the specified device. This usually includes a single application and debug capability, all on one board.

Check the Microchip web page (www.microchip.com) for the complete list of demonstration, development and evaluation kits.

#### 23.0 ELECTRICAL CHARACTERISTICS

This section provides an overview of dsPIC30F electrical characteristics. Additional information will be provided in future revisions of this document as it becomes available.

For detailed information about the dsPIC30F architecture and core, refer to the "dsPIC30F Family Reference Manual" (DS70046).

Absolute maximum ratings for the dsPIC30F family are listed below. Exposure to these maximum rating conditions for extended periods may affect device reliability. Functional operation of the device at these or any other conditions above the parameters indicated in the operation listings of this specification is not implied.

#### Absolute Maximum Ratings(†)

| Ambient temperature under bias  | 40°C to +125°C       |
|---|----------------------|
| Storage temperature   | 65°C to +150°C       |
| Voltage on any pin with respect to Vss (except VDD and MCLR) (Note 1) | 0.3V to (VDD + 0.3V) |
| Voltage on VDD with respect to Vss                                    | 0.3V to +5.5V        |
| Voltage on MCLR with respect to Vss                                   | 0V to +13.25V        |
| Maximum current out of Vss pin  | 300 mA               |
| Maximum current into VDD pin (Note 2)                                 | 250 mA               |
| Input clamp current, IiK (VI < 0 or VI > VDD)                         | ±20 mA               |
| Output clamp current, IOK (VO < 0 or VO > VDD)                        | ±20 mA               |
| Maximum output current sunk by any I/O pin                            | 25 mA                |
| Maximum output current sourced by any I/O pin                         | 25 mA                |
| Maximum current sunk by all ports                                     | 200 mA               |
| Maximum current sourced by all ports (Note 2)                         | 200 mA               |
|   |                      |

- **Note 1:** Voltage spikes below Vss at the MCLR/VPP pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100W should be used when applying a "low" level to the MCLR/VPP pin, rather than pulling this pin directly to Vss.
  - 2: Maximum allowable current is a function of device maximum power dissipation. See Table 23-4

**†NOTICE:** Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

**Note:** All peripheral electrical characteristics are specified. For exact peripherals available on specific devices, please refer to the dsPIC30F3014/4013 Controller Family table.

#### 23.1 DC Characteristics

TABLE 23-1: OPERATING MIPS vs. VOLTAGE

| Vpp Benge | Town Dange     | Max MIPS        |                 |  |  |  |  |  |
|-----------|----------------|-----------------|-----------------|--|--|--|--|--|
| VDD Range | Temp Range     | dsPIC30FXXX-30I | dsPIC30FXXX-20E |  |  |  |  |  |
| 4.5-5.5V  | -40°C to 85°C  | 30              | 1               |  |  |  |  |  |
| 4.5-5.5V  | -40°C to 125°C | _               | 20              |  |  |  |  |  |
| 3.0-3.6V  | -40°C to 85°C  | 15              | _               |  |  |  |  |  |
| 3.0-3.6V  | -40°C to 125°C | _               | 10              |  |  |  |  |  |
| 2.5-3.0V  | -40°C to 85°C  | 10              | _               |  |  |  |  |  |

#### TABLE 23-2: THERMAL OPERATING CONDITIONS

| Rating   | Symbol         | Min       | Тур         | Max  | Unit |  |
|--|----------------|-----------|-------------|------|------|--|
| dsPIC30F3014-30I   |                |           |             |      |      |  |
| dsPIC30F4013-30I   |                |           |             |      |      |  |
| Operating Junction Temperature Range   | TJ             | -40       | _           | +125 | °C   |  |
| Operating Ambient Temperature Range  | T <sub>A</sub> | -40 — +85 |             |      |      |  |
| dsPIC30F3014-20E   |                |           |             |      |      |  |
| dsPIC30F4013-20E   |                |           |             |      |      |  |
| Operating Junction Temperature Range   | TJ             | -40       | _           | +150 | °C   |  |
| Operating Ambient Temperature Range  | T <sub>A</sub> |           |             |      |      |  |
| Power Dissipation:   |                |           |             |      |      |  |
| Internal chip power dissipation:   |                |           |             |      |      |  |
| $Pint = Vdd \times (Idd - \sum Ioh)$   | PD             | ı         | PINT + PI/C | )    | W    |  |
| I/O Pin power dissipation:   |                |           |             |      |      |  |
| $P_{I/O} = \sum (\{V_{DD} - V_{OH}\} \times I_{OH}) + \sum (V_{OL} \times I_{OL})$ |                |           |             |      |      |  |
| Maximum Allowed Power Dissipation  | Ромах          | (         | ΓJ — TA)/θJ | IA   | W    |  |

#### **TABLE 23-3: THERMAL PACKAGING CHARACTERISTICS**

| Characteristic                                      | Symbol | Тур | Max  | Unit | Notes |
|---|--------|-----|------|------|-------|
| Package Thermal Resistance, 40-pin DIP (P)          | θЈА    | _   | 47   | °C/W | 1     |
| Package Thermal Resistance, 44-pin TQFP (10x10x1mm) | θЈА    | _   | 39.3 | °C/W | 1     |
| Package Thermal Resistance, 44-pin QFN              | θЈА    |     | 27.8 | °C/W | 1     |

**Note 1:** Junction to ambient thermal resistance, Theta-ja (θJA) numbers are achieved by package simulations.

TABLE 23-4: DC TEMPERATURE AND VOLTAGE SPECIFICATIONS

| DC CHARACTERISTICS               |                       |  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for Extended |                    |     |       |                                  |  |  |
|----------------------------------|-----------------------|--|--|--------------------|-----|-------|----------------------------------|--|--|
| Param<br>No.                     | Symbol Characteristic |  |  | Typ <sup>(1)</sup> | Max | Units | Conditions                       |  |  |
| Operating Voltage <sup>(2)</sup> |                       |  |  |                    |     |       |                                  |  |  |
| DC10                             | VDD                   | Supply Voltage   | 2.5  | _                  | 5.5 | V     | Industrial temperature           |  |  |
| DC11                             | VDD                   | Supply Voltage   | 3.0  | _                  | 5.5 | V     | Extended temperature             |  |  |
| DC12                             | Vdr                   | RAM Data Retention Voltage <sup>(3)</sup>                        | 1.75   | _                  | _   | V     |                                  |  |  |
| DC16                             | VPOR                  | VDD Start Voltage<br>to Ensure Internal<br>Power-on Reset Signal | _  | _                  | Vss | V     |                                  |  |  |
| DC17                             | SVDD                  | VDD Rise Rate<br>to Ensure Internal<br>Power-on Reset Signal     | 0.05   | _                  | _   | V/ms  | 0-5V in 0.1 sec<br>0-3V in 60 ms |  |  |

**Note 1:** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

**<sup>2:</sup>** These parameters are characterized but not tested in manufacturing.

<sup>3:</sup> This is the limit to which VDD can be lowered without losing RAM data.

TABLE 23-5: DC CHARACTERISTICS: OPERATING CURRENT (IDD)

| DC CHARACT   | ERISTICS                  |     | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |       |      |                |  |  |  |
|--|---------------------------|-----|--|-------|------|----------------|--|--|--|
| Parameter<br>No.   | Typical                   | Max | Units  |       | Со   | nditions       |  |  |  |
| Operating Cur  | rent (IDD) <sup>(1)</sup> |     |  |       |      |                |  |  |  |
| DC31a  | 2                         | 4   | mA   | 25°C  |      |                |  |  |  |
| DC31b  | 2                         | 4   | mA   | 85°C  | 3.3V |                |  |  |  |
| DC31c  | 2                         | 4   | mA   | 125°C |      | 0.128 MIPS     |  |  |  |
| DC31e  | 4                         | 6   | mA   | 25°C  |      | LPRC (512 kHz) |  |  |  |
| DC31f  | 4                         | 6   | mA   | 85°C  | 5V   |                |  |  |  |
| DC31g  | 4                         | 6   | mA   | 125°C | 1    |                |  |  |  |
| DC30a  | 6                         | 11  | mA   | 25°C  |      |                |  |  |  |
| DC30b  | 6                         | 11  | mA   | 85°C  | 3.3V |                |  |  |  |
| DC30c  | 7                         | 11  | mA   | 125°C | 1    | 1.8 MIPS       |  |  |  |
| DC30e  | 11                        | 16  | mA   | 25°C  |      | FRC (7.37 MHz) |  |  |  |
| DC30f  | 11                        | 16  | mA   | 85°C  | 5V   |                |  |  |  |
| DC30g  | 11                        | 16  | mA   | 125°C | 1    |                |  |  |  |
| DC23a  | 13                        | 20  | mA   | 25°C  |      |                |  |  |  |
| DC23b  | 13                        | 20  | mA   | 85°C  | 3.3V |                |  |  |  |
| DC23c  | 14                        | 20  | mA   | 125°C | 1    | 4 MIPS         |  |  |  |
| DC23e  | 22                        | 31  | mA   | 25°C  |      | 4 1/11175      |  |  |  |
| DC23f  | 22                        | 31  | mA   | 85°C  | 5V   |                |  |  |  |
| DC23g  | 22                        | 31  | mA   | 125°C | 1    |                |  |  |  |
| DC24a  | 27                        | 39  | mA   | 25°C  |      |                |  |  |  |
| DC24b  | 28                        | 39  | mA   | 85°C  | 3.3V |                |  |  |  |
| DC24c  | 28                        | 39  | mA   | 125°C |      | 10 MIPS        |  |  |  |
| DC24e  | 46                        | 64  | mA   | 25°C  |      | 10 MIFS        |  |  |  |
| DC24f  | 46                        | 64  | mA   | 85°C  | 5V   |                |  |  |  |
| DC24g  | 46                        | 64  | mA   | 125°C | 1    |                |  |  |  |
| DC27d  | 86                        | 120 | mA   | 25°C  |      |                |  |  |  |
| DC27e  | 85                        | 120 | mA   | 85°C  | 5V   | 20 MIPS        |  |  |  |
| DC27f  | 85                        | 120 | mA   | 125°C | ]    |                |  |  |  |
| DC29a  | 123                       | 170 | mA   | 25°C  | 5V   | 30 MIDS        |  |  |  |
| DC29b  | 122                       | 170 | mA   | 85°C  | ] ov | 30 MIPS        |  |  |  |
| Note 1: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O |                           |     |  |       |      |                |  |  |  |

Note 1: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption. The test conditions for all IDD measurements are as follows: OSC1 driven with external square wave from rail-to-rail. All I/O pins are configured as inputs and pulled to VDD.

MCLR = VDD, WDT, FSCM, LVD and BOR are disabled. CPU, SRAM, program memory and data memory are operational. No peripheral modules are operating.

TABLE 23-6: DC CHARACTERISTICS: IDLE CURRENT (IIDLE)

| DC CHARACT       | ERISTICS                  |     | (unless oth | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |      |                |  |  |  |  |
|------------------|---------------------------|-----|-------------|--|------|----------------|--|--|--|--|
| Parameter<br>No. | Typical                   | Max | Units       |  | Con  | ditions        |  |  |  |  |
| Operating Cur    | rent (IDD) <sup>(1)</sup> |     |             |  |      |                |  |  |  |  |
| DC51a            | 1.4                       | 3   | mA          | 25°C   |      |                |  |  |  |  |
| DC51b            | 1.5                       | 3   | mA          | 85°C   | 3.3V |                |  |  |  |  |
| DC51c            | 1.5                       | 3   | mA          | 125°C  |      | 0.128 MIPS     |  |  |  |  |
| DC51e            | 3                         | 5   | mA          | 25°C   |      | LPRC (512 kHz) |  |  |  |  |
| DC51f            | 3                         | 5   | mA          | 85°C   | 5V   |                |  |  |  |  |
| DC51g            | 3                         | 5   | mA          | 125°C  | ]    |                |  |  |  |  |
| DC50a            | 4                         | 6   | mA          | 25°C   |      |                |  |  |  |  |
| DC50b            | 4                         | 6   | mA          | 85°C   | 3.3V |                |  |  |  |  |
| DC50c            | 4                         | 6   | mA          | 125°C  | ]    | 1.8 MIPS       |  |  |  |  |
| DC50e            | 8                         | 11  | mA          | 25°C   |      | FRC (7.37 MHz) |  |  |  |  |
| DC50f            | 8                         | 11  | mA          | 85°C   | 5V   |                |  |  |  |  |
| DC50g            | 8                         | 11  | mA          | 125°C  | 1    |                |  |  |  |  |
| DC43a            | 7                         | 11  | mA          | 25°C   |      |                |  |  |  |  |
| DC43b            | 7                         | 11  | mA          | 85°C   | 3.3V |                |  |  |  |  |
| DC43c            | 8                         | 11  | mA          | 125°C  | 1    | 4.84100        |  |  |  |  |
| DC43e            | 13                        | 17  | mA          | 25°C   |      | 4 MIPS         |  |  |  |  |
| DC43f            | 13                        | 17  | mA          | 85°C   | 5V   |                |  |  |  |  |
| DC43g            | 13                        | 17  | mA          | 125°C  | 1    |                |  |  |  |  |
| DC44a            | 16                        | 22  | mA          | 25°C   |      |                |  |  |  |  |
| DC44b            | 16                        | 22  | mA          | 85°C   | 3.3V |                |  |  |  |  |
| DC44c            | 17                        | 22  | mA          | 125°C  | 1    | 40.14170       |  |  |  |  |
| DC44e            | 27                        | 36  | mA          | 25°C   |      | 10 MIPS        |  |  |  |  |
| DC44f            | 27                        | 36  | mA          | 85°C   | 5V   |                |  |  |  |  |
| DC44g            | 28                        | 36  | mA          | 125°C  | 1    |                |  |  |  |  |
| DC47d            | 50                        | 65  | mA          | 25°C   |      |                |  |  |  |  |
| DC47e            | 51                        | 65  | mA          | 85°C   | 5V   | 20 MIPS        |  |  |  |  |
| DC47f            | 52                        | 65  | mA          | 125°C  | 1    | -              |  |  |  |  |
| DC49a            | 74                        | 95  | mA          | 25°C   | 5) ( | 00.14120       |  |  |  |  |
| DC49b            | 75                        | 95  | mA          | 85°C   | 5V   | 30 MIPS        |  |  |  |  |

Note 1: Base IIDLE current is measured with core off, clock on and all modules turned off.

TABLE 23-7: DC CHARACTERISTICS: POWER-DOWN CURRENT (IPD)

| DC CHARACT    | ERISTICS                   |     | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |       |      |  |  |  |  |
|---------------|----------------------------|-----|--|-------|------|--|--|--|--|
| Parameter No. | Typical                    | Max | Units  |       |      | Conditions                                     |  |  |  |
| Power-Down (  | Current (IPD) <sup>(</sup> | 1)  |  |       |      |  |  |  |  |
| DC60a         | 1                          | _   | μА   | 25°C  |      |  |  |  |  |
| DC60b         | 3                          | 30  | μА   | 85°C  | 3.3V |  |  |  |  |
| DC60c         | 30                         | 60  | μА   | 125°C |      | Base Power-Down Current <sup>(2)</sup>         |  |  |  |
| DC60e         | 2                          |     | μА   | 25°C  |      | Base Power-Down Current                        |  |  |  |
| DC60f         | 6                          | 45  | μА   | 85°C  | 5V   |  |  |  |  |
| DC60g         | 55                         | 90  | μА   | 125°C |      |  |  |  |  |
| DC61a         | 7                          | 11  | μА   | 25°C  |      |  |  |  |  |
| DC61b         | 7                          | 11  | μА   | 85°C  | 3.3V |  |  |  |  |
| DC61c         | 7                          | 11  | μА   | 125°C |      | Matalada                                       |  |  |  |
| DC61e         | 14                         | 21  | μА   | 25°C  |      | Watchdog Timer Current: ∆IWDT <sup>(2)</sup>   |  |  |  |
| DC61f         | 14                         | 21  | μА   | 85°C  | 5V   |  |  |  |  |
| DC61g         | 14                         | 21  | μА   | 125°C |      |  |  |  |  |
| DC62a         | _                          |     | μА   | 25°C  |      |  |  |  |  |
| DC62b         | _                          | _   | μА   | 85°C  | 3.3V |  |  |  |  |
| DC62c         | _                          |     | μА   | 125°C |      | Time and any (20 to the Company)               |  |  |  |
| DC62e         | _                          |     | μА   | 25°C  |      | Timer1 w/32 kHz Crystal: ΔITι32 <sup>(2)</sup> |  |  |  |
| DC62f         | _                          | _   | μА   | 85°C  | 5V   |  |  |  |  |
| DC62g         | 30                         | 45  | μА   | 125°C |      |  |  |  |  |
| DC63a         | 30                         | 45  | μА   | 25°C  |      |  |  |  |  |
| DC63b         | 33                         | 50  | μА   | 85°C  | 3.3V |  |  |  |  |
| DC63c         | 34                         | 51  | μА   | 125°C |      | BOR on: ΔΙΒΟR <sup>(2)</sup>                   |  |  |  |
| DC63e         | 34                         | 51  | μА   | 25°C  |      | BOR on: Albor                                  |  |  |  |
| DC63f         | 37                         | 56  | μА   | 85°C  | 5V   |  |  |  |  |
| DC63g         | 37                         | 56  | μА   | 125°C |      |  |  |  |  |
| DC66a         | 18                         | 27  | μА   | 25°C  |      |  |  |  |  |
| DC66b         | 20                         | 30  | μΑ   | 85°C  | 3.3V |  |  |  |  |
| DC66c         | 21                         | 32  | μΑ   | 125°C |      | Low-Voltage Detect: ∆ILVD <sup>(2)</sup>       |  |  |  |
| DC66e         | 22                         | 33  | μА   | 25°C  |      | Low-voltage Detect: Allvo-                     |  |  |  |
| DC66f         | 23                         | 35  | μΑ   | 85°C  | 5V   |  |  |  |  |
| DC66g         | 24                         | 36  | μА   | 125°C |      |  |  |  |  |

**Note 1:** Base IPD is measured with all peripherals and clocks shut down. All I/Os are configured as inputs and pulled high. LVD, BOR, WDT, etc. are all switched off.

<sup>2:</sup> The  $\Delta$  current is the additional current consumed when the module is enabled. This current should be added to the base IPD current.

TABLE 23-8: DC CHARACTERISTICS: I/O PIN INPUT SPECIFICATIONS

| DC CHA       | ARACTER | ISTICS                                   | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |                    |         |       |  |  |
|--------------|---------|--|--|--------------------|---------|-------|--|--|
| Param<br>No. | Symbol  | Characteristic                           | Min  | Typ <sup>(1)</sup> | Max     | Units | Conditions   |  |
|              | VIL     | Input Low Voltage <sup>(2)</sup>         |  |                    |         |       |  |  |
| DI10         |         | I/O Pins: with Schmitt Trigger Buffer    | Vss  | _                  | 0.2 VDD | V     |  |  |
| DI15         |         | MCLR                                     | Vss  | _                  | 0.2 VDD | V     |  |  |
| DI16         |         | OSC1 (in XT, HS and LP modes)            | Vss  | _                  | 0.2 VDD | V     |  |  |
| DI17         |         | OSC1 (in RC mode) <sup>(3)</sup>         | Vss  | _                  | 0.3 VDD | V     |  |  |
| DI18         |         | SDA, SCL                                 | Vss  | _                  | 0.3 VDD | V     | SM bus disabled                                      |  |
| DI19         |         | SDA, SCL                                 | Vss  |                    | 0.8     | ٧     | SM bus enabled                                       |  |
|              | VIH     | Input High Voltage <sup>(2)</sup>        |  |                    |         |       |  |  |
| DI20         |         | I/O Pins: with Schmitt Trigger Buffer    | 0.8 VDD  | _                  | VDD     | V     |  |  |
| DI25         |         | MCLR                                     | 0.8 VDD  | _                  | VDD     | V     |  |  |
| DI26         |         | OSC1 (in XT, HS and LP modes)            | 0.7 VDD  | _                  | VDD     | V     |  |  |
| DI27         |         | OSC1 (in RC mode) <sup>(3)</sup>         | 0.9 VDD  | _                  | VDD     | V     |  |  |
| DI28         |         | SDA, SCL                                 | 0.7 VDD  | _                  | VDD     | V     | SM bus disabled                                      |  |
| DI29         |         | SDA, SCL                                 | 2.1  | _                  | VDD     | V     | SM bus enabled                                       |  |
|              | ICNPU   | CNxx Pull-up Current <sup>(2)</sup>      |  |                    |         |       |  |  |
| DI30         |         |  | 50   | 250                | 400     | μΑ    | VDD = 5V, VPIN = VSS                                 |  |
|              | lı∟     | Input Leakage Current <sup>(2,4,5)</sup> |  |                    |         |       |  |  |
| DI50         |         | I/O Ports                                | _  | 0.01               | ±1      | μΑ    | Vss ≤ Vpin ≤ Vdd,<br>Pin at high-impedance           |  |
| DI51         |         | Analog Input Pins                        | _  | 0.50               | _       | μΑ    | Vss ≤ VPIN ≤ VDD,<br>Pin at high-impedance           |  |
| DI55         |         | MCLR                                     | _  | 0.05               | ±5      | μΑ    | $Vss \le Vpin \le Vdd$                               |  |
| DI56         |         | OSC1                                     | _  | 0.05               | ±5      | μΑ    | $Vss \leq VPIN \leq VDD, \ XT, \ HS$ and LP Osc mode |  |

Note 1: Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

- **2:** These parameters are characterized but not tested in manufacturing.
- **3:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the dsPIC30F device be driven with an external clock while in RC mode.
- **4:** The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.
- **5:** Negative current is defined as current sourced by the pin.

TABLE 23-9: DC CHARACTERISTICS: I/O PIN OUTPUT SPECIFICATIONS

| DC CHARACTERISTICS |        |  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for Extended |                    |      |       |  |  |
|--------------------|--------|--|--|--------------------|------|-------|--|--|
| Param<br>No.       | Symbol | Characteristic   | Min  | Typ <sup>(1)</sup> | Max  | Units | Conditions   |  |
|                    | VOL    | Output Low Voltage <sup>(2)</sup>                      |  |                    |      |       |  |  |
| DO10               |        | I/O Ports  | _  | _                  | 0.6  | V     | IOL = 8.5 mA, VDD = 5V   |  |
|                    |        |  | _  | _                  | 0.15 | V     | IOL = 2.0 mA, VDD = 3V   |  |
| DO16               |        | OSC2/CLKO  | _  | _                  | 0.6  | V     | IOL = 1.6 mA, VDD = 5V   |  |
|                    |        | (RC or EC Oscillator mode)                             | _  | _                  | 0.72 | V     | IOL = 2.0  mA, VDD = 3V  |  |
|                    | Vон    | Output High Voltage <sup>(2)</sup>                     |  |                    |      |       |  |  |
| DO20               |        | I/O Ports  | VDD - 0.7  | _                  | _    | V     | IOH = -3.0 mA, VDD = 5V  |  |
|                    |        |  | VDD - 0.2  | _                  | _    | V     | IOH = -2.0 mA, VDD = 3V  |  |
| DO26               |        | OSC2/CLKO  | VDD - 0.7  | _                  | _    | V     | IOH = -1.3 mA, VDD = 5V  |  |
|                    |        | (RC or EC Oscillator mode)                             | VDD - 0.1  | _                  | 1    | V     | IOH = -2.0 mA, VDD = 3V  |  |
|                    |        | Capacitive Loading Specs on Output Pins <sup>(2)</sup> |  |                    |      |       |  |  |
| DO50               | Cosc2  | OSC2/SOSC2 Pin   | _  | _                  | 15   | pF    | In XTL, XT, HS and LP modes when external clock is used to drive OSC1. |  |
| DO56               | Cio    | All I/O Pins and OSC2                                  | _  | _                  | 50   | pF    | RC or EC Oscillator mode   |  |
| DO58               | Св     | SCL, SDA   | _  | _                  | 400  | pF    | In I <sup>2</sup> C mode   |  |

**Note 1:** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

**2:** These parameters are characterized but not tested in manufacturing.

FIGURE 23-1: LOW-VOLTAGE DETECT CHARACTERISTICS




TABLE 23-10: ELECTRICAL CHARACTERISTICS: LVDL

| DC CHARACTERISTICS               |       |  |  |  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) |     |  |         |                           |          |            |    |
|----------------------------------|-------|--|--|--|---|-----|--|---------|---------------------------|----------|------------|----|
| Operating temperature -40°C ≤ TA |       |  |  | Operating temperature -40°C ≤ TA ≤ +85°C for Industria |   |     |  | l       |                           |          |            |    |
|                                  |       |  |  |  |   |     |  | -40°C ≤ | ≤ <b>T</b> A ≤ <b>+</b> ′ | 125°C fo | or Extende | ed |
|                                  | Param |  |  |  |   | (1) |  |         |                           |          |            |    |

| Param<br>No. | Symbol | Characteristic <sup>(</sup>                   | haracteristic <sup>(1)</sup> |      |   | Max  | Units | Conditions |
|--------------|--------|---|------------------------------|------|---|------|-------|------------|
| LV10         | VPLVD  | LVDL Voltage on VDD<br>Transition High-to-Low | LVDL = 0000 <sup>(2)</sup>   |      | _ | _    | V     |            |
|              |        |   | LVDL = 0001 <sup>(2)</sup>   |      |   | _    | V     |            |
|              |        |   | LVDL = 0010 <sup>(2)</sup>   | _    | _ | _    | V     |            |
|              |        |   | LVDL = 0011 <sup>(2)</sup>   | _    | _ | _    | V     |            |
|              |        |   | LVDL = 0100                  | 2.50 | - | 2.65 | V     |            |
|              |        |   | LVDL = 0101                  | 2.70 | _ | 2.86 | V     |            |
|              |        |   | LVDL = 0110                  | 2.80 |   | 2.97 | V     |            |
|              |        |   | LVDL = 0111                  | 3.00 |   | 3.18 | V     |            |
|              |        |   | LVDL = 1000                  | 3.30 |   | 3.50 | V     |            |
|              |        |   | LVDL = 1001                  | 3.50 |   | 3.71 | V     |            |
|              |        |   | LVDL = 1010                  | 3.60 |   | 3.82 | V     |            |
|              |        |   | LVDL = 1011                  | 3.80 |   | 4.03 | V     |            |
|              |        |   | LVDL = 1100                  | 4.00 | 1 | 4.24 | V     |            |
|              |        |   | LVDL = 1101                  | 4.20 | _ | 4.45 | V     |            |
|              |        |   | LVDL = 1110                  | 4.50 | - | 4.77 | V     |            |
| LV15         | VLVDIN | External LVD Input Pin<br>Threshold Voltage   | LVDL = 1111                  |      |   |      | V     |            |

Note 1: These parameters are characterized but not tested in manufacturing.

2: These values not in usable operating range.

FIGURE 23-2: BROWN-OUT RESET CHARACTERISTICS




TABLE 23-11: ELECTRICAL CHARACTERISTICS: BOR

| DC CHARACTERISTICS   |       |                               | (unless otherw           | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for Extended |                    |      |       |                        |  |  |
|----------------------|-------|-------------------------------|--------------------------|--|--------------------|------|-------|------------------------|--|--|
| Param No. Characteri |       |                               | istic                    | Min  | Typ <sup>(1)</sup> | Max  | Units | Conditions             |  |  |
| BO10                 | VBOR  | BOR Voltage on VDD Transition | BORV = 11 <sup>(3)</sup> | _  | _                  | _    | V     | Not in operating range |  |  |
|                      |       | High-to-Low <sup>(2)</sup>    | BORV = 10                | 2.6  | _                  | 2.71 | V     |                        |  |  |
|                      |       |                               | BORV = 01                | 4.1  | _                  | 4.4  | V     |                        |  |  |
|                      |       |                               | BORV = 00                | 4.58   | _                  | 4.73 | V     |                        |  |  |
| BO15                 | VBHYS |                               |                          | _  | 5                  |      | mV    |                        |  |  |

- **Note 1:** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 2: These parameters are characterized but not tested in manufacturing.
  - **3:** '11' values not in usable operating range.

TABLE 23-12: DC CHARACTERISTICS: PROGRAM AND EEPROM

| DC CHARACTERISTICS |        |                                     | (unless |                    | ise state | enditions: 2.5V to 5.5V ed) $-40^{\circ}C \le TA \le +85^{\circ}C \text{ for Industrial} \\ -40^{\circ}C \le TA \le +125^{\circ}C \text{ for Extended}$ |  |  |  |
|--------------------|--------|-------------------------------------|---------|--------------------|-----------|---|--|--|--|
| Param<br>No.       | Symbol | Characteristic                      | Min     | Typ <sup>(1)</sup> | Max       | Units   | Conditions   |  |  |
|                    |        | Data EEPROM Memory <sup>(2)</sup>   |         |                    |           |   |  |  |  |
| D120               | ED     | Byte Endurance                      | 100K    | 1M                 | _         | E/W   | -40°C ≤ TA ≤ +85°C   |  |  |
| D121               | VDRW   | VDD for Read/Write                  | VMIN    | _                  | 5.5       | V   | Using EECON to read/write VMIN = Minimum operating voltage |  |  |
| D122               | TDEW   | Erase/Write Cycle Time              | 0.8     | 2                  | 2.6       | ms  | RTSP   |  |  |
| D123               | TRETD  | Characteristic Retention            | 40      | 100                | _         | Year  | Provided no other specifications are violated              |  |  |
| D124               | IDEW   | IDD During Programming              | _       | 10                 | 30        | mA  | Row Erase  |  |  |
|                    |        | Program Flash Memory <sup>(2)</sup> |         |                    |           |   |  |  |  |
| D130               | EP     | Cell Endurance                      | 10K     | 100K               | _         | E/W   | -40°C ≤ TA ≤ +85°C   |  |  |
| D131               | VPR    | VDD for Read                        | VMIN    | _                  | 5.5       | V   | Vмін = Minimum operating voltage                           |  |  |
| D132               | VEB    | VDD for Bulk Erase                  | 4.5     | _                  | 5.5       | V   |  |  |  |
| D133               | VPEW   | VDD for Erase/Write                 | 3.0     | _                  | 5.5       | V   |  |  |  |
| D134               | TPEW   | Erase/Write Cycle Time              | 0.8     | 2                  | 2.6       | ms  | RTSP   |  |  |
| D135               | TRETD  | Characteristic Retention            | 40      | 100                | _         | Year  | Provided no other specifications are violated              |  |  |
| D137               | IPEW   | IDD During Programming              | _       | 10                 | 30        | mA  | Row Erase  |  |  |
| D138               | lев    | IDD During Programming              | _       | 10                 | 30        | mA  | Bulk Erase   |  |  |

Note 1: Data in "Typ" column is at 5V, 25°C unless otherwise stated.

#### 23.2 AC Characteristics and Timing Parameters

The information contained in this section defines dsPIC30F AC characteristics and timing parameters.


<sup>2:</sup> These parameters are characterized but not tested in manufacturing.

### TABLE 23-13: TEMPERATURE AND VOLTAGE SPECIFICATIONS - AC


Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated)

AC CHARACTERISTICS
Operating temperature  $-40^{\circ}\text{C} \leq \text{TA} \leq +85^{\circ}\text{C}$  for Industrial  $-40^{\circ}\text{C} \leq \text{TA} \leq +125^{\circ}\text{C}$  for Extended Operating voltage VDD range as described in Table 23-1.

#### FIGURE 23-3: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



### FIGURE 23-4: EXTERNAL CLOCK TIMING



**TABLE 23-14: EXTERNAL CLOCK TIMING REQUIREMENTS** 

| AC CHA       | ARACTER       | ISTICS   | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |  |   |  |  |  |  |  |
|--------------|---------------|--|--|--|---|--|--|--|--|--|
| Param<br>No. | Symbol        | Characteristic   | Min  | Typ <sup>(1)</sup>                     | Max   | Units  | Conditions   |  |  |  |
| OS10         | Fosc          | External CLKI Frequency<br>(external clocks allowed<br>only in EC mode) <sup>(2)</sup> | DC<br>4<br>4<br>4  | _<br>_<br>_<br>_                       | 40<br>10<br>10<br>7.5 <sup>(3)</sup>  | MHz<br>MHz<br>MHz<br>MHz   | EC EC with 4x PLL EC with 8x PLL EC with 16x PLL   |  |  |  |
|              |               | Oscillator Frequency <sup>(2)</sup>  | DC<br>0.4<br>4<br>4<br>4<br>10<br>10<br>10<br>10<br>12(4)<br>12(4)<br>12(4)  | <br><br><br><br><br><br><br><br>32.768 | 4<br>4<br>10<br>10<br>10<br>7.5 <sup>(3)</sup><br>25<br>20 <sup>(4)</sup><br>25(3)<br>25<br>22.5 <sup>(3)</sup> | MHz<br>MHz<br>MHz<br>MHz<br>MHz<br>MHz<br>MHz<br>MHz<br>MHz<br>MHz | RC XTL XT XT with 4x PLL XT with 8x PLL XT with 16x PLL HS HS/2 with 4x PLL HS/2 with 8x PLL HS/2 with 16x PLL HS/3 with 4x PLL HS/3 with 4x PLL HS/3 with 8x PLL HS/3 with 16x PLL LP |  |  |  |
| OS20         | Tosc          | Tosc = 1/Fosc  | _  | _                                      |   | 1  | See parameter OS10 for Fosc value  |  |  |  |
| OS25         | Tcy           | Instruction Cycle Time <sup>(2,5)</sup>  | 33   | _                                      | DC  | ns   | See Table 23-16  |  |  |  |
| OS30         | TosL,<br>TosH | External Clock in (OSC1)<br>High or Low Time <sup>(2)</sup>                            | .45 x Tosc   | _                                      | _   | ns   | EC   |  |  |  |
| OS31         | TosR,<br>TosF | External Clock in (OSC1)<br>Rise or Fall Time <sup>(2)</sup>                           |  | _                                      | 20  | ns   | EC   |  |  |  |
| OS40         | TckR          | CLKO Rise Time <sup>(2,6)</sup>  | _  | _                                      | _   | ns   | See parameter DO31   |  |  |  |
| OS41         | TckF          | CLKO Fall Time <sup>(2,6)</sup>  | _  | _                                      |   | ns   | See parameter DO32   |  |  |  |

Note 1: Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

- 2: These parameters are characterized but not tested in manufacturing.
- **3:** Limited by the PLL output frequency range.
- **4:** Limited by the PLL input frequency range.
- 5: Instruction cycle period (TcY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "Max." cycle time limit is "DC" (no clock) for all devices.
- **6:** Measurements are taken in EC or ERC modes. The CLKO signal is measured on the OSC2 pin. CLKO is low for the Q1-Q2 period (1/2 TcY) and high for the Q3-Q4 period (1/2 TcY).

**TABLE 23-15: PLL JITTER** 

| AC CHA       | RACTERISTICS   | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |                    |       |       |                                  |                     |  |  |  |
|--------------|----------------|--|--------------------|-------|-------|----------------------------------|---------------------|--|--|--|
| Param<br>No. | Characteristic | Min  | Typ <sup>(1)</sup> | Max   | Units | Conditions                       |                     |  |  |  |
| OS61         | x4 PLL         | _  | 0.251              | 0.413 | %     | -40°C ≤ TA ≤ +85°C               | VDD = 3.0  to  3.6V |  |  |  |
|              |                | _  | 0.251              | 0.413 | %     | -40°C ≤ TA ≤ +125°C              | VDD = 3.0  to  3.6V |  |  |  |
|              |                | _  | 0.256              | 0.47  | %     | -40°C ≤ TA ≤ +85°C               | VDD = 4.5  to  5.5V |  |  |  |
|              |                | _  | 0.256              | 0.47  | %     | $-40$ °C $\leq$ TA $\leq$ +125°C | VDD = 4.5  to  5.5V |  |  |  |
|              | x8 PLL         | _  | 0.355              | 0.584 | %     | -40°C ≤ TA ≤ +85°C               | VDD = 3.0  to  3.6V |  |  |  |
|              |                | _  | 0.355              | 0.584 | %     | $-40$ °C $\leq$ TA $\leq$ +125°C | VDD = 3.0  to  3.6V |  |  |  |
|              |                | _  | 0.362              | 0.664 | %     | -40°C ≤ TA ≤ +85°C               | VDD = 4.5  to  5.5V |  |  |  |
|              |                | _  | 0.362              | 0.664 | %     | $-40$ °C $\leq$ TA $\leq$ +125°C | VDD = 4.5  to  5.5V |  |  |  |
|              | x16 PLL        |  | 0.67               | 0.92  | %     | -40°C ≤ TA ≤ +85°C               | VDD = 3.0  to  3.6V |  |  |  |
|              |                | _  | 0.632              | 0.956 | %     | -40°C ≤ TA ≤ +85°C               | VDD = 4.5  to  5.5V |  |  |  |
|              |                | _  | 0.632              | 0.956 | %     | -40°C ≤ TA ≤ +125°C              | VDD = 4.5  to  5.5V |  |  |  |

Note 1: These parameters are characterized but not tested in manufacturing.

**TABLE 23-16: INTERNAL CLOCK TIMING EXAMPLES** 

| Clock<br>Oscillator<br>Mode | Fosc<br>(MHz) <sup>(1)</sup> | Tcγ (μsec) <sup>(2)</sup> | MIPS<br>w/o PLL <sup>(3)</sup> | MIPS<br>w/PLL x4 <sup>(3)</sup> | MIPS<br>w/PLL x8 <sup>(3)</sup> | MIPS<br>w/PLL x16 <sup>(3)</sup> |
|-----------------------------|------------------------------|---------------------------|--------------------------------|---------------------------------|---------------------------------|----------------------------------|
| EC                          | 0.200                        | 20.0                      | 0.05                           | _                               | _                               | _                                |
|                             | 4                            | 1.0                       | 1.0                            | 4.0                             | 8.0                             | 16.0                             |
|                             | 10                           | 0.4                       | 2.5                            | 10.0                            | 20.0                            | _                                |
|                             | 25                           | 0.16                      | 6.25                           | _                               | _                               | _                                |
| XT                          | 4                            | 1.0                       | 1.0                            | 4.0                             | 8.0                             | 16.0                             |
|                             | 10                           | 0.4                       | 2.5                            | 10.0                            | 20.0                            | _                                |

**Note 1:** Assumption: Oscillator Postscaler is divide by 1.

**<sup>2:</sup>** Instruction Execution Cycle Time: Tcy = 1/MIPS.

<sup>3:</sup> Instruction Execution Frequency: MIPS = (Fosc \* PLLx)/4 [since there are 4 Q clocks per instruction cycle].

### TABLE 23-17: AC CHARACTERISTICS: INTERNAL FRC ACCURACY

| AC CHARACTERISTICS |                         | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |           |                      |       |  |  |  |  |  |
|--------------------|-------------------------|--|-----------|----------------------|-------|--|--|--|--|--|
| Param<br>No.       | Characteristic          | Min  | Тур       | Max                  | Units | Conditions   |  |  |  |  |
|                    | Internal FRC Accuracy @ | FRC Fr   | eq. = 7.3 | 7 MHz <sup>(1)</sup> |       |  |  |  |  |  |
| OS63               | FRC                     |  | _         | ±2.00                | %     | $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ VDD = 3.0-5.5V |  |  |  |  |
|                    |                         | _  | _         | ±5.00                | %     | -40°C ≤ TA ≤ +125°C  |  |  |  |  |


**Note 1:** Frequency calibrated at 7.372 MHz ±2%, 25°C and 5V. TUN bits (OSCCON<3:0>) can be used to compensate for temperature drift.

### TABLE 23-18: AC CHARACTERISTICS: INTERNAL LPRC ACCURACY

| AC CHA       | RACTERISTICS           | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated)<br>Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |     |     |       |                  |  |
|--------------|------------------------|---|-----|-----|-------|------------------|--|
| Param<br>No. | Characteristic         | Min   | Тур | Max | Units | Conditions       |  |
|              | LPRC @ Freq. = 512 kHz | (1)   |     |     |       |                  |  |
| OS65A        |                        | -50 — +50 % VDD = 5.0V, ±10%  |     |     |       |                  |  |
| OS65B        |                        | -60   |     | +60 | %     | VDD = 3.3V, ±10% |  |
| OS65C        |                        | -70   | _   | +70 | %     | VDD = 2.5V       |  |

Note 1: Change of LPRC frequency as VDD changes.

### FIGURE 23-5: CLKO AND I/O TIMING CHARACTERISTICS



### TABLE 23-19: CLKO AND I/O TIMING REQUIREMENTS

| AC CHAR                        | AC CHARACTERISTICS |                       |                        | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) |                    |     |       |            |  |  |
|--------------------------------|--------------------|-----------------------|------------------------|---|--------------------|-----|-------|------------|--|--|
| Param No. Symbol Characterist  |                    |                       | tic <sup>(1,2,3)</sup> | Min   | Typ <sup>(4)</sup> | Max | Units | Conditions |  |  |
| DO31                           | TioR               | Port Output Rise Tim  | е                      | _   | 7                  | 20  | ns    |            |  |  |
| DO32                           | TioF               | Port Output Fall Time | )                      | _   | 7                  | 20  | ns    |            |  |  |
| DI35                           | TINP               | INTx Pin High or Low  | Time (output)          | 20  | _                  | _   | ns    |            |  |  |
| DI40 TRBP CNx High or Low Time |                    |                       | ne (input)             | 2 Tcy   | _                  | _   | ns    |            |  |  |

Note 1: These parameters are asynchronous events not related to any internal clock edges

- 2: Measurements are taken in RC mode and EC mode where CLKO output is 4 x Tosc.
- 3: These parameters are characterized but not tested in manufacturing.
- **4:** Data in "Typ" column is at 5V, 25°C unless otherwise stated.

FIGURE 23-6: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING CHARACTERISTICS




TABLE 23-20: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER AND BROWN-OUT RESET TIMING REQUIREMENTS

| AC CHA       | AC CHARACTERISTICS      |  |   | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |     |       |                   |  |  |
|--------------|-------------------------|--|---|---|-----|-------|-------------------|--|--|
| Param<br>No. | Symbol                  | Characteristic <sup>(1)</sup>                            | Min   | Typ <sup>(2)</sup>  | Max | Units | Conditions        |  |  |
| SY10         | TmcL                    | MCLR Pulse Width (low)                                   | 2   | _   |     | μS    | -40°C to +85°C    |  |  |
| SY11         | TPWRT                   | Power-up Timer Period                                    | 2 4 8 ms -40°C to +85°C,<br>10 16 32 VDD = 5V<br>43 64 128 User programmable                    |   |     |       |                   |  |  |
| SY12         | TPOR                    | Power-on Reset Delay                                     | 3   | 10  | 30  | μS    | -40°C to +85°C    |  |  |
| SY13         | Tioz                    | I/O High-Impedance from MCLR Low or Watchdog Timer Reset | _   | 0.8   | 1.0 | μS    |                   |  |  |
| SY20         | TWDT1<br>TWDT2<br>TWDT3 | Watchdog Timer Time-out Period (no prescaler)            | d 1.1 2.0 6.6 ms VDD = 2.5V<br>1.2 2.0 5.0 ms VDD = 3.3V, ±10%<br>1.3 2.0 4.0 ms VDD = 5V, ±10% |   |     |       |                   |  |  |
| SY25         | TBOR                    | Brown-out Reset Pulse Width (3)                          | 100   | _   |     | μS    | VDD ≤ VBOR (D034) |  |  |
| SY30         | Tost                    | Oscillator Start-up Timer Period                         | d — 1024 Tosc — — Tosc = OSC1 period  |   |     |       |                   |  |  |
| SY35         | TFSCM                   | Fail-Safe Clock Monitor Delay                            | _   | 500   | 900 | μS    | -40°C to +85°C    |  |  |

- **Note 1:** These parameters are characterized but not tested in manufacturing.
  - 2: Data in "Typ" column is at 5V, 25°C unless otherwise stated.
  - 3: Refer to Figure 23-2 and Table 23-11 for BOR.

FIGURE 23-7: BAND GAP START-UP TIME CHARACTERISTICS




TABLE 23-21: BAND GAP START-UP TIME REQUIREMENTS

| AC CHA       | RACTERIS | TICS                              | (unles                                      | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |    |   |  |  |  |
|--------------|----------|-----------------------------------|---|--|----|---|--|--|--|
| Param<br>No. | Symbol   | Characteristic <sup>(1)</sup>     | Min Typ <sup>(2)</sup> Max Units Conditions |  |    |   |  |  |  |
| SY40         | Твдар    | Band Gap Start-up Time — 40 65 με |   |  | μS | Defined as the time between the instant that the band gap is enabled and the moment that the band gap reference voltage is stable (RCON<13> status bit) |  |  |  |

- Note 1: These parameters are characterized but not tested in manufacturing.
  - 2: Data in "Typ" column is at 5V, 25°C unless otherwise stated.

FIGURE 23-8: TYPE A, B AND C TIMER EXTERNAL CLOCK TIMING CHARACTERISTICS




TABLE 23-22: TYPE A TIMER (TIMER1) EXTERNAL CLOCK TIMING REQUIREMENTS

| AC CHA       | RACTERIST |  | (unles               | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for Extended |   |     |         |       |  |  |
|--------------|-----------|--|----------------------|--|---|-----|---------|-------|--|--|
| Param<br>No. | Symbol    | Charact  | eristic              |  | Min                                     | Тур | Max     | Units | Conditions                               |  |
| TA10         | ТтхН      | TxCK High Time   | Synchro<br>no preso  |  | 0.5 Tcy + 20                            | 1   | _       | ns    | Must also meet parameter TA15            |  |
|              |           |  | Synchro<br>with pres |  | 10                                      | 1   | _       | ns    |  |  |
|              |           |  | Asynchr              | onous  | 10                                      |     | _       | ns    |  |  |
| TA11         | TTXL      | TxCK Low Time  | Synchro<br>no preso  |  | 0.5 Tcy + 20                            | _   | _       | ns    | Must also meet parameter TA15            |  |
|              |           |  | Synchro<br>with pres |  | 10                                      | _   | _       | ns    |  |  |
|              |           |  | Asynchr              | onous  | 10                                      | _   | _       | ns    |  |  |
| TA15         | ТтхР      | TxCK Input Period  | Synchro<br>no preso  |  | Tcy + 10                                | _   | _       | ns    |  |  |
|              |           |  | Synchro<br>with pres |  | Greater of:<br>20 ns or<br>(Tcy + 40)/N | _   | _       | _     | N = prescale<br>value<br>(1, 8, 64, 256) |  |
|              |           |  | Asynchr              | onous  | 20                                      | _   |         | ns    |  |  |
| OS60         | Ft1       | SOSC1/T1CK Osci<br>Frequency Range (<br>enabled by setting<br>(T1CON<1>) | oscillator           |  | DC                                      | _   | 50      | kHz   |  |  |
| TA20         | TCKEXTMRL | Delay from Externa<br>Edge to Timer Incre                                |                      | lock   | 0.5 Tcy                                 | _   | 1.5 TcY | _     |  |  |

Note 1: Timer1 is a Type A.

TABLE 23-23: TYPE B TIMER (TIMER2 AND TIMER4) EXTERNAL CLOCK TIMING REQUIREMENTS

|    | CHARACTERIS | TICE |        | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated)                 |      |                                |          |              |  |  |  |
|----|-------------|------|--------|---|------|--------------------------------|----------|--------------|--|--|--|
| AC | CHARACTERIS | 1103 | Operat | Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for |      |                                |          | r Industrial |  |  |  |
|    |             |      |        |   | -40° | $^{\circ}C \leq TA \leq \cdot$ | +125°C f | or Extended  |  |  |  |
|    |             |      |        |   |      |                                |          |              |  |  |  |

| Param<br>No. | Symbol    | Characte          | eristic                                     | Min                                     | Тур | Max     | Units | Conditions                    |
|--------------|-----------|-------------------|---|---|-----|---------|-------|-------------------------------|
| TB10         | TtxH      | TxCK High Time    | Synchronous, no prescaler                   | 0.5 Tcy + 20                            |     |         | ns    | Must also meet parameter TB15 |
|              |           |                   | Synchronous, with prescaler                 | 10                                      | _   |         | ns    |                               |
| TB11         | TtxL      | TxCK Low Time     | Synchronous, no prescaler                   | 0.5 Tcy + 20                            | _   |         | ns    | Must also meet parameter TB15 |
|              |           |                   | Synchronous, with prescaler                 | 10                                      | _   |         | ns    |                               |
| TB15         | TtxP      | TxCK Input Period | Synchronous, no prescaler                   | Tcy + 10                                | _   |         | ns    | N = prescale<br>value         |
|              |           |                   | Synchronous, with prescaler                 | Greater of:<br>20 ns or<br>(Tcy + 40)/N |     |         |       | (1, 8, 64, 256)               |
| TB20         | TCKEXTMRL | _                 | from External TxCK Clock to Timer Increment |   | _   | 1.5 Tcy | _     |                               |


Note 1: Timer2 and Timer4 are Type B.

### TABLE 23-24: TYPE C TIMER (TIMER3 AND TIMER5) EXTERNAL CLOCK TIMING REQUIREMENTS

| AC CHA                           | AC CHARACTERISTICS |   |                      |         | ard Operating (<br>s otherwise standard<br>ing temperature | <b>ated)</b><br>e -40°( | C ≤ TA ≤ | +85°C fo | V<br>or Industrial<br>for Extended |
|----------------------------------|--------------------|---|----------------------|---------|--|-------------------------|----------|----------|------------------------------------|
| Param No. Characteristic         |                    |   |                      |         | Min  | Тур                     | Max      | Units    | Conditions                         |
| TC10 TtxH TxCK High Time Synchro |                    |   |                      | nous    | 0.5 Tcy + 20   |                         |          | ns       | Must also meet parameter TC15      |
| TC11                             | TtxL               | TxCK Low Time                             | Synchro              | nous    | 0.5 Tcy + 20   |                         | _        | ns       | Must also meet parameter TC15      |
| TC15                             | TtxP               | TxCK Input Period                         | Synchro<br>no preso  |         | Tcy + 10   |                         | _        | ns       | N = prescale value                 |
|                                  |                    |   | Synchro<br>with pres |         | Greater of:<br>20 ns or<br>(Tcy + 40)/N                    |                         |          |          | (1, 8, 64, 256)                    |
| TC20                             | TCKEXTMRL          | Delay from Externa<br>Edge to Timer Incre | lock                 | 0.5 TcY |  | 1.5<br>Tcy              | _        |          |                                    |

Note 1: Timer3 and Timer5 are Type C.

### FIGURE 23-9: INPUT CAPTURE (CAPx) TIMING CHARACTERISTICS




**TABLE 23-25: INPUT CAPTURE TIMING REQUIREMENTS** 

| AC CHA       | RACTERI | STICS               | (unless otherwis      | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated)   Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for Industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for Extended |   |    |                                  |  |  |  |
|--------------|---------|---------------------|-----------------------|--|---|----|----------------------------------|--|--|--|
| Param<br>No. | Symbol  | Characte            | ristic <sup>(1)</sup> | istic <sup>(1)</sup> Min Max   |   |    | Conditions                       |  |  |  |
| IC10         | TccL    | ICx Input Low Time  | No prescaler          | 0.5 Tcy + 20   | 1 | ns |                                  |  |  |  |
|              |         |                     | With prescaler        | 10   | _ | ns |                                  |  |  |  |
| IC11         | TccH    | ICx Input High Time | No prescaler          | 0.5 Tcy + 20   | _ | ns |                                  |  |  |  |
|              |         |                     | With prescaler        | 10   | _ | ns |                                  |  |  |  |
| IC15         | TccP    | ICx Input Period    |                       | (2 Tcy + 40)/N   | _ | ns | N = prescale<br>value (1, 4, 16) |  |  |  |

**Note 1:** These parameters are characterized but not tested in manufacturing.

### FIGURE 23-10: OUTPUT COMPARE MODULE (OCx) TIMING CHARACTERISTICS




### TABLE 23-26: OUTPUT COMPARE MODULE TIMING REQUIREMENTS

| AC CHARACTERISTICS |        |                               | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated)  Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |                    |     |       |                    |  |
|--------------------|--------|-------------------------------|---|--------------------|-----|-------|--------------------|--|
| Param<br>No.       | Symbol | Characteristic <sup>(1)</sup> | Min   | Typ <sup>(2)</sup> | Max | Units | Conditions         |  |
| OC10               | TccF   | OCx Output Fall Time          | _   | _                  | _   | ns    | See Parameter DO32 |  |
| OC11               | TccR   | OCx Output Rise Time          | _   | _                  | _   | ns    | See Parameter DO31 |  |

**Note 1:** These parameters are characterized but not tested in manufacturing.

2: Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

FIGURE 23-11: OCx/PWM MODULE TIMING CHARACTERISTICS



### TABLE 23-27: SIMPLE OCx/PWM MODE TIMING REQUIREMENTS

| AC CHARACTERISTICS |        |                               |     | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for Industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for Extended |    |    |  |  |
|--------------------|--------|-------------------------------|-----|--|----|----|--|--|
| Param<br>No.       | Symbol | Characteristic <sup>(1)</sup> | Min | Typ <sup>(2)</sup> Max Units Conditions  |    |    |  |  |
| OC15               | TFD    | Fault Input to PWM I/O Change | _   | _  | 50 | ns |  |  |
| OC20               | TFLT   | Fault Input Pulse Width       | 50  |  |    | ns |  |  |

Note 1: These parameters are characterized but not tested in manufacturing.

**<sup>2:</sup>** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.




TABLE 23-28: DCI MODULE (MULTICHANNEL, I<sup>2</sup>S MODES) TIMING REQUIREMENTS

| AC CHA       | ARACTERIS   | STICS  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for Extended |                        |    |       |            |  |
|--------------|---|--|--|------------------------|----|-------|------------|--|
| Param<br>No. | Symbol  | Characteristic <sup>(1)</sup>  | Min  | Typ <sup>(2)</sup> Max |    | Units | Conditions |  |
| CS10         | TCSCKL  | CSCK Input Low Time<br>(CSCK pin is an input)                                  | Tcy/2 + 20   |                        | _  | ns    |            |  |
|              | CSCK Output Low Time 30 — (CSCK pin is an output) <sup>(3)</sup>  |  | _  | ns                     |    |       |            |  |
| CS11         | Тсѕскн  | (CSCK pin is an input)   |  | _                      | _  | ns    |            |  |
|              | CSCK Output High Time 30 — (CSCK pin is an output) <sup>(3)</sup> |  | _  | _                      | ns |       |            |  |
| CS20         | Tcsckf  | CSCK Output Fall Time (CSCK pin is an output) <sup>(4)</sup>                   | _  | 10                     | 25 | ns    |            |  |
| CS21         | TCSCKR  | CSCK Output Rise Time (CSCK pin is an output) <sup>(4)</sup>                   | — 10 25 ns   |                        | ns |       |            |  |
| CS30         | Tcsdof  | CSDO Data Output Fall Time(4)  | _  | 10                     | 25 | ns    |            |  |
| CS31         | Tcsdor  | CSDO Data Output Rise Time <sup>(4)</sup>                                      | _  | 10                     | 25 | ns    |            |  |
| CS35         | TDV   | Clock Edge to CSDO Data Valid  | _  | _                      | 10 | ns    |            |  |
| CS36         | TDIV  | Clock Edge to CSDO Tri-Stated  | 10   | _                      | 20 | ns    |            |  |
| CS40         | TCSDI   | Setup Time of CSDI Data Input<br>to CSCK Edge (CSCK pin is<br>input or output) | 20   |                        | _  | ns    |            |  |
| CS41         | THCSDI  | Hold Time of CSDI Data Input to CSCK Edge (CSCK pin is input or output)        | 20   | 1                      | _  | ns    |            |  |
| CS50         | Tcofsf  | COFS Fall Time<br>(COFS pin is output)   | ı  | 10                     | 25 | ns    | Note 1     |  |
| CS51         | Tcofsr  | COFS Rise Time<br>(COFS pin is output)   | ı  | 10                     | 25 | ns    | Note 1     |  |
| CS55         | Tscofs  | Setup Time of COFS Data Input<br>to CSCK edge (COFS pin is<br>input)           | 20   | _                      | _  | ns    |            |  |
| CS56         | THCOFS  | Hold Time of COFS Data Input to CSCK Edge (COFS pin is input)                  | 20   | _                      | _  | ns    |            |  |
| CS57         | TPCSCK  | CSCK Clock Period  | 100  | _                      | _  | ns    |            |  |

- Note 1: These parameters are characterized but not tested in manufacturing.
  - **2:** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The minimum clock period for CSCK is 100 ns. Therefore, the clock generated in Master mode must not violate this specification.
  - 4: Assumes 50 pF load on all DCI pins.




TABLE 23-29: DCI MODULE (AC-LINK MODE) TIMING REQUIREMENTS

| AC CHARACTERISTICS |         |  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |      |    |       |                         |
|--------------------|---------|--|--|------|----|-------|-------------------------|
| Param<br>No.       | Symbol  | Characteristic <sup>(1,2)</sup>                | Min Typ <sup>(3)</sup> Max   |      |    | Units | Conditions              |
| CS60               | TBCLKL  | BIT_CLK Low Time                               | 36   | 40.7 | 45 | ns    |                         |
| CS61               | Твськн  | BIT_CLK High Time                              | 36   | 40.7 | 45 | ns    |                         |
| CS62               | TBCLK   | BIT_CLK Period                                 | _  | 81.4 | _  | ns    | Bit clock is input      |
| CS65               | TSACL   | Input Setup Time to Falling Edge of BIT_CLK    | _  | _    | 10 | ns    |                         |
| CS66               | THACL   | Input Hold Time from Falling Edge of BIT_CLK   | _  | _    | 10 | ns    |                         |
| CS70               | TSYNCLO | SYNC Data Output Low Time                      | _  | 19.5 | _  | μS    | Note 1                  |
| CS71               | TSYNCHI | SYNC Data Output High Time                     | _  | 1.3  | _  | μS    | Note 1                  |
| CS72               | TSYNC   | SYNC Data Output Period                        | _  | 20.8 | _  | μS    | Note 1                  |
| CS75               | TRACL   | Rise Time, SYNC, SDATA_OUT                     |  | 10   | 25 | ns    | CLOAD = 50 pF, VDD = 5V |
| CS76               | TFACL   | Fall Time, SYNC, SDATA_OUT                     | _  | 10   | 25 | ns    | CLOAD = 50 pF, VDD = 5V |
| CS80               | TOVDACL | Output Valid Delay from Rising Edge of BIT_CLK | _  | _    | 15 | ns    |                         |

- **Note 1:** These parameters are characterized but not tested in manufacturing.
  - 2: These values assume BIT\_CLK frequency is 12.288 MHz.
  - **3:** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

FIGURE 23-14: SPI MODULE MASTER MODE (CKE = 0) TIMING CHARACTERISTICS




TABLE 23-30: SPI MASTER MODE (CKE = 0) TIMING REQUIREMENTS

| AC CHA       | AC CHARACTERISTICS    |  |  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |    |    |                    |  |  |  |
|--------------|-----------------------|--|--|--|----|----|--------------------|--|--|--|
| Param<br>No. | Symbol                | Characteristic <sup>(1)</sup>              | Min Typ <sup>(2)</sup> Max Units Condition |  |    |    |                    |  |  |  |
| SP10         | TscL                  | SCKx Output Low Time(3)                    | Tcy/2                                      | _  | _  | ns |                    |  |  |  |
| SP11         | TscH                  | SCKx Output High Time <sup>(3)</sup>       | Tcy/2                                      | _  | _  | ns |                    |  |  |  |
| SP20         | TscF                  | SCKx Output Fall Time <sup>(4</sup>        | _  | _  | _  | ns | See parameter DO32 |  |  |  |
| SP21         | TscR                  | SCKx Output Rise Time <sup>(4)</sup>       | _  | _  | _  | ns | See parameter DO31 |  |  |  |
| SP30         | TdoF                  | SDOx Data Output Fall Time <sup>(4)</sup>  | _  | _  | _  | ns | See parameter DO32 |  |  |  |
| SP31         | TdoR                  | SDOx Data Output Rise Time <sup>(4)</sup>  | _  | _  | _  | ns | See parameter DO31 |  |  |  |
| SP35         | TscH2doV,<br>TscL2doV | SDOx Data Output Valid after SCKx Edge     | _  | _  | 30 | ns |                    |  |  |  |
| SP40         | TdiV2scH,<br>TdiV2scL | Setup Time of SDIx Data Input to SCKx Edge | 20   | _  | _  | ns |                    |  |  |  |
| SP41         | TscH2diL,<br>TscL2diL | Hold Time of SDIx Data Input to SCKx Edge  | 20   | _  | _  | ns |                    |  |  |  |

- **Note 1:** These parameters are characterized but not tested in manufacturing.
  - 2: Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The minimum clock period for SCKx is 100 ns. Therefore, the clock generated in Master mode must not violate this specification.
  - 4: Assumes 50 pF load on all SPI pins.

FIGURE 23-15: SPI MODULE MASTER MODE (CKE =1) TIMING CHARACTERISTICS




TABLE 23-31: SPI MODULE MASTER MODE (CKE = 1) TIMING REQUIREMENTS

| AC CHA       | CCHARACTERISTICS      |   |                        | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for Extended |     |       |                    |  |  |  |
|--------------|-----------------------|---|------------------------|--|-----|-------|--------------------|--|--|--|
| Param<br>No. | Symbol                | Characteristic <sup>(1)</sup>                 | Min Typ <sup>(2)</sup> |  | Max | Units | Conditions         |  |  |  |
| SP10         | TscL                  | SCKx Output Low Time <sup>(3)</sup>           | Tcy/2                  | _  | _   | ns    |                    |  |  |  |
| SP11         | TscH                  | SCKx Output High Time <sup>(3)</sup>          | Tcy/2                  | _  | _   | ns    |                    |  |  |  |
| SP20         | TscF                  | SCKx Output Fall Time <sup>(4)</sup>          | _                      | _  | _   | ns    | See parameter DO32 |  |  |  |
| SP21         | TscR                  | SCKx Output Rise Time <sup>(4)</sup>          | _                      | _  | _   | ns    | See parameter DO31 |  |  |  |
| SP30         | TdoF                  | SDOx Data Output Fall<br>Time <sup>(4)</sup>  | _                      | _  | _   | ns    | See parameter DO32 |  |  |  |
| SP31         | TdoR                  | SDOx Data Output Rise<br>Time <sup>(4)</sup>  | _                      | _  | _   | ns    | See parameter DO31 |  |  |  |
| SP35         | TscH2do,<br>TscL2doV  | SDOx Data Output Valid after SCKx Edge        | _                      | _  | 30  | ns    |                    |  |  |  |
| SP36         | TdoV2sc,<br>TdoV2scL  | SDOx Data Output Setup to First SCKx Edge     | 30                     | _  | _   | ns    |                    |  |  |  |
| SP40         | TdiV2scH,<br>TdiV2scL | Setup Time of SDIx Data<br>Input to SCKx Edge | 20                     | _  |     | ns    |                    |  |  |  |
| SP41         | TscH2diL,<br>TscL2diL | Hold Time of SDIx Data Input to SCKx Edge     | 20                     | _  | _   | ns    |                    |  |  |  |

- Note 1: These parameters are characterized but not tested in manufacturing.
  - 2: Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - 3: The minimum clock period for SCKx is 100 ns. Therefore, the clock generated in Master mode must not violate this specification.
  - 4: Assumes 50 pF load on all SPI pins.

FIGURE 23-16: SPI MODULE SLAVE MODE (CKE = 0) TIMING CHARACTERISTICS




TABLE 23-32: SPI MODULE SLAVE MODE (CKE = 0) TIMING REQUIREMENTS

| AC CHARACTERISTICS |                       |  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |                    |     |       |                    |  |
|--------------------|-----------------------|--|--|--------------------|-----|-------|--------------------|--|
| Param<br>No.       | Symbol                | Characteristic <sup>(1)</sup>                                    | Min  | Typ <sup>(2)</sup> | Max | Units | Conditions         |  |
| SP70               | TscL                  | SCKx Input Low Time  | 30   | _                  | _   | ns    |                    |  |
| SP71               | TscH                  | SCKx Input High Time   | 30   | _                  | _   | ns    |                    |  |
| SP72               | TscF                  | SCKx Input Fall Time <sup>(3)</sup>                              | _  |                    | 25  | ns    |                    |  |
| SP73               | TscR                  | SCKx Input Rise Time <sup>(3)</sup>                              | _  |                    | 25  | ns    |                    |  |
| SP30               | TdoF                  | SDOx Data Output Fall Time <sup>(3)</sup>                        | _  |                    |     | ns    | See parameter DO32 |  |
| SP31               | TdoR                  | SDOx Data Output Rise Time <sup>(3)</sup>                        | _  |                    | _   | ns    | See parameter DO31 |  |
| SP35               | TscH2do,<br>TscL2doV  | SDOx Data Output Valid after SCKx Edge                           | _  |                    | 30  | ns    |                    |  |
| SP40               | TdiV2scH,<br>TdiV2scL | Setup Time of SDIx Data Input to SCKx Edge                       | 20   |                    | _   | ns    |                    |  |
| SP41               | TscH2diL,<br>TscL2diL | Hold Time of SDIx Data Input to SCKx Edge                        | 20   |                    |     | ns    |                    |  |
| SP50               | TssL2scH,<br>TssL2scL | SSx ↓ to SCKx↑ or SCKx↓ Input                                    | 120  |                    |     | ns    |                    |  |
| SP51               | TssH2doZ              | SSx <sup>↑</sup> to SDOx Output<br>High-impedance <sup>(3)</sup> | 10   | _                  | 50  | ns    |                    |  |
| SP52               | TscH2ssH<br>TscL2ssH  | SSx after SCKx Edge  | 1.5 Tcy + 40   | _                  | _   | ns    |                    |  |

Note 1: These parameters are characterized but not tested in manufacturing.

<sup>2:</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

<sup>3:</sup> Assumes 50 pF load on all SPI pins.




TABLE 23-33: SPI MODULE SLAVE MODE (CKE = 1) TIMING REQUIREMENTS

| AC CHA       | RACTERIS'             | TICS   | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |                    |     |       |                    |  |  |
|--------------|-----------------------|--|--|--------------------|-----|-------|--------------------|--|--|
| Param<br>No. | Symbol                | Characteristic <sup>(1)</sup>                        | Min  | Typ <sup>(2)</sup> | Max | Units | Conditions         |  |  |
| SP70         | TscL                  | SCKx Input Low Time                                  | 30   | _                  |     | ns    |                    |  |  |
| SP71         | TscH                  | SCKx Input High Time                                 | 30   | _                  | _   | ns    |                    |  |  |
| SP72         | TscF                  | SCKx Input Fall Time <sup>(3)</sup>                  | _  | _                  | 25  | ns    |                    |  |  |
| SP73         | TscR                  | SCKx Input Rise Time <sup>(3)</sup>                  | _  | _                  | 25  | ns    |                    |  |  |
| SP30         | TdoF                  | SDOx Data Output Fall Time <sup>(3)</sup>            | _  |                    | _   | ns    | See parameter DO32 |  |  |
| SP31         | TdoR                  | SDOx Data Output Rise Time <sup>(3)</sup>            | _  | _                  | _   | ns    | See parameter DO31 |  |  |
| SP35         | TscH2do,<br>TscL2doV  | SDOx Data Output Valid after<br>SCKx Edge            | _  | _                  | 30  | ns    |                    |  |  |
| SP40         | TdiV2scH,<br>TdiV2scL | Setup Time of SDIx Data Input to SCKx Edge           | 20   | _                  | _   | ns    |                    |  |  |
| SP41         | TscH2diL,<br>TscL2diL | Hold Time of SDIx Data Input to SCKx Edge            | 20   | _                  | _   | ns    |                    |  |  |
| SP50         | TssL2scH,<br>TssL2scL | SSx ↓ to SCKx ↓ or SCKx↑ Input                       | 120  | _                  | _   | ns    |                    |  |  |
| SP51         | TssH2doZ              | SSx↑ to SDOx Output<br>High-Impedance <sup>(4)</sup> | 10   | _                  | 50  | ns    |                    |  |  |
| SP52         | TscH2ssH<br>TscL2ssH  | SSx <sup>↑</sup> after SCKx Edge                     | 1.5 Tcy + 40   | _                  | _   | ns    |                    |  |  |
| SP60         | TssL2doV              | SDOx Data Output Valid after SCKx Edge               | _  | _                  | 50  | ns    |                    |  |  |

- Note 1: These parameters are characterized but not tested in manufacturing.
  - **2:** Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.
  - **3:** The minimum clock period for SCKx is 100 ns. Therefore, the clock generated in Master mode must not violate this specification.
  - 4: Assumes 50 pF load on all SPI pins.

FIGURE 23-18: I<sup>2</sup>C™ BUS START/STOP BITS TIMING CHARACTERISTICS (MASTER MODE)




FIGURE 23-19: I<sup>2</sup>C™ BUS DATA TIMING CHARACTERISTICS (MASTER MODE)




TABLE 23-34: I<sup>2</sup>C™ BUS DATA TIMING REQUIREMENTS (MASTER MODE)

| AC CHA                          | RACTER  | ISTICS          |                           | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |     |       |                       |  |  |
|---------------------------------|---------|-----------------|---------------------------|--|-----|-------|-----------------------|--|--|
| Param No. Symbol Characteristic |         |                 |                           | Min <sup>(1)</sup>   | Max | Units | Conditions            |  |  |
| IM10                            | TLO:SCL | Clock Low Time  | 100 kHz mode              | Tcy/2 (BRG + 1)  | -   | μS    |                       |  |  |
|                                 |         |                 | 400 kHz mode              | Tcy/2 (BRG + 1)  | _   | μS    |                       |  |  |
|                                 |         |                 | 1 MHz mode <sup>(2)</sup> | Tcy/2 (BRG + 1)  | _   | μS    |                       |  |  |
| IM11                            | THI:SCL | Clock High Time | 100 kHz mode              | Tcy/2 (BRG + 1)  | _   | μS    |                       |  |  |
|                                 |         |                 | 400 kHz mode              | Tcy/2 (BRG + 1)  | _   | μS    |                       |  |  |
|                                 |         |                 | 1 MHz mode <sup>(2)</sup> | Tcy/2 (BRG + 1)  | _   | μS    |                       |  |  |
| IM20                            | TF:SCL  | SDA and SCL     | 100 kHz mode              | _  | 300 | ns    | CB is specified to be |  |  |
|                                 |         | Fall Time       | 400 kHz mode              | 20 + 0.1 Св  | 300 | ns    | from 10 to 400 pF     |  |  |
|                                 |         |                 | 1 MHz mode <sup>(2)</sup> | _  | 100 | ns    |                       |  |  |

Note 1: BRG is the value of the I<sup>2</sup>C Baud Rate Generator. Refer to **Section 21.** "Inter-Integrated Circuit™ (I<sup>2</sup>C)" in the "dsPIC30F Family Reference Manual" (DS70046).

<sup>2:</sup> Maximum pin capacitance = 10 pF for all  $I^2C$  pins (for 1 MHz mode only).


TABLE 23-34: I<sup>2</sup>C™ BUS DATA TIMING REQUIREMENTS (MASTER MODE) (CONTINUED)

| AC CHA       | ARACTER | ISTICS           |                           | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |      |       |                        |  |
|--------------|---------|------------------|---------------------------|--|------|-------|------------------------|--|
| Param<br>No. | Symbol  | Charac           | teristic                  | Min <sup>(1)</sup>   | Max  | Units | Conditions             |  |
| IM21         | TR:SCL  | SDA and SCL      | 100 kHz mode              | _  | 1000 | ns    | CB is specified to be  |  |
|              |         | Rise Time        | 400 kHz mode              | 20 + 0.1 CB  | 300  | ns    | from 10 to 400 pF      |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | _  | 300  | ns    |                        |  |
| IM25         | TSU:DAT | Data Input       | 100 kHz mode              | 250  | _    | ns    |                        |  |
|              |         | Setup Time       | 400 kHz mode              | 100  | _    | ns    |                        |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | _  | _    | ns    |                        |  |
| IM26         | THD:DAT | Data Input       | 100 kHz mode              | 0  | _    | ns    |                        |  |
|              |         | Hold Time        | 400 kHz mode              | 0  | 0.9  | μS    |                        |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | _  | _    | ns    |                        |  |
| IM30         | TSU:STA | Start Condition  | 100 kHz mode              | Tcy/2 (BRG + 1)  | _    | μS    | Only relevant for      |  |
|              |         | Setup Time       | 400 kHz mode              | Tcy/2 (BRG + 1)  | _    | μS    | Repeated Start         |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | Tcy/2 (BRG + 1)  | _    | μS    | condition              |  |
| IM31         | THD:STA | Start Condition  | 100 kHz mode              | Tcy/2 (BRG + 1)  | _    | μS    | After this period, the |  |
|              |         | Hold Time        | 400 kHz mode              | Tcy/2 (BRG + 1)  | _    | μS    | first clock pulse is   |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | Tcy/2 (BRG + 1)  | _    | μS    | generated              |  |
| IM33         | Tsu:sto | Stop Condition   | 100 kHz mode              | Tcy/2 (BRG + 1)  | _    | μS    |                        |  |
|              |         | Setup Time       | 400 kHz mode              | Tcy/2 (BRG + 1)  | _    | μS    |                        |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | Tcy/2 (BRG + 1)  | _    | μS    |                        |  |
| IM34         | THD:STO | Stop Condition   | 100 kHz mode              | Tcy/2 (BRG + 1)  | _    | ns    |                        |  |
|              |         | Hold Time        | 400 kHz mode              | Tcy/2 (BRG + 1)  | _    | ns    |                        |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | Tcy/2 (BRG + 1)  | _    | ns    |                        |  |
| IM40         | TAA:SCL | Output Valid     | 100 kHz mode              | _  | 3500 | ns    |                        |  |
|              |         | From Clock       | 400 kHz mode              | _  | 1000 | ns    |                        |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> | _  | _    | ns    |                        |  |
| IM45         | TBF:SDA | Bus Free Time    | 100 kHz mode              | 4.7  | _    | μS    | Time the bus must be   |  |
|              |         |                  | 400 kHz mode              | 1.3  | _    | μS    | free before a new      |  |
|              |         |                  | 1 MHz mode <sup>(2)</sup> |  | _    | μS    | transmission can start |  |
| IM50         | Св      | Bus Capacitive L | oading                    | _  | 400  | pF    |                        |  |


Note 1: BRG is the value of the I<sup>2</sup>C Baud Rate Generator. Refer to Section 21. "Inter-Integrated Circuit™ (I<sup>2</sup>C)" in the "dsPIC30F Family Reference Manual" (DS70046).

<sup>2:</sup> Maximum pin capacitance = 10 pF for all  $I^2C$  pins (for 1 MHz mode only).





### FIGURE 23-21: I<sup>2</sup>C™ BUS DATA TIMING CHARACTERISTICS (SLAVE MODE)



**AC CHARACTERISTICS** 

## TABLE 23-35: I<sup>2</sup>C™ BUS DATA TIMING REQUIREMENTS (SLAVE MODE)

Standard Operating Conditions: 2.5V to 5.5V

(unless otherwise stated)

Operating temperature  $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$  for Industrial -40°C < TA < +125°C for Extended

|              |         | •                         | -40°C ≤ TA ≤ +125°C for Extended |             |      |       |   |  |  |
|--------------|---------|---------------------------|----------------------------------|-------------|------|-------|---|--|--|
| Param<br>No. | Symbol  | Charact                   | teristic                         | Min         | Max  | Units | Conditions                                  |  |  |
| IS10         | TLO:SCL | Clock Low Time            | 100 kHz mode                     | 4.7         | _    | μS    | Device must operate at a minimum of 1.5 MHz |  |  |
|              |         |                           | 400 kHz mode                     | 1.3         | _    | μS    | Device must operate at a minimum of 10 MHz. |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0.5         | _    | μS    |   |  |  |
| IS11         | THI:SCL | Clock High Time           | 100 kHz mode                     | 4.0         | _    | μS    | Device must operate at a minimum of 1.5 MHz |  |  |
|              |         |                           | 400 kHz mode                     | 0.6         | _    | μS    | Device must operate at a minimum of 10 MHz  |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0.5         | _    | μS    |   |  |  |
| IS20         | TF:SCL  | SDA and SCL               | 100 kHz mode                     | _           | 300  | ns    | CB is specified to be from                  |  |  |
|              |         | Fall Time                 | 400 kHz mode                     | 20 + 0.1 CB | 300  | ns    | 10 to 400 pF                                |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | _           | 100  | ns    |   |  |  |
| IS21         | TR:SCL  | SDA and SCL               | 100 kHz mode                     | _           | 1000 | ns    | CB is specified to be from                  |  |  |
|              |         | Rise Time                 | 400 kHz mode                     | 20 + 0.1 CB | 300  | ns    | 10 to 400 pF                                |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | _           | 300  | ns    |   |  |  |
| IS25         | TSU:DAT | Data Input                | 100 kHz mode                     | 250         | _    | ns    |   |  |  |
|              |         | Setup Time                | 400 kHz mode                     | 100         | _    | ns    |   |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 100         | _    | ns    |   |  |  |
| IS26         | THD:DAT | Data Input                | 100 kHz mode                     | 0           | _    | ns    |   |  |  |
|              |         | Hold Time                 | 400 kHz mode                     | 0           | 0.9  | μS    |   |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0           | 0.3  | μS    |   |  |  |
| IS30         | Tsu:sta | Start Condition           | 100 kHz mode                     | 4.7         | _    | μS    | Only relevant for Repeated                  |  |  |
|              |         | Setup Time                | 400 kHz mode                     | 0.6         | _    | μS    | Start condition                             |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0.25        | _    | μS    |   |  |  |
| IS31         | THD:STA | Start Condition           | 100 kHz mode                     | 4.0         | _    | μS    | After this period, the first                |  |  |
|              |         | Hold Time                 | 400 kHz mode                     | 0.6         | _    | μS    | clock pulse is generated                    |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0.25        | _    | μS    |   |  |  |
| IS33         | Tsu:sto | Stop Condition            | 100 kHz mode                     | 4.7         | _    | μS    |   |  |  |
|              |         | Setup Time                | 400 kHz mode                     | 0.6         | _    | μS    |   |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0.6         | _    | μS    |   |  |  |
| IS34         | THD:STO | Stop Condition            | 100 kHz mode                     | 4000        | _    | ns    |   |  |  |
|              |         | Hold Time                 | 400 kHz mode                     | 600         | _    | ns    |   |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 250         |      | ns    |   |  |  |
| IS40         | TAA:SCL | Output Valid From         | 100 kHz mode                     | 0           | 3500 | ns    |   |  |  |
|              |         | Clock                     | 400 kHz mode                     | 0           | 1000 | ns    | 1   |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0           | 350  | ns    | 1   |  |  |
| IS45         | TBF:SDA | Bus Free Time             | 100 kHz mode                     | 4.7         | _    | μS    | Time the bus must be free                   |  |  |
|              |         |                           | 400 kHz mode                     | 1.3         | _    | μS    | before a new transmission                   |  |  |
|              |         |                           | 1 MHz mode <sup>(1)</sup>        | 0.5         | _    | μS    | can start                                   |  |  |
| IS50         | Св      | Bus Capacitive<br>Loading |                                  | _           | 400  | pF    |   |  |  |

**Note 1:** Maximum pin capacitance = 10 pF for all I<sup>2</sup>C pins (for 1 MHz mode only).

### FIGURE 23-22: CAN MODULE I/O TIMING CHARACTERISTICS




TABLE 23-36: CAN MODULE I/O TIMING REQUIREMENTS

| AC CHARACTERISTICS |        |   | Standard Op<br>(unless other<br>Operating ter | rwise sta          | <b>ated)</b><br>e -40°C: | s: <b>2.5V to</b><br>≤ TA ≤ +85<br>≤ TA ≤ +12 | °C for Ind |  |
|--------------------|--------|---|---|--------------------|--------------------------|---|------------|--|
| Param<br>No.       | Symbol | Characteri                              | Min   | Typ <sup>(2)</sup> | Max                      | Units   | Conditions |  |
| CA10               | TioF   | Port Output Fall Ti                     | me  | _                  | 10                       | 25  | ns         |  |
| CA11               | TioR   | Port Output Rise Time                   |   | _                  | 10                       | 25  | ns         |  |
| CA20               | Tcwf   | Pulse Width to Trig<br>CAN Wake-up Filt |   | 500                | _                        | _   | ns         |  |

Note 1: These parameters are characterized but not tested in manufacturing.

<sup>2:</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. Parameters are for design guidance only and are not tested.

TABLE 23-37: 12-BIT A/D MODULE SPECIFICATIONS

| AC CHA        | ARACTERIS | STICS  | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |             |                                  |          |   |  |  |
|---------------|-----------|--|--|-------------|----------------------------------|----------|---|--|--|
| Param<br>No.  | Symbol    | Characteristic                                 | Min.   | Тур         | Max.                             | Units    | Conditions  |  |  |
| Device Supply |           |  |  |             |                                  |          |   |  |  |
| AD01          | AVDD      | Module VDD Supply                              | Greater of<br>VDD – 0.3<br>or 2.7  | _           | Lesser of<br>VDD + 0.3<br>or 5.5 | V        |   |  |  |
| AD02          | AVss      | Module Vss Supply                              | Vss - 0.3  | _           | Vss + 0.3                        | V        |   |  |  |
|               |           |  | Reference  | Inputs      |                                  |          |   |  |  |
| AD05          | VREFH     | Reference Voltage High                         | AVss + 2.7   | _           | AVDD                             | V        |   |  |  |
| AD06          | VREFL     | Reference Voltage Low                          | AVss   | _           | AVDD - 2.7                       | V        |   |  |  |
| AD07          | VREF      | Absolute Reference<br>Voltage                  | AVss - 0.3   | _           | AVDD + 0.3                       | V        |   |  |  |
| AD08          | IREF      | Current Drain                                  | _  | 200<br>.001 | 300<br>2                         | μA<br>μA | A/D operating<br>A/D off  |  |  |
| Analog Input  |           |  |  |             |                                  |          |   |  |  |
| AD10          | VINH-VINL | Full-Scale Input Span                          | VREFL  |             | VREFH                            | V        | Note 1  |  |  |
| AD11          | VIN       | Absolute Input Voltage                         | AVss - 0.3   |             | AVDD + 0.3                       | V        |   |  |  |
| AD12          | _         | Leakage Current                                | _  | ±0.001      | ±0.610                           | μА       | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 5V<br>Source Impedance = $2.5 \text{ k}\Omega$    |  |  |
| AD13          | _         | Leakage Current                                | _  | ±0.001      | ±0.610                           | μА       | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 3V<br>Source Impedance =<br>$2.5 \text{ k}\Omega$ |  |  |
| AD15          | Rss       | Switch Resistance                              | _  | 3.2K        | _                                | Ω        |   |  |  |
| AD16          | CSAMPLE   | Sample Capacitor                               | _  | 18          |                                  | pF       |   |  |  |
| AD17          | RIN       | Recommended Impedance of Analog Voltage Source | _  | _           | 2.5K                             | Ω        |   |  |  |
|               |           |  | DC Accu  | racy        |                                  |          |   |  |  |
| AD20          | Nr        | Resolution                                     | 1  | 2 data b    | its                              | bits     |   |  |  |
| AD21          | INL       | Integral Nonlinearity                          | _  | _           | <±1                              | LSb      | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 5V  |  |  |
| AD21A         | INL       | Integral Nonlinearity                          | _  | _           | <±1                              | LSb      | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 3V  |  |  |
| AD22          | DNL       | Differential Nonlinearity                      | _  | _           | <±1                              | LSb      | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 5V  |  |  |
| AD22A         | DNL       | Differential Nonlinearity                      | _  | _           | <±1                              | LSb      | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 3V  |  |  |
| AD23          | GERR      | Gain Error                                     | +1.25  | +1.5        | +3                               | LSb      | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 5V  |  |  |
| AD23A         | GERR      | Gain Error                                     | +1.25  | +1.5        | +3                               | LSb      | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 3V  |  |  |


**Note 1:** The A/D conversion result never decreases with an increase in the input voltage, and has no missing codes.

TABLE 23-37: 12-BIT A/D MODULE SPECIFICATIONS (CONTINUED)

| AC CHARACTERISTICS |        |                                | Standard Operating Conditions: 2.5V to 5.5V (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |        |       |      |  |  |  |
|--------------------|--------|--------------------------------|--|--------|-------|------|--|--|--|
| Param<br>No.       | Symbol | Characteristic                 | Min. Typ Max. Units Conditions   |        |       |      |  |  |  |
| AD24               | EOFF   | Offset Error                   | -2   | -1.5   | -1.25 | LSb  | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 5V |  |  |
| AD24A              | EOFF   | Offset Error                   | -2   | -1.5   | -1.25 | LSb  | VINL = AVSS = VREFL = 0V,<br>AVDD = VREFH = 3V |  |  |
| AD25               | _      | Monotonicity <sup>(1)</sup>    | — — — Guaranteed   |        |       |      | Guaranteed                                     |  |  |
|                    |        | D                              | ynamic Perf  | ormanc | е     |      |  |  |  |
| AD30               | THD    | Total Harmonic Distortion      | _  | -71    |       | dB   |  |  |  |
| AD31               | SINAD  | Signal to Noise and Distortion | _  | 68     |       | dB   |  |  |  |
| AD32               | SFDR   | Spurious Free Dynamic<br>Range | _  | 83     | _     | dB   |  |  |  |
| AD33               | FNYQ   | Input Signal Bandwidth         | _  | _      | 100   | kHz  |  |  |  |
| AD34               | ENOB   | Effective Number of Bits       | 10.95  | 11.1   | _     | bits |  |  |  |

**Note 1:** The A/D conversion result never decreases with an increase in the input voltage, and has no missing codes.

FIGURE 23-23: 12-BIT A/D CONVERSION TIMING CHARACTERISTICS (ASAM = 0, SSRC = 000)



- 1 Software sets ADCON. SAMP to start sampling.
- Sampling starts after discharge period.
   TSAMP is described in Section 18. "12-bit A/D Converter" of the dsPIC30F Family Reference Manual (DS70046).
- 3 Software clears ADCON. SAMP to start conversion.
- 4 Sampling ends, conversion sequence starts.
- (5) Convert bit 11.
- 6 Convert bit 10.
- (7) Convert bit 1.
- (8) Convert bit 0.
- (9) One TAD for end of conversion.

TABLE 23-38: 12-BIT A/D CONVERSION TIMING REQUIREMENTS

| AC CHARACTERISTICS |                     |   | Standard Operating Conditions: 2.7V to 5.5V (unless otherwise stated)<br>Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for Industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for Extended |         |            |      |   |  |
|--------------------|---------------------|---|---|---------|------------|------|---|--|
| Param<br>No.       | Symbol              | Characteristic  | Min. Typ Max. Units Conditions  |         |            |      |   |  |
|                    | •                   | Cloc  | k Parame  | ters    |            | •    |   |  |
| AD50               | TAD                 | A/D Clock Period                                      | 334   | _       | _          | ns   | VDD = 3-5.5V (Note 1)   |  |
| AD51               | tRC                 | A/D Internal RC Oscillator Period                     | 1.2   | 1.5     | 1.8        | μS   |   |  |
| Conversion Rate    |                     |   |   |         |            |      |   |  |
| AD55               | tconv               | Conversion Time                                       | _   | 14 TAD  |            | ns   |   |  |
| AD56               | FCNV                | Throughput Rate                                       | _   | 200     | _          | ksps | VDD = VREF = 5V   |  |
| AD57               | TSAMP               | Sampling Time   | 1 TAD   | _       |            | ns   | $VDD = 3-5.5V$ source resistance $Rs = 0-2.5 \text{ k}\Omega$ |  |
|                    |                     | Timin   | g Parame  | eters   |            |      |   |  |
| AD60               | tPCS                | Conversion Start from Sample Trigger                  | _   | 1 TAD   | _          | ns   |   |  |
| AD61               | tPSS                | Sample Start from Setting Sample (SAMP) Bit           | 0.5 TAD   | _       | 1.5<br>TAD | ns   |   |  |
| AD62               | tcss                | Conversion Completion to Sample Start (ASAM = 1)      | _   | 0.5 TAD | _          | ns   |   |  |
| AD63               | tDPU <sup>(2)</sup> | Time to Stabilize Analog Stage from A/D Off to A/D On | _   | _       | 20         | μS   |   |  |

**Note 1:** Because the sample caps will eventually lose charge, clock rates below 10 kHz can affect linearity performance, especially at elevated temperatures.


<sup>2:</sup> tDPU is the time required for the ADC module to stabilize when it is turned on (ADCON1<ADON> = 1). During this time the ADC result is indeterminate.

NOTES:

### 24.0 PACKAGING INFORMATION

### 24.1 Package Marking Information

40-Lead PDIP



### Example



44-Lead TQFP



### Example



44-Lead QFN



#### Example




Legend: XX...X Customer-specific information
Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')
NNN Alphanumeric traceability code

(e3) Pb-free JEDEC designator for Matte Tin (Sn)
This package is Pb-free. The Pb-free JEDEC designator ((e3))
can be found on the outer packaging for this package.

In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.

### 40-Lead Plastic Dual In-Line (P) - 600 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                            | Units            | INCHES |          |       |  |
|----------------------------|------------------|--------|----------|-------|--|
| Dimensio                   | Dimension Limits |        | NOM      | MAX   |  |
| Number of Pins             | N                |        | 40       |       |  |
| Pitch                      | е                |        | .100 BSC |       |  |
| Top to Seating Plane       | Α                | _      | _        | .250  |  |
| Molded Package Thickness   | A2               | .125   | -        | .195  |  |
| Base to Seating Plane      | A1               | .015   | _        | _     |  |
| Shoulder to Shoulder Width | Е                | .590   | _        | .625  |  |
| Molded Package Width       | E1               | .485   | _        | .580  |  |
| Overall Length             | D                | 1.980  | _        | 2.095 |  |
| Tip to Seating Plane       | L                | .115   | _        | .200  |  |
| Lead Thickness             | С                | .008   | _        | .015  |  |
| Upper Lead Width           | b1               | .030   | _        | .070  |  |
| Lower Lead Width           | b                | .014   | _        | .023  |  |
| Overall Row Spacing §      | eB               | -      | _        | .700  |  |

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-016B

### 44-Lead Plastic Thin Quad Flatpack (PT) – 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



|                          | Units            |           | MILLIMETERS |      |  |
|--------------------------|------------------|-----------|-------------|------|--|
|                          | Dimension Limits |           | NOM         | MAX  |  |
| Number of Leads          | N                |           | 44          |      |  |
| Lead Pitch               | е                |           | 0.80 BSC    |      |  |
| Overall Height           | Α                | _         | _           | 1.20 |  |
| Molded Package Thickness | A2               | 0.95      | 1.00        | 1.05 |  |
| Standoff                 | A1               | 0.05      | _           | 0.15 |  |
| Foot Length              | L                | 0.45      | 0.60        | 0.75 |  |
| Footprint                | L1               | 1.00 REF  |             |      |  |
| Foot Angle               | ф                | 0°        | 3.5°        | 7°   |  |
| Overall Width            | E                | 12.00 BSC |             |      |  |
| Overall Length           | D                |           | 12.00 BSC   |      |  |
| Molded Package Width     | E1               | 10.00 BSC |             |      |  |
| Molded Package Length    | D1               | 10.00 BSC |             |      |  |
| Lead Thickness           | С                | 0.09      | _           | 0.20 |  |
| Lead Width               | b                | 0.30      | 0.37        | 0.45 |  |
| Mold Draft Angle Top     | α                | 11°       | 12°         | 13°  |  |
| Mold Draft Angle Bottom  | β                | 11°       | 12°         | 13°  |  |

### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Chamfers at corners are optional; size may vary.
- 3. Dimensions D1 and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


 ${\tt BSC: Basic \ Dimension. \ Theoretically \ exact \ value \ shown \ without \ tolerances.}$ 

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-076B

### 44-Lead Plastic Thin Quad Flatpack (PT) - 10x10x1 mm Body, 2.00 mm [TQFP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

|                          | MILLIM |          |       |      |
|--------------------------|--------|----------|-------|------|
| Dimension Limits         |        | MIN      | NOM   | MAX  |
| Contact Pitch E          |        | 0.80 BSC |       |      |
| Contact Pad Spacing (    |        |          | 11.40 |      |
| Contact Pad Spacing      | C2     |          | 11.40 |      |
| Contact Pad Width (X44)  | X1     |          |       | 0.55 |
| Contact Pad Length (X44) |        |          |       | 1.50 |
| Distance Between Pads    | G      | 0.25     |       |      |

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.


Microchip Technology Drawing No. C04-2076A

### 44-Lead Plastic Quad Flat, No Lead Package (ML) – 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging







|                        | Units            |             | MILLIMETERS |      |  |
|------------------------|------------------|-------------|-------------|------|--|
|                        | Dimension Limits | MIN         | NOM         | MAX  |  |
| Number of Pins         | N                | 44          |             |      |  |
| Pitch                  | е                |             | 0.65 BSC    |      |  |
| Overall Height         | А                | 0.80 0.90 1 |             |      |  |
| Standoff               | A1               | 0.00        | 0.02        | 0.05 |  |
| Contact Thickness      | A3               | 0.20 REF    |             |      |  |
| Overall Width          | E                | 8.00 BSC    |             |      |  |
| Exposed Pad Width      | E2               | 6.30        | 6.45        | 6.80 |  |
| Overall Length         | D                |             | 8.00 BSC    | •    |  |
| Exposed Pad Length     | D2               | 6.30        | 6.45        | 6.80 |  |
| Contact Width          | b                | 0.25        | 0.30        | 0.38 |  |
| Contact Length         | L                | 0.30        | 0.40        | 0.50 |  |
| Contact-to-Exposed Pad | K                | 0.20        | _           | _    |  |

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated.
- 3. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-103B

### 44-Lead Plastic Quad Flat, No Lead Package (ML) – 8x8 mm Body [QFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

|                            | MILLIMETERS |          |      |      |
|----------------------------|-------------|----------|------|------|
| Dimension Limits           |             | MIN      | NOM  | MAX  |
| Contact Pitch              | E           | 0.65 BSC |      |      |
| Optional Center Pad Width  | W2          |          |      | 6.80 |
| Optional Center Pad Length | T2          |          |      | 6.80 |
| Contact Pad Spacing        | C1          |          | 8.00 |      |
| Contact Pad Spacing        | C2          |          | 8.00 |      |
| Contact Pad Width (X44)    | X1          |          |      | 0.35 |
| Contact Pad Length (X44)   | Y1          |          |      | 0.80 |
| Distance Between Pads      | G           | 0.25     |      |      |

### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2103A

#### APPENDIX A: REVISION HISTORY

#### Revision D (June 2006)

Previous versions of this data sheet contained Advance or Preliminary Information. They were distributed with incomplete characterization data.

This revision reflects these changes:

- Revised I<sup>2</sup>C Slave Addresses (see Table 14-1)
- Updated example for ADC Conversion Clock selection (see Section 19.0 "12-bit Analog-to-Digital Converter (ADC) Module")
- Base instruction CP1 eliminated from instruction set (seeTable 21-2)
- · Revised electrical characteristics:
  - Operating Current (IDD) Specifications (see Table 23-5)
  - Idle Current (IIDLE) Specifications (see Table 23-6)
  - Power-down Current (IPD) Specifications (see Table 23-7)
  - I/O pin Input Specifications (see Table 23-8)
  - Brown Out Reset (BOR) Specifications (see Table 23-11)
  - Watchdog Timer time-out limits (see Table 23-20)

#### **Revision E (January 2007)**

This revision includes updates to the packaging diagrams.

#### Revision F (April 2008)

This revision reflects these updates:

- Added FUSE Configuration Register (FICD) details (see Section 20.8 "Device Configuration Registers" and Table 20-8)
- Added Note 2 in Device Configuration Registers table (Table 20-8)
- Removed erroneous statement regarding generation of CAN receive errors (see Section 17.4.5 "Receive Errors")
- Updated ADC Conversion Clock and Sampling Rate Calculation (see Example 19-1). Minimum TAD is 334 nsec.
- Updated details related to the Input Change Notification module:
  - Updated last sentence in the first paragraph of Section 7.3 "Input Change Notification Module"
  - Updated Table 7-2
  - Removed Table 7-3, Table 7-4, and Table 7-5

- · Electrical Specifications:
  - Resolved TBD values for parameters DO10, DO16, DO20, and DO26 (see Table 23-9)
  - 10-bit High-Speed ADC tPDU timing parameter (time to stabilize) has been updated from 20 μs typical to 20 μs maximum (see Table 23-38)
  - Parameter OS65 (Internal RC Accuracy) has been expanded to reflect multiple Min and Max values for different temperatures (see Table 23-18)
  - Parameter DC12 (RAM Data Retention Voltage) has been updated to include a Min value (see Table 23-4)
  - Parameter D134 (Erase/Write Cycle Time)
     has been updated to include Min and Max
     values and the Typ value has been removed
     (see Table 23-12)
  - Removed parameters OS62 (Internal FRC Jitter) and OS64 (Internal FRC Drift) and Note 2 from AC Characteristics (see Table 23-17)
  - Parameter OS63 (Internal FRC Accuracy) has been expanded to reflect multiple Min and Max values for different temperatures (see Table 23-17)
  - Removed parameters DC27a, DC27b, DC47a, and DC47b (references to IDD, 20 MIPs @ 3.3V) in Table 23-5 and Table 23-6
  - Removed parameters CS77 and CS78 (references to TRACL and TFACL @ 3.3V) in Table 23-29
  - Updated Min and Max values and Conditions for parameter SY11 and updated Min, Typ, and Max values and Conditions for parameter SY20 (see Table 23-20)
- Additional minor corrections throughout the document

### **Revision G (November 2010)**

This revision includes minor typographical and formatting changes throughout the data sheet text.

The major changes are referenced by their respective section in Table A-1.

TABLE A-1: MAJOR SECTION UPDATES

| Section Name  | Update Description  |
|---|---|
| "High-Performance, 16-Bit Digital Signal Controllers" | Added Note 1 to all QFN pin diagrams (see "Pin Diagrams").  |
| Section 1.0 "Device Overview"                         | Removed the "DCI" peripheral block from the dsPIC30F3014 Block Diagram (see Figure 1-1).  |
|   | Updated the Pinout I/O Descriptions for AVDD and AVSS (see Table 1-1).  |
| Section 20.0 "System Integration"                     | Added a note on OSCTUN functionality in Section 20.2.5 "Fast RC Oscillator (FRC)".  |
|   | Updated the operating frequencies for the following Oscillator Operating Modes (see Table 20-1):  |
|   | <ul> <li>XTL</li> <li>XT w/PLL 16x</li> <li>HS/2 w/PLL 4x, 8x, and 16x</li> <li>HS/3 w/PLL 4x, 8x, and 16x</li> <li>EC w/PLL 4x, 8x, and 16x</li> </ul>                   |
| Section 23.0 "Electrical Characteristics"             | Updated the maximum value for parameter DI19 and the minimum value for parameter DI29 in the I/O Pin Input Specifications (see Table 23-8).                               |
|   | Removed parameter D136 and updated the minimum, typical, maximum, and conditions for parameters D122 and D134 in the Program and EEPROM specifications (see Table 23-12). |

### **INDEX**

| Numerics   | CAN Buffers and Protocol Engine        | 112        |
|--|--|------------|
| 12-Bit Analog-to-Digital Converter (A/D) Module131 | DCI Module                             |            |
| _  | Dedicated Port Structure               |            |
| A  | DSP Engine                             |            |
| A/D131   | dsPIC30F3014                           |            |
| Aborting a Conversion133                           | dsPIC30F4013                           |            |
| ADCHS Register131                                  | External Power-on Reset Circuit        |            |
| ADCON1 Register131                                 | I <sup>2</sup> C                       |            |
| ADCON2 Register131                                 | Input Capture Mode                     |            |
| ADCON3 Register131                                 | Oscillator System                      |            |
| ADCSSL Register131                                 | Output Compare Mode                    |            |
| ADPCFG Register131                                 | Reset System                           |            |
| Configuring Analog Port Pins54, 138                | Shared Port Structure                  |            |
| Connection Considerations                          | SPI                                    |            |
| Conversion Operation                               | SPI Master/Slave Connection            | 100        |
| Effects of a Reset137                              | UART Receiver                          | 104        |
| Operation During CPU Idle Mode137                  | UART Transmitter                       | 103        |
| Operation During CPU Sleep Mode137                 | BOR Characteristics                    | 180        |
| Output Formats                                     | BOR. See Brown-out Reset.              |            |
| Power-Down Modes                                   | Brown-out Reset                        |            |
| Programming the Sample Trigger133                  | Timing Requirements                    | 187        |
| Register Map139                                    | •                                      |            |
| Result Buffer                                      | С                                      |            |
| Sampling Requirements                              | C Compilers                            |            |
| Selecting the Conversion Sequence                  | MPLAB C18                              | 168        |
| AC Characteristics                                 | CAN Module                             | 111        |
| Load Conditions 181                                | Baud Rate Setting                      | 116        |
| AC Temperature and Voltage Specifications          | CAN1 Register Map                      | 118        |
|  | Frame Types                            | 111        |
| AC-Link Mode Operation                             | I/O Timing Requirements                |            |
| 16-Bit Mode  | Message Reception                      |            |
| 20-Bit Mode  | Message Transmission                   |            |
| ADC  | Modes of Operation                     |            |
| Selecting the Conversion Clock                     | Overview                               |            |
| ADC Conversion Speeds                              | CLKOUT and I/O Timing                  |            |
| Address Generator Units                            | Requirements                           | 185        |
| Alternate Vector Table                             | Code Examples                          |            |
| Analog-to-Digital Converter. See A/D.              | Data EEPROM Block Erase                | 50         |
| Assembler  | Data EEPROM Block Write                |            |
| MPASM Assembler                                    | Data EEPROM Read                       |            |
| Automatic Clock Stretch                            | Data EEPROM Word Erase                 |            |
| During 10-Bit Addressing (STREN = 1)94             | Data EEPROM Word Write                 |            |
| During 7-Bit Addressing (STREN = 1)94              | Erasing a Row of Program Memory        |            |
| Receive Mode94                                     | Initiating a Programming Sequence      |            |
| Transmit Mode94                                    | Loading Write Latches                  |            |
| В  | Port Write/Read                        |            |
|  | Code Protection                        |            |
| Band Gap Start-up Time                             | Control Registers                      |            |
| Requirements187                                    | NVMADR                                 |            |
| Barrel Shifter                                     | NVMADRU                                |            |
| Bit-Reversed Addressing40                          | NVMCON                                 |            |
| Example40  | NVMKEY                                 |            |
| Implementation40                                   |  | 44         |
| Modifier Values Table41                            | Core Architecture                      | 4.5        |
| Sequence Table (16-Entry)41                        | Overview                               |            |
| Block Diagrams                                     | CPU Architecture Overview              |            |
| 12-Bit A/D Functional131                           | Customer Change Notification Service   |            |
| 16-Bit Timer1 Module67                             | Customer Notification Service          |            |
| 16-Bit Timer273                                    | Customer Support                       | 225        |
| 16-Bit Timer373                                    | D                                      |            |
| 16-Bit Timer478                                    |  | <b>.</b> . |
| 16-Bit Timer578                                    | Data Accumulators and Adder/Subtracter | 21         |
| 32-Bit Timer2/372                                  | Data Accumulators and Adder/Subtractor |            |
| 32-Bit Timer4/577                                  | Data Space Write Saturation            |            |
|  | Overflow and Saturation                | 21         |

| Round Logic  | 22   | Synchronous Data Transfers  | 126   |
|--|--|---|---|
| Write-Back   |  | Timing Requirements   | 0   |
| Data Address Space   |  | AC-Link Mode  | 195   |
| Alignment  |  | Multichannel, I <sup>2</sup> S Modes  |   |
| Alignment (Figure)   |  | Transmit Slot Enable Bits   |   |
| Effect of Invalid Memory Accesses (Table)  |  | Transmit Status Bits  |   |
| MCU and DSP (MAC Class) Instructions Example   |  | Transmit/Receive Shift Register   |   |
| Memory Map   |  | Underflow Mode Control Bit  |   |
| Near Data Space  |  | Word-Size Selection Bits  |   |
| Software Stack   |  | Development Support   |   |
| Spaces   |  | Device Configuration  | 107   |
| Width  |  | Register Map  | 158   |
| Data Converter Interface (DCI) Module  |  | Device Configuration Registers  | 150   |
| , ,  |  | FBORPOR   | 156   |
| Data EEPROM Memory   |  | FGS   |   |
| · ·  |  | FOSC  |   |
| Erasing, Block   |  | FWDT  |   |
| Erasing, Word  |  |   |   |
| Protection Against Spurious Write  |  | Device Overview   |   |
| Reading  |  | Disabling the UART  |   |
| Write Verify   |  | Divide Support  |   |
| Writing  |  | Instructions (Table)  |   |
| Writing, Block   |  | DSP Engine  |   |
| Writing, Word  |  | Multiplier  |   |
| DC Characteristics   |  | Dual Output Compare Match Mode  |   |
| BOR  |  | Continuous Pulse Mode   |   |
| I/O Pin Input Specifications   |  | Single Pulse Mode   | 86  |
| I/O Pin Output Specifications  |  | E   |   |
| Idle Current (IIDLE)   | 175  |   |   |
| LVDL   | -  | Electrical Characteristics  |   |
| Operating Current (IDD)  | 174  | AC  |   |
| Power-Down Current (IPD)   |  | DC  | 172   |
| Program and EEPROM   | 180  | Enabling and Setting Up UART  |   |
| Temperature and Voltage Specifications   | 172  | Alternate I/O   | 105   |
| remperature and voltage opecifications   | 1 / 2  |   |   |
| DCI Module   | 172  | Enabling and Setting up UART  |   |
|  |  |   | 105   |
| DCI Module  Bit Clock Generator  | 125  | Enabling and Setting up UART  |   |
| DCI Module   | 125<br>127   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections  |   |
| DCI Module  Bit Clock Generator  Buffer Alignment with Data Frames  Buffer Control   | 125<br>127<br>121  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105   |
| DCI Module  Bit Clock Generator  Buffer Alignment with Data Frames  Buffer Control  Buffer Data Alignment                                  | 125<br>127<br>121<br>121   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations  | 105<br>133  |
| DCI Module  Bit Clock Generator  Buffer Alignment with Data Frames  Buffer Control   | 125<br>127<br>121<br>121<br>127  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105<br>133<br>107   |
| DCI Module  Bit Clock Generator  Buffer Alignment with Data Frames  Buffer Control  Buffer Data Alignment  Buffer Length Control  COFS Pin | 125<br>127<br>121<br>121<br>127<br>121   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105<br>133<br>107<br>125  |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105<br>133<br>107<br>125<br>123   |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105<br>133<br>107<br>125<br>123<br>96   |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105<br>133<br>107<br>125<br>123<br>96<br>117                                  |
| DCI Module Bit Clock Generator   | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105<br>133<br>107<br>125<br>123<br>96<br>117                                  |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128<br>121<br>126  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock Baud Rate Bit Clock Frequency COFSG Period Serial Clock Rate Time Quantum for Clock Generation Errata Exception Sequence              | 105<br>133<br>107<br>125<br>123<br>96<br>117                                  |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>128<br>121<br>126<br>quen-  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock Baud Rate Bit Clock Frequency COFSG Period Serial Clock Rate Time Quantum for Clock Generation Errata Exception Sequence Trap Sources | 105<br>133<br>107<br>125<br>123<br>96<br>117<br>9                             |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128<br>121<br>126<br>quen-<br>125  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105 133 107 125 123 96 117 9 62 182   |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128<br>121<br>126<br>quen-<br>125<br>128   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock   | 105 133 107 125 123 96 117 9 62 182 188                                       |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128<br>121<br>126<br>quen-<br>125<br>128<br>128  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock Baud Rate   | 105 133 107 125 123 96 117 9 62 182 188 189                                   |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128<br>121<br>126<br>quen-<br>125<br>128<br>123  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock Baud Rate   | 105 133 107 125 123 96 117 9 62 182 188 189 189                               |
| DCI Module  Bit Clock Generator  | 125<br>127<br>121<br>121<br>127<br>121<br>121<br>121<br>128<br>121<br>126<br>quen-<br>125<br>128<br>123<br>123   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock Baud Rate   | 105 133 107 125 123 96 117 9 62 182 188 189 189                               |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121126 quen125128123123123123   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART Equations ADC Conversion Clock Baud Rate   | 105 133 107 125 123 96 117 9 62 182 188 189 189                               |
| DCI Module  Bit Clock Generator  | 125127121121121121121121128121126 quen125128123123123121128  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections  Enabling the UART  Equations ADC Conversion Clock Baud Rate   | 105 133 107 125 123 96 117 9 62 182 188 189 189 64                            |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121126 quen125128123123123123121128121  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections  Enabling the UART Equations ADC Conversion Clock Baud Rate  | 105 133 107 125 123 96 117 9 62 188 189 189 64                                |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121126 quen125128123123123121128121128121123  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections  Enabling the UART  Equations ADC Conversion Clock Baud Rate   | 105 133 107 125 123 96 117 9 62 188 189 189 64                                |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121125128123123123123123123123123123123   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections  Enabling the UART Equations ADC Conversion Clock Baud Rate  | 105 133 107 125 123 96 117 9 62 188 189 189 64                                |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121126 quen125128123123123121128121128121128121128121128121128121128  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 9 62 188 189 189 64                                |
| DCI Module  Bit Clock Generator  | 125127121121121121121121128121125128123123123121128121128121128123123123123121128121128121128  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105<br>133<br>107<br>125<br>123<br>96<br>117<br>62<br>182<br>189<br>189<br>64 |
| Bit Clock Generator  | 125127121121121121121121128121128123123123123123123123123121128121128121128121128121128121128121   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105<br>133<br>107<br>125<br>123<br>96<br>117<br>62<br>182<br>189<br>189<br>64 |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121128123123123123123123123121128121128121128121128121128121123121123121123121123121123121123121  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 182 188 189 189 64 43                              |
| DCI Module Bit Clock Generator   | 125127121121121121121121128121126 quen125128123123123121128123121128121128121123121123121123121123   | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 62 182 188 189 189 64 43                           |
| Bit Clock Generator  | 125127121121121121121121128121126 quen125128123123123121128121128121128121128121128121128121128121123121128121128121128121128121123121123121123121123121123121123121123121123121123121123121123121 | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 9 62 188 189 189 64 43 55 178                      |
| Bit Clock Generator  | 125127121121121121121121128121126 quen125128123123123123121128121128121128121128121128121128121128121128121128121128121128121  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 9 62 188 189 189 64 43 55                          |
| Bit Clock Generator  | 125127121121121121121121128121126 quen125128123123123123121128121128121128121128121128121128121128121128121128121128121128121  | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 9 62 188 189 189 189 43 53 178 55                  |
| Bit Clock Generator  | 125127121121121121121121121128121126 quen125128123123123123121128129129121 | Enabling and Setting up UART Setting up Data, Parity and Stop Bit Selections Enabling the UART  | 105 133 107 125 123 96 117 9 62 188 189 189 64 43 55 178 178 53 93            |

| Transmission                                    | 93       | LVDL Characteristics                               | . 179 |
|---|----------|--|-------|
| I <sup>2</sup> C 7-Bit Slave Mode Operation     | 93       | 3.4  |       |
| Reception                                       | 93       | M  |       |
| Transmission                                    | 93       | Memory Organization                                | 25    |
| I <sup>2</sup> C Master Mode Operation          | 95       | Core Register Map                                  |       |
| Baud Rate Generator                             | 96       | Microchip Internet Web Site                        | . 225 |
| Clock Arbitration                               | 96       | Modes of Operation                                 |       |
| Multi-Master Communication,                     |          | Disable  | . 113 |
| Bus Collision and Bus Arbitration               | 96       | Initialization                                     | . 113 |
| Reception                                       | 96       | Listen All Messages                                | . 113 |
| Transmission                                    | 95       | Listen Only  | . 113 |
| I <sup>2</sup> C Master Mode Support            |          | Loopback   | . 113 |
| I <sup>2</sup> C Module                         |          | Normal Operation                                   |       |
| Addresses                                       |          | Modulo Addressing                                  |       |
| Bus Data Timing Requirements                    |          | Applicability                                      |       |
| Master Mode                                     | 201      | Incrementing Buffer Operation Example              |       |
| Slave Mode                                      |          | Start and End Address                              |       |
| General Call Address Support                    |          | W Address Register Selection                       |       |
| Interrupts                                      |          | MPLAB ASM30 Assembler, Linker, Librarian           |       |
| IPMI Support                                    |          | MPLAB Integrated Development Environment Software. |       |
| Operating Function Description                  |          | MPLAB PM3 Device Programmer                        |       |
| Operation During CPU Sleep and Idle Mode        |          | MPLAB REAL ICE In-Circuit Emulator System          |       |
|   |          | MPLINK Object Linker/MPLIB Object Librarian        |       |
| Pin Configuration                               |          | WILLIAM Object Ellikei/WILLIB Object Elbraham      | . 100 |
| Programmer's Model                              |          | N  |       |
| Register Map                                    |          | NVM  |       |
| Registers                                       |          | Register Map                                       | 47    |
| Slope Control                                   |          | Negister Map                                       | 41    |
| Software Controlled Clock Stretching (STRI      | ,        | 0  |       |
| Various Modes                                   |          | Operating Current (IDD)                            | 174   |
| I <sup>2</sup> S Mode Operation                 |          | Operating Frequency vs Voltage                     | . 177 |
| Data Justification                              |          | dsPIC30FXXXX-20 (Extended)                         | 172   |
| Frame and Data Word Length Selection            |          | Oscillator   | . 112 |
| Idle Current (IIDLE)                            |          | Configurations                                     | 111   |
| In-Circuit Serial Programming (ICSP)            |          | Fail-Safe Clock Monitor                            |       |
| Input Capture Module                            |          |  |       |
| Interrupts                                      |          | Fast RC (FRC)                                      |       |
| Register Map                                    |          | Initial Clock Source Selection                     |       |
| Input Capture Operation During Sleep and Idle N | 1odes 82 | Low-Power RC (LPRC)                                |       |
| CPU Idle Mode                                   | 82       | LP Oscillator Control                              |       |
| CPU Sleep Mode                                  | 82       | Phase Locked Loop (PLL)                            |       |
| Input Capture Timing Requirements               | 190      | Start-up Timer (OST)                               |       |
| Input Change Notification Module                | 56       | Control Registers                                  |       |
| Register Map                                    | 57       | Operating Modes (Table)                            |       |
| Instruction Addressing Modes                    | 37       | System Overview                                    |       |
| File Register Instructions                      |          | Oscillator Selection                               | . 141 |
| Fundamental Modes Supported                     |          | Oscillator Start-up Timer                          |       |
| MAC Instructions                                |          | Timing Requirements                                | . 187 |
| MCU Instructions                                | 37       | Output Compare Interrupts                          | 88    |
| Move and Accumulator Instructions               | 38       | Output Compare Module                              |       |
| Other Instructions                              |          | Register Map dsPIC30F3014                          | 89    |
| Instruction Set                                 |          | Register Map dsPIC30F4013                          | 89    |
| Overview  | 162      | Timing Requirements                                |       |
| Summary   |          | Output Compare Operation During CPU Idle Mode      |       |
| Internal Clock Timing Examples                  |          | Output Compare Sleep Mode Operation                | 88    |
| Internet Address                                |          |  |       |
| Interrupt Controller                            | 225      | Р  |       |
| ·   | 66       | Packaging Information                              | . 211 |
| Register Map                                    |          | Marking  | . 211 |
| Interrupt Priority                              |          | Peripheral Module Disable (PMD) Registers          |       |
| Traps   |          | Pinout Descriptions                                |       |
| Interrupt Sequence                              |          | POR. See Power-on Reset.                           |       |
| Interrupt Stack Frame                           |          | Power Saving Modes                                 |       |
| Interrupts                                      | 59       | Sleep and Idle                                     | . 141 |
| L   |          | Power-Down Current (IPD)                           |       |
| Load Conditions                                 | 101      | Power-Saving Modes                                 |       |
| Low-Voltage Detect (LVD)                        |          | ldle   |       |
| voltage Detect (LVD)                            |          |  |       |

| Sleep  | 155 | Simple Output Compare Match Mode                          | 86  |
|--|-----|---|-----|
| Power-up Timer                                 |     | Simple PWM Mode   | 86  |
| Timing Requirements                            | 187 | Input Pin Fault Protection                                | 8   |
| Program Address Space                          |     | Period  |     |
| Construction                                   | 26  | Software Simulator (MPLAB SIM)                            | 169 |
| Data Access from Program Memory                |     | Software Stack Pointer, Frame Pointer                     | 16  |
| Using Program Space Visibility                 | 28  | CALL Stack Frame  |     |
| Data Access From Program Memory                |     | SPI Module  | 99  |
| Using Table Instructions                       | 27  | Framed SPI Support  | 100 |
| Data Access from, Address Generation           |     | Operating Function Description                            | 99  |
| Data Space Window into Operation               |     | Operation During CPU Idle Mode                            |     |
| Data Table Access (Isw)                        | 27  | Operation During CPU Sleep Mode                           |     |
| Data Table Access (MSB)                        |     | SDOx Disable  |     |
| dsPIC30F3014 Memory Map                        |     | Slave Select Synchronization                              |     |
| dsPIC30F4013 Memory Map                        |     | SPI1 Register Map   |     |
| Table Instructions                             | 20  | Timing Requirements                                       |     |
| TBLRDH   | 27  | Master Mode (CKE = 0)                                     | 196 |
| TBLRDL   |     | Master Mode (CKE = 1)                                     |     |
| TBLWTH   |     | Slave Mode (CKE = 0)                                      |     |
| TBLWTL   |     | Slave Mode (CKE = 1)                                      |     |
| Program and EEPROM Characteristics             |     | Word and Byte Communication                               |     |
| •  |     | Status Bits, Their Significance and the Initialization Co |     |
| Program Counter                                |     | for RCON Register, Case 1                                 |     |
| •  |     | g .   |     |
| Programmer's Model                             |     | Status Bits, Their Significance and the Initialization Co |     |
| Diagram  |     | for RCON Register, Case 2                                 |     |
| Programming Operations                         |     | STATUS Register   |     |
| Algorithm for Program Flash                    |     | Symbols Used in Opcode Descriptions                       |     |
| Erasing a Row of Program Memory                |     | System Integration  |     |
| Initiating the Programming Sequence            |     | Register Map  | 158 |
| Loading Write Latches                          |     | Т   |     |
| Protection Against Accidental Writes to OSCCON | 146 | •   |     |
| R  |     | Table Instruction Operation Summary                       | 43  |
|  |     | Temperature and Voltage Specifications                    |     |
| Reader Response                                | 226 | AC  |     |
| Registers                                      |     | DC  |     |
| OSCCON (Oscillator Control)                    |     | Timer1 Module   |     |
| OSCTUN (Oscillator Tuning)                     |     | 16-Bit Asynchronous Counter Mode                          |     |
| Reset1   |     | 16-Bit Synchronous Counter Mode                           |     |
| BOR, Programmable                              |     | 16-Bit Timer Mode   |     |
| Brown-out Reset (BOR)                          |     | Gate Operation  |     |
| Oscillator Start-up Timer (OST)                | 141 | Interrupt   | 68  |
| POR  |     | Operation During Sleep Mode                               | 68  |
| Operating without FSCM and PWRT                | 153 | Prescaler   | 68  |
| With Long Crystal Start-up Time                | 153 | Real-Time Clock   | 68  |
| POR (Power-on Reset)                           | 151 | Interrupts  | 68  |
| Power-on Reset (POR)                           | 141 | Oscillator Operation                                      | 68  |
| Power-up Timer (PWRT)                          |     | Register Map  |     |
| Reset Sequence                                 |     | Timer2 and Timer3 Selection Mode                          |     |
| Reset Sources                                  |     | Timer2/3 Module   |     |
| Reset Sources                                  |     | 16-Bit Timer Mode   |     |
| Brown-out Reset (BOR)                          | 61  | 32-Bit Synchronous Counter Mode                           |     |
| Illegal Instruction Trap                       |     | 32-Bit Timer Mode   |     |
| Trap Lockout                                   |     | ADC Event Trigger   |     |
| Uninitialized W Register Trap                  |     | Gate Operation  |     |
| Watchdog Time-out                              |     | Interrupt   |     |
|  |     | Operation During Sleep Mode                               |     |
| Reset Timing Requirements                      |     |   |     |
| Revision History                               |     | Register Map  |     |
| Run-Time Self-Programming (RTSP)               | 43  | Timer Prescaler   |     |
| S  |     | Timer4/5 Module   |     |
|  | 04  | Register Map  | 79  |
| Simple Capture Event Mode                      |     | Timing Diagrams   |     |
| Buffer Operation                               |     | A/D Conversion  |     |
| Hall Sensor Mode                               |     | Low-Speed (ASAM = 0, SSRC = 000)                          |     |
| Prescaler                                      |     | Band Gap Start-up Time                                    | 187 |
| Timer2 and Timer3 Selection Mode               |     | Brown-out Reset Characteristics                           |     |
| Simple OCx/PWM Mode Timing Requirements        | 191 | CAN Bit   | 116 |

| CAN Module I/O                                    | 205                      |
|---|--------------------------|
| CLKOUT and I/O                                    | 185                      |
| DCI Module  |                          |
| AC-Link Mode                                      | 194                      |
| Multichannel, I <sup>2</sup> S Modes              |                          |
| External Clock                                    |                          |
| Frame Sync, AC-Link Start-Of-Frame                |                          |
| Frame Sync, Multichannel Mode                     |                          |
| I <sup>2</sup> C Bus Data                         | 124                      |
|   | 004                      |
| Master Mode                                       |                          |
| Slave Mode  | 203                      |
| I <sup>2</sup> C Bus Start/Stop Bits              |                          |
| Master Mode                                       |                          |
| Slave Mode  | 203                      |
| I <sup>2</sup> S Interface Frame Sync             | 124                      |
| Input Capture (CAPx)                              | 190                      |
| Low-Voltage Detect                                |                          |
| OCx/PWM Module                                    |                          |
| Oscillator Start-up Timer                         |                          |
| Output Compare Module                             |                          |
| Power-up Timer                                    |                          |
| PWM Output  |                          |
| •   |                          |
| Reset   | 100                      |
| SPI Module  | 405                      |
| Master Mode (CKE = 0)                             | 195                      |
| Master Mode (CKE = 1)                             |                          |
| Slave Mode (CKE = 0)                              |                          |
| Slave Mode (CKE = 1)                              | 199                      |
| Time-out Sequence on Power-up                     |                          |
| (MCLR Not Tied to VDD), Case 1                    | 152                      |
| Time-out Sequence on Power-up                     |                          |
| (MCLR Not Tied to VDD), Case 2                    | 152                      |
| Time-out Sequence on Power-up                     |                          |
| (MCLR Tied to VDD)                                | 152                      |
| Type A, B and C Timer External Clock              |                          |
| Watchdog Timer                                    |                          |
| Timing Diagrams and Specifications                | 100                      |
| DC Characteristics - Internal RC Accuracy         | 183                      |
| Timing Diagrams.See Timing Characteristics        | 100                      |
|   |                          |
| Timing Requirements  A/D Conversion               |                          |
|   | 000                      |
| Low-Speed   | 209                      |
| Band Gap Start-up Time                            |                          |
| Brown-out Reset                                   |                          |
| CAN Module I/O                                    |                          |
| CLKOUT and I/O                                    | 185                      |
| DCI Module  |                          |
| AC-Link Mode                                      |                          |
| Multichannel, I <sup>2</sup> S Modes              |                          |
| External Clock                                    |                          |
| I <sup>2</sup> C Bus Data (Master Mode)           | 201                      |
| I <sup>2</sup> C Bus Data (Slave Mode)            |                          |
| Input Capture                                     |                          |
| Oscillator Start-up Timer                         |                          |
| Output Compare Module                             |                          |
| Power-up Timer                                    |                          |
| Reset   |                          |
| Simple OCx/PWM Mode                               |                          |
| SPI Module  | 131                      |
|   | 100                      |
| Master Mode (CKE = 0)                             | 190                      |
| Master Mode (CKE = 1)                             | 107                      |
| 213/10 MODE II.K F = (1)                          | 197                      |
|   | 197<br>198               |
| Slave Mode (CKE = 1)                              | 197<br>198<br>200        |
| Slave Mode (CKE = 1)  Type A Timer External Clock | 197<br>198<br>200<br>188 |
| Slave Mode (CKE = 1)                              | 197<br>198<br>200<br>188 |

| Type C Timer External Clock                   | ) |  |  |  |
|---|---|--|--|--|
| Watchdog Timer 187                            | 7 |  |  |  |
| Trap Vectors                                  | 3 |  |  |  |
| U   |   |  |  |  |
|   |   |  |  |  |
| UART Module                                   |   |  |  |  |
| Address Detect Mode                           |   |  |  |  |
| Auto-Baud Support108                          |   |  |  |  |
| Baud Rate Generator                           |   |  |  |  |
| Enabling and Setting Up                       |   |  |  |  |
| Framing Error (FERR)                          |   |  |  |  |
| Idle Status107                                |   |  |  |  |
| Loopback Mode                                 |   |  |  |  |
| Operation During CPU Sleep and Idle Modes 108 |   |  |  |  |
| Overview103                                   |   |  |  |  |
| Parity Error (PERR)                           |   |  |  |  |
| Receive Break 107                             |   |  |  |  |
| Receive Buffer (UxRXB)106                     |   |  |  |  |
| Receive Buffer Overrun Error (OERR Bit) 106   |   |  |  |  |
| Receive Interrupt                             |   |  |  |  |
| Receiving Data106                             |   |  |  |  |
| Receiving in 8-Bit or 9-Bit Data Mode 106     |   |  |  |  |
| Reception Error Handling106                   |   |  |  |  |
| Transmit Break 106                            |   |  |  |  |
| Transmit Buffer (UxTXB)105                    |   |  |  |  |
| Transmit Interrupt106                         |   |  |  |  |
| Transmitting Data105                          |   |  |  |  |
| Transmitting in 8-Bit Data Mode               |   |  |  |  |
| Transmitting in 9-Bit Data Mode105            |   |  |  |  |
| UART1 Register Map109                         |   |  |  |  |
| UART2 Register Map109                         | ) |  |  |  |
| UART Operation                                |   |  |  |  |
| Idle Mode108                                  |   |  |  |  |
| Sleep Mode108                                 | 3 |  |  |  |
| Unit ID Locations                             | ı |  |  |  |
| Universal Asynchronous Receiver Transmitter   |   |  |  |  |
| (UART) Module103                              | 3 |  |  |  |
| W   |   |  |  |  |
| Wake-up from Sleep                            | 1 |  |  |  |
| Wake-up from Sleep and Idle 64                |   |  |  |  |
| Watchdog Timer                                | + |  |  |  |
| Timing Requirements                           | 7 |  |  |  |
| Watchdog Timer (WDT)                          |   |  |  |  |
| Enabling and Disabling                        |   |  |  |  |
| Operation                                     |   |  |  |  |
| WWW Address                                   |   |  |  |  |
| WWW, On-Line Support                          |   |  |  |  |
| vvvvv, On-Line Support                        | , |  |  |  |

NOTES:

#### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com. Under "Support", click on "Customer Change Notification" and follow the registration instructions.

#### CUSTOMER SUPPORT

Users of Microchip products can receive assistance through several channels:

- · Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- · Technical Support
- · Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://support.microchip.com

### **READER RESPONSE**


It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

| TO:<br>RE: | 9  | Total Pages Sent              |
|------------|--|-------------------------------|
| Fror       | m: Name  |                               |
|            | Company  |                               |
|            | Address  |                               |
|            | City / State / ZIP / Country   |                               |
|            | Telephone: ()  | FAX: ()                       |
| App        | lication (optional):   |                               |
| Wou        | uld you like a reply?YN  |                               |
| Dev        | rice: dsPIC30F3014/4013  | Literature Number: DS70138G   |
| Que        | estions:   |                               |
| 1.         | What are the best features of this document?   |                               |
| 2.         | How does this document meet your hardware an   | d software development needs? |
| 3.         | Do you find the organization of this document ea   | sy to follow? If not, why?    |
| 4.         | What additions to the document do you think would enhance the structure and subject?     |                               |
|            |  |                               |
| 5.         | What deletions from the document could be made without affecting the overall usefulness? |                               |
|            |  |                               |
| 6.         | Is there any incorrect or misleading information (                                       | what and where)?              |
| 7.         | How would you improve this document?   |                               |
|            |  |                               |
|            |  |                               |

#### PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.





### Worldwide Sales and Service

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support:

http://support.microchip.com

Web Address: www.microchip.com

Atlanta

Duluth, GA Tel: 678-957-9614 Fax: 678-957-1455

**Boston** 

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

Cleveland

Independence, OH Tel: 216-447-0464 Fax: 216-447-0643

**Dallas** 

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit

Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Kokomo

Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Santa Clara

Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

Toronto

Mississauga, Ontario, Canada

Tel: 905-673-0699 Fax: 905-673-6509 ASIA/PACIFIC

**Asia Pacific Office** 

Suites 3707-14, 37th Floor Tower 6, The Gateway Harbour City, Kowloon Hong Kong

Tel: 852-2401-1200 Fax: 852-2401-3431

Australia - Sydney

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

China - Beijing

Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

China - Chengdu

Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

China - Chongging

Tel: 86-23-8980-9588 Fax: 86-23-8980-9500

China - Hong Kong SAR

Tel: 852-2401-1200 Fax: 852-2401-3431

China - Nanjing

Tel: 86-25-8473-2460 Fax: 86-25-8473-2470

China - Qingdao

Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

China - Shanghai

Tel: 86-21-5407-5533 Fax: 86-21-5407-5066

China - Shenyang

Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

China - Shenzhen

Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

China - Wuhan

Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

China - Xian

Tel: 86-29-8833-7252 Fax: 86-29-8833-7256

China - Xiamen

Tel: 86-592-2388138 Fax: 86-592-2388130

China - Zhuhai

Tel: 86-756-3210040 Fax: 86-756-3210049 ASIA/PACIFIC

India - Bangalore Tel: 91-80-3090-4444 Fax: 91-80-3090-4123

India - New Delhi

Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune

Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

Japan - Yokohama

Tel: 81-45-471- 6166 Fax: 81-45-471-6122

Korea - Daegu

Tel: 82-53-744-4301 Fax: 82-53-744-4302

Korea - Seoul

Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Malaysia - Kuala Lumpur

Tel: 60-3-6201-9857 Fax: 60-3-6201-9859

Malaysia - Penang

Tel: 60-4-227-8870 Fax: 60-4-227-4068

Philippines - Manila

Tel: 63-2-634-9065 Fax: 63-2-634-9069

Singapore

Tel: 65-6334-8870 Fax: 65-6334-8850

Taiwan - Hsin Chu

Tel: 886-3-6578-300 Fax: 886-3-6578-370

Taiwan - Kaohsiung

Tel: 886-7-213-7830 Fax: 886-7-330-9305

Taiwan - Taipei

Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

Thailand - Bangkok

Tel: 66-2-694-1351 Fax: 66-2-694-1350 **EUROPE** 

Austria - Wels

Tel: 43-7242-2244-39 Fax: 43-7242-2244-393

Denmark - Copenhagen

Tel: 45-4450-2828 Fax: 45-4485-2829

France - Paris

Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

Germany - Munich

Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy - Milan

Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen Tel: 31-416-690399

Fax: 31-416-690340

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**UK - Wokingham** Tel: 44-118-921-5869 Fax: 44-118-921-5820

08/04/10