Document Number: MC33887

Rev. 13.0, 10/2008

# 5.0 A H-Bridge with Load **Current Feedback**

The 33887 is a monolithic H-Bridge Power IC with a load current feedback feature making it ideal for closed-loop DC motor control. The IC incorporates internal control logic, charge pump, gate drive, and low R<sub>DS(ON)</sub> MOSFET output circuitry. The 33887 is able to control inductive loads with continuous DC load currents up to 5.0 A, and with peak current active limiting between 5.2 A and 7.8 A. Output loads can be pulse width modulated (PWM-ed) at frequencies up to 10 kHz. The load current feedback feature provides a proportional (1/ 375th of the load current) constant-current output suitable for monitoring by a microcontroller's A/D input. This feature facilitates the design of closed-loop torque/speed control as well as open load detection.

A Fault Status output pin reports undervoltage, short circuit, and overtemperature conditions. Two independent inputs provide polarity control of two half-bridge totem-pole outputs. Two disable inputs force the H-Bridge outputs to tri-state (exhibit high impedance).


The 33887 is parametrically specified over a temperature range of  $-40^{\circ}C \le T_A \le 125^{\circ}C$  and a voltage range of 5.0 V  $\le$  V+  $\le 28$  V. Operation with voltages up to 40 V with derating of the specifications.

#### **Features**

- Fully specified operation 5.0 V to 28 V
- Limited operation with reduced performance up to 40 V
- 120 m $\Omega$  R<sub>DS(ON)</sub> Typical H-Bridge MOSFETs
- · TTL/CMOS Compatible Inputs
- · PWM Frequencies up to 10 kHz
- Active Current Limiting (Regulation)
- · Fault Status Reporting
- Sleep Mode with Current Draw ≤50 μA (Inputs Floating or Set to Match Default Logic States)
- Pb-Free Packaging Designated by Suffix Codes VW and EK

## 33887

### H-BRIDGE



ORDERING INFORMATION						
Device	Package					
MC33887DH/R2						
MC33887VW/R2		20 HSOP				
MC33887AVW/R2	-40°C to 125°C					
MC33887PNB/R2	-40°C to 125°C	36 PQFN				
MC33887DWB/R2		54 SOICW-EP				
MCZ33887EK/R2		54 SOICW-EP				




Figure 1. 33887 Simplified Application Diagram



## **INTERNAL BLOCK DIAGRAM**




Figure 2. 33887 Simplified Internal Block Diagram

## **PIN CONNECTIONS**




Figure 3. 33887 Pin Connections

#### Table 1. 33887 HSOP PIN DEFINITIONS

Pin	Pin Name	Formal Name	Definition
1	AGND	Analog Ground	Low-current analog signal ground.
2	FS	Fault Status for H-Bridge	Open drain active LOW Fault Status output requiring a pull-up resistor to 5.0 V.
3	IN1	Logic Input Control 1	Logic input control of OUT1 (i.e., IN1 logic HIGH = OUT1 HIGH).
4, 5, 16	V+	Positive Power Supply	Positive supply connections
6, 7	OUT1	H-Bridge Output 1	Output 1 of H-Bridge.
8	FB	Feedback for H-Bridge	Current sensing feedback output providing ground referenced 1/375th (0.00266) of H-Bridge high-side current.
9–12	PGND	Power Ground	High-current power ground.
13	D2	Disable 2	Active LOW input used to simultaneously tri-state disable both H-Bridge outputs. When $\overline{D2}$ is Logic LOW, both outputs are tri-stated.
14, 15	OUT2	H-Bridge Output 2	Output 2 of H-Bridge.
17	ССР	Charge Pump Capacitor	External reservoir capacitor connection for internal charge pump capacitor.
18	D1	Disable 1	Active HIGH input used to simultaneously tri-state disable both H-Bridge outputs. When D1 is Logic HIGH, both outputs are tri-stated.
19	IN2	Logic Input Control 2	Logic input control of OUT2 (i.e., IN2 logic HIGH = OUT2 HIGH).
20	EN	Enable	Logic input Enable control of device (i.e., EN logic HIGH = full operation, EN logic LOW = Sleep Mode).
Tab/Pad	Thermal Interface	Exposed Pad Thermal Interface	Exposed pad thermal interface for sinking heat from the device.  Note Must be DC-coupled to analog ground and power ground via very low impedance path to prevent injection of spurious signals into IC substrate.

#### **Transparent Top View of Package** 36 33 33 33 33 30 29 NC 28 NC D1 27 D2 IN2 26 PGND 25 PGND ΕN 24 PGND V+ 23 PGND V+ NC 22 PGND AGND 21 PGND FS 20 FB NC 10 19 NC 7 7 OUT1 OUT1 OUT1

Figure 4. 33887 Pin Connections

**Table 2. PQFN PIN DEFINITIONS** 

Pin	Pin Name	Formal Name	Definition
1, 7, 10, 16, 19, 28, 31	NC	No Connect	No internal connection to this pin.
2	D1	Disable 1	Active HIGH input used to simultaneously tri-state disable both H-Bridge outputs. When D1 is Logic HIGH, both outputs are tri-stated.
3	IN2	Logic Input Control 2	Logic input control of OUT2 (i.e., IN2 logic HIGH = OUT2 HIGH).
4	EN	Enable	Logic input Enable control of device (i.e., EN logic HIGH = full operation, EN logic LOW = Sleep Mode).
5, 6, 12, 13, 34, 35	V+	Positive Power Supply	Positive supply connections.
8	AGND	Analog Ground	Low-current analog signal ground.
9	FS	Fault Status for H-Bridge	Open drain active LOW Fault Status output requiring a pull-up resistor to 5.0 V.
11	IN1	Logic Input Control 1	Logic input control of OUT1 (i.e., IN1 logic HIGH = OUT1 HIGH).
14, 15, 17, 18	OUT1	H-Bridge Output 1	Output 1 of H-Bridge.
20	FB	Feedback for H-Bridge	Current feedback output providing ground referenced 1/375th ratio of H-Bridge high-side current.
21–26	PGND	Power Ground	High-current power ground.
27	D2	Disable 2	Active LOW input used to simultaneously tri-state disable both H-Bridge outputs. When $\overline{\text{D2}}$ is Logic LOW, both outputs are tri-stated.
29, 30, 32, 33	OUT2	H-Bridge Output 2	Output 2 of H-Bridge.
36	CCP	Charge Pump Capacitor	External reservoir capacitor connection for internal charge pump capacitor.
Pad	Thermal Interface	Exposed Pad Thermal Interface	Exposed pad thermal interface for sinking heat from the device.  Note: Must be DC-coupled to analog ground and power ground via very low impedance path to prevent injection of spurious signals into IC substrate.

## **Transparent Top View of Package**




Figure 5. 33887 Pin Connections

## Table 3. SOICW-EP PIN DEFINITIONS

Pin	Pin Name	Formal Name	Definition
1–4, 51–54	PGND	Power Ground	High-current power ground.
5-7, 9, 14, 19-22, 27-29, 33-36, 41, 46, 48-50	NC	No Connect	No internal connection to this pin.
8	D2	Disable 2	Active LOW input used to simultaneously tri-state disable both H-Bridge outputs. When $\overline{\text{D2}}$ is Logic LOW, both outputs are tri-stated.
10–13	OUT2	H-Bridge Output 2	Output 2 of H-Bridge.
15-18, 37-40	V+	Positive Power Supply	Positive supply connections.
23	CCP	Charge Pump Capacitor	External reservoir capacitor connection for internal charge pump capacitor.
24	D1	Disable 1	Active HIGH input used to simultaneously tri-state disable both H-Bridge outputs. When D1 is Logic HIGH, both outputs are tri-stated.
25	IN2	Logic Input Control 2	Logic input control of OUT2 (i.e., IN2 logic HIGH = OUT2 HIGH).
26	EN	Enable	Logic input Enable control of device (i.e., EN logic HIGH = full operation, EN logic LOW = Sleep Mode).
30	AGND	Analog Ground	Low-current analog signal ground.
31	FS	Fault Status for H-Bridge	Open drain active LOW Fault Status output requiring a pull-up resistor to 5.0 V.
32	IN1	Logic Input Control 1	Logic input control of OUT1 (i.e., IN1 logic HIGH = OUT1 HIGH).

## Table 3. SOICW-EP PIN DEFINITIONS

Pin	Pin Name	Formal Name	Definition
42–45	OUT1	H-Bridge Output 1	Output 1 of H-Bridge.
47	FB	Feedback for H-Bridge	Current feedback output providing ground referenced 1/375th ratio of H-Bridge high-side current.
Pad	Thermal Interface	Exposed Pad Thermal Interface	Exposed pad thermal interface for sinking heat from the device.  Note Must be DC-coupled to analog ground and power ground via very low impedance path to prevent injection of spurious signals into IC substrate.

## **ELECTRICAL CHARACTERISTICS**

#### **MAXIMUM RATINGS**

#### **MAXIMUM RATINGS**

All voltages are with respect to ground unless otherwise noted.

Rating	Symbol	Value	Unit
ELECTRICAL RATINGS	·		
Supply Voltage (1)	V+	-0.3 to 40	V
Input Voltage (2)	V <sub>IN</sub>	-0.3 to 7.0	V
FS Status Output (3)	V <sub>FS</sub>	-0.3 to 7.0	V
Continuous Current (4)	I <sub>OUT</sub>	5.0	А
DH Suffix HSOP ESD Voltage (5)			V
Human Body Model			
Each Pin to AGND	V <sub>ESD1</sub>	±1000	
Each Pin to PGND	V <sub>ESD1</sub>	±1500	
Each Pin to V+	V <sub>ESD1</sub>	±2000	
Each I/O to All Other I/Os	V <sub>ESD1</sub>	±2000	
Machine Model	V <sub>ESD2</sub>	±200	
VW Suffix HSOP, SOICW-EP, and PQFN ESD Voltage (5)			V
Human Body Model	V <sub>ESD1</sub>	±2000	
Machine Model	V <sub>ESD2</sub>	±200	
THERMAL RATINGS	1		<b>I</b>
Storage Temperature	T <sub>STG</sub>	-65 to 150	°C
Operating Temperature <sup>(6)</sup>			°C
Ambient	T <sub>A</sub>	-40 to 125	
Junction	T <sub>J</sub>	-40 to 150	
Peak Package Reflow Temperature During Reflow (7), (8)	T <sub>PPRT</sub>	Note 8.	°C

- 1 Performance at voltages greater than 28V is degraded. See Electrical Performance Curves on page 18 and 19 for typical performance. Extended operation at higher voltages has not been fully characterized and may reduce the operational lifetime.
- 2 Exceeding the input voltage on IN1, IN2, EN, D1, or  $\overline{D2}$  may cause a malfunction or permanent damage to the device.
- 3 Exceeding the pull-up resistor voltage on the open Drain FS pin may cause permanent damage to the device.
- 4 Continuous current capability so long as junction temperature is  $\leq 150$  °C.
- 5 ESD1 testing is performed in accordance with the Human Body Model ( $C_{ZAP}$  = 100 pF,  $R_{ZAP}$  = 1500  $\Omega$ ), ESD2 testing is performed in accordance with the Machine Model ( $C_{ZAP}$  = 200 pF,  $R_{ZAP}$  = 0  $\Omega$ ).
- The limiting factor is junction temperature, taking into account the power dissipation, thermal resistance, and heat sinking provided. Brief nonrepetitive excursions of junction temperature above 150°C can be tolerated as long as duration does not exceed 30 seconds maximum. (nonrepetitive events are defined as not occurring more than once in 24 hours.)
- 7 Pin soldering temperature limit is for 10 seconds maximum duration. Not designed for immersion soldering. Exceeding these limits may cause malfunction or permanent damage to the device.
- Freescale's Package Reflow capability meets Pb-free requirements for JEDEC standard J-STD-020C. For Peak Package Reflow Temperature and Moisture Sensitivity Levels (MSL), Go to www.freescale.com, search by part number [e.g. remove prefixes/suffixes and enter the core ID to view all orderable parts. (i.e. MC33xxxD enter 33xxx), and review parametrics.

## **MAXIMUM RATINGS (continued)**

All voltages are with respect to ground unless otherwise noted.

Rating	Symbol	Value	Unit
THERMAL RESISTANCE (AND PACKAGE DISSIPATION) RATINGS	(9) (10) (11) (12)		
Junction-to-Board (Bottom Exposed Pad Soldered to Board)	$R_{ heta JB}$		°C/W
HSOP (6.0 W)		~7.0	
PQFN (4.0 W)		~8.0	
SOICW-EP (2.0 W)		~9.0	
Junction-to-Ambient, Natural Convection, Single-Layer Board (1s) (13)	$R_{ hetaJA}$		°C/W
HSOP (6.0 W)			
PQFN (4.0 W)		~41	
SOICW-EP (2.0 W)		~50	
		~62	
Junction-to-Ambient, Natural Convection, Four-Layer Board (2s2p) (14)	R <sub>θJMA</sub>		°C/W
HSOP (6.0 W)		~18	
PQFN (4.0 W)		~21	
SOICW-EP (2.0 W)		~23	
Junction-to-Case (Exposed Pad) (15)	$R_{ heta JC}$		°C/W
HSOP (6.0 W)		~0.8	
PQFN (4.0 W)	i	~1.2	
SOICW-EP (2.0 W)		~2.0	

- 9 The limiting factor is junction temperature, taking into account the power dissipation, thermal resistance, and heat sinking.
- 10 Exposed heatsink pad plus the power and ground pins comprise the main heat conduction paths. The actual R<sub>θJB</sub> (junction-to-PC board) values will vary depending on solder thickness and composition and copper trace thickness. Maximum current at maximum die temperature represents ~16 W of conduction loss heating in the diagonal pair of output MOSFETs. Therefore, the R<sub>θJC</sub>-total must be less than 5.0 °C/W for maximum load at 70°C ambient. Module thermal design must be planned accordingly.
- 11 Thermal resistance between the die and the printed circuit board per JEDEC JESD51-8. Board temperature is measured on the top surface of the board near the package.
- 12 Junction temperature is a function of on-chip power dissipation, package thermal resistance, mounting site (board) temperature, ambient temperature, air flow, power dissipation of other components on the board, and board thermal resistance.
- 13 Per SEMI G38-87 and JEDEC JESD51-2 with the single-layer board (JESD51-3) horizontal.
- 14 Per JEDEC JESD51-6 with the board horizontal.
- 15 Indicates the maximum thermal resistance between the die and the exposed pad surface as measured by the cold plate method (MIL SPEC-883 Method 1012.1) with the cold plate temperature used for the case temperature.

## STATIC ELECTRICAL CHARACTERISTICS

## Table 4. STATIC ELECTRICAL CHARACTERISTICS

Characteristics noted under conditions 5.0 V  $\leq$  V+  $\leq$  28 V and -40°C  $\leq$  T<sub>A</sub>  $\leq$  125°C unless otherwise noted. Typical values noted reflect the approximate parameter mean at T<sub>A</sub> = 25°C under nominal conditions unless otherwise noted.

Characteristic	Symbol	Min	Тур	Max	Unit
POWER SUPPLY	<u>.</u>				•
Operating Voltage Range (16)	V+	5.0	_	28	V
Sleep State Supply Current (17)  I <sub>OUT</sub> = 0 A, V <sub>EN</sub> = 0 V	I <sub>Q</sub> (SLEEP)	_	25	50	μА
Standby Supply Current I <sub>OUT</sub> = 0 A, V <sub>EN</sub> = 5.0 V	I <sub>Q(STANDBY)</sub>	_	_	20	mA
Threshold Supply Voltage Switch-OFF Switch-ON Hysteresis	V+ <sub>(THRES-OFF)</sub> V+ <sub>(THRES-ON)</sub> V+ <sub>(HYS)</sub>	4.15 4.5 150	4.4 4.75 –	4.65 5.0 –	V V mV
CHARGE PUMP			1		I
Charge Pump Voltage $V+ = 5.0 \text{ V}$ $8.0 \text{ V} \le V+ \le 28 \text{ V}$	V <sub>CP</sub> -V+	3.35	_ _	- 20	V
CONTROL INPUTS	!	ļ.			1
Input Voltage (IN1, IN2, D1, $\overline{\text{D2}}$ )  Threshold HIGH  Threshold LOW  Hysteresis	V <sub>IH</sub> V <sub>IL</sub> V <sub>HYS</sub>	3.5 - 0.7	- - 1.0	- 1.4 -	V
Input Current (IN1, IN2, D1) V <sub>IN</sub> - 0.0 V	I <sub>INP</sub>	-200	-80	_	μА
Input Current ( $\overline{D2}$ , EN) V $\overline{D2}$ = 5.0 V	I <sub>INP</sub>	-	25	100	μА

Specifications are characterized over the range of 5.0 V ≤ V+ ≤ 28 V. See See Electrical Performance Curves on page 18 and 19 and the See Functional Description on page 21 for information about operation outside of this range.

<sup>17</sup> I<sub>Q(sleep)</sub> is with sleep mode function enabled.

## **Table 4. STATIC ELECTRICAL CHARACTERISTICS**

Characteristics noted under conditions 5.0 V  $\leq$  V+  $\leq$  28 V and -40°C  $\leq$  T<sub>A</sub>  $\leq$  125°C unless otherwise noted. Typical values noted reflect the approximate parameter mean at T<sub>A</sub> = 25°C under nominal conditions unless otherwise noted.

Characteristic	Symbol	Min	Тур	Max	Unit
POWER SUPPLY					
POWER OUTPUTS (OUT1, OUT2)					
Output ON-Resistance (18)	R <sub>DS(ON)</sub>				mΩ
$5.0 \text{ V} \le \text{V+} \le 28 \text{ V}, \text{ T}_{\text{J}} = 25^{\circ}\text{C}$	-(-,	_	120	_	
8.0 V ≤ V+ ≤ 28 V, T <sub>J</sub> = 150°C		_	-	225	
$5.0 \text{ V} \le \text{V+} \le 8.0 \text{ V}, \text{ T}_{\text{J}} = 150 ^{\circ}\text{C}$		_	_	300	
Active Current Limiting Threshold (via Internal Constant OFF-Time PWM) on Low-Side MOSFETs (19)	I <sub>LIM</sub>	5.2	6.5	7.8	А
High-Side Short Circuit Detection Threshold	I <sub>SCH</sub>	11	_	_	Α
Low-Side Short Circuit Detection Threshold	I <sub>SCL</sub>	8.0	-	-	Α
Leakage Current (20)	I <sub>OUT(LEAK)</sub>				μА
V <sub>OUT</sub> = V+		_	100	200	
V <sub>OUT</sub> = Ground		_	30	60	
Output MOSFET Body Diode Forward Voltage Drop	V <sub>F</sub>				V
I <sub>OUT</sub> = 3.0 A		_	_	2.0	
Overtemperature Shutdown					°C
Thermal Limit	$T_{LIM}$	175	_	225	
Hysteresis	T <sub>HYS</sub>	10	_	30	
HIGH-SIDE CURRENT SENSE FEEDBACK					
Feedback Current	I <sub>FB</sub>				
I <sub>OUT</sub> = 0 mA		-	-	600	μΑ
I <sub>OUT</sub> = 500 mA		1.07	1.33	1.68	mA
I <sub>OUT</sub> = 1.5 A		3.6	4.0	4.62	mA
I <sub>OUT</sub> = 3.0 A		7.2	8.0	9.24	mA
I <sub>OUT</sub> = 6.0 A		14.4	16	18.48	mA
FAULT STATUS <sup>(21)</sup>		•			
Fault Status Leakage Current (22)	I <del>FS</del> (LEAK)				μА
V <sub>FS</sub> = 5.0 V	, ,	_	_	10	
Fault Status SET Voltage (23)	V <sub>FS(LOW)</sub>				V
I <del>FS</del> = 300 μA		_	_	1.0	
				1	·

- 18 Output-ON resistance as measured from output to V+ and ground.
- 19 Active current limitation applies only for the low-side MOSFETs.
- 20 Outputs switched OFF with D1 or  $\overline{D2}$ .
- 21 Fault Status output is an open Drain output requiring a pull-up resistor to 5.0 V.
- 22 Fault Status Leakage Current is measured with Fault Status HIGH and not SET.
- Fault Status Set Voltage is measured with Fault Status LOW and SET with  $\overline{\text{FS}}$  = 300  $\mu$ A.

#### DYNAMIC ELECTRICAL CHARACTERISTICS

#### **Table 5. DYNAMIC ELECTRICAL CHARACTERISTICS**

Characteristics noted under conditions 5.0 V  $\leq$  V+  $\leq$  28 V and -40°C  $\leq$  T<sub>A</sub>  $\leq$  125°C unless otherwise noted. Typical values noted reflect the approximate parameter mean at T<sub>A</sub> = 25°C under nominal conditions unless otherwise noted.

Characteristic	Symbol	Min	Тур	Max	Unit
TIMING CHARACTERISTICS					
PWM Frequency (24)	f <sub>PWM</sub>	-	10	_	kHz
Maximum Switching Frequency During Active Current Limiting (25)	f <sub>MAX</sub>	-	_	20	kHz
Output ON Delay <sup>(26)</sup> V+ = 14 V	t <sub>D(ON)</sub>	_	_	18	μs
Output OFF Delay <sup>(26)</sup> V+ = 14 V	t <sub>D(OFF)</sub>	-	_	18	μs
I <sub>LIM</sub> Output Constant-OFF Time for Low-Side MOSFETs (27), (28)	t <sub>A</sub>	15	20.5	26	μs
I <sub>LIM</sub> Blanking Time for Low-Side MOSFETs <sup>(29)</sup> , <sup>(28)</sup>	t <sub>B</sub>	12	16.5	21	μs
Output Rise and Fall Time <sup>(30)</sup> V+ = 14 V, I <sub>OUT</sub> = 3.0 A	t <sub>F</sub> , t <sub>R</sub>	2.0	5.0	8.0	μs
Disable Delay Time (31)	t <sub>D(DISABLE)</sub>	-	_	8.0	μs
Power-ON Delay Time (32)	t <sub>POD</sub>	_	1.0	5.0	ms
Wake-Up Delay Time (32)	t <sub>WUD</sub>	-	1.0	5.0	ms
Output MOSFET Body Diode Reverse Recovery Time (33)	t <sub>RR</sub>	100	-	-	ns

- 24 The outputs can be PWM-controlled from an external source. This is typically done by holding one input high while applying a PWM pulse train to the other input. The maximum PWM frequency obtainable is a compromise between switching losses and switching frequency. See Typical Switching Waveforms, Figures 12 through 19, pp. 14–17.
- The Maximum Switching Frequency during active current limiting is internally implemented. The internal current limit circuitry produces a constant-OFF-time pulse-width modulation of the output current. The output load's inductance, capacitance, and resistance characteristics affect the total switching period (OFF-time + ON-time) and thus the PWM frequency during current limit.
- Output Delay is the time duration from the midpoint of the IN1 or IN2 input signal to the 10% or 90% point (dependent on the transition direction) of the OUT1 or OUT2 signal. If the output is transitioning HIGH-to-LOW, the delay is from the midpoint of the input signal to the 90% point of the output response signal. If the output is transitioning LOW-to-HIGH, the delay is from the midpoint of the input signal to the 10% point of the output response signal. See Figure 6, page 12.
- 27 I<sub>LIM</sub> Output Constant-OFF Time is the time during which the internal constant-OFF time PWM current regulation circuit has tri-stated the output bridge.
- Load currents ramping up to the current regulation threshold become limited at the I<sub>LIM</sub> value. The short circuit currents possess a di/dt that ramps up to the I<sub>SCH</sub> or I<sub>SCL</sub> threshold during the I<sub>LIM</sub> blanking time, registering as a short circuit event detection and causing the shutdown circuitry to force the output into an immediate tri-state latch-OFF. See Figures 10 and 11, page 13. Operation in Current Limit mode may cause junction temperatures to rise. Junction temperatures above ~160°C will cause the output current limit threshold to progressively "fold back", or decrease with temperature, until ~175°C is reached, after which the T<sub>LIM</sub> thermal latch-OFF will occur. Permissible operation within this fold-back region is limited to nonrepetitive transient events of duration not to exceed 30 seconds. See Figure 9, page 12.
- 29 I<sub>LIM</sub> Blanking Time is the time during which the current regulation threshold is ignored so that the short-circuit detection threshold comparators my have time to act.
- 30 Rise Time is from the 10% to the 90% level and Fall Time is from the 90% to the 10% level of the output signal. See Figure 8, page 12.
- 31 Disable Delay Time is the time duration from the midpoint of the D (disable) input signal to 10% of the output tri-state response. See Figure 7, page 12.
- 32 Parameter has been characterized but not production tested.
- 33 Parameter is guaranteed by design but not production tested.

## **TIMING DIAGRAMS**




Figure 6. Output Delay Time




Figure 7. Disable Delay Time




Figure 8. Output Switching Time




Figure 9. Active Current Limiting Versus Temperature (Typical)




Figure 10. Operating States




Figure 11. Example Short Circuit Detection Detail on Low-Side MOSFET

#### TYPICAL SWITCHING WAVEFORMS

**Important** For all plots, the following applies:

• Ch2=2.0 A per division

- L<sub>LOAD</sub>=533 μH @ 1.0 kHz
- $L_{LOAD}$ =530  $\mu H$  @ 10.0 kHz
- $R_{LOAD}$ =4.0  $\Omega$




Figure 12. Output Voltage and Current vs. Input Voltage at V+ = 24 V, PMW Frequency of 1.0 kHz, and Duty Cycle of 10%




Figure 13. Output Voltage and Current vs. Input Voltage at V+ = 24 V, PMW Frequency of 1.0 kHz, and Duty Cycle of 50%




Figure 14. Output Voltage and Current vs. Input Voltage at V+ = 34 V, PMW Frequency of 1.0 kHz, and Duty Cycle of 90%, Showing Device in Current Limiting Mode




Figure 15. Output Voltage and Current vs. Input Voltage at V+ = 22 V, PMW Frequency of 1.0 kHz, and Duty Cycle of 90%




Figure 16. Output Voltage and Current vs. Input Voltage at V+ = 24 V, PMW Frequency of 10 kHz, and Duty Cycle of 50%




Figure 17. Output Voltage and Current vs. Input Voltage at V+ = 24 V, PMW Frequency of 10 kHz, and Duty Cycle of 90%




Figure 18. Output Voltage and Current vs. Input Voltage at V+ = 12 V, PMW Frequency of 20 kHz, and Duty Cycle of 50% for a Purely Resistive Load




Figure 19. Output Voltage and Current vs. Input Voltage at V+ = 12 V, PMW Frequency of 20 kHz, and Duty Cycle of 90% for a Purely Resistive Load

## **ELECTRICAL PERFORMANCE CURVES**




Figure 20. Typical High-Side  $R_{DS(ON)}$  Versus V+




Figure 21. Typical Low-Side  $R_{DS(ON)}$  Versus V+




Figure 22. Typical Quiescent Supply Current Versus V+

Table 6. Truth Table

The tri-state conditions and the fault status are reset using D1 or  $\overline{D2}$ . The truth table uses the following notations: L = LOW, H = HIGH, X = HIGH or LOW, and Z = High impedance (all output power transistors are switched off).

Device State	Input Conditions					Fault Status Flag	Output	States
	EN	D1	D2	IN1	IN2	FS	OUT1	OUT2
Forward	Н	L	Н	Н	L	Н	Н	L
Reverse	Н	L	Н	L	Н	Н	L	Н
Freewheeling Low	Н	L	Н	L	L	Н	L	L
Freewheeling High	Н	L	Н	Н	Н	Н	Н	Н
Disable 1 (D1)	Н	Н	х	Х	Х	L	Z	Z
Disable 2 (D2)	Н	х	L	Х	Х	L	Z	Z
IN1 Disconnected	Н	L	Н	Z	Х	Н	Н	Х
IN2 Disconnected	Н	L	Н	Х	Z	Н	Х	Н
D1 Disconnected	Н	Z	Х	Х	Х	L	Z	Z
D2 Disconnected	Н	Х	Z	Х	Х	L	Z	Z
Undervoltage (34)	Н	х	х	Х	Х	L	Z	Z
Overtemperature (35)	Н	х	х	Х	Х	L	Z	Z
Short Circuit (35)	Н	х	х	Х	х	L	Z	Z
Sleep Mode EN	L	х	х	Х	х	Н	Z	Z
EN Disconnected	Z	х	х	Х	х	Н	Z	Z

In the case of an undervoltage condition, the outputs tri-state and the fault status is SET logic LOW. Upon undervoltage recovery, fault status is reset automatically or automatically cleared and the outputs are restored to their original operating condition.

When a short circuit or overtemperature condition is detected, the power outputs are tri-state latched-OFF independent of the input signals and the fault status flag is SET logic LOW.

#### **FUNCTIONAL DESCRIPTION**

#### **INTRODUCTION**

Numerous protection and operational features (speed, torque, direction, dynamic braking, PWM control, and closed-loop control), in addition to the 5.0 A current capability, make the 33887 a very attractive, cost-effective solution for controlling a broad range of small DC motors. In addition, a

pair of 33887 devices can be used to control bipolar stepper motors. The 33887 can also be used to excite transformer primary windings with a switched square wave to produce secondary winding AC currents.

#### **FUNCTIONAL PIN DESCRIPTIONS**

# POWER GROUND AND ANALOG GROUND (PGND AND AGND)

Power and analog ground pins should be connected together with a very low impedance connection.

## POSITIVE POWER SUPPLY (V+)

V+ pins are the power supply inputs to the device. All V+ pins must be connected together on the printed circuit board with as short as possible traces offering as low impedance as possible between pins.

V+ pins have an undervoltage threshold. If the supply voltage drops below a V+ undervoltage threshold, the output power stage switches to a tri-state condition and the fault status flag is SET and the Fault Status pin voltage switched to a logic LOW. When the supply voltage returns to a level that is above the threshold, the power stage automatically resumes normal operation according to the established condition of the input pins and the fault status flag is automatically reset logic HIGH.

As V+ increases in value above 28 V, the charge pump performance begins to degrade. At +40 V, the charge pump is effectively non-functional. Operation at this high voltage level will result in the output FETs not being enhanced when turned on. This means that the voltage on the output will be  $V_{OUT} = (V+) - V_{GS}$ . This increased voltage drop under load will produce a higher power dissipation.

## FAULT STATUS (FS)

The FS pin is the device fault status output. This output is an active LOW open drain structure requiring a pull-up resistor to 5.0 V. Refer to Table 6, Truth Table, page 20.

# LOGIC INPUT CONTROL AND DISABLE (IN1, IN2, D1, AND D2)

These pins are input control pins used to control the outputs. These pins are 5.0 V CMOS-compatible inputs with hysteresis. The IN1 and IN2 independently control OUT1 and OUT2, respectively. D1 and  $\overline{D2}$  are complementary inputs used to tri-state disable the H-Bridge outputs.

When either D1 or  $\overline{D2}$  is SET (D1 = logic HIGH or  $\overline{D2}$  = logic LOW) in the disable state, outputs OUT1 and OUT2 are both tri-state disabled; however, the rest of the circuitry is fully operational and the supply  $I_{Q(standby)}$  current is reduced to a

few milliamperes. Refer to Table <u>6, Truth Table</u>, and <u>STATIC</u> <u>ELECTRICAL CHARACTERISTICS</u> table, page <u>9</u>.

## H-BRIDGE OUTPUT (OUT1 AND OUT2)

These pins are the outputs of the H-Bridge with integrated output MOSFET body diodes. The bridge output is controlled using the IN1, IN2, D1, and  $\overline{\rm D2}$  inputs. The low-side MOSFETs have active current limiting above the I $_{\rm LIM}$  threshold. The outputs also have thermal shutdown (tri-state latch-OFF) with hysteresis as well as short circuit latch-OFF protection.

A disable timer (time  $t_b$ ) USED to detect currents that are higher than current limit is activated at each output activation to facilitate hard short detection (see Figure 11, page 13).

#### Charge Pump Capacitor (CCP)

A filter capacitor (up to 33 nF) can be connected from the charge pump output pin and PGND. The device can operate without the external capacitor, although the  $C_{CP}$  capacitor helps to reduce noise and allows the device to perform at maximum speed, timing, and PWM frequency.

#### **ENABLE (EN)**

The EN pin is used to place the device in a sleep mode so as to consume very low currents. When the EN pin voltage is a logic LOW state, the device is in the sleep mode. The device is enabled and fully operational when the EN pin voltage is logic HIGH. An internal pull-down resistor maintains the device in sleep mode in the event EN is driven through a high impedance I/O or an unpowered microcontroller, or the EN input becomes disconnected.

#### FEEDBACK FOR H-BRIDGE (FB)

The 33887 has a feedback output (FB) for "real time" monitoring of H-Bridge high-side current to facilitate closed-loop operation for motor speed and torque control.

The FB pin provides current sensing feedback of the H-Bridge high-side drivers. When running in forward or reverse direction, a ground referenced 1/375th (0.00266) of load current is output to this pin. Through an external resistor to ground, the proportional feedback current can be converted to a proportional voltage equivalent and the controlling microcontroller can "read" the current proportional

33887

# FUNCTIONAL DESCRIPTION FUNCTIONAL PIN DESCRIPTIONS

voltage with its analog-to-digital converter (ADC). This is intended to provide the user with motor current feedback for motor torque control. The resistance range for the linear operation of the FB pin is  $100 < R_{FB} < 200 \ \Omega.$ 

If PWM-ing is implemented using the disable pin inputs (either D1 or  $\overline{D2}$ ), a small filter capacitor (1.0  $\mu F$  or less) may be required in parallel with the external resistor to ground for fast spike suppression.

## **FUNCTIONAL DEVICE OPERATION**

#### **OPERATIONAL MODES**

The 33887 Simplified Internal Block Diagram shown in Figure 2, page 2, is a fully protected monolithic H-Bridge with Enable, Fault Status reporting, and High-Side current sense feedback to accommodate closed-loop PWM control. For a DC motor to run, the input conditions need be as follows: Enable input logic HIGH, D1 input logic LOW,  $\overline{D2}$  input logic HIGH,  $\overline{FS}$  flag cleared (logic HIGH), one IN logic LOW and the other IN logic HIGH (to define output polarity). The 33887 can execute dynamic braking by simultaneously turning on either both high-side MOSFETs or both low-side MOSFETs in the output H-Bridge; e.g., IN1 and IN2 logic HIGH or IN1 and IN2 logic LOW.

The 33887 outputs are capable of providing a continuous DC load current of 5.0 A from a 28 V V+ source. An internal charge pump supports PWM frequencies to 10 kHz. An external pull-up resistor is required at the  $\overline{\text{FS}}$  pin for fault status reporting. The 33887 has an analog feedback (current mirror) output pin (the FB pin) that provides a constant-current source ratioed to the active high-side MOSFET. This can be used to provide "real time" monitoring of load current to facilitate closed-loop operation for motor speed/torque control.

Two independent inputs (IN1 and IN2) provide control of the two totem-pole half-bridge outputs. Two disable inputs (D1 and  $\overline{D2}$ ) provide the means to force the H-Bridge outputs to a high-impedance state (all H-Bridge switches OFF). An EN pin controls an enable function that allows the 33887 to be placed in a power-conserving sleep mode.

The 33887 has undervoltage shutdown with automatic recovery, active current limiting, output short-circuit latch-OFF, and overtemperature latch-OFF. An undervoltage shutdown, output short-circuit latch-OFF, or overtemperature latch-OFF fault condition will cause the outputs to turn OFF (i.e., become high impedance or tri-stated) and the fault output flag to be set LOW. Either of the Disable inputs or V+ must be "toggled" to clear the fault flag.

Active current limiting is accomplished by a constant OFF-time PWM method employing active current limiting threshold triggering. The active current limiting scheme is unique in that it incorporates a junction temperature-dependent current limit threshold. This means the active current limiting threshold is "ramped down" as the junction temperature increases above 160°C, until at 175°C the current will have been decreased to about 4.0 A. Above 175°C, the overtemperature shutdown (latch-OFF) occurs. This combination of features allows the device to remain in operation for 30 seconds at junction temperatures above 150°C for nonrepetitive unexpected loads.

#### PROTECTION AND DIAGNOSTIC FEATURES

#### SHORT CIRCUIT PROTECTION

If an output short circuit condition is detected, the power outputs tri-state (latch-OFF) independent of the input (IN1 and IN2) states, and the fault status output flag is SET logic LOW. If the D1 input changes from logic HIGH to logic LOW, or if the  $\overline{D2}$  input changes from logic LOW to logic HIGH, the output bridge will become operational again and the fault status flag will be reset (cleared) to a logic HIGH state.

The output stage will always switch into the mode defined by the input pins (IN1, IN2, D1, and  $\overline{D2}$ ), provided the device junction temperature is within the specified operating temperature range.

## **ACTIVE CURRENT LIMITING**

The maximum current flow under normal operating conditions is internally limited to  $I_{LIM}$  (5.2 A to 7.8 A). When the maximum current value is reached, the output stages are tri-stated for a fixed time ( $t_a$ ) of 20  $\mu$ s typical. Depending on the time constant associated with the load characteristics, the current decreases during the tri-state duration until the next output ON cycle occurs (see <u>Figures 11</u> and <u>14</u>, page <u>13</u> and page <u>15</u>, respectively).

The current limiting threshold value is dependent upon the device junction temperature. When -40°C  $\leq$   $T_{\rm J} \leq$  160°C,  $I_{\rm LIM}$  is between 5.2 A to 7.8 A. When  $T_{\rm J}$  exceeds 160°C, the  $I_{\rm LIM}$  current decreases linearly down to 4.0 A typical at 175°C. Above 175°C the device overtemperature circuit detects  $T_{\rm LIM}$ 

and overtemperature shutdown occurs (see Figure 9, page 12). This feature allows the device to remain operational for a longer time but at a regressing output performance level at junction temperatures above 160°C.

#### **Output Avalanche Protection**

An inductive fly-back event, namely when the outputs are suddenly disabled and V+ is lost, could result in electrical overstress of the drivers. To prevent this the V+ input to the 33887 should not exceed the maximum rating during a fly-back condition. This may be done with either a zener clamp and/or an appropriately valued input capacitor with sufficiently low ESR.

# OVERTEMPERATURE SHUTDOWN AND HYSTERESIS

If an overtemperature condition occurs, the power outputs are tri-stated (latched-OFF) and the fault status flag is SET to logic LOW.

To reset from this condition, D1 must change from logic HIGH to logic LOW, or  $\overline{D2}$  must change from logic LOW to logic HIGH. When reset, the output stage switches ON again, provided that the junction temperature is now below the overtemperature threshold limit minus the hysteresis.

**Note** Resetting from the fault condition will clear the fault status flag.

## **TYPICAL APPLICATIONS**

<u>Figure 23</u> shows a typical application schematic. For precision high-current applications in harsh, noisy environments, the V+ by-pass capacitor may need to be substantially larger.





Figure 23. 33887 Typical Application Schematic

## **PACKAGING**

## **SOLDERING INFORMATION**

The 33887 packages are designed for thermal performance. The significant feature of these packages is the exposed pad on which the power die is soldered. When soldered to a PCB, this pad provides a path for heat flow to the ambient environment. The more copper area and thickness on the PCB, the better the power dissipation and transient behavior will be.

**Example** Characterization on a double-sided PCB: bottom side area of copper is 7.8 cm<sup>2</sup>; top surface is 2.7 cm<sup>2</sup> (see Figure ); grid array of 24 vias 0.3 mm in diameter






Top Side

**Bottom Side** 

Figure 24. PCB Test Layout


## **PACKAGING DIMENSIONS**

**Important** For the most current revision of the package, visit <u>www.freescale.com</u> and perform a keyword search on the 98A drawing number below




© FREESCALE SEMICONDUCTOR, INC. ALL RIGHTS RESERVED.	MECHANICAL OUTLINE		PRINT VERSION NO	T TO SCALE
TITLE:		DOCUMENT NO	): 98ASH70273A	REV: E
20 LEAD HSOP		CASE NUMBER: 979-04		19 MAY 2005
		STANDARD: NO	DN-JEDEC	

DH SUFFIX VW SUFFIX 20-PIN HSOP PLASTIC PACKAGE 98ASH70273A ISSUE E




© FREESCALE SEMICONDUCTOR, INC. ALL RIGHTS RESERVED.	MECHANICAL OUTLINE		PRINT VERSION NOT TO SCALE	
TITLE:		DOCUMENT NO	): 98ASH70273A	REV: E
20 LEAD HSOP		CASE NUMBER	₹: 979–04	19 MAY 2005
		STANDARD: NO	N-JEDEC	


DH SUFFIX VW SUFFIX 20-PIN HSOP PLASTIC PACKAGE 98ASH70273A ISSUE E



© FREESCALE SEMICONDUCTOR, INC.  ALL RIGHTS RESERVED.  MECHANICA		L OUTLINE	PRINT VERSION NO	T TO SCALE
TITLE: POWER QUAD FLAT		DOCUMENT NO	): 98ASA10583D	REV: C
NON-LEADED PACKAGE (PWR QFN),		CASE NUMBER	: 1503–04	14 JUL 2005
36 TERMINAL 0.8 PITCH(9X9X2.1)		STANDARD: JE	DEC MO-251A AEEB-	1


PNB (Pb-FREE) SUFFIX 36-PIN PQFN Pb-Free PACKAGE 98ASA10583D ISSUE C





© FREESCALE SEMICONDUCTOR, INC.  ALL RIGHTS RESERVED.  MECHANICA		L OUTLINE	PRINT VERSION NO	T TO SCALE
TITLE: POWER QUAD FLAT		DOCUMENT NO	): 98ASA10583D	REV: C
NON-LEADED PACKAGE (PWR QFN),		CASE NUMBER	2: 1503–04	14 JUL 2005
36 TERMINAL 0.8 PITCH(9X9X2.1)		STANDARD: JE	DEC MO-251A AEEB-	1

PNB (Pb-FREE) SUFFIX 36-PIN PQFN Pb-Free PACKAGE 98ASA10583D ISSUE C





DWB SUFFIX EK SUFFIX (PB-FREE) 54-PIN SOICW EXPOSED PAD PLASTIC PACKAGE 98ASA10506D ISSUE C

STANDARD: NON-JEDEC

33887

CASE-OUTLINE





© FREESCALE SEMICONDUCTOR, INC.  ALL RIGHTS RESERVED.  MECHANIC	AL OUTLINE	PRINT VERSION NO	OT TO SCALE
TITLE:		): 98ASA10506D	REV: C
54LD SOIC W/B, 0.65 PITCH 4.6 X 4.6 EXPOSED PAD,	CASE NUMBER	R: 1390–02	11 MAR 2005
CASE-OUTLINE	STANDARD: NO	N-JEDEC	

## **DWB SUFFIX**

EK SUFFIX (PB-FREE) 54-PIN SOICW EXPOSED PAD PLASTIC PACKAGE 98ASA10506D ISSUE C

## ADDITIONAL DOCUMENTATION

## THERMAL ADDENDUM (REV 2.0)

#### Introduction

This thermal addendum is provided as a supplement to the MC33887 technical data sheet. The addendum provides thermal performance information that may be critical in the design and development of system applications. All electrical, application, and packaging information is provided in the data sheet.

#### **Packaging and Thermal Considerations**

The MC33887 is offered in a 20 pin HSOP exposed pad, single die package. There is a single heat source (P), a single junction temperature ( $T_J$ ), and thermal resistance ( $R_{\theta,JA}$ ).

$$\{T_J\} = [R_{\theta JA}] \cdot \{P\}$$

The stated values are solely for a thermal performance comparison of one package to another in a standardized environment. This methodology is not meant to and will not predict the performance of a package in an application-specific environment. Stated values were obtained by measurement and simulation according to the standards listed below.

## 33887DH

## 20-PIN HSOP-EP



**Note** For package dimensions, refer to the 33887 device data sheet.

#### **Standards**

**Table 7. Thermal Performance Comparison** 

Thermal Resistance	[°C/W]
R <sub>0JA</sub> <sup>(1),(2)</sup>	20
R <sub>0JB</sub> (2),(3)	6.0
R <sub>0JA</sub> (1), (4)	52
R <sub>θJC</sub> <sup>(5)</sup>	1.0

#### NOTES:

- 1.Per JEDEC JESD51-2 at natural convection, still air condition.
- 2.2s2p thermal test board per JEDEC JESD51-5 and JESD51-7.
- 3.Per JEDEC JESD51-8, with the board temperature on the center trace near the center lead.
- 4.Single layer thermal test board per JEDEC JESD51-3 and JESD51-5.
- 5.Thermal resistance between the die junction and the exposed pad surface; cold plate attached to the package bottom side, remaining surfaces insulated




Figure 25. Thermal Land Pattern for Direct Thermal Attachment According to JESD51-5




Figure 26. Thermal Test Board

## **Device on Thermal Test Board**

Material: Single layer printed circuit board

FR4, 1.6 mm thickness

Cu traces, 0.07 mm thickness

Outline: 80 mm x 100 mm board area,

including edge connector for thermal

testing

Area A: Cu heat spreading areas on board

surface

Ambient Conditions: Natural convection, still air

**Table 8. Thermal Resistance Performance** 

Thermal Resistance	Area A (mm²)	°C/W
$R_{\theta JA}$	0.0	52
	300	36
	600	32
$R_{ heta JS}$	0.0	10
	300	7.0
	600	6.0

 $R_{\theta JA}$  is the thermal resistance between die junction and ambient air.

 $R_{\theta JS}$  is the thermal resistance between die junction and the reference location on the board surface near a center lead of the package (see Figure 26).




Figure 27. Device on Thermal Test Board  $R_{\theta J A}$ 




Figure 28. Transient Thermal Resistance  $R_{\theta JA}$  Device on Thermal Test Board Area A = 600 (mm²)

## **REVISION HISTORY**

REVISION	DATE	DESCRIPTION
10.0	7/2005	<ul> <li>Added Thermal Addendum &amp; Converted to Freescale format, Revised PQFN drawing, made several minor spelling correction. Added 33887A</li> </ul>
11.0	11/2006	<ul> <li>Updated Ordering information block with new epp information</li> <li>Changed the supply/ operating voltage from 40 V to 28 V</li> <li>Updated all package drawings to the current revision</li> <li>Adjusted to match device performance characteristics</li> <li>Updated the document to the prevailing Freescale form and style</li> <li>Removed Peak Package Reflow Temperature During Reflow (solder reflow) parameter from Maximum Ratings on page 7.</li> <li>Added note <sup>(8)</sup></li> <li>Added MCZ33887EK/R2 to the Ordering Information on Page 1</li> <li>Removed the 33887A from the data sheet and deleted Product Variation section now that is no longer needed.</li> </ul>
12.0	1/2007	<ul> <li>Changed the third paragraph of the introduction on page 1</li> <li>Altered feature number 1 on page 1</li> <li>Added feature number 2 on page 1</li> <li>Changed Maximum Supply Voltage <sup>(1)</sup> to 0.3 to 40 V</li> <li>Added note <sup>(1)</sup></li> <li>Changed note <sup>(16)</sup></li> <li>Added a third paragraph to Positive Power Supply (V+) on page 21</li> <li>Replaced Figure 20, Figure 21, and Figure 22 with updated information.</li> </ul>
13.0	10/2008	Added Part Number MC33887AVW/R2 to Ordering Information Table on page 1.

#### How to Reach Us:

#### Home Page:

www.freescale.com

#### Web Support:

http://www.freescale.com/support

#### **USA/Europe or Locations Not Listed:**

Freescale Semiconductor, Inc.
Technical Information Center, EL516
2100 East Elliot Road
Tempe, Arizona 85284
+1-800-521-6274 or +1-480-768-2130
www.freescale.com/support

#### Europe, Middle East, and Africa:

Freescale Halbleiter Deutschland GmbH Technical Information Center Schatzbogen 7 81829 Muenchen, Germany +44 1296 380 456 (English) +46 8 52200080 (English) +49 89 92103 559 (German) +33 1 69 35 48 48 (French) www.freescale.com/support

#### Japan:

Freescale Semiconductor Japan Ltd. Headquarters ARCO Tower 15F 1-8-1, Shimo-Meguro, Meguro-ku, Tokyo 153-0064 Japan 0120 191014 or +81 3 5437 9125 support.japan@freescale.com

#### Asia/Pacific:

Freescale Semiconductor Hong Kong Ltd. Technical Information Center 2 Dai King Street
Tai Po Industrial Estate
Tai Po, N.T., Hong Kong
+800 2666 8080
support.asia@freescale.com

#### For Literature Requests Only:

Freescale Semiconductor Literature Distribution Center P.O. Box 5405
Denver, Colorado 80217
1-800-441-2447 or 303-675-2140
Fax: 303-675-2150
LDCForFreescaleSemiconductor@hibbertgroup.com

RoHS-compliant and/or Pb-free versions of Freescale products have the functionality and electrical characteristics of their non-RoHS-compliant and/or non-Pb-free counterparts. For further information, see <a href="http://www.freescale.com">http://www.freescale.com</a> or contact your Freescale sales representative.

For information on Freescale's Environmental Products program, go to http://www.freescale.com/epp.

Information in this document is provided solely to enable system and software implementers to use Freescale Semiconductor products. There are no express or implied copyright licenses granted hereunder to design or fabricate any integrated circuits or integrated circuits based on the information in this document.

Freescale Semiconductor reserves the right to make changes without further notice to any products herein. Freescale Semiconductor makes no warranty, representation or guarantee regarding the suitability of its products for any particular purpose, nor does Freescale Semiconductor assume any liability arising out of the application or use of any product or circuit, and specifically disclaims any and all liability, including without limitation consequential or incidental damages. "Typical" parameters that may be provided in Freescale Semiconductor data sheets and/or specifications can and do vary in different applications and actual performance may vary over time. All operating parameters, including "Typicals", must be validated for each customer application by customer's technical experts. Freescale Semiconductor does not convey any license under its patent rights nor the rights of others. Freescale Semiconductor products are not designed, intended, or authorized for use as components in systems intended for surgical implant into the body, or other applications intended to support or sustain life, or for any other application in which the failure of the Freescale Semiconductor product could create a situation where personal injury or death may occur. Should Buyer purchase or use Freescale Semiconductor products for any such unintended or unauthorized application, Buyer shall indemnify and hold Freescale Semiconductor and its officers, employees, subsidiaries, affiliates, and distributors harmless against all claims, costs, damages, and expenses, and reasonable attorney fees arising out of, directly or indirectly, any claim of personal injury or death associated with such unintended or unauthorized use, even if such claim alleges that Freescale Semiconductor was negligent regarding the design or manufacture of the part.

Freescale ™ and the Freescale logo are trademarks of Freescale Semiconductor, Inc. All other product or service names are the property of their respective owners.

© Freescale Semiconductor, Inc., 2007 - 2008. All rights reserved.

