#### **Features**

- Utilizes the AVR® RISC Architecture
- AVR High-performance and Low-power RISC Architecture
  - 120 Powerful Instructions Most Single Clock Cycle Execution
  - 32 x 8 General Purpose Working Registers
  - Fully Static Operation
  - Up to 20 MIPS Throughput at 20 MHz
- Data and Non-volatile Program and Data Memories
  - 2K Bytes of In-System Self Programmable Flash Endurance 10,000 Write/Erase Cycles
  - 128 Bytes In-System Programmable EEPROM Endurance: 100,000 Write/Erase Cycles
  - 128 Bytes Internal SRAM
  - Programming Lock for Flash Program and EEPROM Data Security
- Peripheral Features
  - One 8-bit Timer/Counter with Separate Prescaler and Compare Mode
  - One 16-bit Timer/Counter with Separate Prescaler, Compare and Capture Modes
  - Four PWM Channels
  - On-chip Analog Comparator
  - Programmable Watchdog Timer with On-chip Oscillator
  - USI Universal Serial Interface
  - Full Duplex USART
- Special Microcontroller Features
  - debugWIRE On-chip Debugging
  - In-System Programmable via SPI Port
  - External and Internal Interrupt Sources
  - Low-power Idle, Power-down, and Standby Modes
  - Enhanced Power-on Reset Circuit
  - Programmable Brown-out Detection Circuit
  - Internal Calibrated Oscillator
- I/O and Packages
  - 18 Programmable I/O Lines
  - 20-pin PDIP, 20-pin SOIC, and 32-pin MLF
- Operating Voltages
  - 1.8 5.5V (ATtiny2313)
- Speed Grades
  - ATtiny2313V: 0 4 MHz @ 1.8 5.5V, 0 10 MHz @ 2.7 5.5V
  - ATtiny2313: 0 10 MHz @ 2.7 5.5V, 0 20 MHz @ 4.5 5.5V
- Power Consumption Estimates
  - Active Mode
    - 1 MHz, 1.8V: 300 μA
    - 32 kHz, 1.8V: 20 µA (including oscillator)
  - Power-down Mode
    - < 0.2 µA at 1.8V




8-bit **AVR**® Microcontroller with 2K Bytes In-System Programmable Flash

ATtiny2313/V

Preliminary Summary

Rev. 2543ES-AVR-04/04



is available on our Web site at www.atmel.com.






### **Pin Configurations**

Figure 1. Pinout ATtiny2313

#### PDIP/SOIC




#### **Overview**

The ATtiny2313 is a low-power CMOS 8-bit microcontroller based on the AVR enhanced RISC architecture. By executing powerful instructions in a single clock cycle, the ATtiny2313 achieves throughputs approaching 1 MIPS per MHz allowing the system designer to optimize power consumption versus processing speed.

### **Block Diagram**

Figure 2. Block Diagram







The AVR core combines a rich instruction set with 32 general purpose working registers. All the 32 registers are directly connected to the Arithmetic Logic Unit (ALU), allowing two independent registers to be accessed in one single instruction executed in one clock cycle. The resulting architecture is more code efficient while achieving throughputs up to ten times faster than conventional CISC microcontrollers.

The ATtiny2313 provides the following features: 2K bytes of In-System Programmable Flash, 128 bytes EEPROM, 128 bytes SRAM, 18 general purpose I/O lines, 32 general purpose working registers, a single-wire Interface for On-chip Debugging, two flexible Timer/Counters with compare modes, internal and external interrupts, a serial programmable USART, Universal Serial Interface with Start Condition Detector, a programmable Watchdog Timer with internal Oscillator, and three software selectable power saving modes. The Idle mode stops the CPU while allowing the SRAM, Timer/Counters, and interrupt system to continue functioning. The Power-down mode saves the register contents but freezes the Oscillator, disabling all other chip functions until the next interrupt or hardware reset. In Standby mode, the crystal/resonator Oscillator is running while the rest of the device is sleeping. This allows very fast start-up combined with low-power consumption.

The device is manufactured using Atmel's high density non-volatile memory technology. The On-chip ISP Flash allows the program memory to be reprogrammed In-System through an SPI serial interface, or by a conventional non-volatile memory programmer. By combining an 8-bit RISC CPU with In-System Self-Programmable Flash on a monolithic chip, the Atmel ATtiny2313 is a powerful microcontroller that provides a highly flexible and cost effective solution to many embedded control applications.

The ATtiny2313 AVR is supported with a full suite of program and system development tools including: C Compilers, Macro Assemblers, Program Debugger/Simulators, In-Circuit Emulators, and Evaluation kits.

#### **Pin Descriptions**

Port D (PD6..PD0)

VCC Digital supply voltage.

**GND** Ground.

Port A (PA2..PA0)

Port A is a 3-bit bi-directional I/O port with internal pull-up resistors (selected for each bit). The Port A output buffers have symmetrical drive characteristics with both high sink and source capability. As inputs, Port A pins that are externally pulled low will source

current if the pull-up resistors are activated. The Port A pins are tri-stated when a reset condition becomes active, even if the clock is not running.

Port A also serves the functions of various special features of the ATtiny2313 as listed

on page 52.

Port B (PB7..PB0)

Port B is an 8-bit bi-directional I/O port with internal pull-up resistors (selected for each bit). The Port B output buffers have symmetrical drive characteristics with both high sink and source capability. As inputs, Port B pins that are externally pulled low will source current if the pull-up resistors are activated. The Port B pins are tri-stated when a reset condition becomes active, even if the clock is not running.

Port B also serves the functions of various special features of the ATtiny2313 as listed on page 52.

Port D is a 7-bit bi-directional I/O port with internal pull-up resistors (selected for each bit). The Port D output buffers have symmetrical drive characteristics with both high sink and source capability. As inputs, Port D pins that are externally pulled low will source current if the pull-up resistors are activated. The Port D pins are tri-stated when a reset condition becomes active, even if the clock is not running.

Port D also serves the functions of various special features of the ATtiny2313 as listed on page 55.

Reset input. A low level on this pin for longer than the minimum pulse length will generate a reset, even if the clock is not running. The minimum pulse length is given in Table 15 on page 33. Shorter pulses are not guaranteed to generate a reset. The Reset Input is an alternate function for PA2 and dW.

Input to the inverting Oscillator amplifier and input to the internal clock operating circuit.

XTAL1 is an alternate function for PA0.

Output from the inverting Oscillator amplifier, XTAL2 is an alternate function for PA1.

XTAL2

XTAL1

**RESET** 





## **Register Summary**

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Page
0x3F (0x5F)	SREG	ı	Т	Н	S	V	N	Z	С	7
0x3E (0x5E)	Reserved	_	_	_	_	_	-	_	_	,
0x3D (0x5D)	SPL	SP7	SP6	SP5	SP4	SP3	SP2	SP1	SP0	10
0x3C (0x5C)	OCR0B			-	Fimer/Counter0 –	Compare Registe	er B			76
0x3B (0x5B)	GIMSK	INT1	INT0	PCIE	-	-	-	_	-	59
0x3A (0x5A)	EIFR	INTF1	INTF0	PCIF	-	-	-	-	_	60
0x39 (0x59)	TIMSK	TOIE1	OCIE1A	OCIE1B	-	ICIE1	OCIE0B	TOIE0	OCIE0A	77, 108
0x38 (0x58)	TIFR	TOV1	OCF1A	OCF1B	-	ICF1	OCF0B	TOV0	OCF0A	77
0x37 (0x57)	SPMCSR	-	-	-	CTPB	RFLB	PGWRT	PGERS	SELFPRGEN	154
0x36 (0x56) 0x35 (0x55)	OCR0A MCUCR	PUD	SM1	SE	Fimer/Counter0 – SM0	ISC11	ISC10	ISC01	ISC00	76 52
0x34 (0x54)	MCUSR	-	- SIVIT	- -	- SIVIO	WDRF	BORF	EXTRF	PORF	36
0x33 (0x53)	TCCR0B	FOC0A	FOC0B	_	_	WGM02	CS02	CS01	CS00	75
0x32 (0x52)	TCNT0				Timer/Co	unter0 (8-bit)				76
0x31 (0x51)	OSCCAL	_	CAL6	CAL5	CAL4	CAL3	CAL2	CAL1	CAL0	25
0x30 (0x50)	TCCR0A	COM0A1	COM0A0	COM0B1	COM0B0	-	-	WGM01	WGM00	72
0x2F (0x4F)	TCCR1A	COM1A1	COM1A0	COM1B1	COM1BO	-	-	WGM11	WGM10	103
0x2E (0x4E)	TCCR1B	ICNC1	ICES1	=	WGM13	WGM12	CS12	CS11	CS10	106
0x2D (0x4D)	TCNT1H				er/Counter1 - Co					107
0x2C (0x4C)	TCNT1L				er/Counter1 – Co					107
0x2B (0x4B)	OCR1AH OCR1AL				/Counter1 – Com					107 107
0x2A (0x4A) 0x29 (0x49)	OCR1BH				/Counter1 – Com /Counter1 – Com					107
0x28 (0x48)	OCR1BL				/Counter1 – Com		<u> </u>			108
0x27 (0x47)	Reserved	_	_	_		–		_	_	100
0x26 (0x46)	CLKPR	CLKPCE	_	_	-	CLKPS3	CLKPS2	CLKPS1	CLKPS0	27
0x25 (0x45)	ICR1H			Timer/	Counter1 - Input (		High Byte		•	108
0x24 (0x44)	ICR1L	Timer/Counter1 - Input Capture Register Low Byte					108			
0x23 (0x43)	GTCCR	-	-	_	-	-	-	_	PSR10	80
0x22 (ox42)	TCCR1C	FOC1A	FOC1B	_	-	-	-	-	-	107
0x21 (0x41)	WDTCSR	WDIF	WDIE	WDP3	WDCE	WDE	WDP2	WDP1	WDP0	41
0x20 (0x40)	PCMSK	PCINT7	PCINT6	PCINT5	PCINT4	PCINT3	PCINT2	PCINT1	PCINT0	60
0x1F (0x3F)	Reserved EEAR	_	-	-	-			-	-	45
0x1E (0x3E) 0x1D (0x3D)	EEDR	_				PROM Address Re Data Register	egister			15 16
0x1C (0x3C)	EECR	_	_	EEPM1	EEPM0	EERIE	EEMPE	EEPE	EERE	16
0x1B (0x3B)	PORTA	_	_	_	_		PORTR2	PORTA1	PORTA0	57
0x1A (0x3A)	DDRA	_	_	_	_	_	DDA2	DDA1	DDA0	57
0x19 (0x39)	PINA	-	-	-	-	-	PINA2	PINA1	PINA0	57
0x18 (0x38)	PORTB	PORTB7	PORTB6	PORTB5	PORTB4	PORTB3	PORTB2	PORTB1	PORTB0	57
0x17 (0x37)	DDRB	DDB7	DDB6	DDB5	DDB4	DDB3	DDB2	DDB1	DDB0	57
0x16 (0x36)	PINB	PINB7	PINB6	PINB5	PINB4	PINB3	PINB2	PINB1	PINB0	57
0x15 (0x35)	GPIOR2	General Purpose I/O Register 2					20			
0x14 (0x34) 0x13 (0x33)	GPIOR1 GPIOR0	General Purpose I/O Register 1 General Purpose I/O Register 0					20 20			
0x12 (0x32)	PORTD	_	PORTD6	PORTD5	PORTD4	PORTD3	PORTD2	PORTD1	PORTD0	57
0x11 (0x31)	DDRD	-	DDD6	DDD5	DDD4	DDD3	DDD2	DDD1	DDD0	57
0x10 (0x30)	PIND	-	PIND6	PIND5	PIND4	PIND3	PIND2	PIND1	PIND0	57
0x0F (0x2F)	USIDR				USI Dat	a Register				143
0x0E (0x2E)	USISR	USISIF	USIOIF	USIPF	USIDC	USICNT3	USICNT2	USICNT1	USICNT0	144
0x0D (0x2D)	USICR	USISIE	USIOIE	USIWM1	USIWM0	USICS1	USICS0	USICLK	USITC	145
0x0C (0x2C)	UDR		I	l		Register (8-bit)				128
0x0B (0x2B)	UCSRA	RXC	TXC	UDRE	FE	DOR	UPE	U2X	MPCM	128
0x0A (0x2A)	UCSRB	RXCIE	TXCIE	UDRIE	RXEN	TXEN RH[7:0]	UCSZ2	RXB8	TXB8	130
0x09 (0x29) 0x08 (0x28)	UBRRL ACSR	ACD	ACBG	ACO	ACI	ACIE	ACIC	ACIS1	ACIS0	132 148
0x08 (0x28) 0x07 (0x27)	Reserved	ACD -	ACBG	ACO –	ACI	ACIE -	ACIC	ACIST	ACISU –	140
0x06 (0x26)	Reserved	_	_	_	_	_	_	_	_	
0x05 (0x25)	Reserved	_	_	_	_	_	_	_	_	
0x04 (0x24)	Reserved	-	=	=	-	=	-	-	-	
	UCSRC	-	UMSEL	UPM1	UPM0	USBS	UCSZ1	UCSZ0	UCPOL	131
0x03 (0x23)					_		LIBBE	RH[11:8]		132
0x03 (0x23) 0x02 (0x22)	UBRRH	-	-	-	_		OBITI	[]		102
` '	UBRRH DIDR	- -	_ _	-	_	-	-	AIN1D	AIN0D	149

Note:

- 1. For compatibility with future devices, reserved bits should be written to zero if accessed. Reserved I/O memory addresses should never be written.
- 2. I/O Registers within the address range 0x00 0x1F are directly bit-accessible using the SBI and CBI instructions. In these registers, the value of single bits can be checked by using the SBIS and SBIC instructions.
- 3. Some of the status flags are cleared by writing a logical one to them. Note that, unlike most other AVRs, the CBI and SBI instructions will only operate on the specified bit, and can therefore be used on registers containing such status flags. The CBI and SBI instructions work with registers 0x00 to 0x1F only.
- 4. When using the I/O specific commands IN and OUT, the I/O addresses 0x00 0x3F must be used. When addressing I/O Registers as data space using LD and ST instructions, 0x20 must be added to these addresses.





### **Instruction Set Summary**

Mnemonics	Operands	Description	Operation	Flags	#Clocks
ARITHMETIC AND I	OGIC INSTRUCTIONS	S			
ADD	Rd, Rr	Add two Registers	$Rd \leftarrow Rd + Rr$	Z,C,N,V,H	1
ADC	Rd, Rr	Add with Carry two Registers	$Rd \leftarrow Rd + Rr + C$	Z,C,N,V,H	1
ADIW	Rdl,K	Add Immediate to Word	Rdh:Rdl ← Rdh:Rdl + K	Z,C,N,V,S	2
SUB	Rd, Rr	Subtract two Registers	Rd ← Rd - Rr	Z,C,N,V,H	1
SUBI	Rd, K	Subtract Constant from Register	$Rd \leftarrow Rd - K$	Z,C,N,V,H	1
SBC	Rd, Rr	Subtract with Carry two Registers	$Rd \leftarrow Rd - Rr - C$	Z,C,N,V,H	1
SBCI	Rd, K	Subtract with Carry Constant from Reg.	Rd ← Rd - K - C	Z,C,N,V,H	1
SBIW	Rdl,K	Subtract Immediate from Word	Rdh:Rdl ← Rdh:Rdl - K	Z,C,N,V,S	2
AND	Rd, Rr	Logical AND Registers	Rd ← Rd • Rr	Z,N,V	1
ANDI	Rd, K	Logical AND Register and Constant	$Rd \leftarrow Rd \bullet K$	Z,N,V	1
OR	Rd, Rr	Logical OR Registers	$Rd \leftarrow Rd v Rr$	Z,N,V	1
ORI	Rd, K	Logical OR Register and Constant	$Rd \leftarrow Rd \vee K$	Z,N,V	1
EOR	Rd, Rr	Exclusive OR Registers	$Rd \leftarrow Rd \oplus Rr$	Z,N,V	1
COM	Rd	One's Complement	$Rd \leftarrow 0xFF - Rd$	Z,C,N,V	1
NEG	Rd	Two's Complement	Rd ← 0x00 – Rd	Z,C,N,V,H	1
SBR	Rd,K	Set Bit(s) in Register	$Rd \leftarrow Rd \vee K$	Z,N,V	1
CBR	Rd,K	Clear Bit(s) in Register	$Rd \leftarrow Rd \bullet (0xFF - K)$	Z,N,V	1
INC	Rd	Increment	Rd ← Rd + 1	Z,N,V	1
DEC	Rd	Decrement	Rd ← Rd – 1	Z,N,V	1
TST	Rd	Test for Zero or Minus	$Rd \leftarrow Rd \bullet Rd$	Z,N,V	1
CLR	Rd	Clear Register	$Rd \leftarrow Rd \oplus Rd$	Z,N,V	1
SER	Rd	Set Register	Rd ← 0xFF	None	1
BRANCH INSTRUC	TIONS		1	,	
RJMP	k	Relative Jump	PC ← PC + k + 1	None	2
IJMP		Indirect Jump to (Z)	PC ← Z	None	2
RCALL	k	Relative Subroutine Call	PC ← PC + k + 1	None	3
ICALL		Indirect Call to (Z)	PC ← Z	None	3
RET		Subroutine Return	PC ← STACK	None	4
RETI		Interrupt Return	PC ← STACK	1	4
CPSE	Rd,Rr	Compare, Skip if Equal	if (Rd = Rr) PC ← PC + 2 or 3	None	1/2/3
CP	Rd,Rr	Compare	Rd – Rr	Z, N,V,C,H	1
CPC	Rd,Rr	Compare with Carry	Rd – Rr – C	Z, N,V,C,H	1
CPI	Rd,K	Compare Register with Immediate	Rd – K	Z, N,V,C,H	1
SBRC	Rr, b	Skip if Bit in Register Cleared	if (Rr(b)=0) PC ← PC + 2 or 3	None	1/2/3
SBRS	Rr, b	Skip if Bit in Register is Set	if (Rr(b)=1) PC ← PC + 2 or 3	None	1/2/3
SBIC	P, b	Skip if Bit in I/O Register Cleared	if (P(b)=0) PC ← PC + 2 or 3	None	1/2/3
SBIS	P, b	Skip if Bit in I/O Register is Set	if $(P(b)=1)$ PC $\leftarrow$ PC + 2 or 3	None	1/2/3
BRBS	s, k	Branch if Status Flag Set	if (SREG(s) = 1) then PC←PC+k + 1	None	1/2
BRBC	s, k	Branch if Status Flag Cleared	if (SREG(s) = 0) then PC←PC+k + 1	None	1/2
BREQ	k	Branch if Equal	if $(Z = 1)$ then $PC \leftarrow PC + k + 1$	None	1/2
BRNE	k	Branch if Not Equal	if $(Z = 0)$ then $PC \leftarrow PC + k + 1$	None	1/2
BRCS	k	Branch if Carry Set	if (C = 1) then PC $\leftarrow$ PC + k + 1	None	1/2
BRCC	k	Branch if Carry Cleared	if (C = 0) then PC $\leftarrow$ PC + k + 1	None	1/2
BRSH	k	Branch if Same or Higher	if (C = 0) then PC $\leftarrow$ PC + k + 1	None	1/2
BRLO	k	Branch if Lower	if (C = 1) then PC $\leftarrow$ PC + k + 1	None	1/2
BRMI	k	Branch if Minus	if $(N = 1)$ then $PC \leftarrow PC + k + 1$	None	1/2
BRPL	k	Branch if Plus	if $(N = 0)$ then $PC \leftarrow PC + k + 1$	None	1/2
BRGE	k	Branch if Greater or Equal, Signed	if (N $\oplus$ V= 0) then PC $\leftarrow$ PC + k + 1	None	1/2
BRLT	k	Branch if Less Than Zero, Signed	if (N $\oplus$ V= 1) then PC $\leftarrow$ PC + k + 1	None	1/2
BRHS	k	Branch if Half Carry Flag Set	if (H = 1) then PC ← PC + k + 1	None	1/2
BRHC	k	Branch if Half Carry Flag Cleared	if (H = 0) then PC $\leftarrow$ PC + k + 1	None	1/2
BRTS	k	Branch if T Flag Set	if (T = 1) then PC $\leftarrow$ PC + k + 1	None	1/2
BRTC	k	Branch if T Flag Cleared	if (T = 0) then PC $\leftarrow$ PC + k + 1	None	1/2
BRVS	k	Branch if Overflow Flag is Set	if $(V = 1)$ then $PC \leftarrow PC + k + 1$	None	1/2
BRVC	k	Branch if Overflow Flag is Cleared	if $(V = 0)$ then $PC \leftarrow PC + k + 1$	None	1/2
BRIE	k	Branch if Interrupt Enabled	if ( I = 1) then PC ← PC + k + 1	None	1/2
BRID	k	Branch if Interrupt Disabled	if ( I = 0) then PC $\leftarrow$ PC + k + 1	None	1/2
BIT AND BIT-TEST			1	1	
SBI	P,b	Set Bit in I/O Register	I/O(P,b) ← 1	None	2
CBI	P,b	Clear Bit in I/O Register	I/O(P,b) ← 0	None	2
LSL	Rd	Logical Shift Left	$Rd(n+1) \leftarrow Rd(n), Rd(0) \leftarrow 0$	Z,C,N,V	1
LSR	Rd	Logical Shift Right	$Rd(n) \leftarrow Rd(n+1), Rd(7) \leftarrow 0$	Z,C,N,V	1

Mnemonics	Operands	Description	Operation	Flags	#Clocks
ROR	Rd	Rotate Right Through Carry	$Rd(7)\leftarrow C,Rd(n)\leftarrow Rd(n+1),C\leftarrow Rd(0)$	Z,C,N,V	1
ASR	Rd	Arithmetic Shift Right	Rd(n) ← Rd(n+1), n=06	Z,C,N,V	1
SWAP	Rd	Swap Nibbles	Rd(30)←Rd(74),Rd(74)←Rd(30)	None	1
BSET	s	Flag Set	SREG(s) ← 1	SREG(s)	1
BCLR	s	Flag Clear	$SREG(s) \leftarrow 0$	SREG(s)	1
BST	Rr, b	Bit Store from Register to T	$T \leftarrow Rr(b)$	Т	1
BLD	Rd, b	Bit load from T to Register	Rd(b) ← T	None	1
SEC		Set Carry	C ← 1	С	1
CLC		Clear Carry	C ← 0	С	1
SEN		Set Negative Flag	N ← 1	N	1
CLN		Clear Negative Flag	N ← 0	N	1
SEZ		Set Zero Flag	Z ← 1	Z	1
CLZ		Clear Zero Flag	Z ← 0	Z	1
SEI		Global Interrupt Enable	1←1	1	1
CLI		Global Interrupt Disable	1←0	<del>-   '</del>	1
SES		Set Signed Test Flag	S ← 1	S	1
CLS		Clear Signed Test Flag	S ← 0	S	1
SEV		Set Twos Complement Overflow.	V ← 1	V	1
CLV		· · · · · · · · · · · · · · · · · · ·	V ← 1 V ← 0	V	1
	+	Clear Twos Complement Overflow		T	-
SET	+	Set T in SREG	T ← 1	T	1
SEH	+	Clear T in SREG Set Half Carry Flag in SREG	T←0	H	1 1
CLH			H ← 1	Н	1
	NOTOLIOTIONO	Clear Half Carry Flag in SREG	H ← 0	11	1 1
DATA TRANSFER I		I Maria Batarana Bandatana	D.I. D.	None	1
MOV	Rd, Rr	Move Between Registers	Rd ← Rr	None	1
MOVW	Rd, Rr	Copy Register Word	Rd+1:Rd ← Rr+1:Rr	None	1
LDI	Rd, K	Load Immediate	Rd ← K	None	1
LD	Rd, X	Load Indirect	Rd ← (X)	None	2
LD	Rd, X+	Load Indirect and Post-Inc.	$Rd \leftarrow (X), X \leftarrow X + 1$	None	2
LD	Rd, - X	Load Indirect and Pre-Dec.	$X \leftarrow X - 1$ , $Rd \leftarrow (X)$	None	2
LD	Rd, Y	Load Indirect	$Rd \leftarrow (Y)$	None	2
LD	Rd, Y+	Load Indirect and Post-Inc.	$Rd \leftarrow (Y), Y \leftarrow Y + 1$	None	2
LD	Rd, - Y	Load Indirect and Pre-Dec.	$Y \leftarrow Y - 1$ , $Rd \leftarrow (Y)$	None	2
LDD	Rd,Y+q	Load Indirect with Displacement	$Rd \leftarrow (Y + q)$	None	2
LD	Rd, Z	Load Indirect	$Rd \leftarrow (Z)$	None	2
LD	Rd, Z+	Load Indirect and Post-Inc.	$Rd \leftarrow (Z), Z \leftarrow Z+1$	None	2
LD	Rd, -Z	Load Indirect and Pre-Dec.	$Z \leftarrow Z - 1$ , $Rd \leftarrow (Z)$	None	2
LDD	Rd, Z+q	Load Indirect with Displacement	$Rd \leftarrow (Z + q)$	None	2
LDS	Rd, k	Load Direct from SRAM	Rd ← (k)	None	2
ST	X, Rr	Store Indirect	$(X) \leftarrow Rr$	None	2
ST	X+, Rr	Store Indirect and Post-Inc.	$(X) \leftarrow Rr, X \leftarrow X + 1$	None	2
ST	- X, Rr	Store Indirect and Pre-Dec.	$X \leftarrow X - 1$ , $(X) \leftarrow Rr$	None	2
ST	Y, Rr	Store Indirect	$(Y) \leftarrow Rr$	None	2
ST	Y+, Rr	Store Indirect and Post-Inc.	$(Y) \leftarrow Rr, Y \leftarrow Y + 1$	None	2
ST	- Y, Rr	Store Indirect and Pre-Dec.	$Y \leftarrow Y - 1$ , $(Y) \leftarrow Rr$	None	2
STD	Y+q,Rr	Store Indirect with Displacement	$(Y + q) \leftarrow Rr$	None	2
ST	Z, Rr	Store Indirect	(Z) ← Rr	None	2
ST	Z+, Rr	Store Indirect and Post-Inc.	(Z) ← Rr, Z ← Z + 1	None	2
ST	-Z, Rr	Store Indirect and Pre-Dec.	$Z \leftarrow Z - 1$ , $(Z) \leftarrow Rr$	None	2
STD	Z+q,Rr	Store Indirect with Displacement	$(Z + q) \leftarrow Rr$	None	2
STS	k, Rr	Store Direct to SRAM	(k) ← Rr	None	2
LPM		Load Program Memory	R0 ← (Z)	None	3
LPM	Rd, Z	Load Program Memory	$Rd \leftarrow (Z)$	None	3
LPM	Rd, Z+	Load Program Memory and Post-Inc	$Rd \leftarrow (Z), Z \leftarrow Z+1$	None	3
SPM		Store Program Memory	(Z) ← R1:R0	None	-
IN	Rd, P	In Port	Rd ← P	None	1
OUT	P, Rr	Out Port	P ← Rr	None	1
PUSH	Rr	Push Register on Stack	STACK ← Rr	None	2
POP	Rd	Pop Register from Stack	Rd ← STACK	None	2
MCU CONTROL INS	•			· ·	<del>-</del>
NOP		No Operation		None	1
SLEEP		Sleep	(see specific descr. for Sleep function)	None	1
	Ī.	o.oop	(acc apositio desci. for dieep fullotion)	140116	
WDR		Watchdog Reset	(see specific descr. for WDR/timer)	None	1





### **Ordering Information**

Speed (MHz)	Power Supply	Ordering Code	Package <sup>(1)</sup>	Operation Range
		ATtiny2313V-10PI	20P3	
10 <sup>(3)</sup>	10 557	ATtiny2313V-10PJ <sup>(2)</sup>	20P3	Industrial
10(-)	1.8 - 5.5V	ATtiny2313V-10SI	20S	(-40°C to 85°C)
		ATtiny2313V-10SJ <sup>(2)</sup>	20S	
	2.7 - 5.5V	ATtiny2313-20PI	20P3	
20 <sup>(3)</sup>		ATtiny2313-20PJ <sup>(2)</sup>	20P3	Industrial
20(-)		ATtiny2313-20SI	20S	(-40°C to 85°C)
		ATtiny2313-20SJ <sup>(2)</sup>	20S	


Note:


- 1. This device can also be supplied in wafer form. Please contact your local Atmel sales office for detailed ordering information and minimum quantities.
- 2. Pb-free packaging alternative.
- 3. See Figure 81 on page 177 and Figure 82 on page 177.

Package Type				
20P3	20-lead, 0.300" Wide, Plastic Dual Inline Package (PDIP)			
20\$	20-lead, 0.300" Wide, Plastic Gull Wing Small Outline (SOIC)			

### **Packaging Information**

#### 20P3





Notes:

- 1. This package conforms to JEDEC reference MS-001, Variation AD.
- 2. Dimensions D and E1 do not include mold Flash or Protrusion. Mold Flash or Protrusion shall not exceed 0.25 mm (0.010").

#### **COMMON DIMENSIONS** (Unit of Measure = mm)

(							
SYMBOL	MIN	NOM	MAX	NOTE			
Α	_	_	5.334				
A1	0.381	_	_				
D	25.493	_	25.984	Note 2			
E	7.620	_	8.255				
E1	6.096	_	7.112	Note 2			
В	0.356	_	0.559				
B1	1.270	_	1.551				
L	2.921	_	3.810				
С	0.203	_	0.356				
eB	-	_	10.922				
eC	0.000	_	1.524				
е		2.540 7	YP				

1/12/04



2325 Orchard Parkway San Jose, CA 95131

TITLE


 $\bf 20P3, \, 20\text{-lead} \, (0.300\mbox{"}/7.62 \; mm \, Wide)$  Plastic Dual Inline Package (PDIP)

DRAWING NO. 20P3


REV. С








Top View



Side View



#### **COMMON DIMENSIONS**

(Unit of Measure = inches)

(						
SYMBOL	MIN	NOM	MAX	NOTE		
Α	0.0926		0.1043			
A1	0.0040		0.0118			
b	0.0130		0.0200	4		
С	0.0091		0.0125			
D	0.4961		0.5118	1		
Е	0.2914		0.2992	2		
Н	0.3940		0.4190			
L	0.0160		0.050	3		
е	0.050 BSC					

Notes: 1. This drawing is for general information only; refer to JEDEC Drawing MS-013, Variation AC for additional information.
2. Dimension "D" does not include mold Flash, protrusions or gate burrs. Mold Flash, protrusions and gate burrs shall not exceed

- 0.15 mm (0.006") per side.
- 3. Dimension "E" does not include inter-lead Flash or protrusion. Inter-lead Flash and protrusions shall not exceed 0.25 mm
- (0.010") per side.
  "L" is the length of the terminal for soldering to a substrate.
  The lead width "b", as measured 0.36 mm (0.014") or greater above the seating plane, shall not exceed a maximum value of 0.61 mm (0.024") per side.



2325 Orchard Parkway San Jose, CA 95131

<b>20S2</b> , 20-lead, 0.300" Wide Body, Plastic Gull Wing Small Outline Package (SOIC)	IIILE	
Wing Small Outline Package (SOIC)	20S2, 20-lead, 0.300" Wid	de Body, Plastic Gull
	Wing Small Outline Packa	age (SOIC)

DRAWING NO. REV. 20S2 Α

#### **Errata**

The revision in this section refers to the revision of the ATtiny2313 device.

#### ATtiny2313 Rev B

- Wrong values read after Erase Only operation
- Parallel Programming does not work
- Watchdog Timer Interrupt disabled

#### 1. Wrong values read after Erase Only operation

At supply voltages below 2.7 V, an EEPROM location that is erased by the Erase Only operation may read as programmed (0x00).

#### **Problem Fix/Workaround**

If it is necessary to read an EEPROM location after Erase Only, use an Atomic Write operation with 0xFF as data in order to erase a location. In any case, the Write Only operation can be used as intended. Thus no special considerations are needed as long as the erased location is not read before it is programmed.

#### 2. Parallel Programming does not work

Parallel Programming is not functioning correctly. Because of this, reprogramming of the device is impossible if one of the following modes are selected:

- In-System Programming disabled (SPIEN unprogrammed)
- Reset Disabled (RSTDISBL programmed)

#### **Problem Fix/Workaround**

Serial Programming is still working correctly. By avoiding the two modes above, the device can be reprogrammed serially.

#### 3. Watchdog Timer Interrupt disabled

If the watchdog timer interrupt flag is not cleared before a new timeout occurs, the watchdog will be disabled, and the interrupt flag will automatically be cleared. This is only applicable in interrupt only mode. If the Watchdog is configured to reset the device in the watchdog time-out following an interrupt, the device works correctly.

#### Problem fix / Workaround

Make sure there is enough time to always service the first timeout event before a new watchdog timeout occurs. This is done by selecting a long enough time-out period.

#### ATtiny2313 Rev A

Revision A has not been sampled.





## Datasheet Change Log for ATtiny2313

Please note that the referring page numbers in this section are referred to this document. The referring revision in this section are referring to the document revision.

## Changes from Rev. 2514D-03/04 to Rev. 2514E-04/04

- 1. Speed Grades changed
  - 12MHz to 10MHz
  - 24MHz to 20MHz
- 2. Updated Figure 1 on page 2.
- 3. Updated "Ordering Information" on page 10.
- 4. Updated "Maximum Speed vs. VCC" on page 177.

## Changes from Rev. 2514C-12/03 to Rev. 2514D-03/04

- 1. Updated Table 2 on page 22.
- 2. Replaced "Watchdog Timer" on page 38.
- 3. Added "Maximum Speed vs. VCC" on page 177.
- 4. "Serial Programming Algorithm" on page 171 updated.
- 5. Changed mA to  $\mu$ A in preliminary Figure 110 on page 192.
- 6. "Ordering Information" on page 10 updated.
  MLF package option removed
- 7. Package drawing "20P3" on page 11 updated.
- 8. Updated C-code examples.
- 9. Renamed instances of SPMEN to SELFPRGEN, Self Programming Enable.

# Changes from Rev. 2514B-09/03 to Rev. 2514C-12/03

1. Updated "Calibrated Internal RC Oscillator" on page 24.

# Changes from Rev. 2514A-09/03 to Rev. 2514B-09/03

- 1. Fixed typo from UART to USART and updated Speed Grades and Power Consumption Estimates in "Features" on page 1.
- 2. Updated "Pin Configurations" on page 2.
- 3. Updated Table 15 on page 33 and Table 80 on page 176.
- 4. Updated item 5 in "Serial Programming Algorithm" on page 171.
- 5. Updated "Electrical Characteristics" on page 175.
- 6. Updated Figure 81 on page 177 and added Figure 82 on page 177.
- 7. Changed SFIOR to GTCCR in "Register Summary" on page 6.
- 8. Updated "Ordering Information" on page 10.
- 9. Added new errata in "Errata" on page 13.



#### **Atmel Corporation**

2325 Orchard Parkway San Jose, CA 95131, USA Tel: 1(408) 441-0311

Fax: 1(408) 487-2600

#### **Regional Headquarters**

#### Europe

Atmel Sarl Route des Arsenaux 41 Case Postale 80 CH-1705 Fribourg Switzerland

Tel: (41) 26-426-5555 Fax: (41) 26-426-5500

#### Asia

Room 1219 Chinachem Golden Plaza 77 Mody Road Tsimshatsui East Kowloon Hong Kong

Tel: (852) 2721-9778 Fax: (852) 2722-1369

#### Japan

9F, Tonetsu Shinkawa Bldg. 1-24-8 Shinkawa Chuo-ku, Tokyo 104-0033 Japan

Tel: (81) 3-3523-3551 Fax: (81) 3-3523-7581

#### **Atmel Operations**

#### Memory

2325 Orchard Parkway San Jose, CA 95131, USA Tel: 1(408) 441-0311 Fax: 1(408) 436-4314

#### Microcontrollers

2325 Orchard Parkway San Jose, CA 95131, USA Tel: 1(408) 441-0311 Fax: 1(408) 436-4314

La Chantrerie BP 70602 44306 Nantes Cedex 3, France Tel: (33) 2-40-18-18-18

Fax: (33) 2-40-18-19-60

#### ASIC/ASSP/Smart Cards

Zone Industrielle 13106 Rousset Cedex, France Tel: (33) 4-42-53-60-00

Fax: (33) 4-42-53-60-01

1150 East Cheyenne Mtn. Blvd. Colorado Springs, CO 80906, USA

Tel: 1(719) 576-3300 Fax: 1(719) 540-1759

Scottish Enterprise Technology Park Maxwell Building East Kilbride G75 0QR, Scotland

Tel: (44) 1355-803-000 Fax: (44) 1355-242-743

#### RF/Automotive

Theresienstrasse 2 Postfach 3535 74025 Heilbronn, Germany Tel: (49) 71-31-67-0 Fax: (49) 71-31-67-2340

1150 East Cheyenne Mtn. Blvd. Colorado Springs, CO 80906, USA

Tel: 1(719) 576-3300 Fax: 1(719) 540-1759

Biometrics/Imaging/Hi-Rel MPU/ High Speed Converters/RF Datacom Avenue de Rochepleine

Avenue de Rochepi BP 123

38521 Saint-Egreve Cedex, France

Tel: (33) 4-76-58-30-00 Fax: (33) 4-76-58-34-80

Literature Requests www.atmel.com/literature

**Disclaimer:** Atmel Corporation makes no warranty for the use of its products, other than those expressly contained in the Company's standard warranty which is detailed in Atmel's Terms and Conditions located on the Company's web site. The Company assumes no responsibility for any errors which may appear in this document, reserves the right to change devices or specifications detailed herein at any time without notice, and does not make any commitment to update the information contained herein. No licenses to patents or other intellectual property of Atmel are granted by the Company in connection with the sale of Atmel products, expressly or by implication. Atmel's products are not authorized for use as critical components in life support devices or systems.

© Atmel Corporation 2004. All rights reserved. Atmel<sup>®</sup> and combinations thereof, AVR<sup>®</sup>, and AVR Studio<sup>®</sup> are the registered trademarks of Atmel Corporation or its subsidiaries. Microsoft<sup>®</sup>, Windows NT<sup>®</sup>, and Windows XP<sup>®</sup> are the registered trademarks of Microsoft Corporation. Other terms and product names may be the trademarks of others

